UNIVERSITY OF TORONTO
3 1761 01606015 4



Presented to the
LIBRARY *of the*
UNIVERSITY OF TORONTO
from
the estate of
VERNON R. DAVIES

WORKS OF CHARLES B. BREED

AND

GEORGE L. HOSMER

PUBLISHED BY

JOHN WILEY & SONS, INC.

THE PRINCIPLES AND PRACTICE OF SURVEYING

Volume I. Elementary Surveying.

PART I. Use, Adjustment, and Care of Instruments.

PART II. Surveying, Stadia, Meridian Observations, Leveling; City, Mine, and Topographic Surveying.

PART III. Computations.

PART IV. Plotting, Finishing, and Filing Plans.

TABLES. Logarithmic, Trigonometric, Stadia, and others.

Fourth Edition. Revised. 591 pages, 216 cuts. Flexible Leather, Pocket Size, $3.00.

Volume II. Higher Surveying.

PART I. Triangulation, Astronomical Observations; Precise, Trigonometric and Barometric Leveling.

PART II. Stadia, Plane Table, Photographic Surveying, Relation of Geology to Topography.

PART III. Hydrographic Surveying, Stream Gauging.

PART IV. Constructing and Finishing Maps.

TABLES. Geodetic Position, Polyconic Projections, Barometric, Stadia, and others.

Second Edition. 443 pages, 158 cuts and 7 full page plates. Flexible Leather, Pocket Size, $2.50.

THE PRINCIPLES AND PRACTICE OF SURVEYING

VOLUME I. ELEMENTARY SURVEYING

BY

CHARLES B. BREED AND GEORGE L. HOSMER

Professor of Railroad Engineering — *Assistant Professor of Civil Engineering*

MASSACHUSETTS INSTITUTE OF TECHNOLOGY

FOURTH EDITION

TOTAL ISSUE TWENTY-THREE THOUSAND

NEW YORK

JOHN WILEY & SONS, INC.

LONDON: CHAPMAN & HALL, LIMITED

1916

COPYRIGHT, 1906, 1908, 1915
BY
CHARLES B. BREED AND GEORGE L. HOSMER

PRINTED AND BOUND AT THE NORWOOD PRESS,
NORWOOD, MASS., U.S.A.

PREFACE TO THE FOURTH EDITION

In presenting the fourth edition of this book the authors desire to call attention to two radical changes from the original plan of the work, both of which have been made in response to repeated requests from many teachers and practising surveyors. First, this volume is now bound in pocket size for the benefit of numerous schools which require the use of a text-book in the field. This change has been made, however, without reducing the size of type, a matter of great importance in any book which has to be used for evening study. Second, the subject of Stadia Surveying has been fully treated in a new chapter in this volume. The Stadia Tables have been extended a full page.

The entire volume has been revised and much of it rewritten. The description of various steel tapes has been brought up to date, and prominence is given to a modern method of measuring slope distances to avoid plumbing. To this end a table of Versed Sines has been added which will assist in shortening the necessary computations.

The chapter on Mine Surveying has been entirely rewritten, and brought more closely in touch with the modern practice. Practically all of the illustrations are new. The authors are indebted to Professor John W. Howard of the Massachusetts Institute of Technology for his valuable suggestions and criticisms of this chapter.

This volume has been entirely repaged and the Table of Contents, Index, and all cross references adapted to the new paging.

The authors desire to thank all those who have assisted in the past by their suggestions and criticisms, and to request further criticisms of this new edition. Notices of any errors will be appreciated.

C. B. B.
G. L. H.

Boston, Mass., *February*, 1915.

PREFACE TO THE FIRST EDITION

In the preparation of this volume, it has been the authors' chief purpose to produce a text-book which shall include the essentials of a comprehensive knowledge of practical surveying and at the same time be adapted to the use of teachers and students in technical schools. In this book, which is essentially an elementary treatise, such subjects as stadia, plane table, hydrographic and geodetic surveying, are entirely omitted, these subjects being left for a later volume.

Considerable stress is laid upon the practical side of surveying. The attempt is made not only to give the student a thorough training in the fundamental principles and in approved methods of surveying, computing, and plotting, but also to impress upon him the importance of accuracy and precision in all of his work in the field and the drafting-room. In carrying out this purpose it has seemed necessary to lay particular stress upon some points which to the experienced engineer or the advanced student may appear too obvious to require explanation, but which teaching experience has shown to be most helpful to the beginner. The most common errors and mistakes have therefore been pointed out and numerous methods of checking have been explained. Every effort has been made to inculcate right methods even in minor details, and for this purpose a large number of examples from actual practice have been introduced.

In arranging the subject matter of the work, the four parts are presented in what appears to be a logical sequence. First, the use, adjustment, and care of instruments are taken up; then the next three parts, surveying methods, computations, and plotting, are taken in the order in which they are met in the daily practice of the surveyor. To show more clearly the steps in the process, the notes which are used as illustrations in surveying methods are calculated in the computation section, and

are treated again under the methods of plotting, finally appearing as a completed plan.

While the authors recognize fully their indebtedness to those who have preceded them in this field, they hope that they have made some useful contributions of their own to the treatment of the subject. Thus in the section on Surveying Methods, many practical suggestions have been inserted which they have found of value in their own work and which, so far as they are aware, now appear in a text-book for the first time. On the subject of Computations, much emphasis is laid upon the proper use of significant figures and the arrangement of the work, matters which heretofore have not been adequately treated in books on surveying. The section on Plotting contains many hints referring particularly to surveying drafting, which are not given in the published books on drawing and lettering. It is hoped also that the complete set of original illustrations which have been introduced throughout the book will aid materially in making the text clear.

A comprehensive cross-reference system giving the page as well as the article number has been adopted : this, together with the complete index at the end of the book and the many practical hints throughout the volume will, it is hoped, render it useful to the practical surveyor as a reference book.

The authors desire to acknowledge their indebtedness to their various associates in the teaching and engineering professions who have kindly responded to requests for information and assisted in the preparation of this work, particularly to Blamey Stevens, M. Sc., of Ellamar, Alaska, who supplied the entire chapter on Mining Surveying. They are also under obligations for the use of electrotype plates of tables : to W. H. Searles for Tables IV, V, and VI ; to Professor J. C. Nagle for Tables II and III ; and to Professor Daniel Carhart for Table I ; all of these plates were furnished by John Wiley & Sons. The authors are under special obligation to Professors C. F. Allen, A. G. Robbins, and C. W. Doten of the Massachusetts Institute of Technology, and to H. K. Barrows, Engineer U. S. Geological Survey, who have read the entire manuscript and who have offered many valuable suggestions in preparing the work for the press.

The authors also desire to express their appreciation of the excellent work of W. L. Vennard, who made the drawings for illustrations.

No pains has been spared to eliminate all errors, but the authors cannot hope that their efforts in this line have been completely successful, and they will consider it a favor if their attention is called to any which may be found.

C. B. B.
G. L. H.

BOSTON, MASS., *September*, 1906.

CONTENTS.

PART I.

USE, ADJUSTMENT, AND CARE OF INSTRUMENTS.

CHAPTER I. — GENERAL DEFINITIONS. — MEASUREMENT OF LINES.

ART.		PAGE
1.	DEFINITION	1
2.	PURPOSES OF SURVEYS	1
3.	HORIZONTAL LINES	1
	INSTRUMENTS FOR MEASURING LINES.	
4.	THE CHAIN	1
5.	METRIC CHAIN	3
6.	THE TAPE	3
7.	STEEL TAPES	3
8.	THE STADIA	5
9.	OTHER INSTRUMENTS; — WOODEN RODS, TWO-FOOT RULE, ODOMETER, PEDOMETER	5
	MEASUREMENT OF LINES.	
10.	MEASUREMENT ON LEVEL GROUND WITH A TAPE	5
11.	MEASUREMENT WITH THE CHAIN	8
12.	HORIZONTAL MEASUREMENT ON SLOPING GROUND WITH TAPE	8
13.	SLOPE MEASUREMENT WITH A TAPE	9
14.	COMMON SOURCES OF ERROR IN MEASUREMENT OF LINES	10
15.	COMMON MISTAKES IN READING AND RECORDING MEASUREMENTS	10
16.	AVOIDING MISTAKES	10
17.	ACCURACY REQUIRED	11
18.	AMOUNT OF DIFFERENT ERRORS	12
19.	PULL	12
20.	TEMPERATURE	12
21.	ALIGNMENT	12
22.	SAG	13
23.	ACCURACY OF MEASUREMENTS	14
	PROBLEMS	15

CHAPTER II. — MEASUREMENT OF DIRECTION.

24.	THE SURVEYOR'S COMPASS	16
25.	THE POCKET COMPASS	18
26.	METHOD OF TAKING A MAGNETIC BEARING	18
27.	THE EARTH'S MAGNETISM, — DIP OF THE NEEDLE	19
28.	DECLINATION OF THE NEEDLE	19
29.	VARIATIONS IN DECLINATION	20
30.	ISOGONIC CHART	25
31.	OBSERVATIONS FOR DECLINATION	25

ADJUSTMENTS OF THE COMPASS.

Art.		Page
33.	Adjustment of the Bubbles	25
34.	Detecting Errors in Adjustment of the Needle	25
35.	To Straighten the Compass-Needle	26
36.	To Center the Pivot-Point	27
37.	To Remagnetize the Needle	28
38.	Common Sources of Error in Compass Work	28
39.	Common Mistakes	28
40.	Detecting Local Attractions of the Needle	29
41.	Calculating Angles from Bearings	30
	Problems	30

Chapter III. — Measurement of Angles.

THE TRANSIT.

42.	General Description of the Transit	31
45.	The Telescope	34
46.	The Objective	35
47.	Cross-Hairs	36
48.	Eyepiece	37
49.	Magnifying Power	37
51.	Field of View	38
52.	The Vernier	38
53.	Verniers Used on Transits	39
54.	Eccentricity	44

USE OF THE TRANSIT.

56.	Setting up the Transit	45
58.	To Measure a Horizontal Angle	47
59.	To Measure an Angle by Repetition	48
61.	To Lay Off an Angle by Repetition	50
62.	Running a Straight Line — One Point Visible from the Other	51
63.	Neither Point Visible from the Other	51
64.	Prolonging a Straight Line	52
65.	Methods of Showing Sights	52
66.	Signals	53
67.	To Measure a Vertical Angle	54
68.	Precautions in the Use of the Transit	55

ADJUSTMENTS OF THE TRANSIT.

70.	Adjustment of the Plate Bubbles	56
71.	Adjustment of the Cross-Hairs	57
73.	Adjustment of the Standards	59
74.	Adjustment of the Telescope Bubble	59
75.	Adjustment of the Auxiliary Level on the Vernier of the Vertical Arc	59
76.	Adjustment of the Vernier of the Vertical Circle	60
77.	Adjustment of the Objective Slide	60
78.	Shop Adjustments	61
79.	How to Eliminate the Effect of Errors of Adjustment in the Transit	61
80.	Care of Instruments	61
81.	Common Sources of Error in Transit Work	62
82.	Common Mistakes in Transit Work	62

THE SOLAR ATTACHMENT.

ART. PAGE
83. DESCRIPTION OF SOLAR ATTACHMENT 63
84. THE CELESTIAL SPHERE 65
85. OBSERVATION ON THE SUN FOR MERIDIAN WITH SOLAR ATTACHMENT 66
86. COMPUTATION OF DECLINATION SETTINGS 68
87. COMSTOCK'S METHOD OF FINDING THE REFRACTION 69
89. MISTAKES IN USING THE SOLAR ATTACHMENT 70

ADJUSTMENTS OF THE SOLAR ATTACHMENT.

90. ADJUSTMENT OF THE POLAR AXIS 70
91. ADJUSTMENT OF THE CROSS-HAIRS 70
92. ADJUSTMENT OF TELESCOPE BUBBLE 71
PROBLEMS 71

CHAPTER IV. — MEASUREMENT OF DIFFERENCES OF ELEVATION.

93. LEVEL SURFACE 72
94. THE SPIRIT LEVEL 72
95. ANGULAR VALUE OF ONE DIVISION OF THE LEVEL TUBE . . . 73

THE LEVEL

97. THE WYE LEVEL 73
98. THE DUMPY LEVEL 74
99. COMPARISON OF WYE AND DUMPY LEVELS 77
100. MICROMETER ADJUSTMENT 77
101. THE LOCKE HAND LEVEL 78

LEVELING RODS.

102. BOSTON ROD 78
103. NEW YORK ROD 80
104. PHILADELPHIA ROD. 81
105. SPECIAL SELF-READING RODS 81
106. TAPE ROD 81
107. PRECISE LEVEL ROD 82
108. ADVANTAGES OF THE SELF-READING ROD 82
109. ATTACHMENTS TO THE ROD FOR PLUMBING 84
110. EFFECT OF HEAT AND MOISTURE 84

USE OF THE LEVEL AND ROD.

112. TO LEVEL THE INSTRUMENT 84
113. TO TAKE A ROD-READING 85
114. WAVING THE ROD 85
115. SIGNALS 86
116. DIFFERENTIAL LEVELING 86
117. THE PROPER LENGTH OF SIGHT 88
118. EFFECT OF THE EARTH'S CURVATURE AND OF REFRACTION ON LEVELING 88
119. PRECAUTIONS IN LEVEL WORK 89

ADJUSTMENTS OF THE LEVEL.

I. ADJUSTMENTS OF THE WYE LEVEL.

120. ADJUSTMENT OF THE CROSS-HAIR 89
122. ADJUSTMENT OF THE LEVEL TUBE 90

ART. PAGE
123. ADJUSTMENT OF THE LEVEL TUBE BY INDIRECT METHOD . . . 90
125. ADJUSTMENT OF THE WYES 91

II. ADJUSTMENTS OF THE DUMPY LEVEL.

126. ADJUSTMENT OF THE CROSS-HAIRS 92
127. ADJUSTMENT OF THE BUBBLE TUBE 92
128. THE DIRECT OR "PEG" ADJUSTMENT 92
129. ADJUSTMENT OF THE LOCKE HAND LEVEL 94

130. COMMON SOURCES OF ERROR IN LEVELING 95
131. COMMON MISTAKES IN LEVELING 95
PROBLEMS 95

PART II.

SURVEYING METHODS.

CHAPTER V. — LAND SURVEYING.

132. SURVEYING FOR AREA 99
133. SURVEYING FOR AREA WITH COMPASS AND CHAIN 99

SURVEY OF FIELD WITH TRANSIT AND TAPE.

134. SURVEY OF A FIELD BY A TRAVERSE 101
137. IRREGULAR CURVED BOUNDARIES 105
138. SURVEY OF A FIELD WITH A SINGLE SET-UP OF THE TRANSIT . . 105
139. SURVEY OF A FIELD WITH A TAPE ONLY 106
140. SELECTING THE CORNERS 106
141. METHOD OF PROCEDURE 107
142. TIES 107
143. MEASUREMENT OF THE ANGLES OF THE TRAVERSE 108
144. MEASUREMENT OF AZIMUTH ANGLES 109
145. CHECKING THE FIELDWORK 110
146. ACCURACY REQUIRED 111
147. ORGANIZATION OF TRANSIT PARTY 112
148. NOTE-KEEPING 112
149. SURVEY OF A FIELD FOR A DEED 114
150. DEED DESCRIPTION 115
151. JUDICIAL FUNCTIONS OF THE SURVEYOR 116
152. RERUNNING OLD SURVEYS FROM A DEED 118
153. HOW TO LOOK UP A RECORDED DEED 120

THE UNITED STATES SYSTEM OF SURVEYING THE PUBLIC LANDS.

154. THE SYSTEM 121
155. PROCESS OF SUBDIVISION 123
156. METHODS OF DESIGNATING LINES AND AREAS 127
157. FIELD METHODS 128
158. TO ESTABLISH A PARALLEL OF LATITUDE 128
159. THE SECANT METHOD 129
160. THE TANGENT METHOD 131
161. INITIAL POINTS 134

ART. PAGE
162. BASE-LINE 134
163. PRINCIPAL MERIDIAN 136
164. STANDARD PARALLELS 136
165. GUIDE MERIDIANS 136
166. TOWNSHIP EXTERIORS 138
167. SUBDIVISION OF TOWNSHIPS 139
168. FRACTIONAL SECTIONS 142
169. SUMMARY OF OBJECTS AND DATA INTERSECTED BY THE LINE . . 145
170. MARKING CORNERS 146
171. WITNESSING CORNERS 148
172. WITNESS CORNERS 149
173. MEANDER CORNERS 149
174. MEANDERING 151
175. ACCESS TO RECORDS AND MAPS 153
176. RELOCATING LOST CORNERS 154
177. SUBDIVISION OF SECTIONS 157
178. CONVERGENCE OF THE MERIDIANS 161

CHAPTER VI. — TRAVERSE LINES — LOCATION OF BUILDINGS — MISCELLANEOUS SURVEYING PROBLEMS.

TRAVERSE LINES.

179. TRAVERSES WHICH DO NOT FORM CLOSED FIGURES 163
180. METHOD OF CHECKING TRAVERSES WHICH DO NOT FORM CLOSED FIGURES, — CHECKING BY ASTRONOMICAL METHODS 163
181. CHECKING BY CUT-OFF LINES 164
182. CHECKING BY ANGLES TO A DISTANT OBJECT 165
183. CHECKING BY CONNECTING WITH TRIANGULATION POINTS . . . 165

LOCATION OF BUILDINGS FROM TRANSIT LINE.

184. METHODS OF LOCATING BUILDINGS 166
185. GEOMETRIC PRINCIPLES 166
186. TIES, OFFSETS, SWING OFFSETS, AND RANGE LINES 166
187. GENERAL SUGGESTIONS 167
188. TYPICAL CASES 167
189. BUILDING NEAR TRANSIT LINE AND NEARLY PARALLEL TO IT . . 167
PLOTTING 168
190. BUILDING NEAR TRANSIT LINE, MAKING A SLIGHT ANGLE WITH IT . 168
PLOTTING 169
191. BUILDING LOCATED ENTIRELY BY DIRECT TIES 169
PLOTTING 170
192. BUILDING LOCATED AT A CONSIDERABLE SKEW TO THE TRANSIT LINE 170
PLOTTING 171
193. BUILDINGS AT A LONG DISTANCE FROM THE TRANSIT LINE . . . 171
PLOTTING 171
194. BUILDINGS LOCATED FROM OTHER BUILDINGS 172
195. BUILDINGS OF IRREGULAR SHAPE 173
196. LARGE CITY BUILDINGS 173
197. LOCATION OF BUILDINGS BY ANGLES AND DISTANCES 174
198. LOCATION OF BUILDINGS AND FENCES FROM TRANSIT LINE . . . 174

MISCELLANEOUS SURVEYING PROBLEMS.

199. RANDOM LINE 177
200. OBSTACLES ON LINE 178

Art.		Page
201.	Offsetting Transit Line	178
202.	Short Transit Sights	180
203.	Bisection Method	180
204.	Measuring around a Small Obstacle	181
205.	Equilateral Triangle Method	182
206.	Inaccessible Distances	182
207.	By Right Triangle Method	182
208.	Intersecting Transit Lines	183
209.	By Swing Offset Method	183
210.	By Tangent Offset Method	184
211.	By Oblique Triangle Method	185
212.	To Obtain the Distance between Two Inaccessible Points by Observation from Two Accessible Points	186
213.	To Obtain the Inaccessible Distance between Two Accessible Points by Observation on Two Inaccessible Points of Known Distance Apart	187

Chapter VII. — The Stadia Method.

214.	Stadia Method of Measuring Distances	188
215.	Instruments	189
216.	Stadia Rods	190
217.	Principle of the Stadia	191
218.	Stadia Constants	193
219.	Formulas for Inclined Sights	195
222.	Fieldwork	198
223.	Azimuth Angles	199
224.	Vertical Angles	200
225.	Distances	200
226.	Stadia Traverses	202
227.	Checks on the Traverse	202
228.	Stadia Notes	202
229.	Methods of Reducing the Notes	208
230.	Use of Stadia Tables	209
231.	Methods of Plotting Stadia Notes	210
	Problem	211

Chapter VIII. — Observations for Meridian and Latitude.

Observations for Meridian.

232.	To Establish a True Meridian Line by Observation on Polaris with the Transit	212
233.	Observation for Meridian on Polaris at Elongation	214
234.	Observation for Meridian on Polaris at Culmination	217
235.	To Find the Standard Time of Culmination and Elongation	218
236.	Meridian Observations on Polaris with the Compass	219
237.	Meridian Observation on Polaris at any Time with the Transit	220
238.	Solar Observations	222
239.	Observation for Meridian by Equal Altitudes of the Sun in the Forenoon and Afternoon	222
240.	Observation for Meridian by a Single Altitude of the Sun	225
241.	Observation for Meridian by Means of the Solar Attachment	229

OBSERVATIONS FOR LATITUDE.

ART. PAGE
242. By the Altitude of Polaris at Upper or Lower Culmination 230
243. By the Altitude of the Sun at Noon 230
Problems 231

CHAPTER IX. — LEVELING.

244. Definitions 232
245. Leveling to Establish Bench Marks 232
248. Double Rodded Lines 235
250. Bench Marks and Turning Points 236
251. Leveling for Profile 237
253. Cross-Sectioning 240
254. Use of the Tape Rod in Cross-Section Work 240
255. Cross-Sectioning for Earthwork 241
256. Road Cross-Sections 241
257. Setting Slope Stakes 242
258. Earthwork Notes for Road Cross-Sections 243
259. Cross-Sections for Borrow-Pits 244
260. Cross-Sections for Trench Excavation 244
261. Leveling to Establish a Grade Line 244
262. "Shooting in" a Grade Line 245
263. To Establish a Datum Plane by Means of Tidal Observations 245
264. The Staff Gauge 246
265. Leveling across a River 247
Problems 249

CHAPTER X. — CITY SURVEYING.

266. Instruments Used 251
267. Tapes and Tape Measurements 251
268. Transits and Levels 252
269. City Standard 253

CITY LAYOUTS.

271. Streets 254
272. Location of Streets 255
273. Size of Blocks and Lots 257
274. Width of Streets 257
275. Street Grades 259
276. The Datum Plane 261
277. Establishing Bench Marks 261

STAKING OUT CITY WORK.

278. Staking out a New District 262
279. Monuments 262
280. Setting Stone Bounds 264
281. Curved Layouts 266
282. Elements of a Circular Curve 267
283. Staking out Circular Curves 268
284. Deflection Angles 268
285. Keeping the Notes 271
286. When the Entire Curve Cannot be Laid Out from One End 272
287. First Method 272

Art.		Page
288.	Second Method	273
289.	Curved Street Corners	273
290.	One Street Line Straight, the Other Curved	273
291.	Both Street Lines Curved	274
292.	Intersection of Circular Arc and Straight Line	275
293.	Staking Out Street Grades	276
294.	Vertical Curves	277
295.	Cross-Section of Street	278
296.	Gutters at Same Elevation	279
297.	One Gutter Higher than the Other	280
299.	Irregular Shaped Blocks	281
300.	Staking Out City Lots	282
301.	Staking Out Curb Lines and Grades	283
302.	Staking Out Sewers	285
303.	Staking Out Street Railway Tracks	285
304.	Rerunning Street Lines and Grades	285
305.	Revising Street Lines	286
306.	Revising Street Grades	287
307.	Layout of Cemeteries	287
308.	Accident Plans	287
309.	Miscellaneous Surveying Problems	288
311.	Setting Batter-Boards for a Building	289
312.	City Plans and Records	291
	RECTANGULAR COÖRDINATE SYSTEM OF SURVEYING CITIES.	
313.	General Description	291
314.	Triangulation Scheme	292
315.	Measurement of Base-Line	297
316.	Measurement of Angles	297
317.	Adjustment of the Angles	298
318.	Azimuth	298
319.	Secondary and Tertiary Triangulation	299
320.	Traverses	299
321.	Method of Locating Property Lines and Buildings	299
	Chapter XI. — Topographical Surveying.	
323.	Triangulation for Control	300
324.	Location of Points from the Transit Line	301
325.	Contour Lines	301
326.	Characteristics of Contours	304
327.	Relation Between Contour Map and Profile	306
328.	Relation Between Contour Map and Side Elevation or Projection	307
329.	Drainage Areas	309
330.	Sketching Contours from Streams and Summits	309
331.	Sketching Contours from Known Elevations	312
332.	Mistakes in Sketching Contours	312
333.	Locating Contours	313
334.	Locating Contours by Cross-Sections	314
335.	Locating Contours by Profiles	314
336.	Locating Points on Contours	314
337.	Locating Contours by Means of the Hand Level	314
338.	Location of Streams and Shore Lines	316
339.	Contour Problems	316

ART. PAGE
340. INTERSECTION OF PLANE WITH SURFACE OF GROUND 316
341. INTERSECTION OF CURVED SURFACE WITH SURFACE OF GROUND 317
342. INTERSECTION OF SIDE SLOPES OF ROAD WITH SURFACE OF GROUND 319

CHAPTER XII. — MINE AND MOUNTAIN SURVEYING.

343. GENERAL REMARKS 321
344. DEFINITIONS OF MINING TERMS 321

MINING INSTRUMENTS.

345. MINING TRANSITS 323
346. ECCENTRIC TELESCOPES 324
347. CORRECTION FOR ECCENTRICITY 326
348. VERTICAL ANGLE CORRECTION FOR ECCENTRICITY OF TOP TELESCOPE 326
349. HORIZONTAL ANGLE CORRECTION FOR ECCENTRICITY OF SIDE TELESCOPE 327
350. ADJUSTMENT OF MINING TRANSITS 328
351. COMBINED SOLAR ATTACHMENT AND TOP TELESCOPE 329
352. FITTINGS OF MINING TRANSITS 329
353. COMPASSES USED IN MINES 330
354. OTHER INSTRUMENTS 331

UNDERGROUND SURVEYING.

355. TRANSFERRING A MERIDIAN INTO A MINE 332
356. TRANSFERRING A MERIDIAN DOWN SHAFT BY USE OF TRANSIT . 333
357. PLUMBING THE MERIDIAN DOWN A SHAFT 334
358. MEASUREMENTS OF DISTANCES DOWN VERTICAL SHAFT 337
359. TRANSFERRING A MERIDIAN INTO A MINE WHEN THERE ARE TWO SHAFTS 337
360. UNDERGROUND TRAVERSES 338
361. TRAVERSE STATIONS AND STATION MARKS 339
362. SETTING UP THE TRANSIT 341
363. TRAVERSING 342
367. TRAVERSE NOTES 345
368. STATION, COMPUTATION, AND COÖRDINATE BOOKS 351
372. MINE MAPS 354
373. MINE MODELS 357
374. LAYING OUT MINING WORK 357
375. UNDERGROUND SURVEYING PROBLEMS 357
376. TO FIND AN ORE SHOOT BY DRIVING A LEVEL 357
377. TO LAY OUT A CONNECTION IN A MINE 358
378. TO ESTABLISH A BOUNDARY LINE OF THE CLAIM UNDERGROUND 358
379. BOREHOLE SURVEYING 359
380. TUNNEL AND SUBWAY SURVEYS 360

SURFACE SURVEYING.

381. SURFACE SURVEYING IN RUGGED MOUNTAIN REGIONS 362
382. MINE BOUNDARIES — APPROPRIATIONS UNDER UNITED STATES LAWS 363
383. SURVEYING FOR PATENT 365
PROBLEMS 366

PART III.

COMPUTATIONS.

Chapter XIII. — General Principles — Miscellaneous Problems — Earthwork Computations.

Art.		Page
384.	General Remarks	371
389.	Logarithmic or Natural Functions	375
390.	Short Cuts	376
392.	Arrangement of Computations	378
393.	Checks	378
394.	Slide Rule	378
395.	Thacher Slide Rule	381
396.	Reducing the Field Notes for Computations	381
397.	Curved Boundary by Offsets	381
398.	Trapezoidal Rule	382
399.	Simpson's One-Third Rule	382
400.	Straightening Crooked Boundary Lines	384
401.	Area by Triangles	384
402.	Area of a Quadrilateral by Triangles	385
403.	Area of a Curved Corner Lot	386
404.	Rough Checks on Areas	387
405.	Planimeter	387
406.	Deflection Angles and Chords for a Circular Curve	389
407.	Computations of Observations	390

COMPUTATION OF VOLUME.

408.	Borrow-Pits	390
409.	Volume of Prismoid	392
410.	End Area Formula	392
411.	Prismoidal Formula	392
413.	Estimates for Grading	393
417.	Rough Estimates	397
	Problems	398

Chapter XIV. — Area by Double Meridian Distances — Coördinates.

418.	Computation of Area	400
419.	Area by Double Meridian Distance Method	400
421.	Computation of Area of Compass Survey	404
422.	Balancing a Chain and Compass Traverse	406
425.	Double Parallel Distance	407
426.	Error of Closure	408
427.	Computation of Area of a Transit and Tape Survey	408
430.	Balancing a Transit and Tape Survey	412
431.	Fractional Areas	413
432.	Supplying Missing Data	414
436.	Detecting Mistakes	416
437.	The Subdivision of Land	416

ART. PAGE
438. To Cut Off from a Traverse a Given Area by a Straight Line Starting from a Known Point on the Traverse 417
439. To Cut Off from a Traverse a Given Area by a Line Running in a Given Direction 417
440. To Find the Area Cut Off from a Traverse by a Line Running in a Given Direction from a Given Point in the Traverse 418

CALCULATIONS RELATING TO TRAVERSES WHICH DO NOT CLOSE.

441. To Calculate the Total Distance Between End Points . . 419
442. Cut-Off Lines 419
443. Computation of Azimuths when Checking Angles to a Distant Object 420
444. Calculation of Triangulation 420
445. Coördinates 421
446. To Determine the Area of a Field by Rectangular Coördinates 422
Problems 424

PART IV.

PLOTTING.

Chapter XV. — Drafting Instruments and Material.

ENGINEERING DRAFTING INSTRUMENTS.

450. Straight Edge 429
451. Engineer's Scale 430
452. Protractor 430
453. Semicircular Protractor 430
454. Full-Circle Protractor 432
456. Three-Armed Protractor 432
458. Pantograph 433
459. Parallel Ruler 434
460. Beam Compass 434
461. Contour Pen 434
462. Proportional Dividers 435
463–6. Railroad Curves, French Curves, Flexible Curves, and Spline 435

DRAWING PAPERS.

468. Drawing Paper for Plans 436
469. Tracing Paper and Tracing Cloth 437
471. Cross-Section and Profile Papers 438
473. Process Papers, — Blue-Prints 439
476. Vandyke Solar Paper 441
477. Electrical Printing Frames 443
478. Inks and Water-Colors 443

Chapter XVI. — Methods of Plotting.

Art.		Page
479.	Laying Out a Plan	445
480.	Scale	445
	Methods of plotting traverses.	
481.	Plotting by Protractor and Scale	446
482.	Checks	446
483.	Protractor and T-Square	448
484.	Plotting by Rectangular Coördinates	449
489.	Checks	453
490.	Plotting by Tangents	453
491.	Checks	455
492.	Plotting by Chords	456
493.	Use of the Sine	457
494.	Checks	457
	Method of plotting details.	
495.	Buildings, Fences, Streams, Etc.	458
496.	Contours	458
497.	Cross-Sections	459
498.	Profiles	459
502.	Checks	461
	Problems	461

Chapter XVII. — Finishing and Filing Drawings.

503.	What Should Appear on a Drawing	460
504.	Traverse Lines	463
505.	Physical Features	464
506.	Topographic Conventional Signs	464
508.	Lettering	470
509.	Titles	471
510.	Notes	474
511.	Border Lines	475
512.	Meridians	475
513.	Scales	476
514.	Shrinkage of Drawing Papers	476
515.	Maps of Large Extent	477
516.	Inking in a Profile	478
517.	Cleaning Drawings	478
518.	Filing Drawings	479
519.	Indexing Drawings	480
520.	Filing Note-Books	480
521.	Indexing Notes	481
522.	Other Records	481

TABLES.

I.	Logarithms of Numbers	484
II.	Logarithmic Sines and Cosines	503
III.	Logarithmic Tangents and Cotangents	518

Art.		Page
IV.	Natural Sines and Cosines	533
V.	Natural Tangents and Cotangents	542
VI.	Natural Versed Sines	554
VII.	Lengths of Circular Arcs: Radius = 1	556
VIII.	Stadia Reductions	557
IX.	Mean Refractions in Declination	561
X.	Trigonometric and Miscellaneous Formulas	565
XI.	Circular Curve Formulas	567
XII.	Geometric Formulas	567
XIII.	Linear Measure	568
XIV.	Square Measure	568
XV.	Linear Measure — Metric System	568
XVI.	Square Measure — Metric System	568
XVII.	Constants	569
	Greek Alphabet	570

APPENDICES.

Appendix A	— The Planimeter	573
Appendix B	— Mounting Paper for Drawings	581

THE PRINCIPLES AND PRACTICE OF SURVEYING.

PART I.

USE, ADJUSTMENT, AND CARE OF INSTRUMENTS.

CHAPTER I.

GENERAL DEFINITIONS. — MEASUREMENT OF LINES.

1. DEFINITION. — Surveying is the art of measuring and locating lines and angles on the surface of the earth. When the survey is of such limited extent that the effect of the earth's curvature may be safely neglected it is called *Plane Surveying*. When the survey is so large that the effect of curvature of the earth must be taken into account as, for instance, in the survey of a state or a country, it is called *Geodetic Surveying*.

2. Purposes of Surveys. — Surveys are made for a variety of purposes such as the determination of areas, the fixing of boundary lines, and the plotting of maps. Furthermore, engineering constructions, such as waterworks, railroads, mines, bridges, and buildings, all require surveys.

3. Horizontal Lines. — In surveying, all measurements of lengths are **horizontal** or else are subsequently reduced to horizontal distances. As a matter of convenience, measurements are sometimes taken on slopes, but the horizontal projection is afterward computed. The distance between two points as shown on a map then is always this horizontal projection.

INSTRUMENTS FOR MEASURING LINES.

4. THE CHAIN. — Formerly two kinds of chain (Fig. 1) were used by surveyors, but these have been almost wholly superseded by steel tapes. The *Surveyor's (or Gunter's) Chain* is 66 feet long and its use was confined chiefly to land surveying on account of its simple relation to the acre and to the mile.

1 Gunter's Chain = 4 Rods = 100 Links.
1 Mile = 80 Chains.
1 Acre = 10 Square Chains.

Evidently each link is $\frac{66}{100}$ of a foot (or 7.92 inches) long. The inch, however, is never used in surveying fieldwork.

The *Engineer's Chain* is 100 feet long and is divided into one hundred links of one foot each. Each end link is provided with a handle, the outside of which is the zero point, or end, of the chain. In these chains, every tenth link counting from either end is marked by a brass tag having one, two, three or four points corresponding to the number of tens which it marks. The middle of the chain is marked by a round tag. In the engineer's chain then the 10-ft. and 90-ft. points, the 20-ft. and 80-ft. points, etc., are marked alike; hence it is necessary to



ENGINEER'S CHAIN. GUNTER'S HALF-CHAIN.

FIG. 1.

observe on which side of the 50-ft. point a measurement falls in order to read the distance correctly. Distances measured with the surveyor's chain are recorded as *chains and links* (or in *chains and decimals*); while those measured with the engineer's chain are recorded as *feet and decimals*.

On account of the large number of wearing surfaces and the consequent lengthening with use, the chain should be frequently compared with a standard of length (Art. 269, p. 253). It may be adjusted by means of a nut on the handle, which allows the

total length of the chain to be altered by lengthening or shortening the end link, although intermediate foot-marks may be in error.

5. Metric Chain. — The *Metric Chain* is usually 20 meters long and is divided into one hundred links, each 2 decimeters long.

6. The Tape. — There are three kinds of tape in common use, — *cloth*, *metallic*, and *steel*. Cloth tapes stretch so easily that they are of little use in surveying. The so-called metallic tapes are cloth tapes having very fine brass wires woven into them to prevent stretching. They are usually graduated into feet, tenths, and half-tenths and are made in lengths of 25 ft., 50 ft., and 100 ft. When precise results are required a steel tape should be used. While a steel tape varies a slight amount in length with the temperature and with the pull, it is possible to determine the amount of these variations and hence to arrive at accurate results.

7. Steel Tapes. — Steel tapes are almost universally used for accurate measurements of length. They may be obtained in lengths up to 1000 feet, but the most common are the 50-ft., 100-ft., and 300-ft. lengths. While the shorter tapes are usually made of thin steel ribbon, the longer ones are of sufficiently large cross-section to withstand rough usage. These heavy tapes are generally marked every 10 feet, the 10-ft. length at one end of the tape being marked at every foot, and the last foot divided into tenths. Some of these tapes are marked at every foot throughout their length. The light tapes are divided throughout their length into feet, tenths, and hundredths, each line being etched on the steel. The numbering is continuous from the zero point to the end. (Fig 2.) These tapes are more convenient to handle than the heavy ones, but are not suited to very rough work as they are easily kinked and broken. They can be readily mended, however, by riveting to the back of the tape a piece of tape of the same width.

Since the surveyor's measurements are usually in feet and decimals, they are not in convenient form for use by mechanics in construction work. It is therefore often necessary to convert decimals of a foot into inches and *vice versa*. The following table shows the general relation between these two and is sufficiently close for most work.

TABLE I.

DECIMALS OF FOOT IN INCHES.

DECIMAL OF FOOT.		INCHES.
.01	=	$\frac{1}{8}$ −
.08	=	1 −
.17	=	2 +
.25	=	3 (exact)
.50	=	6 (exact)
.75	=	9 (exact)

Decimals of a foot can easily be converted mentally into inches by use of the equivalents in the above table, for example, 0.22 ft. = .25 − .03 = $3'' - \frac{3}{8}'' = 2\frac{5}{8}''$.



FIG. 2. STEEL TAPES.
(Upper tape is light weight, remaining six tapes are heavy weight.)

In city surveys, and in fact in all surveys where great accuracy is demanded, the steel tape is indispensable. In surveys of farms or timber land and in preliminary railroad surveys the chain

has been replaced by the long heavy tape which, while adapted to rough work, will give accurate results.

8. THE STADIA. — Where it is desired to measure distances with great rapidity but not with very great accuracy the *stadia* method is very generally used. The distance is obtained by simply sighting with a transit instrument at a graduated rod held at the other end of the line and noting the space on the rod included between two special cross-hairs set in the instrument at a known distance apart. From this observed interval on the rod the distance from the transit to the rod can be easily calculated. (See Chap. VII, Vol. I, and Chap. IV, Vol. II.)

9. OTHER INSTRUMENTS. — *Wooden Rods* are used in certain kinds of work for making short measurements, usually less than 15 ft.

The *Two-Foot Rule* divided into tenths and hundredths of a foot is very convenient for short measurements.

The *Odometer* is an instrument which may be attached to a carriage in such a manner as to register the number of revolutions of one of the wheels. The circumference of the wheel being known the approximate distance traversed is easily determined.

The *Pedometer* is a small instrument, about the size of a watch, which records the distance travelled by the person carrying the instrument. The mechanism requires that it should be carried vertically in the pocket. The instrument may be adjusted for length of pace.

MEASUREMENT OF DISTANCES.

10. MEASUREMENT ON LEVEL GROUND WITH A TAPE.— One man, the head-tapeman, takes the forward end of the tape and ten marking pins and goes ahead along the line to be measured, while a second man, the rear-tapeman, takes his position at the stake marking the beginning of the line. The rear-tapeman, with his eye over the point, places the head-tapeman in line with some object, such as a lining pole, which marks the other end of the line to be measured. When the head-tapeman is nearly in line he takes a pin and, standing to one side of the line, holds it upright on the ground a foot or so short of the end of the tape

and the rear-tapeman motions him to the right or left until his pin is on the line. When the head-tapeman has the pin in line he stretches the tape taut, seeing that there are no kinks and that no obstructions cause bends in the tape. The rear-tapeman at the same time holds the zero-point of the tape at his pin and when he calls out, "All right here," the head-tapeman stretching the tape past his line pin, removes this line pin, places it at the end graduation of the tape, and presses it vertically into the ground. When the tapemen are experienced the pin may be set for both line and distance at the same time. When the pin is in place the head-tapeman calls, "All right," the rear-tapeman takes the pin left at his end of the line and they proceed to the next tape-length. The pin that the rear-tapeman has is a record of the first tape-length. Just before reaching the second pin the rear-tapeman calls out, "Tape," to give the head-tapeman warning that he has nearly reached a tape-length. The process of lining in the head-tapeman and measuring a tape-length is then repeated. When the third pin is stuck in the ground the rear-tapeman pulls out the second pin; in this way the number of pins the rear-tapeman holds is a record of the number of tape-lengths measured. There is always one pin in the ground which marks the distance but is not counted. When 10 tape-lengths have been measured the head-tapeman will be out of pins and calls to the rear-tapeman, who brings forward 10 pins. The pins are then counted by **both men.** Every time 10 tape-lengths are measured a record of it is made in note-books kept by **both men** and the process is repeated until the end of the line is reached. The fractional part of a tape-length at the end of the line is read by the head-tapeman.

It can be shown (Art. 21) that if a pin is placed a few tenths of a foot to the right or left of the line at the end of a tape-length the resulting error in the **distance** is very small and consequently "lining in" by eye is accurate enough, so far as the **distance** is concerned. But when any side measurements or angles are to be taken the points should be set accurately on line by means of a transit instrument. It is obvious that any error in lining in the pin produces a greater error in a short measurement than in a full tape-length.

Pacing furnishes a Convenient Means of obtaining Approximate Distances. — In measuring a long line much time can be saved if the head-tapeman will **pace** the tape-length and then place himself very nearly in the line by means of objects which he knows to be on line as, for example, the instrument, a pole, or the last pin. While no great accuracy is to be expected from pacing, its importance to the surveyor should not be underestimated. It is often necessary to know a distance roughly and to obtain it quickly. Furthermore in all surveys the accuracy should be frequently tested by the application of rough check measurements, and these are readily determined by pacing. If much pacing is to be done it will be found more accurate and certainly less tiresome to assume one's natural gait, determining by actual trial the number of steps per 100 feet, and not attempt to take steps exactly three feet long.

In precise tape measurements it is often necessary to employ more exact methods of marking the intermediate points than by the use of pins. In some cases stakes are driven into the ground and tacks or pencil marks used to mark the points. A small nail pressed into the ground so that the center of the head is in the proper position makes a good temporary mark, but of course is easily lost. In measuring on the surfaces of hard roads, spikes are used for permanent marks.

Measurements of important lines which are not checked by some geometric test should be checked by repeating the measurement, and in such a way as not to use the same intermediate points taken in the first measurement.*

Where distances are to be measured continuously from the initial point of a line without regard to angles in the line, as in railroad surveys, it is customary to establish the 100-ft. points. Mistakes will often be avoided by setting the 100-ft. points as

* In measuring with the tape some prefer to make a series of measurements between points set in the ground a little less than 100 feet apart, summing up the partial measurements when the end of the line is reached. This guards against the mistake of omitting a whole tape-length. Another advantage is that it is easier to read the distance to a fixed point than to set a point accurately at the end of the tape; this is especially true in measurements where plumbing is necessary. This method takes less time than the usual method, but it is not applicable when it is necessary to mark the 100-ft. points on the line.

follows: — suppose an angle to occur at 870.1 ft. from the point of beginning; this would be called "Station 8 + 70.1." To set "Station 9" the 70.1-ft. point of the tape should be held on stake 8 + 70.1 and the stake at station 9 placed at the 100-ft. point of the tape. This is preferable to making a measurement of 29.9 ft. from the zero end of the tape.

11. Measurement with the Chain. — In measuring with the chain the process is similar to that described for the tape, except that it will always be sufficiently exact to use marking pins. In measuring the fraction of a chain the head-chainman holds his end of the chain at the required point and the fractional distance is read by the rear-chainman at the last pin. In some kinds of work, however, it is more convenient to draw the chain ahead past the end point and, while the rear-chainman holds his end of the chain at the last pin, the head-chainman reads the fractional measurement. The links are read by counting from the proper tag and the tenths of a link are estimated. Great care should be taken to count the tags from the proper end of the chain since the 10-ft. points each side of the center, as has been explained, are marked alike.

When a chain is new it is very nearly the standard length. During its first use the links become bent and the chain thus shortened. But there are nearly six hundred wearing surfaces and before long the amount of wear on each surface lengthens the chain an appreciable amount. It is very common to find chains which, after considerable use, have lengthened 0.3 ft. or more.

12. Horizontal Measurement on Sloping Ground with a Tape. — The tape must be held horizontal and the distance transferred to the ground by means of plumb-lines. This is difficult to do accurately and is a fruitful source of error. Beginners usually hold the downhill end of the tape too low. Horizontal lines on buildings are very useful in judging when the tape is level. Since it is supported only at the ends its weight will cause it to sag so that the distance between the ends tends to be less than a tape-length. The pull exerted on the tape should be such that it will stretch enough to balance as nearly as possible the shortening due to sag.

Whenever a slope is so steep that the tapeman on the lower

end cannot plumb high enough to keep the tape horizontal the measurement must be made in sections, 50-ft., 20-ft., or even 10-ft. lengths being used. Mistakes will be avoided if the rear-tapeman comes forward at each measurement and holds the same fractional point on the tape that the head-tapeman held, and so on until a whole tape-length has been measured; using this method it will be unnecessary to count the fractional distances, but care should be taken that these pins which marked the intermediate points are returned to the head-tapeman so that the count of the tape-lengths will not be lost. Measuring downhill will, in general, give more accurate results than measuring uphill, because in the former case the rear end is held firmly at a point on the ground and the head-tapeman can pull steadily on the tape and transfer the distance to the ground by means of the plumb-line; in the latter case the rear-tapeman is plumbing his end of the tape over the point and it is difficult for him to hold it steady while the head-tapeman is pulling on the tape.

13. **Slope Measurements with a Tape.** — Owing to the difficulties of obtaining accurate horizontal measurements on sloping ground by the use of plumb-lines a more accurate and more common method is to measure directly the inclined distance between points on the line which are less than a tape-length apart and then compute the horizontal distance between these points from additional data obtained in the field. There are two general methods of doing this, one requiring the direct determination of the difference in elevation of the ends of the tape, the other requiring the measurement of the (vertical) angle of slope of the tape.

If the difference in elevation of the ends of the tape is determined with the level the horizontal distance may be found by computing the long leg of a right triangle in which the hypotenuse is the measured distance and the short side is the difference in elevation. If the latter is small, compared with the distance, as is usually the case, the calculation may readily be made by the method of Art. 21.

If the vertical angle is measured with the transit the horizontal side of the triangle is best found by first calculating the difference in length between the measured slope and the horizon-

tal distance. (Fig. 2a.) This equals the slope distance (measured from one end of the horizontal axis directly to the station) times the natural versed sine of the vertical angle. This result may be obtained in most cases with sufficient precision, by use of the slide rule. This difference subtracted from the slope distance gives the required horizontal distance.



FIG. 2a

14. COMMON SOURCES OF ERROR IN MEASUREMENT OF LINES. —

1. Not pulling tape taut.
2. Careless plumbing.
3. Incorrect alignment.
4. Effect of wind.
5. Variation in temperature.
6. Erroneous length of tape.

15. COMMON MISTAKES IN READING AND RECORDING MEASUREMENTS. —

1. Failure to observe the position of the zero point of the tape. (In some tapes it is not at the end of the ring.)
2. Omitting a whole chain- or tape-length.
3. Reading from wrong end of chain, as 40 ft. for 60 ft., or in the wrong direction from a tag, as 47 ft. for 53 ft.
4. Transposing figures, e.g., 46.24 for 46.42 (mental); or reading tape upside down, e.g., 6 for 9, or 86 for 98.
5. Reading wrong foot-mark, as 48.92 for 47.92.

16. AVOIDING MISTAKES. — Mistakes in counting the tape-lengths may be avoided if more than one person keeps the tally. Mistakes of reading the wrong foot-mark may be avoided by noting not only the foot-mark preceding, but also the next fol-

lowing foot-mark, as, "46.84 . . . 47 feet," and also by holding the tape so that the numbers are right side up when being read.

In calling off distances to the note keeper, the tapeman should be systematic and always call them distinctly and in such terms that they cannot be mistaken. As an instance of how mistakes of this kind occur, suppose a tapeman calls, "Forty nine, three"; it can easily be mistaken for "Forty-nine feet." The note keeper should repeat the distances aloud so that the tapeman may know that they were correctly understood. It is frequently useful in doubtful cases for the note keeper to use different words in answering, which will remove possible ambiguity. For example, if the tapeman calls, "Thirty-six, five," the note keeper might answer, "Thirty-six and a half." If the tapeman had meant 36.05 the mistake would be noticed. The tapeman should have called in such a case, "Thirty-six naught five." The following is a set of readings which will be easily misinterpreted unless extreme care is taken in calling them off.

40.7 — "Forty and seven."
47.0 — "Forty seven naught."
40.07 — "Forty, — naught seven."

All of these might be carelessly called off, "Forty-seven."

In all cases the tapemen should make **mental estimates** of the distances when measuring, in order to avoid large and absurd mistakes.

17. Accuracy Required. — If, in a survey, it is allowable to make an error of one foot in every five hundred feet the chain is sufficiently accurate for the work. To reach an accuracy of 1 in 1000 or greater with a chain it is necessary to give careful attention to the **pull,** the **plumbing,** and the deviation from the **standard length.** With the steel tape an accuracy of 1 in 5000 can be obtained without difficulty if ordinary care is used in plumbing and aligning, and if an allowance is made for any considerable error in the length of the tape. For accuracy greater than about 1 in 10,000 it is necessary to know definitely the temperature and the tension at which the tape is of standard length and to make allowance for any considerable variation from these values. While the actual deviation from the U. S. Standard

under certain conditions may be 1 in 10,000, still a series of measurements of a line all taken under similar conditions may check themselves with far greater precision.

18. AMOUNT OF DIFFERENT ERRORS. — The surveyor should have a clear idea of the effects of the different errors on his results. For very precise work they should be accurately determined, but for ordinary work it is sufficient to know approximately the amount of each of them. A general idea of the effect of these errors will be shown by the following.

19. Pull. — At the tension ordinarily used the light steel tape will stretch between 0.01 and 0.02 ft. in 100 ft. if the pull is increased 10 pounds. Since the amount of stretch is different, however, for different tapes it is advisable to investigate it by fastening the ring of the tape to a nail in the floor and, with the tape lying flat, applying different tensions. The tensions should be measured with a spring balance and the variations in length under these different tensions may be determined from the tape readings of some reference point marked on the floor near the 100-ft. end of the tape. In this manner the length of any particular tape for any given tension may be found.

20. Temperature. — The average coefficient of expansion for a steel tape is nearly 0.0000063 for 1° F. Hence a change of temperature of 15° produces nearly 0.01 ft. change in the length of the tape. Tapes are usually manufactured to be of standard length at 62° F. and under a tension of 12 lbs. while supported throughout their length. When great accuracy is demanded the temperature of the tape must be determined and the corresponding temperature correction applied to the measurements. Small tape thermometers are made especially for this purpose. The thermometer bulb should be in contact with the tape so as to obtain as nearly as possible the temperature of the steel. Even under these conditions it is difficult to determine the true temperature if the tape is exposed to sunlight.

21. Alignment. — The error in length due to poor alignment can be calculated from the approximate formula

$$c - a = \frac{h^2}{2c} \quad *$$

where h is the distance of the end of the tape from the line, c is the length of the tape, and a is the distance along the straight line. For example, if one end of a 100-ft. tape is held 1 ft. to one side of the line the error produced in this tape-length will be $\frac{1^2}{2 \times 100} = 0.005$ ft. (about $\frac{1}{16}$ inch). The correction to be applied to the distance when the two ends of the tape are not at the same level, as when making slope measurements, is computed in the same way.

22. Sag. — If a tape is suspended only at the ends it will hang in a curve which is known as the "catenary." On account of this curvature the distance between the end points is evidently less than the length of the tape. The amount of this shortening, called the *effect of sag*, depends upon the weight of the tape, the distance between the points of suspension, and the pull exerted at the ends of the tape. With a 12-lb. pull on an ordinary 100-ft. steel tape supported at the ends the effect of sag is from .01 ft. to .02 ft.

The amount of shortening due to sag may be computed by the formula in Art. 30, Vol. II. The most practical way to eliminate the effect of sag, however, is to determine by actual test the length between the end marks of the suspended tape as fol-

---

* In the right triangle,

$$c^2 - a^2 = h^2,$$

$$(c + a)(c - a) = h^2,$$

assuming $c = a$ and applying it to the first parenthesis only,

$$2c(c - a) = h^2 \text{ (approximately)}$$

$$c - a = \frac{h^2}{2c} \text{ (approximately)}$$

Similarly $$c - a = \frac{h^2}{2a} \text{ (approximately)}$$



It is evident that the smaller h is in comparison with the other two sides the more exact will be the results obtained by this formula. This formula is correct to the nearest $\frac{1}{100}$ ft. even when $h = 14$ ft. and $a = 100$ ft., or when $h = 30$ ft. and $a = 300$ ft.

lows: First, while the tape is supported its whole length mark its end points while a pull of 12 pounds is exerted. Then establish two points, by means of the transit or a plumb-line, at the same distance apart, but in such positions that the tape may be tested while supported at the ends only. Then determine the pull necessary to bring the end marks of the suspended tape to coincide with these reference marks. If this tension is always applied then the two ends of the suspended tape will be the same distance apart as the ends of the supported tape were under a 12-pound pull. If the supported tape is not of standard length when a 12-pound pull is used this error should be allowed for in all measurements. Or, if preferred, the reference marks just mentioned may be placed exactly 100 feet apart and the amount of pull required to make the suspended tape correct may be determined.

23. ACCURACY OF MEASUREMENTS. — In surveying we are dealing entirely with measurements. Since absolute accuracy can never be attained, we are forced to make a careful study of the **errors** of measurement. Extremely accurate measurements are expensive, and the cost of making the survey usually limits its accuracy. On the other hand, if a given degree of accuracy is required, the surveyor must endeavor to do the work at a minimum cost. In most surveys certain measurements are far more important than others and should therefore be taken with more care than the relatively unimportant measurements.

The surveyor should distinguish carefully between errors which are of such a nature that they tend to balance each other and those which continually accumulate. The latter are by far the more serious. Suppose that a line 5000 ft. long is measured with a steel tape which is 0.01 ft. too long and that the error in measuring a tape-length is, say, 0.02 ft., which may of course be a + or a − error. There will then be 50 tape-lengths in the 5000-ft. line. A study of the laws governing the distribution of accidental errors (Method of Least Squares) shows that in such a case as this the number of errors that will probably remain uncompensated is the **square root of the total number of opportunities for error,** i.e., in the long run this would be true. Hence the total number of such uncompensated errors in the line is 7;

and $7 \times 0.02 = 0.14$ ft., which is the total error due to inaccuracy in marking the tape-lengths on the ground. Since the error due to erroneous length of tape increases directly as the number of measurements, and since these errors are not compensating, the total error in the line due to the fact that the tape is 0.01 ft. too long is $50 \times 0.01 = 0.50$ ft. The small (0.01) **accumulative error** is therefore seen to have far greater effect than the larger (0.02) **compensating error.**

PROBLEMS.

1. A distance is measured with an engineer's chain and found to be 796.4 ft. The chain when compared with a standard is found to be 0.27 ft. too long. What is the actual length of the line?

2. A metallic tape which was originally 50 ft. is found to be 50.14 ft. long. A house 26 ft. $\times$ 30 ft. is to be laid out. What measurements must be made, using this tape, in order that the house shall have the desired dimensions?

3. A steel tape is known to be 100.000 ft. long at 62° F. with a pull of 12 lbs. and supported its entire length. Its coefficient of expansion is 0.0000063 for 1° F. A line was measured and found to be 142.67 ft. when the temperature was 8° below zero. What is the true length of the line?

4. In chaining down a hill with a surveyor's chain the head-chainman held his end of the chain 1.5 ft. too low. What error per chain-length would this produce?

5. In measuring a line with a 100-ft. tape the forward end is held 3 ft. to the side of the line. What is the error in one tape-length?

6. A certain 100-ft. steel tape was tested by the Bureau of Standards and its length given as 100.015 ft. at 62° F. when supported throughout its length and a 10 lb. tension applied. The tape was afterward tested with a 10 and then a 20 lb. pull and found to stretch .016 ft. (or .0016 per lb.). To obtain the length when supported only at the ends a 12 lb. pull was used and the full length between end graduations was marked off on tripods, the tape being supported throughout its length. The intermediate supports were then removed. The tape was found to sag 0.77 ft. and was .017 shorter than when supported full length, the tension remaining at 12 lbs. Compute the true length of the tape for 12 lb. pull, 62° F. supported at ends only.

7. A distance measured with a steel tape is recorded as 696.41 ft. The tape is known to be 49.985 ft. long. What is the correct length of the line?

8. Two measurements of a line were made with the same tape on different days. The first length was 510.02 ft., the temperature being 65° F. The second length was 510.06, the temperature being 50° F. What are the results of the two measurements? The tape is standard at 60°; coefficient = .0000065.

9. A distance is measured on slope with a 300-ft. tape and found to be 299.79 ft. If the difference of level of the ends of the tape is 15.1 ft. what is the horizontal distance?

10. If the slope distance is 201.61 ft. and the vertical angle is 4° 21′ what is the horizontal distance?

CHAPTER II.

MEASUREMENT OF DIRECTION.

24. THE SURVEYOR'S COMPASS. — The surveyor's compass (Fig. 3) is an instrument for determining the direction of a line with reference to the direction of a magnetic needle. The needle is balanced at its center on a *pivot* so that it swings freely in a horizontal plane. The pivot is at the center of a horizontal circle which is graduated to degrees and half-degrees, and numbered from two opposite zero points each way to 90°. The zero points are marked with the letters N and S, and the 90° points are marked E and W. The circle is covered with a glass plate to protect the needle and the graduations, the part enclosed being known as the *compass-box*. A screw is provided for raising the needle from the pivot by means of a lever. The needle should always be raised when the compass is lifted or carried, to prevent dulling the pivot-point; a dull pivot-point is a fruitful source of error. Both the circle and the pivot are secured to a brass frame, on which are two vertical sights so placed that the plane through them also passes through the two zero points of the circle. This frame rests on a tripod and is fastened to it by means of a ball-and-socket joint. On the frame are two spirit levels at right angles to each other, which afford a means of leveling the instrument. This ball-and-socket joint is connected with the frame by means of a spindle which allows the compass-head to be revolved in a horizontal plane, and to be clamped in any position.

The magnetic needle possesses the property of pointing in a fixed direction, namely, the *Magnetic Meridian*. The horizontal angle between the direction of this meridian and of any other line may be determined by means of the graduated circle, and this angle is called the *Magnetic Bearing* of the line, or simply its *Bearing*. By means of two such bearings the angle between two lines may be obtained. Bearings are reckoned from 0° to 90°,

the 0° being either at the N or the S point and the 90° either at the E or the W point. The quadrant in which a bearing falls is designated by the letters N.E., S.E., S.W., or N.W. For example, if a line makes an angle of 20° with the meridian and is in the southeast quadrant its bearing is written S 20° E. Sometimes the bearing is reckoned in a similar manner from



FIG. 3. SURVEYOR'S COMPASS.

the geographical meridian, when it is called the *true bearing*. In general this will not be the same as the magnetic bearing. True bearings are often called *azimuths*, and are commonly reckoned from the **south** point right-handed (clockwise) to 360°; i.e., a line running due West has an azimuth of 90°, a line due North an azimuth of 180°. Sometimes, however, the azimuth

is reckoned from the north as in the case of the azimuth of the Pole-Star (Art. 232, p. 212).

25. THE POCKET COMPASS. — The *pocket compass* is a small hand instrument for obtaining roughly the bearing of a line. There are two kinds, the *plain* and the *prismatic*. The former is much like the surveyor's compass, except that it has no sights. In the prismatic compass the graduations, instead of being on the compass-box, are on a card which is fastened to the needle (like a mariner's compass) and which moves with it. This compass is provided with two short sights and the bearing can be read, by means of a prism, at the same instant that the compass is sighted along the line.

26. METHOD OF TAKING A MAGNETIC BEARING. — The surveyor's compass is set up (and leveled) at some point on the line whose bearing is desired. The needle is let down on the pivot ; and the compass is turned so that the sights point along the line. While looking through the two sights the sur-



FIG. 4. DIAGRAM ILLUSTRATING READING OF BEARINGS.

veyor turns the compass-box so that they point exactly at a lining pole or other object marking a point on the line. The glass should be tapped lightly over the end of the needle to be sure that the latter is free to move. If it appears to cling to the glass this may be due to the glass being electrified, which condition can be removed at once by placing the moistened finger on the glass. The position of the end of the needle is then read on the circle and recorded. Bearings are usually read to the nearest quarter of a degree.

Since the needle stands still and the box turns under it, the letters E and W on the box are reversed from their natural position so that the reading of the needle will not only give the

angle but also the proper quadrant. Reference to Fig. 4 will show the following rule to be correct: — **When the north point of the compass-box is toward the point whose bearing is desired, read the north end of the needle.** When the south point of the box is toward the point, read the south end of the needle. If a bearing of the line is taken looking in the opposite direction it is called the *reverse bearing*.

Since iron or steel near the instrument affects the position of the needle, great care should be taken that the chain, axe, or marking pins are not left near the compass. Small pieces of iron on the person, such as keys, iron buttons, or the iron wire in a stiff hat, also produce a noticeable effect on the needle. Electric currents are a great source of disturbance to the needle and in cities, where electricity is so common, the compass is practically useless.

In reading the compass-needle, the surveyor should take care to read the farther end of the needle, always looking along the needle, not across it. By looking at the needle sidewise it is possible to make it appear to coincide with a graduation which is really at one side of it. This error is called *parallax*.

27. **THE EARTH'S MAGNETISM. — Dip of the Needle.** — The earth is a great magnet. On account of its magnetic influence a permanent magnet, such as a compass-needle, when freely suspended will take a definite direction depending upon the direction of the lines of magnetic force at any given place and time. If the needle is perfectly balanced before it is magnetized it will, after being magnetized, dip toward the pole. In the northern hemisphere the end of the needle toward the north pole points downward, the inclination to the horizon being slight in low latitudes and great near the polar region. In order to counteract this dipping a small weight, usually a fine brass wire, is placed on the higher end of the needle at such a point that the needle assumes a horizontal position.

28. **DECLINATION OF THE NEEDLE.** — The direction which the needle assumes after the counterweight is in position is called the magnetic meridian and rarely coincides with the true meridian. The angle which the needle makes with the true meridian is called the *declination of the needle*. When the north

end of the needle points east of the true, or geographical, north the declination is called *east;* when the north end of the needle points west of true north it has a *west* declination.

29. Variations in Declination. — The needle does not constantly point in the same direction. Changes in the value of the declination are called *variations of the declination.** The principal variations are known as the *Secular, Daily, Annual,* and *Irregular.*

The *Secular Variation* is a long, extremely slow swing. It is probably periodic in character but its period covers so many years that the nature of it is not thoroughly understood. The following table shows the amount of secular variation as observed in Massachusetts during two centuries.

TABLE 2.

OBSERVED DECLINATIONS OF NEEDLE IN EASTERN MASSACHUSETTS.†

YEAR.	DECLINATION.
1700	10° 31′ W.
1750	7° 13′ W.
1800	6° 28′ W.
1850	9° 10′ W.
1900	12° 00′ W.

In the United States all declinations are now increasing (except those in the region just west of the agonic line) at an average rate of about 3 minutes per year.

The *Daily Variation* consists of a swing which averages about 7 minutes of arc from its extreme easterly position at about 8 A.M. to its most westerly position at about 1.30 P.M. It is in its mean position at about 10 A.M. and at 5 or 6 P.M. The amount of daily variation is from 3 to 12 minutes according to the season and the locality.

The *Annual Variation* is a periodic variation so small (about one minute a year) that it need not be considered in surveying work.

---

* The angle called *Declination* by surveyors is usually called *Variation* by navigators.

† See p. 107 of U. S. Coast and Geodetic Survey special publication entitled "U. S. Magnetic Declination Tables and Isogonic Chart for 1902, and Principal Facts Relating to the Earth's Magnetism," by L. A. Bauer, issued in 1902.



FIG. 5. ISOGONIC CHART OF THE UNITED STAT

(From the U. S. Coast and Geo

The lines of equal magnetic declination, or isogonic lines, are given for every degree, and are based on marked zero, the magnetic needle points true north and south.

The north end of the compass needle is moving to the westward for places east of the line of no change, equal annual change (dash lines). Or, east of the line of no change the isogonic lines are moving westward a



Irregular Variations in the declination are due chiefly to magnetic storms. They are uncertain in character and cannot be predicted. They are, however, usually observed whenever there is a display of the Aurora Borealis. Such storms often cause variations of from ten to twenty minutes in the United States and even more in higher latitudes.

30. Isogonic Chart. — If lines are drawn on a map so as to join all places where the declination of the needle **is the same at a given time,** the result will be what is called an *isogonic chart.* (See Fig. 5.) Such charts have been constructed by the United States Coast and Geodetic Survey. While they do not give results at any place with great precision they are very useful in finding approximate values of the declination in different localities.

An examination of the isogonic chart of the United States shows that in the Eastern States the needle points west of north while in the Western States it points east of north. The line of no declination, or the *agonic line*, passes at the present time (1915) through the Carolinas, Ohio and Michigan.

31. OBSERVATIONS FOR DECLINATION. — For any survey where the value of the present declination is important, it should be found by special observations. The value found at one place may be considerably different from that of a place only a few miles distant. The method of finding the declination by observation on the Pole-Star (Polaris) is described in Art. 236, p. 219.

ADJUSTMENTS OF THE COMPASS.

32. The three adjustments which need to be most frequently made are (1) adjusting the bubbles, (2) straightening the needle, (3) centering the pivot-point.

33. ADJUSTMENT OF THE BUBBLES. — To make the Plane of the Bubbles Perpendicular to the Vertical Axis. — Level the instrument in any position. Turn 180° about the vertical axis and, if the bubbles move from the center, bring each half-way back by means of the adjusting screws; and repeat the process until the desired fineness of adjustment is secured.

34. DETECTING ERRORS IN ADJUSTMENT OF THE NEEDLE. — If the readings of the two ends of the needle are not 180°

apart, this may be due to the needle being bent, to the pivot-point not being in the center of the graduated circle, or to both. If the difference of the two readings is the same in whatever direction the compass is turned, it follows that the needle is bent but the pivot-point is in the center of the circle. (See Fig. 6.) The bent needle is represented by the line AOB and the position of a straight needle shown by the line AOC. In the two positions shown it is seen that the difference in readings will be the same, i.e., arc CB = arc $C'B'$. If the difference of the readings varies as the compass is turned around it follows that the pivot-point is not in the center, and the needle may or may not be bent. Suppose the needle is straight but the pivot is not in the center, then the effect in different parts of the circle is shown in Fig. 7. When the needle is in the position AD, perpendicular to CC', (where C is the true center and C' is the position of the pivot-point), then the error is a maximum. If B is a point 180° from A then the difference of the two readings is BD. When the needle is at $A'D'$ the error is less than before and equals $B'D'$. When the needle is in the line CC', i.e., in the position $A''D''$, the ends read alike.



FIG. 6. BENT COMPASS-NEEDLE.



FIG. 7. PIVOT-POINT OUT OF CENTER.

In making these adjustments it is better to first straighten the needle, because the error due to the needle being bent can be detected independently of the error of the pivot.

35. TO STRAIGHTEN THE COMPASS-NEEDLE. — Level the instrument and let the needle down on the pivot. Remove the glass cover. By means of a brass wire or a light stick of wood

steady the needle so that one end of it, say the south end, is opposite some graduation on the circle as A in Fig. 8. Note the position of the north end of the needle C. Now, without moving the compass itself, turn the needle around so that the north end is at the graduation A. Hold it in this position with the brass wire and read the position of the south end C'. One-half the difference of the readings, or, the distance $C'D$ is the amount by which the needle is bent. Carefully remove the needle from the pivot and bend it by the amount $C'D$ in the direction which will move the south end half-way back from C' toward C. It is better not to touch the needle with the hands more than is absolutely necessary as this weakens the magnetism. Instrument makers usually leave the central part of the needle quite soft so that it can be easily bent in making this adjustment. Since the amount by which the needle is bent is a matter of estimation it should be replaced on the pivot and the test repeated until it is found that reversing the needle does not change the readings.



FIG. 8. STRAIGHTENING THE COMPASS-NEEDLE.

36. TO CENTER THE PIVOT-POINT. — If the difference of readings of the two ends of the needle varies in different parts of the circle it is due to the pivot-point being out of center. Take readings of the two ends of the needle in various positions of the compass and find the position of the needle in which the difference of the two readings is greatest (Art. 34, p. 25). The pivot is to be bent at right angles to this direction an amount equal to half this difference. Remove the needle and bend the pivot by means of a pair of small flat pliers. Replace the needle and see if the difference of end readings is zero. If not, the pivot must be bent until this condition is fulfilled. As the pivot may become bent somewhat in a direction other than that intended, a complete test for adjustment must be made again, and the process continued until the difference in the readings of the ends of the needle is zero in all positions of the compass. The

metal at the base of the pivot is left soft so that it can be easily bent.

37. TO REMAGNETIZE THE NEEDLE. — Rub each end of the needle from the center toward the end several times with a bar-magnet, using the N end of the magnet for the S end of the needle and *vice versa*. (The N end of the magnet attracts the S end of the needle and repels its N end.) When the magnet is drawn along the needle it should move in a **straight line,** parallel to the axis of the needle. When returning the bar from the end of the needle toward the center, lift it several inches **above** the needle as indicated in Fig. 9.



FIG. 9. REMAGNETIZING THE COMPASS-NEEDLE.

38. COMMON SOURCES OF ERROR IN COMPASS WORK. —

1. Iron or steel near compass.
2. Parallax in reading needle.

39. COMMON MISTAKES. —

1. Reading wrong end of needle.
2. Not letting needle down on pivot.
3. Reading the wrong side of the 10th degree, viz., reading 61° instead of 59°.

40. Detecting Local Attraction of the Needle. — As the needle is always affected by masses of iron near the compass it is important that the bearings in any survey should be checked. This is most readily done by taking the bearing of any line from both its ends or from intermediate points on the line. If the two bearings agree it is probable that there is no local magnetic disturbance. If the two do not agree it remains to discover which is correct.

In Fig. 10 suppose that the compass is at *A* and that the



Fig. 10. Diagram Illustrating Local Attraction at A.

bearing of *AB* is N 50°¼ E, and with the compass at *B* the bearing *BA* is found to be S 49° W. It is evident that there is local attraction at one or both points. In order to ascertain the correct magnetic bearing, turn the compass toward a point *C* which is apparently free from magnetic disturbance, and observe the bearing of *BC*, which is, say, S 72° E. Now move the compass to *C* and observe the bearing *CB*. If this is N 72° W it indicates that there is no local attraction at *C* or *B*, hence S 49° W is the correct bearing of line *BA*, and there is 1°¼ error in all bearings taken at *A*. If the bearings of *BC* and *CB* had not agreed it would have been necessary to take the bearing and reverse bearing of a new line *CD*. This process is continued until a line is found whose bearing and reverse bearing differ by exactly 180°.

41. CALCULATING ANGLES FROM BEARINGS. — In calculating the angle between two lines it is necessary only to remember that the bearing is in all cases reckoned from the meridian, either N or S, toward the E and W points. In Fig. 11,

AOB = difference of bearings.
AOC = 180° − sum of bearings.
AOD = 180° − difference of bearings.
AOF = sum of bearings.



FIG. 11.

PROBLEMS.

1. Compute the angle AOB from the given bearings in each of the following cases.

(a) OA, N $39°\frac{1}{4}$ E.
OB, N $76°\frac{3}{4}$ E.

(b) OA, N 35° 15′ E.
OB, S 88° 00′ W.

(c) OA, N 15° E.
OB, S 36° E.

(d) OA, N 40° 15′ E.
OB, N 66° 45′ W.

2. The bearing of one side of a field in the shape of a regular hexagon is S $10°\frac{1}{4}$ E. Find the bearings of the other sides taken around the field in order.

3. (a) In 1859 a certain line had a bearing of N 21° W. The declination of the needle at that place in 1859 was 8° 39′ W. In 1902 the declination was 10° 58′ W. What was the bearing of the line in 1902?

(b) In 1877 a line had a bearing of N 89° 30′ E. The declination was 0° 13′ E. In 1902 the declination was 1° 39′ W. Find the bearing of the line in 1902.

4. Correct the bearings in the following traverse.

STA.	FORWARD BEARING	REVERSE BEARING	STA.	FORWARD BEARING	REVERSE BEARING
A	N $5°\frac{1}{4}$ E.	S $39°\frac{3}{4}$ E.	D	S 12° W.	N 28° W.
B	N $54°\frac{3}{4}$ E.	S $5°\frac{1}{4}$ W.	E	S $59°\frac{1}{2}$ W.	N $10°\frac{1}{4}$ E.
C	S $29°\frac{1}{2}$ E.	S $54°\frac{3}{4}$ W.	F	N $39°\frac{3}{4}$ W.	N 60° E.

Note: — FE is the shortest line.

CHAPTER III.

MEASUREMENT OF ANGLES.

THE TRANSIT.

42. General Description of the Transit. — The engineer's transit is an instrument for measuring horizontal and vertical angles. A section of the transit is shown in Fig. 12.



FIG. 12. SECTION OF TRANSIT.

Two spindles, one inside the other, are each attached to a horizontal circular plate, the outer spindle being attached to the lower plate and the inner one to the upper plate. Except in some older instruments, the lower plate carries a graduated circle and the upper plate carries the *verniers* for reading the circle. On this upper plate are two uprights or *standards*

supporting a horizontal axis. The length of the telescope and the height of the standards are commonly such as to allow the telescope to make a complete rotation on its horizontal axis. The motion of this axis is usually controlled by a clamp and a *slow-motion screw* called a *tangent screw*. In older instruments this often consisted of two opposing screws; in modern instruments it usually consists of a single screw with an opposing spring. At the center of the horizontal axis is a telescope attached at right angles to it.

For leveling the instrument, there are two spirit levels on the upper plate, one parallel and the other at right angles to the horizontal axis. The spirit level which is parallel to the axis is the more important one because it controls the position of the horizontal axis of the telescope; it should be and generally is made more sensitive than the other. In the transit, the leveling is done by means of four (sometimes three) leveling screws.

The upper plate is usually provided with a magnetic needle and a graduated circle so that the transit may be used as a compass. The lower spindle is attached to the base of the instrument by means of a ball-and-socket joint the same as in the compass. Both the upper and lower plates are provided with clamps for holding them in any desired position and with tangent screws for making exact settings.

At the center of the ball-and-socket joint is a ring to which the plumb-line may be attached. The plumb-bob used with the transit is generally heavier than that used in taking tape measurements. Modern transits are so made that the entire head of the instrument can be shifted laterally with reference to the tripod and can thus be readily placed exactly over a point on the ground.

The horizontal circle is usually graduated either to half-degrees or to 20-minute spaces. The graduations are often numbered from 0° to 360° by two rows of figures running in opposite directions. In some transits they are numbered from 0° to 360° in a right-hand direction and, by a second row of figures, from 0° each way to 180°; and still others (older types) are numbered from 0° to 90° in opposite directions, like a compass circle. Transits are usually provided with opposite pairs of verniers.



FIG. 13. ENGINEER'S TRANSIT.



FIG. 14. LONGITUDINAL SECTION OF A TRANSIT TELESCOPE.

43. The *normal* or *direct* position of the transit is with the upper clamp and its tangent screw nearest the observer and the focusing screw of the telescope on the right-hand side (in some instruments, on top) of the telescope. When the instrument is turned 180° in azimuth from the direct position and the telescope is *inverted* (turned over about the horizontal axis) it is said to be in the *reversed* position.

44. If the telescope is provided with a long level tube and a vertical circle, or arc, it is called an *Engineer's Transit*, or *Surveyor's Transit*. (Fig. 13.) If it does not have these attachments it is called a *Plain Transit*.

45. THE TELESCOPE. — The essential parts of the telescope are the *objective*, the *cross-hairs*, and the *eyepiece*. (See Fig. 14.)

The line of sight, or *line of collimation*, is the straight line drawn through the optical center of the objective and the point of intersection of the cross-hairs. When light from any point A falls on the objective, the rays from A are bent and brought to a focus at a single point B called the *image*. The only exception to this is in the case when A is on the optical axis; the ray which coincides with the optical axis is not bent. The cross-hairs are placed in the telescope tube near where the image is formed, as shown in Fig. 14. The objective is screwed into a tube, which is inside the main tube and which can be moved by means of a rack-and-pinion screw so as to bring the plane of the image of the object into coincidence with the plane of the cross-hairs. The instrument is so constructed that the motion

of this tube is **parallel** to the line of sight. The eyepiece is simply a microscope for viewing the image and the cross-hairs. When the plane of the image coincides with the plane of the cross-hairs, both can be viewed at the same instant by means of the eyepiece. The adjustment of the eyepiece and the objective, to enable the cross-hairs and the image to be clearly seen at the same time, is called *focusing*.

In focusing, first the eye-piece tube is moved in or out until the cross-hairs appear distinct; then the objective is moved until the image is distinct. If it is found that the cross-hairs are no longer distinct after moving the objective the above process is repeated until both image and cross-hairs are clearly seen **at the same instant**. The focus should be tested for parallax by moving the eye slightly from one side to the other; if the cross-hairs appear to move over the image the focus is imperfect. In focusing on objects at different distances it should be remembered that the nearer the object is to the telescope, the farther the objective must be from the cross-hairs; and that for points near the instrument the focus changes rapidly, i.e., the objective is moved considerably in changing from a focus on a point 10 ft. away to one 20 ft. away, whereas for distant objects the focus changes very slowly, the focus for 200 ft. being nearly the same as that for 2000 ft. An instrument can be quickly focused on a distant object if the objective is first moved in as far as it will go and then moved out slowly until the image is distinct. The objective should not be moved too rapidly as it may pass the correct position before the eye can detect the distinct image. If an instrument is badly out of focus it may be pointing directly at an object and yet the image may not be visible.

46. The Objective. — The objective might consist of a simple bi-convex lens, like that shown in Fig. 15, which is formed by the intersection of two spheres. The line OO' joining the centers of the two spheres is called the *optical axis*. If rays parallel to the optical axis fall on the lens those near the edge of the lens are bent, or refracted, more than those near the center, so that all the rays are brought to a focus (nearly) at a point F on the optical axis called the *principal focus*. If light falls on the lens from any direction there is one of the rays such as

AC or *BD* which passes through the lens without permanent deviation, i.e., it emerges from the other side of the lens parallel to its original direction. All such rays intersect at a point *X* on the optical axis which is called the *optical center.*

A simple bi-convex lens does not make the best objective because the rays do not all come to a focus at **exactly** the same point. This causes indistinctness and also color in the field of



FIG. 15. BI-CONVEX LENS.

view, particularly near the edges. This difficulty is overcome by using a combination of lenses, consisting of "crown" and "flint" glass as shown in Fig. 14, which very nearly corrects these imperfections.

The position of the image of any point is located on a straight line (nearly) through the point and the optical center; hence it will be seen that the image formed by the objective is inverted.



FIG. 16. CROSS-HAIR RING.

47. Cross-Hairs. — The cross-hairs consist of two very fine spider threads stretched across a metallic ring at right angles to each other and fastened by means of shellac. The cross-hair ring (Fig. 16) is held in place by four capstan-headed screws which permit of its being moved

vertically or horizontally in the telescope tube. The holes in the tube through which the screws pass are large enough to allow some motion of the ring in adjusting.

48. Eyepiece. — The eyepiece of the ordinary transit telescope may be either of two kinds, that which shows an inverted image or that which shows an erect image. An erecting eyepiece requires two more lenses than the inverting eyepiece, which add to its length and also absorb light; but in spite of these disadvantages the erecting eyepiece is generally used on ordinary transits. It will be seen, however, that with the same length of telescope a greater magnifying power and a clearer definition of the image can be obtained by the use of the inverting eyepiece. These advantages are so important and the disadvantage of seeing objects inverted is so slight that inverting eyepieces should be used more generally than they are at present.

49. Magnifying Power. — The magnifying power is the amount by which an object is increased in apparent size. It is equal to $\frac{\tan \frac{1}{2} A}{\tan \frac{1}{2} a}$, (or nearly equal to $\frac{A}{a}$), A being the angle subtended by an object as seen through the telescope and a the angle as seen by the unaided eye.

50. The magnifying power may be measured in two ways. (1) The dimensions on a graduated rod will appear magnified when viewed through a telescope. If, with one eye at the telescope, the rod is viewed directly with the other eye it will be noticed that one space as viewed through the telescope will appear to cover a certain number of spaces as seen with the naked eye. This number is approximately the magnifying power of the telescope.

(2) Viewed through a telescope wrong-end-to, an object is reduced in apparent size in the same ratio that it is magnified when seen through the telescope in the usual manner. Measure with a transit some small angle A between distant points and then place the telescope to be tested in front of the transit, with its objective next the objective of the transit. Measure the angle a between the same points; this new angle will be smaller. Then the Magnifying Power $= \frac{\tan \frac{1}{2} A}{\tan \frac{1}{2} a}$. The magnifying power

of the ordinary transit telescope is between twenty and thirty diameters.

51. Field of View. — The field of view is the angular space that can be seen at one time through the telescope. It is the angle subtended at the optical center of the objective by the opening in the eyepiece. In the ordinary transit this angle is about one degree, but in some instruments it is considerably more.



FIG. 17.



FIG. 18.



FIG. 19.

52. THE VERNIER. — The vernier is a device for determining the subdivision of the smallest division of a scale more accu-

rately than can be done by simply estimating the fractional part. It depends upon the fact that the eye can judge much more exactly when two lines coincide than it can estimate a fractional part of a space.

A simple form of vernier, shown in Fig. 17, is constructed by taking a length equal to 9 divisions on the scale and dividing this length into 10 equal parts. One space on the vernier is then equal to $\frac{9}{10}$ of a space on the scale, i.e., it is $\frac{1}{10}$ part shorter than a space on the scale, hence $ab = \frac{1}{10}$ of a space on the scale, $cd = \frac{2}{10}$ of a space, etc. Now if the vernier is raised until a coincides with b, i.e., until the first line on the vernier coincides with the next higher line on the scale, then the index line has moved over $\frac{1}{10}$ of a space and the reading will be 501. If the vernier is moved $\frac{1}{10}$ space higher then line 2 coincides with the next higher line on the scale and the reading is 502, as shown in Fig. 18. Similarly Fig. 19 shows reading 526. Thus it is seen that the number of the line on the vernier which coincides with a line on the scale is the number of tenths of the smallest division of the scale that the index point (zero) lies above the next lower division on the scale. Furthermore it will be seen from its construction that it is impossible to have more than one coincidence at a time on a single vernier. The type of vernier just described is used on leveling rods.

53. Verniers used on Transits. — In transits, since angles may be measured in either direction, the verniers are usually double, i.e., there is a single vernier on each side of the index point, one of which is to be used in reading angles to the right, and the other in reading angles to the left.

The vernier most commonly found on the transit reads to one minute of arc (Fig. 20). When this vernier is used the circle is divided into degrees and half-degrees. The vernier scale is made by taking a length equal to 29 of the half-degree spaces and subdividing it into 30 equal parts. Each space on the vernier is then equal to $\frac{29}{30} \times 30' = 29'$. Therefore the difference in length of one division on the circle and one division on the vernier is equal to the difference between the 30′ on the circle and the 29′ on the vernier, or one minute of arc. In

Fig. 20 the zero of the vernier coincides with the 0° mark on the circle. The first graduation on the vernier to the left of the zero fails to coincide with the 0° 30′ line by just 1′ of arc. The second line on the vernier falls 2′ short of the 1° mark, the third line 3′ short of the 1° 30′ mark, etc. If the vernier should be moved one minute to the left the first line would coin-



FIG. 20. ONE-MINUTE VERNIER SET AT 0°.

cide and the reading would be 0° 01′. If the vernier were moved one minute more the second line would coincide and the reading would be 0° 02′, etc. Therefore the number of the line on the vernier which coincides with some line on the circle is the number of minutes to be added to 0°. After the vernier has moved beyond the point where the 30′ line coincides, it begins subdividing the next space of the circle, and we must then add the vernier reading to 0° 30′.

The following figures show various types of vernier commonly used on transits.



FIG. 21.

Fig. 21. — Double vernier reading to 1′. Circle divided into 30′ spaces. 29 divisions of the circle divided into 30 parts to make one division of the vernier.

Reading, outer row of figures, 9° 16′.
Reading, inner row of figures, 350° 44′.

Since the vernier moves with the telescope, **read the angle on the circle in the same direction that the telescope has moved.** Read the number of degrees and half-degrees the index has passed over and estimate roughly the number of minutes beyond the last half-degree mark. Then follow along the vernier in the **same** direction and find the coincidence. The number of this line is the number of minutes to be added to the degrees and half-degrees which were read from the circle. An estimate of the number of minutes should always be made as a check against large mistakes in reading the vernier or in reading the wrong vernier.

Fig. 22. — Double vernier reading to 30″. Circle divided



FIG. 22.

into 20′ spaces. 39 divisions of the circle divided into 40 parts to make one division of the vernier.

Reading, inner row of figures, 31° 17′ 30″.
Reading, outer row of figures, 328° 42′ 30″.

Fig. 23. — Single vernier reading to 20″. Circle divided into 20′ spaces. 59 divisions of the circle divided into 60 parts to make one division of the vernier.

Reading, 73° 48′ 40″.



FIG. 23.

On account of the length of this vernier it is impracticable to use a double vernier. Where it is desirable to read the angles in either direction the circle has two rows of figures as shown in Fig. 24.

Fig. 24. — Reading, inner row of figures, 73° 48′ 40″.
Reading, outer row of figures, 266° 31′ 20″.



FIG. 24.

It is evident that if angles are to be read "clockwise" the index at the right end of this vernier should be set at 0°. If

angles are to be measured in the opposite direction the index at the left end should be set at 0°. To avoid this inconvenience of resetting, some surveyors set the middle line (10′ line) of the vernier on 0° and disregard the numbering on the vernier, reading it as explained under Fig. 26.

Fig. 25. — Single vernier reading to 10″. Circle divided



FIG. 25.

into 10′ spaces. 59 divisions of the circle divided into 60 parts to make one division of the vernier.

Reading, 59° 15′ 50″.

Fig. 26. — Single vernier reading in either direction to 1′.



FIG. 26.

Circle divided into 30′ spaces. 29 divisions of the circle divided into 30 parts to make one division of the vernier.

Reading, 2° 23′.

This vernier is read like the ordinary 1′ vernier except that if a coincidence is not reached by passing along the vernier in the direction in which the circle is numbered, it is necessary to go to the other end of the vernier and continue in the same direction, toward the center, until the coincidence is found. This vernier is used on the vertical circle of transits when the space is too small for a double vernier.

There is another type of transit vernier, which is occasionally used, in which the degree is divided into hundredths instead of minutes.

54. ECCENTRICITY. — If the two opposite verniers of a transit do not read exactly alike it is usually due to a combination of two causes, (1) because the center of the vernier plate does not coincide with the center of the graduated circle, (2) because the vernier zeros have not been set exactly 180° apart. The first cause produces a variable difference while the second produces a constant difference.

It will be noticed that the effect of these errors is similar to that described in Art. 34, p. 25, on Adjustments of the Compass; the eccentricity of the circles of the transit corresponding to the bent pivot of the compass and the error in the position of the verniers of the transit corresponding to the bent needle of the compass.



FIG. 27. ECCENTRICITY OF CIRCLE.

With reference to the eccentricity of the plates, let C in Fig. 27 be the center of the vernier plate and C' the center of the circle. Let GF be a line through the two centers. When one vernier is at F and the other is at G the vernier readings will be the same as though C and C' were coincident, since the displacement of the center of the circle occurs in the direction of the lines of graduation at F and G. If the telescope is then turned at right angles to its former position, the verniers then being at D and E, the readings

of opposite verniers will differ by the maximum amount. Suppose that the graduations are numbered from 0° right-handed to 360°. When the vernier is at an intermediate position, as at A, it will be seen that it reads too much by the amount AA'. The opposite vernier at B reads too little by the amount BB'. Since AB and $A'B'$ are parallel, BB' and AA' are equal. Consequently the mean of the two vernier readings will be the true reading and the eccentricity is in this way eliminated. Since the effect of eccentricity is never more than a very few minutes it is customary to read the degrees and minutes on one vernier and the minutes only on the other.

55. In spite of the fact that the two verniers are not 180° apart no error is introduced provided; (1) that the same vernier is always used, or (2) that the mean of the two vernier readings is always taken. But if vernier A is set and the angle is read on vernier B an error does enter. Where only one vernier is read **always read the vernier that was set at O°.**

In good instruments both of these errors are very small, usually smaller than the finest reading of the vernier.

USE OF THE TRANSIT.

56. SETTING UP THE TRANSIT. — In setting up the transit, first give the tripod sufficient spread to insure steadiness, keeping the plate of the instrument **approximately level,** the plumb-bob being nearly over the point. Then if the instrument is so far from the point that it cannot be brought into the correct position by pressing the legs into the ground the instrument should be lifted bodily and moved so that the plumb-bob is practically over the point; then press the legs firmly into the ground, doing this in such a manner as to gradually bring the plumb-bob accurately over the point. The nuts on the tripod legs should be tight enough so that the legs are just about to fall of their own weight when raised from the ground. If they are loose the instrument is not rigid; if they are too tight it is not in a stable condition and may shift at any moment.

If the point is on sloping ground it is often convenient, and insures greater stability, to set two legs downhill and one uphill. When the instrument is over the point the tripod head can be

leveled approximately without moving the instrument away from the point by moving one, sometimes two, of the tripod legs in an arc of a circle about the point. Nothing but practice will make one expert in setting up the transit.

It is desirable to bring the instrument very nearly level by means of the tripod; this is really a saving of time because under ordinary conditions it takes longer to level up by the leveling screws than by the tripod. It also saves time on the next set-up to have the leveling screws nearly in their mid position. If the transit is set by means of the tripod, say, within 0.01 or 0.02 ft. of the point, the exact position can be readily reached by means of the *shifting head*, which may be moved freely after any two adjacent leveling screws are loosened. When the transit has been brought directly over the point, the leveling screws should be brought back to a bearing. In the first (rough) setting the plumb-bob should hang, say, an inch above the point, but when the shifting head is used it should be lowered to within about $\frac{1}{8}$ inch or less of the point.

57. In leveling the instrument, first turn the plates so that each plate level is parallel to a pair of opposite leveling screws.



FIG. 28. CUT SHOWING HOW FINGERS MOVE IN LEVELING.

Each level is therefore controlled by the pair of leveling screws which is parallel to it. Great care should be used in leveling. The screws must not be loose as this will cause the plates to tip and perhaps to move horizontally which would change the position of the plumb-bob over the point. On the other hand they

must not be too tight as this will not only injure the instrument but will cause errors due to strains in the metal. To level the instrument, grasp one pair of opposite screws between the thumbs and forefingers and turn so that the thumbs move either **toward** each other or **away from** each other, as illustrated in Fig. 28. In this way one screw is tightened as much as the other is loosened. The motion of both screws must be uniform; if they bind, the one which is being loosened should be turned faster. If this does not appear to remedy matters then the other pair of screws is binding and should be loosened slightly. Only experience will teach one to level an instrument quickly and correctly. It may be convenient for beginners to remember that in leveling the instrument the bubble will move in the same direction as the left thumb moves. After one bubble has been brought nearly to the center of its tube the other bubble is centered in a similar manner by its pair of leveling screws. Instead of trying to center one bubble **exactly** before beginning on the second one it is better to get both of them approximately level, after which first one bubble and then the other may be brought exactly to the center. After the instrument is leveled the plumb-bob should be examined to see that it has not been moved from over the point during the process of leveling.

58. To Measure a Horizontal Angle. — After setting the instrument up over the point, first set the zero of one of the verniers opposite the zero of the circle. This is done by turning the two plates until the two zeros are nearly opposite, clamping the plates firmly together with the **upper clamp,** and then bringing the two into exact coincidence by means of the tangent screw which goes with the **upper clamp.** If a line on the vernier is coincident with a line on the circle then the two adjacent lines on the vernier will fail to coincide with the corresponding lines on the circle by **equal amounts** (Art. 53, p. 39). Hence the coincidence of any line on the vernier with a line on the circle can be more accurately judged by examining also the adjacent divisions and noting that they are symmetrical with respect to the coincident lines. A pocket magnifier, or "reading glass," is generally used for setting and reading the vernier. **Never touch the clamp after a setting has been made by means of the**

tangent screw. In setting with the tangent screw it is better to do this by a **right-hand turn,** i.e., by turning the screw in the direction which **compresses** the spring against which it works. If the screw needs to be turned back, instead of turning it to the exact setting turn it back too far and then bring it up to the accurate setting with a right-hand motion, thereby insuring a firm bearing of the spring against the screw. The two plates which are now clamped in proper position are free to turn together about the vertical axis. Turn to the first object and point the telescope at it approximately by looking over the top of the telescope. When turning the instrument so as to sight the first point it is good practice to touch the lower plate only. Focus the telescope by moving the eyepiece until the cross-hairs are distinct and then moving the objective until the image is distinct. It is sometimes convenient to point the telescope at the object when focusing the cross-hairs so that they can be readily seen.* Test for parallax by moving the eye slightly from one side to the other. Move the telescope until the vertical cross-hair is very nearly on the point. It is better to use that part of the cross-hair which is near the center of the field of view. Clamp the lower plate by means of the **lower clamp,** and set exactly on the point by the **lower** tangent screw. The line of sight is now fixed on the first object. To measure the angle loosen the **upper clamp,** turn the telescope to the second point, and focus the objective if necessary. Set nearly on the point, clamp the **upper** plate, and set the vertical cross-hair exactly on the point by means of the **upper** tangent screw. The angle is then read **on the vernier which was set at 0°.**

The tangent screws should **not** be used to move the plates over large angles. Acquire the habit of setting closely by hand and using the tangent screw for slight motions only.

59. TO MEASURE AN ANGLE BY REPETITION. — The eyepiece magnifies the image so much that it is possible to set the cross-hair on a point much more closely than the vernier will

* If the eyepiece is focused on the cross-hairs with the telescope pointing at the sky, as is frequently done, they will be found to be approximately in focus when looking at the object; but for accurate work the eyepiece should be focused on the cross-hairs when the objective is in focus on the object.

read. The graduation of the circle is very accurate and can be depended upon closer than the vernier can be read, consequently the full value of the instrument is not utilized by single readings of an angle. To obtain the value of an angle more accurately proceed as follows. After the first angle has been measured leave the two plates clamped together, loosen the **lower clamp** and turn back to the first point. Set on the first point, using the **lower clamp** and its tangent screw. Then loosen the upper clamp and set on the second point, using the **upper clamp** and its tangent screw, thus adding another angle, equal to the first one, to the reading on the circle. Repeat this operation, say, six times. The total angle divided by six will give a more precise result than the first reading. Suppose that the angle is actually 18° 12′ 08″; if a "one-minute" instrument is being used it is impossible to read the 08″ on the vernier, so the reading will be 18° 12′. Each repetition will add 08″ (nearly) and after the 6th repetition, the amount will be 48″ which will be read as 1′. After the 6th pointing the total angle will then be read 109° 13′ which divided by 6 gives 18° 12′ 10″, a result in this case correct to the nearest 10″. To eliminate errors in the adjustment of the transit the above process should be repeated with the instrument reversed and the mean of the two values used. (See Art. 79, p. 61.) It is customary to take only the 1st and 6th readings, but as a check against mistakes it is well for the beginner to examine the vernier reading after each repetition and see that $\frac{1}{2}$ the second reading, $\frac{1}{3}$ the third, etc., nearly equals the first reading.

Repetition has also the advantage of eliminating, to a great extent, errors of graduation. If an angle is about 60° and is repeated 6 times it will cover a whole circumference. If there are systematic errors in the graduations the result is nearly free from them. The effect of accidental, or irregular, errors of graduation is decreased in proportion to the number of repetitions. In the best modern instruments the errors of graduation seldom exceed a few seconds.

Little is gained by making a very large number of repetitions as there are systematic errors introduced by the action of the clamps, and the accuracy apparently gained is really lost on this

account. Three repetitions with the telescope normal and three with the telescope inverted are sufficient for anything but very exact work.

It is desirable that as little time as possible should elapse between pointings, as the instrument cannot be relied upon to remain perfectly still. As a matter of fact it is vibrating and "creeping" nearly all the time from numerous causes. For example, when the instrument is set up on frozen ground, it will quickly change its position on account of the unequal settlement of the tripod legs. Changes of temperature, causing expansion or contraction of the metal of the instrument, and the effect of wind introduce errors. The more rapidly the measurements can be made, consistent with careful manipulation, the better the results will be. If the transit is set up on shaky ground the transitman should avoid walking around his instrument.

60. Repetition is useful not only to secure precision, but also as a check against mistakes. If a mistake is made on the first reading of an angle the vernier, on the second reading, falls in a new place on the circle so that the mistake is not likely to be repeated. It is common practice to repeat, or "double," all important angles and divide the second reading by 2 simply as a check on the first reading.

61. **TO LAY OFF AN ANGLE BY REPETITION.** — There is no direct method of laying off an angle by repetition as in the case of measuring an angle, therefore the following indirect method is used. With the vernier set at 0° and the telescope sighted on the first point the angle is carefully laid off on the circle and the second point set in line with the new position of the telescope. Then this angle which has been laid off is measured by repetition as precisely as is desired as described in Art. 59. The resulting angle obtained by repetition is a more precise value than the angle first set on the vernier. The difference between this value and the angle desired is the correction which should be made at the second point. This can be readily done by measuring approximately the distance from the instrument to the second point, and computing the perpendicular offset to be laid off at the second point. (The offset for an angle of one minute at a distance of 100 ft. is nearly 0.03 ft.)

62. RUNNING A STRAIGHT LINE — One Point Visible from the Other. — There are several ways in which a straight line may be fixed on the ground, depending upon the existing conditions. If the line is fixed by the two end points one of which is visible from the other, the method of setting intermediate points would be to set the transit over one point, take a "foresight" on the other and place points in line. For very exact work the instrument should be used in both the direct and reversed positions (Art. 79, p. 61). This will eliminate errors of adjustment such as failure of the telescope to revolve in a true vertical plane, or failure of the objective tube to travel parallel to the line of sight.

63. RUNNING A STRAIGHT LINE — Neither Point Visible from the Other. — If neither point can be seen from the other then it is necessary to find some point, by trial, from which the terminal points can be seen. The transit is set up at some point estimated to be on the line, a "backsight" is taken on one of the points and the instrument clamped. The telescope is then reversed on its horizontal axis. If the vertical cross-hair strikes the second point the instrument is in line; if not, then the error in the position of the instrument must be estimated (or measured) and a second approximation made. In this way, by successive trials, the true point is attained. The final tests should be made with the instrument in direct and reversed positions to eliminate errors of adjustment of the line of sight and the horizontal axis. To eliminate errors in the adjustment of the plate bubbles the plate level which is perpendicular to the line should be releveled just before making the second backsight and while the telescope is pointing in that direction. This can be more readily done if, when the transit is set up, one pair of opposite leveling screws is turned so as to be in the direction of the line; then the other pair will control the level which is perpendicular to the line of sight. After one point has been found by this method other points may be set as described in the previous article.

Another method of running a line between two points one of which is not visible from the other would be to run what is called a *random line* as described in Art. 199, p. 177.

64. Prolonging a Straight Line. — If a line is fixed by two points A and B and it is desired to prolong this line in the direction AB, the instrument should be set up at A, a sight taken on B and other points set in line beyond B. When it is not possible to see beyond B from A, the transit should be set up at B and points ahead should be set by the method of backsighting and foresighting as follows. With the transit at B a backsight is taken on A and the instrument clamped. The telescope is inverted and a point set ahead in line. The process is repeated, the backsight being taken with the telescope in the inverted position. The mean of the two results is a point on the line AB produced. The transit is then moved to the new point, a backsight is taken on B, and another point set ahead as before.

In this last case, if a line is prolonged several times its own length by backsighting and foresighting, there is likely to be a constantly increasing error. In the first case, where the line is run continually toward a point known to be correct, the errors are not accumulating.

65. Methods of Showing Sights. — If the point sighted is within a few hundred feet of the instrument, a pencil may be used and held vertically in showing a point for the transitman to sight on. Sighting-rods are used on long distances.* Where only the top of the rod or pole is visible a considerable error is introduced if it is not held plumb. A plumb-line is much more accurate for such work but cannot be easily seen on long sights. Under conditions where the plumb-line cannot be readily seen some surveyors use for a sight an ordinary white card held with **one edge** against the string or held so that the **center** of the card is directly behind the string. If the edge of the card is held against the string, the transitman must be **extremely** careful that he is sighting on the proper edge.†

* It is desirable that the foresight should be of a color such that the cross-hair is clearly seen, and of a width such that the cross-hair nearly (but not quite) covers it.

† It is common among some surveyors to use a two-foot rule for a sight. The rule is opened so that it forms an inverted V (Λ). The plumb-string is jammed into the angle of the Λ by pressing the two arms of the rule together. The rule is then held so that the plumb-string as it hangs from the rule appears to bisect the angle of the Λ.

Another device is to attach to the plumb-line an ordinary fish-line float (shaped

Whenever the instrument is sighted along a line which is to be frequently used or along which the transit is to remain sighted for any considerable time the transitman should if possible select some well-defined point which is in the line of sight, called a "foresight." If no definite point can be found one may be placed in line for his use. By means of this "foresight" the transitman can detect if his instrument moves off the line, and can set the telescope exactly "on line" at any time without requiring the aid of another man to show him a point on the line.

66. Signals. — In surveying work the distances are frequently so great that it is necessary to use hand signals. The following are in common use.

"*Right*" or "*Left.*" — The arm is extended in the direction of the motion desired, the right arm being used for a motion to the right and the left arm for a motion to the left. A slow motion is used to indicate a long distance and a quick motion a short distance.

"*Plumb the Pole.*" — The hand is extended vertically above the head and moved slowly in the direction it is desired to have the pole plumbed.

"*All Right.*" — Both arms are extended horizontally and moved vertically.

"*Give a Foresight.*" — The transitman, desiring a foresight, motions to the rodman, by holding one arm vertically above his head.

"*Take a Foresight.*" — The rodman desiring the transitman to sight on a point, motions the transitman by holding one arm vertically above his head and then he holds his lining-pole vertically on the point.

"*Give Line.*" — When the rodman desires to be placed "on line" he holds his lining-pole horizontally with both hands over his head and then brings it down to the ground in a vertical position. If the point is to be set carefully, as a transit point,

---

like a plumb-bob). This may be fastened so that its axis coincides with the string and so that it can be raised and lowered on the string. It should be painted with such colors that it can be seen against any background.

The man showing the sight for the transitman should always try to stand so that the sun will shine on the object he is holding; on long sights it is difficult (sometimes impossible) to see an object in a shadow.

the rodman waves the top end of pole in a circle before bringing it to the vertical position.

"*Pick up the Transit.*" — When the chief of the party desires to have the instrument set at another point he signals to the transitman by extending both arms downward and outward and then raising them quickly.

All signals should be distinct so as to leave no doubt as to their meaning. Care should be taken to stand so that the background will not prevent the signals being distinctly seen. The palms of the hands should be shown in making the signals, and for distant signals a white handkerchief is often used. Where much distant signaling is to be done flags are attached to the lining-poles. Special signals may be devised for different kinds of work and conditions.

67. TO MEASURE A VERTICAL ANGLE. — In measuring a vertical angle with a transit, first point the vertical cross-hair approximately at the object, then set the horizontal cross-hair exactly on the point by means of the clamp and tangent screw controlling the vertical motion. Next read the vertical arc or circle. Then, **without disturbing the rest of the transit,** unclamp the vertical arc, and bring the telescope to the horizontal position by means of the level attached to the telescope, and the clamp and tangent screw of the vertical arc. When the telescope bubble is in the center read the vertical arc again. This gives the *index correction*, to be added or subtracted according to whether the two readings are on opposite or on the same side of zero. The instrument is supposed to be so adjusted that the vernier reads zero when the telescope is level, so that a circle reading gives the angle above or below the horizontal line. The index correction is seldom zero because, even though this adjustment were perfect, the plate is seldom exactly level. In some forms of transit the vernier is on a separate arm which also carries a level. By bringing this level to the center of the tube by means of its tangent screw the index correction is reduced to zero each time and the true angle read directly. Instruments provided with this form of level often have no level attached to the telescope. (See Fig. 91, p. 190.)

If the transit has a complete vertical circle errors in the ad-

justment of the bubble and the horizontal cross-hair may be eliminated by inverting the telescope, turning it through 180° azimuth, and remeasuring the angle. The mean of the two results is free from such errors. If the transit is provided with only a portion of a circle the vernier will be off the arc when the telescope is inverted, consequently with a transit of this type the elimination cannot be effected.

68. PRECAUTIONS IN THE USE OF THE TRANSIT. — In the preceding text several sources of error and also precautions against mistakes have been mentioned, but in order that the beginner may appreciate the importance of handling the instrument carefully he should make the following simple tests.

1. Set the transit up with the three points of the tripod rather near together so that the instrument will be high and unstable. Sight the cross-hair on some definite object, such as the tip of a church spire, so that the slightest motion can be seen. Take one tripod leg between the thumb and forefinger and twist it strongly; at the same time look through the telescope and observe the effect.

2. Press the tripod leg laterally and observe the effect on the level attached to the telescope; center the bubble before testing.

3. Step on the ground about 1 or 2 inches from the foot of one of the tripod legs and observe the effect on the line of sight.

4. Breathe on one end of the level vial and observe the motion of the bubble.

5. Press laterally on the eyepiece and observe the effect on the line of sight.

These motions, plainly seen in such tests, are really going on all the time, even if they are not readily apparent to the observer, and show the necessity for careful and skillful manipulation. The overcoat dragging over the tripod, or a hand carelessly resting on the tripod, are common sources of error in transit work.

Before picking up the transit **center the movable head, bring the leveling screws back to their mid position, loosen the lower clamp, and turn the telescope either up or down.**

ADJUSTMENTS OF THE TRANSIT.

69. If an instrument is badly out of adjustment in all respects, it is better not to try to completely adjust one part at a time but to bring the instrument as a whole gradually into adjustment. If this is done, any one process of adjusting will not disturb the preceding adjustments, the parts are not subjected to strains, and the instrument will be found to remain in adjustment much longer than it would if each adjustment were completed separately.

Nearly all adjustments of the transit, in fact of nearly all surveying instruments, are made to depend on the principle of *reversion.* By reversing the position of the instrument the effect of an error is doubled.

70. ADJUSTMENT OF THE PLATE BUBBLES. — **To adjust the Plate Levels so that Each lies in a Plane Perpendicular to the Vertical Axis of the Instrument.** Set up the transit and bring



FIG. 29. ADJUSTMENT OF THE PLATE BUBBLES.

the bubbles to the center of their respective tubes. Turn the plate 180° about its vertical axis and see if the bubbles remain in the center. If they move from the center, half this distance is the error in the adjustment of the tube. (See Fig. 29.) The adjustment is made by turning the capstan-headed screws on the

bubble tube until the bubble moves half-way back to the center as nearly as this can be estimated. Each bubble must be adjusted independently. The adjustment should be tested again by releveling and reversing as before, and the process continued until the bubbles remain in the center when reversed. When both levels are adjusted the bubbles should remain in the centers during an entire revolution about the vertical axis.

71. ADJUSTMENT OF THE CROSS-HAIRS. — 1st. To put the Vertical Cross-Hair in a Plane Perpendicular to the Horizontal Axis. Sight the vertical hair on some well-defined point, and, leaving both plates clamped, rotate the telescope slightly about the horizontal axis (see Fig. 30).

The point should appear to travel on the vertical cross-hair throughout its entire length. If it does not, loosen the screws



FIG. 30. ADJUSTMENT OF THE CROSS-HAIRS (FIRST PART).

holding the cross-hair ring, and by tapping lightly on one of the screws, rotate the ring until the above condition is satisfied. Tighten the screws and proceed with the next adjustment.

72. 2nd. To make the Line of Sight Perpendicular to the Horizontal Axis.* (See Fig. 31.) Set the transit over a point



FIG. 31. ADJUSTMENT OF THE CROSS-HAIRS (SECOND PART).

A. Level up, clamp both plates, and sight accurately on a point *B* which is approximately at the same level as *A*. Reverse the telescope and set *C* in line with the vertical cross-hair. *B*, *A*, and *C* should be in a straight line. To test this, turn the instrument about the **vertical** axis until *B* is again sighted. Clamp the plate, reverse the telescope, and observe if point *C* is in line. If not, set point *D* in line just to one side of *C* and then the cross-hair ring must be moved until the vertical hair appears to have moved to point *E*, **one-fourth** the distance from *D* toward *C*, since, in this case, a **double reversal** has been made.

The cross-hair ring is moved by loosening the screw on one side of the telescope tube and tightening the opposite screw. If *D* falls to the **right** of *C* then the cross-hair ring should be moved to the **left**; but if the transit has an erecting eyepiece the cross-hair will **appear** to move to the **right** when viewed through the telescope. If the transit has an inverting eyepiece the cross-hair appears to move in the same direction in which the cross-hair is actually moved.

The process of reversal should be repeated until no further adjustment is required. When finally adjusted, the screws should hold the ring firmly but without straining it.

* In making the adjustment in the shop with collimators instrument makers seldom level the transit carefully. In field adjustments it is desirable, although not necessary, to level the instrument. The essential condition is that the vertical axis shall not alter its position.

73. ADJUSTMENT OF THE STANDARDS. — To make the Horizontal Axis of the Telescope Perpendicular to the Vertical Axis of the Instrument. (See Fig. 32.) Set up the transit and sight the vertical cross-hair on a high point *A*, such as the top of a church steeple. Lower the telescope and set a point *B* in line, on the same level as the telescope. Reverse the telescope, turn the instrument about its vertical axis, and sight on *B*. Raise the telescope until the point *A* is visible and see if the cross-hair comes on *A*. If not, note point *C* in line and at same height as *A*. Then half the distance from *C* to *A* is the error of adjustment. Loosen the screws in the pivot cap and raise or lower the adjustable end of the horizontal axis by means of the capstan-headed screw under the end of the axis. Repeat the test until the high and the low points are both on the cross-hair in either the direct or reversed positions of the transit. The adjusting screw should be brought into position by a right-hand turn, otherwise the block on which the horizontal axis rests may stick and not follow the screw. The cap screws should then be tightened just enough to avoid looseness of the bearing.



FIG. 32. ADJUSTMENT OF THE STANDARDS.

74. Adjustment of the Telescope Bubble. — This is adjusted by the "*peg*" *method*, or *direct method*, as explained in Art. 128, p. 92. This consists in first determining a level line by using the instrument in such a way as to eliminate the error of the bubble, and then centering the bubble while the line of sight is horizontal.

75. Adjustment of the Auxiliary Level on the Vernier of the Vertical Arc. — (See Art. 67, p. 54.) **To adjust the Level so that it is in the Center of the Tube when the Line of Sight is Level and the Vernier reads 0°.** This is adjusted by the "peg

method" (Art. 128, p. 92). The bubble is first brought to the center of the tube by means of its tangent screw. Then the telescope is moved until the vernier of the vertical arc reads 0°. The instrument is then in condition to be used as a leveling instrument and is adjusted by the "peg method."

If the telescope is provided with an attached level the auxiliary level could be adjusted by comparing it with the telescope level as follows. Level the telescope by means of its attached level, make the vernier read 0 by means of the tangent screw of the vernier, and then bring the bubble of the auxiliary level to the center by means of its adjusting screws.

76. Adjustment of the Vernier of the Vertical Circle. — To make the Vernier read 0° when the Telescope Bubble is in the Center of the Tube. If there is any index error (Art. 67, p. 54) bring the bubble to the center, loosen the screws holding the vernier, and tap lightly until the zeros coincide. Tighten the screws and test again. In some instruments the vernier is controlled by a slow-motion screw for setting the index at the zero of the circle.

77. Adjustment of the Objective Slide. — To make the Objective Slide move Parallel to the Line of Sight. If the tube holding the objective is adjustable it must be placed so that the direction of the line of sight will not be disturbed when the telescope is focused. The adjustment may be made as follows. Adjust the line of sight as in Art. 72, using very distant points. This will require the objective to be drawn in nearly as far as it will go and hence the position of the objective will be changed but little by any subsequent lateral adjustment of the tube. Next repeat the test for the adjustment of the line of sight by using two points which are very near the instrument. In sighting on these points the objective must be run out and any error in its adjustment will change the direction of the line of sight so that it is no longer perpendicular to the horizontal axis of the instrument. In case the instrument fails to stand this test the objective slide does not move parallel to the line of sight. The adjustment is made by moving the adjustment screws of the objective slide so as to apparently increase the error making, by estimation, one-quarter the correction required.

The adjustment of the line of sight should be again tested on two distant points and the cross-hairs moved in case the second adjustment appears to have disturbed the first.

78. SHOP ADJUSTMENTS. — The adjustment of the objective slide and other adjustments such as centering the eyepiece tube and centering the circles are usually made by the instrument maker.

79. HOW TO ELIMINATE THE EFFECT OF ERRORS OF ADJUSTMENT IN THE TRANSIT. — Errors of adjustment in the plate bubble may be avoided by leveling up and reversing as when adjusting. Then, instead of altering the adjustment, simply move the bubble half-way back by means of the **leveling screws.** This makes the vertical axis truly vertical. Then the bubbles should remain in the same parts of their respective tubes as the instrument revolves about its vertical axis.

Errors of the line of sight and errors of the horizontal axis are eliminated by using the instrument with the telescope in the direct and then in the reversed position and taking the mean of the results whether the work is measuring angles or running straight lines.

Errors of eccentricity of the circle are completely eliminated by reading the two opposite verniers and taking the mean.

Errors of graduation of the circle are nearly eliminated by reading the angle in different parts of the circle or by measuring the angle by repetition.

80. Care of Instruments. — A delicate instrument like the transit requires constant care in order that the various parts may not become loose or strained. Care should be taken that the tripod legs do not move too freely, and that the metal shoes on the feet of the tripod do not become loose. The transit should be securely screwed to the tripod. In caring for the lenses a camel's hair brush should be used for dusting them and soft linen with alcohol for cleaning them. The objective should not be unscrewed except when absolutely necessary, and when replaced it should be screwed in to the reference mark on the barrel of the telescope. Grease should never be used on exposed parts of an instrument, as it collects dust. Care should be taken not to strain the adjusting screws in making adjustments.

The instrument should be protected as much as possible from the sun, rain, and dust. If the instrument is carried in the box it is less likely to get out of adjustment than when carried on the shoulder, but the former is often inconvenient. It is customary in traveling by carriage or rail to carry the transit in its box. While being carried on the shoulder the lower clamp should be left unclamped so that in case the instrument strikes against anything, some parts can give easily and save the instrument from a severe shock. When the transit is in use, be careful not to clamp it too hard, but clamp it firmly enough to insure a positive working of the tangent screws and so that no slipping can occur. Do not allow the hands to touch the vertical circle or vernier because the silver will tarnish quickly and make it difficult to read.

81. COMMON SOURCES OF ERROR IN TRANSIT WORK. —

1. Nonadjustment, eccentricity of circle, and errors of graduation.
2. Changes due to temperature and wind.
3. Uneven settling of tripod.
4. Poor focusing (parallax).
5. Inaccurate setting over point.
6. Irregular refraction of atmosphere.

82. COMMON MISTAKES IN TRANSIT WORK. —

1. Reading in the wrong direction from the index on a double vernier.
2. Reading the opposite vernier from the one which was set.
3. Reading the circle wrong, e.g., reading 59° for 61°. If the angle is nearly 90°, reading the wrong side of the 90° point, e.g., 88° for 92°.
4. Using the wrong tangent screw.

THE SOLAR ATTACHMENT.

83. Description of Solar Attachment. — One of the auxiliaries to the engineer's transit, formerly in common use, is the *solar attachment*, one make of which is illustrated in Fig. 33. This consists of a small instrument having motions about two axes at right angles to each other, like the transit itself, and which is attached to the transit; by means of this attachment a true meridian line can be found by an observation on the sun. This instrument seldom gives as great precision as direct solar observations but has the advantage that less calculation is required than in case of direct observations. In the form shown in Fig. 33, which is a modification of the Saegmuller pattern, the principal parts are the *polar axis*, which is attached to the telescope tube and is adjusted perpendicular to the line of sight and also the horizontal axis, and the *solar telescope*, which is mounted on the polar axis. The solar telescope is provided with clamps and tangent screws and can be revolved about the polar axis and can also be inclined to it at any desired angle. Attached to the solar telescope is a level tube, the axis of which is supposed to be parallel to the line of sight of the solar telescope. This is used when setting off the sun's declination by means of the vertical circle of the transit. At the base of the polar axis are four adjusting screws for making this axis perpendicular to the line of sight and to the horizontal axis of the main telescope. The solar telescope is provided with four cross-hairs (in addition to the usual vertical and horizontal hairs) which form a square whose angular diameter is equal* to that of the sun. The eyepiece is covered with a colored glass to protect the eye while observing.

In another form of attachment, known as Burt's Solar Attachment, the telescope is replaced by a small bi-convex lens and a metallic screen carrying ruled lines in place of cross-hairs. The sun's image can be thrown on the screen and viewed with a magnifying glass, so that this device is really the equivalent

* The sun's apparent diameter varies about 3 per cent during the year. The sun's image may always be placed symmetrically with respect to the square, so that no appreciable error is introduced by this variation.



FIG. 33. SOLAR ATTACHMENT TO TRANSIT.

(The authors are indebted to C. L. Berger & Son for the photograph from which this cut was made.)

of a telescope of low power. In pointing on the sun the image is centered in the square formed by the ruled lines. The instrument is provided with a special arc graduated to half minutes and known as the *declination arc;* it is used for setting off the declination of the sun when determining the direction of the meridian. In order to avoid the necessity of having a declination arc extending both ways from 0° the instrument is provided with two sets of solar lenses and screens pointing in opposite directions; one is used for north declinations and one for south declinations.

The Shattuck solar attachment consists of two plane mirrors having a relative motion like the mirrors of a sextant. It is clamped to the objective end of the transit telescope, the telescope itself serving both as a polar axis and a solar telescope. The sun's image is seen in the telescope by double reflection from the two mirrors. This attachment offers the advantage that the usual errors of adjustment of the polar axis and solar telescope bubble are not present.

In the Smith solar attachment (invented by Benjamin H. Smith) the solar attachment is mounted on the side of one of the standards of the transit. In this instrument the solar telescope serves as the polar axis. In front of the objective of the solar telescope is a mirror which is attached to a movable arm to which is attached the vernier of the declination arc. Attached to the solar telescope is a special *latitude arc,* the vernier of which is at the top of the standard. The solar telescope may be rotated about its own axis. This instrument has the advantage that all of the settings may be made and allowed to remain without interfering with the use of the transit telescope for other purposes.

84. The Celestial Sphere. — In order to understand the theory of this instrument it will be necessary to define a few astronomical terms. Fig. 34 represents that half of the celestial sphere which is visible at one time to an observer on the surface of the earth. For the purposes of this problem the celestial sphere may be regarded as one having its center at the center of the earth and a radius equal to the distance of the sun from the earth. The sun in its apparent daily motion would then move around in a circle on the surface of this

sphere. The circle $NESW$ is the observer's *horizon* and is the boundary between the visible and invisible parts of the celestial sphere. The point Z is the *zenith* and is the point where a plumb-line produced would pierce the celestial sphere. The circle $SZPN$ is the observer's *meridian* and is a vertical circle through the pole. The circle EQW is the *celestial equator.* The circle AMB, parallel to the equator, is a *parallel of declination,* or the path described by the sun in its apparent daily



FIG. 34. DIAGRAM OF THE CELESTIAL HEMISPHERE.

motion from east to west. The *sun's declination* is its angular distance from the equator, or the arc OT. The declination is considered **positive** when north and **negative** when south. The *polar distance* of the sun is the complement of the declination represented by the arc OP

85. OBSERVATION ON THE SUN FOR MERIDIAN WITH SOLAR ATTACHMENT. — If the polar axis of the instrument is made to point to the celestial pole, i.e., made parallel to the earth's axis, then the small telescope can be made to follow the sun in its daily path by simply giving it an inclination to the polar axis equal to the sun's polar distance and revolving it about the polar axis.

(1) To find the true meridian by an observation on the sun first make the angle between the polar axis and the solar telescope equal to the sun's polar distance at the time of the observation. This is done by turning the solar telescope into the same plane as the main telescope by sighting both on some distant object, and then making the angle between the two telescopes equal to the sun's declination. Some instruments are provided with a *declination arc* upon which the declination angle can be laid off directly. Others have a small spirit level attached to the small telescope, in which case the vertical circle of the transit is used for laying off the declination angle. Incline the main telescope until the reading of the vertical circle equals the declination, and clamp; then level the solar telescope by means of the attached level. The angle between the polar axis and the solar telescope is then 90° plus or minus the reading of the vertical circle.

(2) By means of the vertical circle of the transit incline the polar axis to the vertical by an angle equal to the **co-latitude of the place,** which is 90° minus the latitude. The polar axis now has the same angle of elevation as the celestial pole.

(3) If the observation is in the forenoon, place the solar telescope on the left of the main telescope (on the right if in the afternoon); then, by moving the whole instrument about the vertical axis and the solar telescope about the polar axis, point the solar telescope at the sun. The sun's image is brought to the center of the square formed by four cross-hairs, or ruled lines, in the solar telescope. The final setting is made by the tangent screw controlling the horizontal motion of the transit and the one controlling the motion of the solar about the polar axis. **Only one position can be found where the solar telescope will point to the sun.** In this position the vertical axis points to the zenith, the polar axis to the pole, and the solar telescope to the sun. The instrument has thus solved mechanically the spherical triangle having these three points (Z, P, O) as vertices. The horizontal angle between the two telescopes is equal to the sun's true bearing. Since the solar telescope is pointing to the sun the main telescope must be in the plane of the meridian. If all of the work has been correctly done it will be observed

that the sun's image will remain between the cross-hairs set parallel to the equator, and therefore the sun can be followed in its path by a motion of the solar telescope alone. If it is necessary to move the instrument about the vertical axis to point the solar telescope again at the sun this shows that the main telescope was not truly in the meridian.

After the meridian has been determined the main telescope may then be lowered and a point set which will be due north or due south of the instrument.

86. Computation of Declination Settings. — The sun's polar distance may be obtained from the "American Ephemeris and Nautical Almanac," published by the Government. The polar distance is not given directly, but its complement, the *sun's apparent declination*, is given for each day and for the instant of *Greenwich Mean Noon*. The rate of change of the declination, or the *difference for 1 hour*, is also given. In order to use this for any given locality, it is first necessary to find the local or the standard time corresponding to mean noon of Greenwich. In the United States, where standard time is used, the relation to Greenwich time is very simple. In the *Eastern* time belt the time is exactly 5 hours earlier than at Greenwich; in the *Central*, 6 hours earlier; in the *Mountain*, 7 hours earlier; in the *Pacific*, 8 hours earlier. If a certain declination corresponds to Greenwich mean noon, then the same declination corresponds to 7 A.M. in the Eastern belt or 6 A.M. in the Central belt, etc. The declination for any subsequent hour of the day may be found by adding (algebraically) the difference for 1 hour multiplied by the number of hours elapsed. Declinations marked *North* must be regarded as **positive** and those marked *South* as **negative.** An examination of the values of the declination for successive days will show which way the correction is to be applied. It will be useful also to remember that the declination is 0° about March 21, and increases until about June 22, when it is approximately 23° 27′ North; it then decreases, passing the 0° point about September 22, until about December 21 when it is approximately 23° 27′ South; it then goes North until March 21 when it is 0° again.

After the correct declination is found it has still to be cor-

rected for refraction of the atmosphere. The effect of refraction is to make the sun appear higher up in the sky than it actually is. In the northern hemisphere, when the declination is North the correction must be added, when South, subtracted. This correction may be taken from Table IX, p. 561, the declination being given at the top and the number of hours from local noon at the left.

The co-latitude which must be set off on the vertical circle may be obtained from a map or may be determined by an observation which is made as follows. Set off the sun's declination for **noon,** as for any other observation, the two telescopes being in the same vertical plane, and point the small telescope at the sun. By varying the angle of elevation of the main telescope, keep the solar telescope pointing at the sun until the maximum altitude is reached. The angle read on the vertical circle is the co-latitude (see also Art. 243, p. 230).

EXAMPLE.

Latitude 40° N. Longitude 4h 45m W.

Jan. 10, 1900.

Declination for Greenwich mean noon S 21° 59′ 04″

Difference for 1 h + 22″ .25

TIME.	DECLINATION.	REFRACTION.	SETTING.
7 h. A.M.	21° 59′ 04″ S		
8	58 42	4′ 59″	21° 53′ 43″
9	58 20	2 36	21 55 44
10	57 57	1 57	21 56 00
11	57 35	1 48	21 55 47
12 M.	57 13	(1 39)	(21 55 34)
1 P.M	56 51	1 48	21 55 03
2	56 28	1 57	21 54 31
3	56 06	2 36	21 53 30
4	55 44	4 59	21 50 45

87. * Comstock's Method of finding the Refraction. — Set the vertical cross-hair on one edge (or *limb*) of the sun and note the instant by a watch. Set the vernier of the plate 10′ ahead and note the time when the limb again touches the cross-hair,

* See Bulletin of the University of Wisconsin, Science Series, Vol. I, No. 3.

Call the number of seconds between these observations n. Read the altitude h. Then the refraction in minutes will be nearly equal to $\frac{2000}{hn}$, h being expressed in degrees.

88. Observation for meridian should not be made when the sun's altitude is less than about 10°, because the refraction correction will be unreliable. Observations near noon are to be avoided because a slight error in altitude produces a large error in the resulting meridian. For good results therefore the observation should be made neither within an hour of noon nor near sunrise or sunset.

89. MISTAKES IN USING THE SOLAR ATTACHMENT. —

1. Solar on wrong side of main telescope.
2. Refraction correction applied wrong way.

ADJUSTMENTS OF THE SOLAR ATTACHMENT.

90. ADJUSTMENT OF POLAR AXIS. — **To make the Polar Axis Perpendicular to the Plane of the Line of Sight and the Horizontal Axis.** Level the transit and the main telescope. Bring the bubble of the solar telescope to the center of its tube while it is parallel to a pair of opposite adjusting screws which are at the foot of the polar axis. Reverse the solar telescope 180° about the polar axis. If the bubble moves from the center position, bring it half-way back by means of the adjusting screws just mentioned and the other half by means of the tangent screw controlling the vertical motion of the solar. This should be done over each pair of opposite adjusting screws and repeated until the bubble remains central in all positions.

91. ADJUSTMENT OF THE CROSS-HAIRS. — **To make the Vertical Cross-Hair truly Vertical.** Sight on some distant point with all the clamps tightened and, by means of the tangent screw controlling the vertical motion of the solar, revolve the solar telescope about its horizontal axis and see if the vertical cross-hair remains on the point. If not, adjust by rotating the cross-hair ring, as described in Art. 71, p. 57.

92. ADJUSTMENT OF TELESCOPE BUBBLE. — To make the Axis of the Bubble Parallel to the Line of Sight. Level the main telescope and mark a point about 200 ft. from the instrument in line with the horizontal cross-hair. Measure the distance between the two telescopes and lay this off above the first point which will give a point on a level with the center of the solar telescope. Sight the solar at this point and clamp. Bring the bubble to the center by means of the adjusting screws on the bubble tube.

PROBLEMS.

1. Is it necessary that the adjustments of the transit should be made in the order given in this chapter? Give your reasons.

2. A transit is sighting toward B from a point A. In setting up the transit at A it was carelessly set 0.01 ft. directly to one side of A, as at A'. What would be the resulting error, i.e., the difference in direction (in seconds) between AB and $A'B$, (1) when $AB = 40$ ft., (2) when $AB = 1000$ ft.?

3. An angle of 90° is laid off with a "one minute" transit, and the angle then determined by six repetitions, the final reading being $179° 58' + 360°$. The point sighted is 185 feet from the transit. Compute the offset to be laid off in order to correct the first angle. Express the result in feet and also in inches.

4. An angle measured with a transit is $10° 15' 41''$. The telescope of a leveling instrument is placed in front of the transit (with its objective toward the transit) and the angle again measured and found to be $0° 18' 22''$. What is the magnifying power of this level telescope?

5. The line of sight of a transit is one minute to the right of its true position. If the cross-hair is sighted at a high point and then the telescope lowered and a point set in line with the cross-hair, what is the angular error in the position (bearing) of the last point if the vertical angle to the first point is 60° and to the second 0°?

6. If a transit is set up so that the horizontal axis is inclined one minute with the true horizontal direction, what will be the angular error in sighting on a point on a hill, vertical angle 20°, and then setting a point in line and on the same level as the instrument?

7. Design a vernier to read to 30″ for a circle divided into 15′ spaces.

8. Design a vernier to read to 5′ when the circle is divided into degrees.

CHAPTER IV.

MEASUREMENT OF DIFFERENCE OF ELEVATION.

93. LEVEL SURFACE. — A level surface is a **curved** surface which at every point is perpendicular to the direction of gravity at that point, such, for example, as the surface of still water. Any line of sight which is perpendicular to the direction of gravity at a given point is therefore tangent to the level surface at that point and is called a *horizontal line.*

94. The Spirit Level. — In nearly all instruments the direction of gravity is determined by means of either a plumb-line or a spirit level. A spirit level is a glass tube, the inside of which is ground to a circular curve longitudinally, and nearly filled with a liquid such as alcohol or ether, leaving enough space to form a bubble. The grinding is usually done only on the inside upper surface of the tube. The radius of the curve varies according to the use which is to be made of the level; a very short radius makes a slow moving bubble while a long radius makes a very sensitive bubble. It is important that the curve should be exactly circular so that equal distances on the tube should subtend equal angles at the center. The level is provided with a scale of equal parts, which may be either a metallic scale screwed to the brass case holding the glass bubble tube, or it may consist of lines etched on the glass itself. A point near the middle of the tube is selected as the *zero point* and the graduations are numbered both ways from that point. The straight line tangent to the curve at the zero point of the scale is called the *axis of the bubble.* The position of the bubble in the tube is determined by noting the positions of both ends. The bubble will change its length with changes in temperature, consequently the reading of one end is not sufficient to determine the position of the bubble. On account of the action of gravity the bubble will always move toward the higher end of the tube; hence, when the bubble is **central** the axis of the tube is **horizontal.**

95. Angular Value of One Division of the Level Tube. — The angular value of one division of a level tube is the angle, usually expressed in seconds, through which the axis of the tube must be tilted to cause the bubble to move over the length of one division on the scale. The simplest way of finding this in the field consists in moving the bubble over several divisions on the scale by means of the leveling screws and observing the space on a rod passed over by the horizontal cross-hair, the rod being placed at a known distance from the instrument. The space on the rod divided by the distance to the rod gives the natural tangent of the angle through which the line of sight has moved. Since the angle is very small its value in seconds of arc may be obtained by dividing its tangent by the tangent of one second, (log tan $1'' = 4.6855749 - 10$). Dividing the angle found by the number of divisions of the scale passed over on the bubble tube, gives a result which is the average number of seconds corresponding to a single division.

In a properly constructed leveling instrument the value of one division of the level should have a definite relation to the magnifying power of the telescope. The smallest angular movement that can be detected by the level bubble should correspond to the smallest movement of the cross-hairs that can be detected by means of the telescope.

THE LEVEL.

96. The instruments chiefly used for the direct determination of differences of elevation are known as the *Wye Level*, the *Dumpy Level*, and the *Hand Level*. The *Precise Level* differs in its details from the others but does not really constitute a different type; it is essentially a wye level or a dumpy level, according to the principle of its construction. The engineer's transit, which has the long level attached to the telescope, is frequently used for direct leveling. All of these instruments are so constructed that the line of sight is horizontal when the bubble of the attached spirit level is in the middle of its tube.

97. THE WYE LEVEL. — In the wye level (Figs. 35 and 36) the spirit level is attached to the telescope tube which rests in



FIG. 35. LONGITUDINAL SECTION OF A WYE LEVEL.

two Y shaped bearings from which it derives its name. Those parts of the telescope which bear on the wyes are made cylindrical and are called *rings* or *pivots*. The telescope is held in the wyes by means of two *clips*. The level is attached to the telescope by means of screws which allow vertical and lateral adjustments. The two wye supports are secured, by means of adjusting screws, to a horizontal bar which is attached rigidly at right angles to a spindle, or vertical axis, similar to that of a transit. The instrument is provided with leveling screws, clamp, and tangent screw, but has no shifting head nor plumb-line attachment. The whole upper portion of the instrument is screwed to a tripod in the same manner as a transit. The characteristic feature of the wye level is that the telescope can be lifted out of its supports, turned end for end and replaced, each ring then resting in the opposite wye.

98. **THE DUMPY LEVEL.** — In the dumpy level (Fig. 37) the telescope, the vertical supports, the horizontal bar and the vertical spindle are all made in one casting or else the parts are fastened together rigidly so as to be essentially one piece. The



FIG. 36. THE WYE LEVEL.



FIG. 37. THE DUMPY LEVEL.

spirit level is fastened to the horizontal bar and can be adjusted in the vertical plane; there is no other adjustable part except the cross-hair ring.

99. Comparison of Wye and Dumpy Levels. — The wye level has long been a favorite in this country, chiefly on account of the ease with which it can be adjusted, which depends upon the fact that when the telescope is reversed in the wye supports the line through the centers of the pivots is exactly coincident with its first position. While this feature of the wye level is of practical advantage in adjusting the instrument it is based on the assumption that both pivots are **circular** and of **exactly the same diameter,** which may or may not be true. For, even if the pivots are perfect when new, they soon wear, and perhaps unevenly, and consequently the method of adjusting by reversal will then fail and the "*peg*" *adjustment*, or *direct* method, must be used. (See Art. 128, p. 92.) It is not uncommon to find a wye level of excellent manufacture which, after being adjusted by reversals, fails to stand the test by the direct method, but which is capable of excellent work when adjusted by the latter method.

The dumpy level has very few movable parts, and consequently it does not easily get out of adjustment even when subjected to rough usage.* Furthermore the recent work of the U. S. Coast and Geodetic Survey with a new precise level, which is really a dumpy level with certain refinements, indicates the superiority of the dumpy form for the most precise work.

100. MICROMETER ADJUSTMENT. — One of the limitations of the ordinary level is the lack of means of accurately centering the level bubble. The distance between opposite leveling screws is so short that it requires a very delicate touch to set the bubble within a tenth of a division of the central position. Therefore that form of level which admits of a delicate adjustment at the eye end of the bar enables the observer to do more accurate work with a given bubble than the common form in which the leveling screws themselves must be relied upon for the fine adjustments. This attachment also admits of greater speed in leveling.

* See Reports of the Superintendent of the U. S. Coast and Geodetic Survey for the year 1898–99, p. 351, and the year 1900, p. 525.

101. THE LOCKE HAND LEVEL. — The hand level (Fig. 38) has no telescope, but is simply a metal tube with plain glass covers at the ends and with a spirit level on top. When looking through the tube one sees the level bubble on one side of the tube in a reflecting prism with the line of sight and the landscape on the other side. In order that the eye may



FIG. 38. THE LOCKE HAND LEVEL.

see the bubble and the distant object at the same instant the instrument is focused on the bubble by means of a lens placed in a sliding tube. The level line is marked by a horizontal wire, which can be adjusted by means of two screws. The instrument is held at the eye and the farther end is raised or lowered until the bubble is in the center of the tube. At this instant a point in line with the horizontal wire is noted. In this way approximate levels may be obtained.

LEVELING RODS.

According to their construction rods are either *Self-reading* or *Target* rods, or a combination of the two. Self-reading rods are those which can be read directly from the instrument by the levelman whereas target rods can be read only by the rodman. The commonest forms of leveling rods are known as the *Boston*, the *New York*, and the *Philadelphia* rods. (See Fig. 39.)

102. BOSTON ROD. — The Boston rod (Fig. 39) is a target rod of well seasoned wood about $6\frac{1}{2}$ ft. long, made in two strips, one of which slides in a groove in the other. A target is fastened rigidly to one of these strips about 0.3 ft. from one end. Clamps are provided for holding the two parts in any desired position. There is a scale on each side of the rod, one starting from either end, graduated to hundredths of a foot and

Tape Rod.



Self-Reading Rod.

Philadelphia Rod.

New York Rod.

Boston Rod.

FIG. 39. LEVELING RODS.

each with a vernier placed about the height of the eye and reading to thousandths of a foot. When the rod-reading is less than 5.8 ft. the rod is first placed on the ground with the target near the bottom. Then the strip carrying the target is raised to the proper height while the bottom of the other strip rests on the ground, as shown in Fig. 39. For readings over 5.8 ft. the rod is turned end for end so that the target is at the top and can be



FIG. 40. BOSTON ROD TARGET.



FIG. 41. BISECTION TARGET.

moved from 5.8 to 11.4 ft., the limit of the rod. The terms "*short rod*" and "*long rod*" are used to distinguish these two positions.

The common form of target used on the Boston rod is shown in Fig. 40. Instead of this target one of a design similar to that in Fig. 41 is sometimes used, in which the white strip in the center may be bisected by the horizontal cross-hair. Bisection is more precise under all conditions than setting on a single line or on the division line between two surfaces of different color.

A serious objection to the Boston rod is that in reversing it (changing from long to short rod) any error in the position of the target with reference to the scale is doubled by the reversal, and such an error is not readily eliminated.

103. NEW YORK ROD. — The New York rod (Fig. 39) consists of two strips of wood, arranged similarly to those of the Boston rod. Unlike the latter the target on the New York rod is **movable.** For "short rod" the target is moved up or down on the rod until the proper height is reached. The face

of the rod is graduated to hundredths of a foot. The vernier is on the target itself and reads to thousandths of a foot. The graduations on the rod cannot be read from the instrument except at short distances. For "long rod" the target is set at the highest graduation, usually 6.5 ft., and clamped to one of the sliding strips which is then raised until the target is in the right position. A clamp is provided for holding the two strips together. The reading for "long rod" is found on the side of the strip that is raised, and opposite the vernier which is on the other strip, the scale reading downward. In this case the rod cannot be read directly from the instrument.

104. PHILADELPHIA ROD. — This rod has the graduations plainly painted on its face so that it can be used as a self-reading rod (Fig. 39). It has a target reading to thousandths, like that of the New York rod. In some cases the target has no vernier but is graduated directly to 0.005 ft.; the thousandths can be readily estimated. The rod is extended in the same manner as the New York rod, and it can be read to 0.005 ft. and estimated to 0.001 ft. by means of a scale fastened on the back of the rod. When the rod is fully extended, the graduations on the front face are continuous and the readings can be made directly by the levelman if desired. On some rods the graduations are at every tenth of a foot and on others at every half tenth, while in a third pattern every hundredth of a foot is marked; in the last case the lines are .01 ft. wide, the upper edges of the lines being the even numbered hundredths.

105. SPECIAL SELF-READING RODS. — There are a large number of self-reading rods of special design. One of the commonest types, shown in Fig. 39, is similar to the Philadelphia rod except that it has no target and is not graduated closer than tenths. The figures on the face of the rod are made of definite height (0.06 or 0.08 ft.) and of definite thickness (0.01 or 0.02 ft.) so that it is easy for the levelman to estimate the readings to hundredths of a foot. These rods are usually constructed so that they can be extended for "long rod" readings.

106. Tape Rod.* — The tape rod (Fig. 39) is a self-reading

* This rod was invented by Thomas F. Richardson and is used extensively by the Metropolitan Water and Sewerage Board of Boston, Mass.

rod of decidedly different design from the Philadelphia rod. It is a wooden rod made in one piece with a metal roller set in it near each end. Passing over these rollers is a continuous steel band 20 ft. long and 0.1 ft. wide, on the outside of which for its entire length is painted a scale graduated to feet, tenths, and half-tenths, with the details of the numbers so designed that readings to the nearest 0.01 ft. can readily be made. Unlike the other rods mentioned the scale reads **down** on the face of the rod instead of up. It is provided with a clamp so that the metal band, or tape, can be set at any desired reading and held firmly in that position. The use of this type of rod is limited to certain kinds of work, its advantage being the time saved in calculations as explained in Art. 254, p. 240.

107. Precise Level Rod. — The self-reading rod used by the U. S. Coast and Geodetic Survey is made of a single piece of wood, soaked in paraffin to prevent changes in length due to moisture. Metal plugs are inserted at equal distances so that changes in length can be accurately determined. It is divided into centimeters, painted alternately black and white. The bottom of the rod carries a foot-plate. The meters and centimeters are read directly and the millimeters estimated. This rod has attached to it a thermometer, and a level for plumbing.

108. Advantages of the Self-Reading Rod. — While the advantage in the **speed** with which leveling can be accomplished by use of the self-reading rod is well understood, it is also true although not so generally recognized that very **accurate** results can be obtained. For any single reading the error may be larger than with the target rod, but the errors of estimating fractional parts are **compensating,** so that in the long run the results are found to be very accurate. Precise leveling carried on by the U. S. Coast and Geodetic Survey and by European surveys has demonstrated the superiority of such rods. The self-reading rod might to advantage be more generally used than it is at present.

The sensitiveness of the bubble used on the ordinary leveling instrument is about 20″ of angle for a division one-tenth of an inch long on the level scale. This corresponds to an interval on the rod of about .01 ft. per 100 feet or, say, about .02

ft. to .03 ft. for ordinary sights. It is probably fair to assume that, with the ordinary means of leveling, the bubble cannot be centered closer than a tenth of a scale division, and considering the instability of the instrument, seldom is centered closer than a fifth of a division at the instant of sighting. These errors correspond to errors of rod-reading of about .002 and .004 respectively, for a distance of 200 ft. At a distance of 200 feet the .01 ft. division of the Philadelphia rod can be read to the *nearest* .005 without difficulty if the magnifying power of the telescope is consistent with the sensitiveness of the bubble. A



FIG. 42. ROD LEVELS.

rod-reading to .005 ft. is therefore as fine as the sensitiveness of the bubble permits; and any reading of the target vernier smaller than .005 has the appearance of accuracy which does not exist.

It would seem therefore that there is no advantage whatever in the target rod over a self-reading rod as regards accuracy. This statement, however, should not be construed as meaning that the target has no place in leveling. On very long sights, where the scale divisions of the rod are difficult to see, the target is almost indispensable. In thick woods where it is difficult to identify the graduations the use of the target will remove all uncertainty.

109. Attachments to the Rod for Plumbing. — In accurate work it will be convenient to use some device for holding the rod plumb. Spirit levels attached to brass "angles" which may be secured to a corner of the rod are very convenient. Two patterns are shown in Fig. 42. In some rods, such as those used for precise leveling, the levels are set permanently into the rod itself.

110. Effect of Heat and Moisture. — Changes of temperature do not have a serious effect on rods since the coefficient of expansion of wood is small. The effect of moisture is greater, however, and consequently if very accurate leveling is to be done the rod should be compared frequently with a standard. Rods soaked in paraffin are less affected by moisture than those which have not been so treated.

USE OF THE LEVEL AND ROD.

111. In order to obtain the difference in elevation between two points, hold the rod at the first point and, while the instrument is level, take a rod-reading. This is the distance that the bottom of the rod is below the line of sight of the level. Then take a rod-reading on the second point and the difference between the two rod-readings is the difference in elevation of the two points.

112. TO LEVEL THE INSTRUMENT. — Set up the instrument in such a position that the rod can be seen when held on either point and at such height that the horizontal cross-hair will strike somewhere on the rod. In setting up the level, time will be saved if the habit is formed of doing nearly all of the leveling by means of the tripod legs, using the leveling screws only for slight motions of the bubble in bringing it to the middle of the tube. Turn the telescope so that it is directly over two opposite leveling screws. Bring the bubble to the center of the tube **approximately**; then turn the telescope until it is over the other pair of leveling screws and bring the bubble **exactly** to the center. Move the telescope back to the first position and level carefully, and again to the second position if

necessary. If the instrument is in adjustment and is properly leveled in both directions, then the bubble will remain in the center during an entire revolution of the telescope about the vertical axis. The instrument should not be clamped ordinarily, but this may be necessary under some circumstances, for example, in a strong wind.

113. **To Take a Rod-Reading.** — The rodman holds the rod on the first point, taking pains to keep it as nearly plumb as possible. The levelman focuses the telescope on the rod, and brings the bubble to the center **while the telescope is pointing at the rod,** because leveling over both sets of screws will not make the bubble remain in the center in all positions unless the adjustment is perfect. If a target rod is used, the target should be set so that the horizontal cross-hair bisects it **while the bubble is in the center of the tube.** It is not sufficient to trust the bubble to remain in the center; it should be examined just before setting the target and immediately afterward, **at every reading.** The levelman signals the rodman to move the target up or down. When the center of the target coincides with the horizontal cross-hair the levelman signals the rodman, "All right" (Art. 115), and the rodman clamps the target and reads the rod. This reading is then recorded in the note-book. In accurate work the levelman should check the position of the target after it has been clamped to make sure that it has not slipped in clamping. For readings to hundredths of a foot it is not necessary to clamp the target; the rodman can hold the two parts of the rod firmly together while he reads it.

While the levelman is sighting the target, the rodman should stand **beside** the rod so that he can hold it as nearly vertical as possible in the direction of the line of sight. The levelman can tell by means of the vertical cross-hair whether it is plumb in the direction at right angles to the line of sight. **It is extremely important that the rod be held plumb.** Vertical lines on buildings are a great aid to the rodman in judging when his rod is plumb. If the wind is not blowing the rodman can tell when the rod is plumb by balancing it on the point.

114. Waving the Rod. — In careful work when the "long rod" is used it may be plumbed in the direction of the line of

sight by "*waving the rod.*" To do this the rodman stands directly behind the rod and inclines it toward the instrument so that the target will drop below the line of sight. He then slowly draws it back, causing the target to rise. It will be highest when the rod is plumb. If at any point the target appears above the cross-hair it should be lowered. If, while the rod is being waved, the target does not reach the cross-hair the target must be raised and the process repeated until as the rod is waved there appears to be just one place where the target coincides with the horizontal line of sight. Whenever close results are desired it will be well to take several readings on each point and use the mean.

115. Signals. — While the rodman is seldom very far away from the levelman in this work still it is often convenient to use hand signals. The following are commonly used in leveling.

"*Up*" or "*Down.*" — The levelman motions to the rodman by raising his arm above his shoulder for an upward motion and dropping his arm below his waist for a downward motion. A slow motion indicates that the target should be moved a considerable amount and a quick motion indicates a short distance.

"*All Right.*" — The levelman extends both hands horizontally and waves them up and down.

"*Plumb the Rod.*" — The hand is extended vertically above the head and moved slowly in the direction it is desired to have the rod plumbed.

"*Take a Turning Point.*" — The arm is swung slowly in a circle above the head.

"*Pick up the Level.*" — When a new set-up of the level is desired the chief of party signals the levelman by extending both arms downward and outward and then raising them quickly.

Some surveyors use a system of signals for communicating the rod-readings, but mistakes are liable to be made unless great care is used.

116. DIFFERENTIAL LEVELING. — Differential leveling is the name given to the process of finding the difference in elevation of any two points. In Art. 111 the simplest case of differential leveling is described. When the points are far apart the instrument is set up and a rod-reading is taken on the first point.

This is called a *backsight* or *plus sight* and is usually written *B. S.* or + *S.* Next the rod is taken to some well-defined point which will not change in elevation (such as the top of a firm rock, the top of a hydrant, a spike in the root of a tree) and held upon it and a reading taken. This is called a *foresight* or *minus sight* and is written *F. S.* or − *S.* The difference between the two readings gives the difference in elevation between this new point and the first point. This second point is called a *turning point* and is written *T. P.* The level is next set up in a new



FIG. 43. DIAGRAM ILLUSTRATING DIFFERENTIAL LEVELING.

position and a backsight taken on the same turning point. A new turning point further ahead is then selected and a foresight taken upon it.

This process is continued until a foresight is taken on the last point. The elevation of the last point above the first is equal to the sum of all the backsights minus the sum of all the foresights. If the result is **negative,** i.e., if the sum of the foresights is the **greater,** then the last point is **below** the first One form of notes which may be used for this work is shown below, and the field-work is illustrated by Fig. 43.

POINT	+ S.	− S.	REMARKS
A.	8.160	.....	Highest point on stone bound, S. W. cor. X and Y Sts.
T. P.	7.901	2.404	
T. P.	9.446	3.070	
T. P.	8.005	6.906	
B.	....	2.107	N. E. cor. stone step No. 64 M St.
	33.512	14.487	
	14.487		
Diff.	19.025	B above A.	

117. The Proper Length of Sight. — The proper length of sight will depend upon the distance at which the rod appears distinct and steady to the levelman, upon the variations in readings taken on the same point, and upon the degree of precision required. Under ordinary conditions the length of sight should not exceed about 300 ft. where elevations to the nearest 0.01 ft. are desired. "Boiling" of the air due to irregular refraction is frequently so troublesome that long sights cannot be taken accurately.

If the level is out of adjustment the resulting error in the rod-reading is proportional to the distance from the instrument to the rod. If the level is at equal distances from the rod the errors are equal and since it is the **difference** of the rod-readings that gives the difference in elevation, the error is eliminated from the final result if the rodman makes **the distance to the point where the foresight is taken equal to the distance to the backsight** by counting his paces as he goes from one point to the other.

118. Effect of the Earth's Curvature and of Refraction on Leveling. — Since the surface of the earth is very nearly spherical,



FIG. 44. DIAGRAM ILLUSTRATING EFFECT OF EARTH'S CURVATURE AND OF REFRACTION.

any line on it made by the intersection of a vertical plane with the earth's surface is practically circular. In Fig. 44 the distance AA' varies nearly as $\overline{A'L}^2$ (see foot-note, p. 387). The effect of

the refraction of the atmosphere is to make this offset from the tangent appear to be $A'B$ which is about one-seventh part smaller than $A'A$. This offset, corrected for refraction, is about 0.57 ft. in one mile; for 300 ft. it is 0.002 ft.; for 500 ft., 0.005 ft.; for 1000 ft., 0.020 ft. If the rod is equally distant from the instrument on the foresight and backsight the effect of curvature and refraction is eliminated from the result.

119. PRECAUTIONS IN LEVEL WORK. — Nearly all of the precautions mentioned in Art. 68, p. 55, for the transit instrument, are also applicable to the level. Care should be taken not to strike the rod on the ground after it has been clamped and before it has been read.

ADJUSTMENTS OF THE LEVEL.

1. ADJUSTMENTS OF THE WYE LEVEL.

120. ADJUSTMENT OF THE CROSS-HAIRS. — (a) **To make the Horizontal Cross-Hair truly Horizontal when the Instrument is Leveled.** This may be done by rotating the cross-hair ring as in the case of the transit (Art. 71, p. 57), if the instrument is so constructed that the telescope cannot be rotated in the wyes. In many instruments the telescope can be rotated in the wyes. In some levels the telescope is always free to rotate in the wyes, while others are provided with a stop regulated by an adjusting screw, which prevents the telescope from rotating beyond a certain point.

The instrument is leveled and some point found which is covered by the horizontal cross-hair. The telescope is turned slowly about the vertical axis so that the point appears to traverse the field of view. If the point remains on the cross-hair the adjustment is perfect. If it does not, then an adjustment must be made, the manner of doing this depending upon the construction of the instrument. If the telescope cannot be rotated in the wyes the adjustment is made by rotating the cross-hair ring, similar to the adjustment described in Art. 71, p. 57. If the telescope has a stop-screw this must be moved until the instrument

satisfies this test. If the telescope can rotate freely in the wyes it can be turned by hand until it satisfies the test. Since there is nothing to hold the telescope in this position the adjustment in the last case is likely to be disturbed at any time.

121. (b) When the above adjustment is completed **the Line of Sight should be made to Coincide with the Axis of Pivots, or Parallel to it.** (See Fig. 45.) Pull out the pins which hold the clips on the telescope and turn the clips back so that the telescope is free to turn in the wyes. Sight the intersection of the cross-hairs at some well-defined point, using the leveling screws for the vertical motion and the clamp and tangent screw for the horizontal motion. Then rotate the telescope 180° in the wyes, so that the level tube is above the telescope. The intersection of the cross-hairs should still be on the point. If not, move the horizontal cross-hair half-way back to its first position by means of the upper and lower adjusting screws of the cross-hair ring. Then move the vertical cross-hair half-way back to its first position by the other pair of screws. Repeat the test until the adjustment is perfect.



FIG. 45. ADJUSTMENT OF THE CROSS-HAIRS (SECOND PART).

122. ADJUSTMENT OF THE LEVEL TUBE. — **To make the Line of Sight and the Level Tube Parallel to Each Other.** Two methods are used, — the *direct*, or "*peg*," method and the *indirect* method. While the former is the only one applicable to the dumpy level either one can be used for the wye level, although the indirect method is the simpler.

123. ADJUSTMENT OF THE LEVEL TUBE BY INDIRECT METHOD. — (a) **To put the Axis of the Bubble Tube in the Same Plane with the Line of Sight.** Bring the bubble to the center of the tube and rotate the telescope in the wyes for a few degrees (very little is necessary); if the bubble moves toward one end of the tube that end must be the higher, which indicates the direction in which the adjustment should be made. Move

the lateral motion screws of the tube until the bubble returns to the center. Test adjustment by rotating telescope each way.

124. (b) To make the Axis of the Bubble Tube and the Line of Sight Parallel to Each Other. First clamp the instrument, then bring the bubble to the center of the tube, lift the telescope out of the wyes, turn it end for end and set it down in the wyes, the eye end now being where the objective was originally. (See Fig. 46.) This operation must be performed with the greatest care, as the slightest jar of the instrument will vitiate the result. If the bubble returns to the center of the tube, the axis of the tube is in the correct position. If it does not return to the center, the



FIG. 46. ADJUSTMENT OF THE BUBBLE TUBE BY INDIRECT METHOD.

end of the tube provided with the vertical adjustment should be moved until the bubble moves half-way back to the center. This test must be repeated to make sure that the movement is due to defective adjustment and not to the jarring of the instrument.

125. ADJUSTMENT OF THE WYES. — To make the Axis of



FIG. 47. ADJUSTMENT OF THE WYES.

the Level Tube Perpendicular to the Vertical Axis of the Instrument. Bring the two clips down over the telescope and fasten them. Level the instrument, bring the bubble precisely to the middle of the tube over one set of leveling screws, and then turn the telescope 180° about the vertical axis. If the bubble moves from the center bring it half-way back by means of the adjusting screws at the foot of one of the wye supports. (See Fig. 47.)

Since the bubble is brought to the center of the tube each time a rod-reading is taken this last adjustment in no way affects the accuracy of the leveling work but is a convenience and a saving of time.

II. ADJUSTMENTS OF THE DUMPY LEVEL.

126. ADJUSTMENT OF THE CROSS-HAIR. — If the horizontal cross-hair is not truly horizontal when the instrument is level it should be made so by rotating the cross-hair ring as described in the adjustment of the transit, Art. 71, p. 57.

127. ADJUSTMENT OF THE BUBBLE TUBE. — **To make the Axis of the Bubble Tube Perpendicular to the Vertical Axis.** Owing to the construction of the dumpy level it is necessary to make this adjustment before making the line of sight parallel to the bubble tube. It is done by centering the bubble over one pair of leveling screws, and turning the instrument 180° about the vertical axis. If the bubble does not remain in the center of the tube, move it half-way back to the center by means of the adjusting screws on the level tube.

128. THE DIRECT, OR "PEG," ADJUSTMENT. — **To make the Line of Sight Parallel to the Axis of the Bubble.** (See Fig. 48.) Select two points A and B, say, 200 ft. or more apart. Set up the level close to A so that when a rod is held upon it the eye-piece will be only about a quarter of an inch from the rod. Look through the telescope wrong end to at the rod and find the reading opposite the center of the field. After a little experience it will be found that this can be done very accurately. From the fact that only a small portion of the rod is visible it will be found convenient to set a pencil-point on the rod at the center of

the small field of view. Turn the telescope toward B and take a rod-reading on it in the usual way, being certain that the bubble is in the middle of the tube. The difference between these two rod-readings is the difference of elevation of the two points **plus** or **minus** the error of adjustment. The level is next taken to B and the above operation is repeated. The result is the difference in elevation **minus** or **plus** the same error of adjustment. The mean of the two results is the true difference in elevation of points A and B. Knowing the difference in elevation between the two points and the height of the instrument above B the rod-reading at A which will bring the target on the same level as



FIG. 48. PEG ADJUSTMENT.

EXAMPLE. (See Fig. 48.)

Instrument at A.

Rod-reading	on	A	= 4.062
Rod-reading	on	B	= 5.129
Diff. in elev. of A and B			= 1.067

Instrument at B.

Rod-reading	on	B	= 5.076
Rod-reading	on	A	= 4.127
Diff. in elev. of B and A			= 0.949

Mean of two diff. in elev. $= \frac{1.067 + 0.949}{2} = 1.008$ true diff. in elev.

Instrument is now 5.076 above B.
Rod-reading at A should be 5.076 − 1.008 = 4.068 to give a level sight.

the instrument may be computed. The bubble is brought to the center of the tube and the horizontal cross-hair raised or lowered by means of the adjusting screws on the cross-hair ring until the line of sight strikes the target. In this method the small error due to curvature of the earth (nearly 0.001 ft. for a 200-ft. sight) has been neglected.

The peg method may be used for adjusting the wye level or the transit, the difference being that in the dumpy level the axis of the bubble tube is first made horizontal and then the line of sight is brought parallel to it, while in the wye level and in the transit the line of sight is first made horizontal and then the axis of the bubble tube is made parallel to it. Consequently, in the former case the cross-hair ring is moved in adjusting whereas in the latter case the adjustment is made in the bubble tube. This adjustment in its simplest form is described in the following article.

129. ADJUSTMENT OF THE LOCKE HAND LEVEL. — In adjusting the hand level the principle of the peg adjustment is used. The level is placed at a mark A (Fig. 49) and another mark B in line with the cross-hair is made, say, 100 ft. away,



FIG. 49. PEG ADJUSTMENT FOR HAND LEVEL.

when the bubble is in the middle. The level is then taken to B, held so that its center is at the height of this mark, and sighted toward the first point. A third point C is marked in

line with the cross-hair when the bubble is in the middle. The point midway between A and C is at the same level as B. The adjustment is made by screws which move the horizontal wire.

130. Common Sources of Error in Leveling. —

1. Improper focusing (parallax).
2. Bubble not in middle of tube at instant of sighting.
3. Rod not held plumb.
4. Foresights and corresponding backsights on turning points not equally distant from the instrument.
5. Poor turning points selected. (See Art. 250, p. 236.)

131. Common Mistakes. —

1. Foresight and Backsight not taken on exactly the same point.
2. Neglecting to set target accurately when "long rod" is used.
3. In the use of the self-reading rod neglecting to clamp the rod at the proper place when "long rod" is used.
4. Reading the wrong foot-mark or tenth-mark.
5. In keeping notes, — getting F. S. in B. S. column or *vice versa.*
6. In working up notes, adding F. S. or subtracting B. S.

PROBLEMS.

1. A wye level was tested for the sensitiveness of the bubble, as follows: the rod was held on a point 200 ft. away; the bubble was moved over 13.6 divisions of the scale; the rod-readings at the two extreme positions of the bubble were 4.360 and 4.578. Compute the average angular value of one division of the level.

2. A dumpy level was tested by the peg method with the following results.

Instrument at A: —	Instrument at B: —
+ S. on A, 4.139	+ S. on B, 3.900
− S. on B, 4.589	− S. on A, 3.250

Find the rod-reading on A to give a level line of sight, the instrument remaining 3.900 above B. Was the line of sight inclined upward or downward? How much?

3. The target on a Boston rod has been disturbed and it is desired to find out if the target is in the correct position with reference to the scale. Describe a method by which the amount of this error can be determined.

4. A New York rod is found to be 0.002 ft. short, due to wear on the brass foot-plate. Explain what effect this will have in finding the difference in elevation between two points.

5. (a). A level is set up and a + S. of 5.098 is taken on a point 400 ft. away, then a − S. of 3.260 is taken on a point 900 ft. away. What is the curvature and refraction correction? What is the difference in elevation of the two points?

(b). In another case a + S. of 8.266 was taken on a point 100 ft. away and a − S. of 6.405 taken on a point 600 ft. away. What is the curvature and refraction correction? What is the difference in elevation of the two points?

6. A level is set up near a hydrant and a back sight taken on the hydrant, the reading being 3.17. A foresight is taken to a stone bound and equals 5.29. The level is next set up close to the bound, the rod reading upon it being 4.82. The second reading upon the hydrant is 2.66. What is the error of the sight line and which way must the cross-hairs be moved to correct this error?

7. In testing a level by the "peg method" the following rod readings are taken:

Instrument at $B.M._1$, + sight on $B.M._1 = 4.01$, − sight on $B.M._2 = 4.29$: Instrument at $B.M._2$, + sight on $B.M._2 = 4.36$; − sight on $B.M._1 = 4.10$. Which way should the cross-hairs be moved and how much?

8. The level bubble of a certain wye level is centered and the telescope then reversed in the wye, the bubble moving 4 divisions toward the eyepiece. If the angular value of 1 division of the level scale corresponds to 0.02 ft. on the rod per 100 ft. of distance, what is the error from this source alone in the elevation of $B.M._2$ above $B.M._1$ when the sum of the backsights taken with this level is 200 ft. greater than the sum of the foresights?

9. The line of sight of a level is found by the "peg adjustment" test to be inclined downward .011 ft. per 100 ft. in distance. What is the allowable difference in the backsight and foresight distances if readings are to be correct within .002 ft., and sights are not to exceed 300 ft. in length?

PART II.

SURVEYING METHODS.

PART II.

SURVEYING METHODS.

CHAPTER V.

LAND SURVEYING.

132. SURVEYING FOR AREA. — In surveying a field for the purpose of finding its area the instruments and methods used will be determined largely by the degree of accuracy required. If it is permissible to have an error in the area of, say, 0.5 per cent then the compass and chain may be used. If accuracy much greater than this is required it will be necessary to use the transit and the steel tape. At the present time, however, in nearly all work except surveys of farms and woodlands, the transit is used even under conditions where the compass would give the required accuracy.

In surveying a field all the angles and lengths of the sides are determined consecutively, the survey ending at the point from which it was started. Then by trigonometry the position of the final point or of any other point with relation to the starting point can be readily calculated. If the survey were absolutely accurate the last point as calculated would coincide with the first, but this condition is never attained in practice. The calculated distance between the two, divided by the perimeter of the field, is usually called the *error of closure*;* it is often expressed in the form of a fraction in which the numerator is unity. In surveying with a compass and chain the error of closure expected is about 1 part in 500, expressed as $\frac{1}{500}$.

133. SURVEYING FOR AREA WITH COMPASS AND CHAIN. — If the area alone is desired the surveyor's 4-rod chain will be

* The term *error of closure* more properly applies to the actual distance by which the survey fails to close, but as this is generally expressed in the form of a fraction the term has commonly been applied to the latter.

convenient on account of the simple relation existing between the square chain and the acre (Art. 4, p. 3). In making a survey enclosing an area it is customary to begin at some convenient corner and to take the bearings and the distances **in order** around the field. As the measurements are made they are recorded in a field note-book. It is not **necessary** to take the sides in order, but since they must be arranged in order for the purpose of computing the area it will be **convenient** to have them so arranged in the original notes. If the length and bearing of any side are omitted the area is nevertheless completely determined (Art. 432, p. 414), but as these two measurements furnish a valuable check on the accuracy of all the measurements

(LEFT-HAND PAGE) (RIGHT-HAND PAGE)

Survey of Wood Lot of John Smith, Northboro, Mass. — N. Brown, Surveyor; J. Long, Chainman; Oct. 7, 1906. — 2 rod chain – Temple Compass – Chain 0.1 link too long.

Sta	Bearing	Reversed Bearing	Distance (chains)			Remarks
A	Due E	N32°¼W	17.75			Stake and stones cor. J. Smith, B. White and L. Richardson.
B	N58¾°E	N69½°W	13.55			Pine Stump
C	N1½°E	S58°¼W	32.36			Oak Stump
D	S85°¾W	S1½°W	23.75			Cedar Stk. 3' S.E. of large oak.
E	S23°½W	N85°¾E	30.94			Stone bound, E. side Pine St.
F	S32°¼E	N23°½E	11.16			Stone bound, E. side Pine St.

FIG. 50. NOTES OF CHAIN AND COMPASS SURVEY.

they **never** should be omitted if they can be taken. It is of the utmost importance in every survey that check measurements should be taken. Even a few rough checks taken in the field which will require only a little extra time often prove to be of great value in detecting mistakes. Both a forward bearing and a back (or reversed) bearing should be taken at each corner; from these the angle at a corner can be obtained free from error due to any local attraction of the needle. The above process gives a series of connected straight lines and their bearings (or the angles between them), which is called a *traverse*.

It is often impossible to set the compass up at the corners of the property, and in such cases assumed lines running parallel or approximately parallel to the property lines can be

surveyed as described in Art. 134, and the area determined. In some cases the compass can be set on the property line at an intermediate point and the bearing obtained, but the surveyor must be sure that there is no local attraction of the needle at this point. All points where the compass is set should be marked and described so that they can be found again. If any instrument point is not otherwise defined it may be temporarily marked by a small stake and several reference measurements made from this stake to prominent objects nearby, so that its position can be relocated if the stake is lost. These measurements are called *ties*.

Notes of the traverse are usually recorded as shown in Fig. 50.

SURVEY OF FIELD WITH TRANSIT AND TAPE.

134. SURVEY OF A FIELD BY A TRAVERSE. — Surveying a field for area can usually be done in one of the three following ways.

(1). By setting up the transit at the corners of the property and measuring the angles directly; the distances being measured directly along the property lines.

(2). When the property lines are so occupied by buildings or fences that the transit cannot be set up at the corners, but the distances can still be measured along the property lines, then the angles at the corners are obtained by measuring the angles between lines which are parallel to the property lines.

(3). If the boundaries of the property are such that it is not practicable to set the transit up at the corners nor to measure the distance directly on the property lines, a traverse is run approximately parallel to the property lines and these lines connected with the traverse by means of angles and distances.

135. In case (2) the parallel lines are established in the following manner. Set the transit up at some point E

(Fig. 51) within 2 or 3 ft. of the corner A. Establish the line EF parallel to AD by making $DF = AH$ by trial. Point H cannot be seen through the telescope, but it is so near the instrument that by means of the plumb-line on the transit it can be accurately sighted in by eye. Similarly EG is established parallel to AB. Then the angle FEG is measured; and this is the property



FIG. 51. TRANSIT LINES PARALLEL TO THE SIDES OF FIELD.

angle at A. It is evident that the values of AH and DF and of AI and BG are of no permanent use and are therefore not recorded in the notes. When practicable it is advisable to choose the transit point, K for example, on one of the property lines or its prolongation. Fig. 52 is a set of notes illustrating either case (1) or (2).

136. In case (3) the transit can be set up at an arbitrary point marked by a stake and chosen far enough from one of the corners so that the telescope can be focused on it. In this way all the corners of the traverse are chosen so that the traverse will be approximately parallel to the sides of the field. The angles and distances of this traverse are then measured. To connect the property lines with this traverse, angles and distances are measured to the respective corners of the property before the instrument is moved to the next point. Fig. 53 is a set of notes illustrating this case. Time can be saved in the computations and a good check on the work may be obtained if the property lines are also measured when possible. These are not only useful as checks on the accuracy of the survey, but the



FIG. 52. NOTES OF SURVEY WITH TRANSIT AND TAPE.



FIG. 53. NOTES OF SURVEY WITH TRANSIT AND TAPE.

length of the sides will be needed in giving a description of the property. For methods of measuring distances see Arts. 10–22.

These three methods which have been described may be combined in any survey according to circumstances.

137. Irregular Curved Boundaries. — When a tract of land is bounded by an irregular curved line such as a brook it is customary to run the traverse line near it, sometimes crossing it several times, and to take perpendicular offsets to the brook. If it is a winding brook with no distinct turns in it, offsets at regular intervals are measured from the transit line as in the portion near point *A* of Fig. 53. Near point *B* in this figure the brook has practically a direct course between its turns, in which case the proper measurements to make are the offsets to those points where the course of the brook changes and the distances along the transit line between these offset lines. Since they are usually short the right-angle offset lines are laid off by eye.

138. Survey of a Field by a Single Set-up of the Transit. — When it is necessary to economize time in the field at the expense of accuracy and of the time required to calculate the survey the following method may be used. If possible set up at a point within the field, preferably near the middle, from which all the corners can be seen, and measure the angles and distances to each corner. In this way the field is divided into several oblique triangles in each of which two sides and the included angle have been measured and from these the area and third side (property line) can be computed. As a check on the measured angles their sum should be 360°; there is no check on the property lines unless they are measured directly.

This method of surveying a field may be employed as a check on one of the other methods which have already been described, but is not recommended as a method to be used by itself except in emergencies. The weak point in it is the low degree of precision with which the angles are usually measured. Here the effect of an error of, say, 30 seconds in an angle may often be much larger than the errors in the measured distances (Art. 387, p. 373). The additional measurement of the property line gives the length of all three sides of the various triangles into which

the field is divided. If the area is calculated from the three sides of the triangles, using the measured angles as checks only, an accurate result may be obtained, but at the expense of considerable office work.

139. SURVEY OF A FIELD WITH A TAPE ONLY. — Sometimes it may be necessary to survey a field when a transit is not at hand. This can be done by dividing the field into several triangles and measuring all their sides. To insure accuracy of results the triangles should be so chosen that there are no angles in them less than 30° or greater than 150°. This method will require a large amount of computation if the angles as well as the area of the field are desired. Lining in by eye will give accurate results in distances along the line, but only approximate side measurements can be obtained from such a line.

140. SELECTING THE CORNERS. — If a corner is marked by a stone bound the exact point may be easily found; but where it is simply defined as the intersection of stone walls or fences the surveyor will have to examine all evidence as to its position and use his judgment in deciding where the true corner is located (Art. 151, p. 116). When the property is bounded by a public way or a town boundary such data relating to the location of these lines must be obtained from the proper local authorities. After determining the position of the corner points, the surveyor should use precisely the same points in all distance or angle measurements. If stakes are used the exact point is marked by a small tack driven into the top of the stake.

In deciding upon the location of the boundary lines from an examination of artificial features it should be borne in mind that it is customary to build fences or walls along highways entirely on private property so that the face of the wall or fence is on the side line of the highway. In cities the base-board of a fence is usually built so that its face is on the street line, but the location of the fences has no weight when the street line is defined by stone bounds or other permanent marks (Art. 278, p. 262). For boundaries between private lands the legal line is the center of the stone wall or Virginia rail fence, the line between the bottom stringer and the boarding or pickets of an ordinary fence, the fence-posts being entirely on one side of the boundary

line. If deed reads "to thread of stream" the boundary is the line midway between the shores when the stream has its average regimen of flow. Not infrequently woodland is marked off by blazing the trees on one or both sides of the boundary line, the blazing being done on the side of the tree nearest the boundary line. If a tree comes directly on the line it is blazed on both sides. A small pile of stones, sometimes with a stake in the center of the pile, is often used to mark the corners of such land.

141. METHOD OF PROCEDURE. — In deciding where the traverse shall be run the surveyor should keep in mind both convenience in fieldwork and economy in office work. Frequently a method of procedure which shortens the time spent in the field will greatly increase the amount of labor in the office. Circumstances will determine which method should be used. If there is no special reason why the time in the field should be shortened, the best arrangement of the traverse will be the one that will make the computation simple, and hence mistakes will be less liable to occur. If the lines of the traverse coincide with the boundary, as in cases (1) and (2), the amount of office work will be the least. If in case (3) the traverse lines are approximately parallel and near to the boundaries of the property the computation of the small areas to be added to or subtracted from the area enclosed by the traverse is simplified to some extent.

142. TIES. — All important points temporarily marked by stakes should be "tied in," i.e., measurements should be so taken that the point may be readily found or replaced in the future. There should be at least three horizontal ties which intersect at angles not less than 30°. They should be taken from easily recognized definite points, such as blazed trees, stone bounds, fence posts, or buildings. All such measurements should be carefully recorded, usually by means of a sketch. Fig. 54 shows a stake located by ties measured to tenths of a foot; these are taken



FIG. 54. APPROXIMATE TIES.



FIG. 55. EXACT TIES.

simply to aid in finding the stake.

It is often desired to take the ties so that the exact point can be replaced. In such cases the surveyor should mark carefully by tack or crow-foot the exact points from which measurements (taken to $\frac{1}{100}$ ft.) are made, and record the entire information in the notes as shown in Fig. 55.

143. Measurement of the Angles of the Traverse. — The angles of the traverse may be measured in any one of three ways; by measuring the *interior angle*, by measuring the *deflection angle*, which is the difference between the interior angle and 180°, or by measuring the *azimuth angle*.

In practice the deflection angle is measured directly by sighting back on the previous point with the vernier at 0° and the telescope **inverted,** then revolving the telescope about its horizontal axis to the **direct** position and turning the upper limb to the right or left until the next point is sighted. The deflection angle as recorded in the notes is marked *R* or *L* to indicate whether the telescope was turned to the right or left. It is evident that a single measurement of the deflection angle is affected by any error in the adjustment of the line of sight as well as of the standards. If the deflection angle is "doubled" by turning to the backsight with the instrument **direct** and the angle repeated a check on the angle is obtained and the errors of adjustment are also eliminated (Art. 79, p. 61). Where this procedure is followed it will be convenient to make the first backsight with the instrument **direct** so that when the second foresight is taken the instrument will again be in the **direct** position and ready for lining in.

If a very short line enters into a traverse, the errors in angle which would occur on this line owing to errors in centering the instrument over the point may be eliminated by marking a foresight 200 feet or more distant in the prolongation of this short line and measuring all angles from the foresight. The

angle between the lines on either side of the short line will then be correct, for any error in setting the foresight affects both angles alike.

144. MEASUREMENT OF AZIMUTH ANGLES — By the azimuth method the angles are measured as follows. The transit is set up at a point A (Fig. 56), the vernier set at 0°, the telescope turned until it points to the south, and the lower plate clamped. Either the true or the magnetic south may be used, but if neither is known any arbitrary direction may be assumed. The upper clamp is loosened and the telescope sighted on B. The angle read on the vernier is the azimuth of AB, the circle being read in a clockwise direction (Art. 24, p. 16). The transit is next moved to B.

The azimuth of BC may be obtained in one of two ways. (1) Invert the telescope and backsight on A, the vernier remaining at the reading it had at A; then clamp the lower plate, turn the telescope to its direct position, and sight on C. The angle on the vernier is the azimuth of BC referred to the same meridian as the azimuth of AB. The disadvantage of this method is that the error of collimation enters the azimuth angle each time. (2) Add 180° to the azimuth of AB, set this off on the vernier, and sight on A. The telescope may then be turned directly to C (without inverting) and the azimuth of BC can be read directly on the vernier. The disadvantages of this method as compared with the former are that the error of eccentricity of the circle enters, that time is consumed in setting the vernier at each set-up of the instrument, and that there is an opportunity for mistakes in calculating and in making the setting on the vernier.



FIG. 56. AZIMUTH ANGLES.

In the azimuth method the angles of the traverse are checked

by the fieldwork. After point D has been occupied, the transit is again set up at A and the azimuth of AB determined from a backsight on D. This azimuth of AB should agree with the original azimuth of this line. In ordinary land surveying the azimuth method of measuring the angles is little used.

145. Checking the Fieldwork. — The transit is set over the selected points and the angles between the adjacent lines measured. If the work is not to be of unusual precision a transit reading to one minute will be sufficient. A single measurement will give the angle with sufficient precision, but as it is important in all cases to have a check on the work it is advisable to "double the angle" (Art. 60, p. 50), even though it is not necessary to use this method for the purpose of precision. Referring to Fig. 52, p. 103, it will be seen that the angles were quadrupled where the sides were long, and doubled where they were short. In this case the angles were repeated to obtain greater precision.

As an additional check against large errors in the angles, the magnetic bearing of each line should be read, thus enabling one to detect large mistakes and to guard against reading Right for Left in deflection angles. These bearings also show the approximate directions of the lines of the survey. This check should always be applied **in the field** so that any mistake in reading the angles can be rectified before leaving the work. This may be done by calculating each angle from the **observed bearings** of the adjacent sides; or by starting with one observed bearing (assumed to be correct), calculating the other bearings in succession by means of the measured angles, and noting whether the observed bearings agree approximately with the *calculated bearings*.

The accuracy of the transit work may be tested by adding the values of the measured angles. The sum of the interior angles of the field should equal $(n - 2) \times 180°$, where n is the number of sides in the field. If the deflection angles are used the sum of all the right deflections should differ from the sum of all the left deflections by 360°, or in other words, **the algebraic sum of the deflection angles should be 360°.**

It is frequently important to check the distances before

leaving the field. If there is any doubt as regards the correctness of the measurement of a line it should be remeasured, preferably in the **opposite direction,** so that the same mistake will not be repeated. (See line AB in Fig. 52, p. 103.) If the traverse lines do not coincide with the boundaries, an independent check is obtained by measuring along the boundaries as well as on the traverse line, as in Fig. 53, p. 104. This furnishes at once a **rough** check on the distances in the field and a **close** check after the survey has been calculated. It is often advisable to run a line across the traverse, especially when there are many sides to the field, thus dividing the field into two parts, as in Fig. 52, p. 103. If any mistake has been made it is then possible to tell in which portion of the traverse it occurred (Art. 442, p. 419). If the transit is provided with stadia hairs all traverse distances should when practicable be checked by stadia readings.

146. ACCURACY REQUIRED. — In order that the accuracy in the measurement of distances shall be consistent with that of the angles it is necessary that great care should be exercised in holding the tape horizontal, in the plumbing, in the aligning, and in securing the proper tension. On sloping ground inclined distances are measured as explained in Art. 13, p. 9.

If the angles are measured to the nearest minute and the distances to the nearest tenth of a foot, it will be sufficiently accurate to use sighting-rods in "giving line." The error of closure of such a survey should be not greater than $\frac{1}{500}$, but would seldom be less than $\frac{1}{1000}$ (Art. 132, p. 99).

If the property is very valuable, as in the case of city building lots, it is well to use a transit reading to 30″ or 20″. The angles should be repeated, not only as a check against mistakes, but to increase the precision of the measurement (Art. 59, p. 48). The tape measurements should be made with special care, and should be taken to the nearest hundredth of a foot. In the best work the temperature correction should be applied, a spring balance should be used to give the right pull on the tape, the correction to the standard distance should be determined (Art. 267, p. 251), the alignment given with the transit, and great care taken in plumbing. Sights are given by holding a pencil vertically on top of the tack on the stake or by plumb-line (Art. 65, p. 52).

In this work it is important that the property line should be followed, when possible, to insure the most accurate results. In such work an error of closure of $\frac{1}{4000}$ or better is expected. It is customary on most city work to neglect the effect of temperature and to omit the use of the spring balance, the pull being carefully judged. This sort of work should give results as close as $\frac{1}{20000}$, and an accuracy of $\frac{1}{40000}$ is sometimes reached.

147. ORGANIZATION OF TRANSIT PARTY. — Transit surveys can be readily carried on by a party of three men. The note keeper who is in charge of the party directs the entire work; the transit-man who has the instrument always in his care sets it up where directed by the note keeper, reads the angles and gives line when desired; the tape-man generally acting as head-tape-man and the note keeper as rear-tape-man measure all distances.

148. NOTE KEEPING. — All measurements should be recorded in a special note-book as soon as they are made and never left to be filled in from memory. **The notes should be neat and in clear form so that there will be no doubt as to their meaning.** Great care should be taken so that they shall not be susceptible of any interpretation except the right one. They are generally recorded in pencil, but they should always be regarded as permanent records and not as temporary memoranda. As other persons who are not familiar with the locality will probably use the notes and will depend entirely on what is recorded, it is very important that the notes should contain all necessary data without any superfluous information. If the note keeper will bear in mind constantly how the survey is to be calculated or plotted it will aid him greatly in judging which measurements must be taken and which ones are unnecessary. Clearness is of utmost importance in note keeping, and to attain it the usual custom is not to attempt to sketch to scale; and yet in surveys where considerable detail is desired it is sometimes well to carry out the sketches in the note-book approximately to scale. Care should be taken not to crowd the notes, — paper is cheap, — and an extra page of the note-book devoted to a survey may save hours of time in the office consumed in trying to interpret a page of crowded data. Too much stress cannot be laid on the importance of being careful not to lose the note-

book; not infrequently a note-book contains data which thousands of dollars could not replace.

Although sufficient fulness to make the notes clear is desirable, it is customary to abbreviate the names of the artificial features most commonly met with by the surveyor. To properly understand a set of notes one must be familiar with these abbreviations, some of the more common of which are enumerated.

△	Triangulation Station.	c.	Center.
⊙	Traverse Point.	℄.	Center line.
⊡	Stadia Station.	na.	Nail.
S.B	Stone bound.	tk	Tack.
Mon.	Monument.	cb.	Curb.
Stk.	Stake.	C.B.	Catch basin.
Spk.	Spike.	M.H.	Manhole.
dh.	Drill-hole.	Tel.	Telephone pole.
B.M.	Bench-mark.	F.S.	Foresight.
T.P.	Turning point.	B.S.	Backsight.
c.f.	Crow-foot (a mark like this ⅄ or ⅄).		
c.c.f.	Cut crow-foot (cut into wood or stone).		
—·—·—	Fence.	b.b.	Base-board of fence.
o o o	Fence, showing on which side the posts are.		
	Line of building; the outside line is the base-board, the cross-hatched part is the line of the stone or brick underpinning.		

Distances should always be recorded in such a way as to indicate the precision with which they were taken. For example, if they were taken to hundredths of a foot and a measurement happened to be just 124 ft. it should be recorded as 124.00, not as 124. The two zeros are of as much consequence as any other two digits which might have come in their places. Angles which have been read to the nearest half-minute, however, are recorded as follows: 6° 47′ 30″. It will be seen that this is not consistent with the foregoing. A more

proper way of reading this angle would be 6° 47½′, but this is not common practice.

In addition to the measurements every set of notes should contain the following information: — the kind of work, the locality, the date, and the names of members of the field party. It is well to also state the names or numbers of the instruments used and their errors. Where a survey is continued for several pages the date may be placed at the top of every page; other data need not be repeated. Fig. 50, p. 100, Fig. 52, p. 103, and Fig. 53, p. 104, are good examples of field notes.

149. SURVEY OF A FIELD FOR A DEED. — In this case the lengths and bearings of all the boundaries are desired. The traverse lines should therefore follow the property lines, if possible. The bearings desired are not the observed magnetic bearings, but are those calculated by means of the transit angles as explained in Art. 145, p. 110, and therefore are relatively as accurate as the angles themselves. In case a true meridian is found by observation (Chapter VIII) the bearings should be referred to this and marked **true bearings** by a note on the plan, and this information should also be contained in the deed.

A plan which is to accompany a deed should show such features as watercourses, highways, buildings, and adjoining property lines, as well as stone bounds, stakes, fences, walls, or other artificial objects which mark the boundaries of the property.

This plan should contain the following information.

(1) Lengths of all property lines together with their calculated bearings or the angles at the corners.*

(2) Location and description of corner bounds.

(3) Conventional sign or name on walls, fences, etc.

* It is customary with many surveyors to omit from the plan certain data such as the angles or bearings, so that, while it may answer the purpose for which it was made, it does not contain all the data and frequently not enough to enable another surveyor to relocate the property by means of it. This is done, of course, so that when the tract is to be resurveyed or plotted it will be necessary to employ the same surveyor who has in his possession data for which the owner has paid and which the surveyor should have turned over to him. For a valuable paper on this subject see "The Ownership of Surveys, and what Constitutes a Survey and Map," by Professor William G. Raymond, published in *The Polytechnic*, the student journal of the Rensselaer Polytechnic Institute, Troy, N. Y., January 1894.

(4) Names of highways, streams or ponds, and names of adjacent property owners.

(5) Scale of drawing and direction of the meridian used (true or magnetic). It is better to refer all bearings to the true meridian when possible, and in such a case the direction of the magnetic needle should also be shown.*

(6) The title should include a simple and complete statement giving the name of owner, place, date, and name of surveyor. An explanatory note such as a statement as to whether bearings refer to true or magnetic meridian may also be necessary. (See Art. 503, p. 463.)

150. Deed Description. — The written description of the property which is recorded in the deed should be given by bearings (or angles) and distances, stating in every case how the sides of the property are marked and whether bounded by a highway, stream, or private property, giving the name of the present owner of the adjacent property. The following is an example of a deed description of the property shown in the form of notes in Fig. 53, p. 104.

"Beginning at a point in the northerly line of Willow Road in the town of Bancroft Mills, Maine, at an iron pipe sunk in the ground at the S.E. corner of land now or formerly belonging to Nathan H. Barnes, and running along the said northerly line N 85° 34′ E a distance of two hundred ninety-seven and seven-tenths (297.7) feet to the thread of channel of Stony Brook at land now or formerly belonging to James F. Hall; thence turning and running in a northerly direction, by thread of channel of said Stony Brook and land of said Hall, a distance of about three hundred and eight (308±) feet to a stone wall at land now or formerly belonging to Hiram Cole; thence turning and running along the middle of said stone wall and by land of said Cole

* As magnetic bearings are unreliable (Art. 28, p. 19) true bearings should be used wherever their adoption does not entail too much additional expense. In those parts of the country which have been subdivided by the U. S. General Land Office true meridians can be readily obtained from the government surveys; in many of the older (Eastern) states true meridians have been established by local authorities. If the survey can be connected with any triangulation system such as that of the United States or state surveys then, since the true bearings of all of the triangulation lines are known, the bearings of the traverse lines can be obtained.

N 86° 45′ W a distance of two hundred and five and eight-tenths (205.8) feet to the middle of another stone wall at land of said Barnes; thence turning and running by latter stone wall and land of said Barnes S 0° 53′ E a distance of one hundred and seventy-seven and two-tenths (177.2) feet to a fence; thence turning and running by said fence and land of said Barnes N 87° 09′ W a distance of ninety-three and three-tenths (93.3) feet to an iron pipe sunk in the ground; thence turning and running by a fence and land of said Barnes S 1° 51′ W a distance of one hundred and sixty-nine and four-tenths (169.4) feet to the point of beginning; all the bearings being magnetic and the parcel containing a calculated area of 79,305 square feet more or less."

It is unfortunate that the description of the property in deeds in the vast majority of cases, does not define the property in such a manner that it can be plotted from the description. Some deeds are so loosely written as to contain only the names of the owners of adjacent property, no bearings or distances being given.

151. JUDICIAL FUNCTIONS OF THE SURVEYOR. — In rerunning old property lines which have been obliterated, the surveyor is called upon to set aside temporarily his strict adherence to the mathematical side of surveying and must endeavor to find if possible **where the lines originally ran.** He should therefore be familiar with the relative importance of various evidence regarding the location of the property lines, as determined by court decisions. It is distinctly his duty to **find the position of the original boundaries** of the property and **not attempt to correct the original survey** even though he may be sure that an error exists in it. Very often it is true that, owing to the cheapness of land, the original survey was roughly made with little thought of the effect it would have when the land became valuable.

The surveyor therefore must first of all hunt for all physical evidence of the location of the boundaries * and failing in this he

* It must not be assumed that a boundary is missing because it is not at once visible. Stone bounds are often buried two or three feet deep; the top of a stake soon rots off, but evidences of the existence of the stake are often found many years after the top has disappeared, and the supposed location should be carefully dug over to find traces of the old stake. The shovel and common sense are of as much use as the transit and tape in relocating an old corner.

will base his judgment on any other reliable evidence such as occupancy or the word of competent witnesses. It is obvious that this is along equitable lines, since the property was originally purchased with reference to the actual or visible bounds which vest the owner with rights to the property bounded by these lines.

If there is a dispute between adjoining owners over the location of a boundary line this presents a question which must be settled by the courts unless the parties can come to an agreement themselves. In such cases the surveyor acts simply as an expert in judging where the line originally ran and has no power to establish a new line. He can, however, be employed by the disputing parties as an arbitrator to decide on the equitable line, but they are not necessarily obliged to accept his judgment.

If they come to an agreement between themselves, however, regarding the location of the line and occupy to that line, this agreement is binding even though no court has intervened in the matter.

It is to be assumed that the deed was drawn by the grantor with honest intent to convey the property to the grantee. It is intended then that it shall be interpreted if possible so as to make it effectual rather than void. The deed should also be construed in the light of what was known at the time when the title was transferred.

In the interpretation of a deed it is assumed that it was intended to convey property the boundaries of which will form a **closed** traverse. Therefore it is within the jurisdiction of the surveyor to reject any **evident** mistake in the description when running out the property line, e.g., a bearing may have been recorded in the opposite direction or an entire side omitted. Where artificial features are mentioned as boundaries, these always take precedence over the recorded measurements or angles, but these marks must be mentioned in the deed in order to have the force or authority of monuments. When the area does not agree with the boundaries as described in the deed the boundaries control. All distances unless otherwise specified are to be taken as straight lines; but distances given as so many feet along a wall or highway are supposed to follow these lines even if they are not

straight. When a deed refers to a plan the dimensions on this plan become a part of the description of the property.

Where property is bounded by a highway the abutters usually own to the center line, but where it is an accepted street each abutter yields his portion of the street for public use; if, however, the street is abandoned the land reverts to the original owners. If a street has been opened and used for a long period bounded by walls or fences, and there has been no protest regarding them, these lines hold as legal boundaries. In the case of a line between private owners acquiescence in the location of the boundary will, in general, make it the legal line. But if there is a mistake in its location and it has not been brought to the attention of the interested parties or the question of its position raised, then occupancy for many years does not make it a legal line.

Where property is bounded by a non-navigable stream it extends to the thread of the stream. If the property is described as running to the bank of a river it is interpreted to mean to the low water mark unless otherwise stated. Where original ownership ran to the shore line of a navigable river and the water has subsequently receded the proper subdivision is one that gives to each owner along the shore his proportional share of the channel of the river. These lines will therefore run, in general, perpendicular to the channel of the stream from the original intersection of division lines and shore lines.

A more complete statement of the principles mentioned above particularly with reference to the U. S. Public Land Surveys will be found in an address on "The Judicial Functions of Surveyors," by Chief-Justice Cooley of the Michigan Supreme Court, read before the Michigan Association of Engineers and Surveyors, and published in the proceedings of the society for 1882, pp. 112–122.

152. RERUNNING OLD SURVEYS FROM A DEED. — The visible marks which are mentioned in a deed are of primary importance in determining the extent of a piece of property; the lengths of the sides and the bearings (or angles), which should agree with the boundaries, are of secondary importance. It sometimes occurs, however, that all evidences of artificial bound-

aries of the property or of portions of it are missing, and the surveyor must then fall back on the dimensions given in the deed as the best information available (Art. 150, p. 115). Furthermore it is sometimes necessary to "run out" an old deed to determine which of two lines is the correct boundary, or in some cases to find how close the actual boundaries of a property agree with the original deed.

If the directions of the boundaries are defined in the deed by the magnetic bearings, as was formerly the usual custom, it is necessary first to find the declination of the needle at the date of the original survey as well as the present declination of the needle and to correct all the bearings accordingly (Art. 29, p. 20). The declination of the needle should appear on the original deed or plan; but unfortunately it seldom does, and the year the survey was made must then be obtained either from the deed, the old plan, or from witnesses, and the declination of the needle at that time computed. Observations at different places and times have been compiled by the U. S. Coast and Geodetic Survey, and these results may be found in convenient form for calculation in the annual Reports of the Superintendent, particularly the 1886 report.* From these observations the approximate change in declination may be obtained. In this way the magnetic bearings, corrected to date, can be determined as closely probably as the original bearings were taken. It is evident that the change in the declination of the needle between the date of the original survey and the present time is what is desired. If there exists therefore one well-defined line which is known to be one of the original boundary lines, a bearing taken on this line and compared with that given in the deed will determine directly the change in declination. There may be more than one well-defined line whose bearings can be obtained and a comparison of the results on these different lines will give an idea of the reliability of the original survey as well as a more accurate determination of the change in declination.

---

* In 1902 the U. S. Coast and Geodetic Survey issued a special publication entitled, "Magnetic Declination Tables and Isogonic Charts for 1902," in which is given a very complete list of declinations for various places in the United States.

Not infrequently in attempting to rerun old compass surveys it is found that the traverse as described in the deed does not "close," i.e., the last point does not coincide with the first. If this error of closure is small it may be due to the difference in length between the chain used for the original survey and the one being used. Before any attempt is made to run out the old survey this difference should be determined by measuring one or more of the well-defined lines of the property, if any can be found, and comparing the measurements obtained with the recorded distances.

Occasionally it is found that the traverse will not close by a large amount owing to a mistake in the original survey. Often in such cases the deeds of **adjacent** property will show what the mistake was, and in such cases it is allowable to make a correction if it will give a description that is consistent. For example, it occasionally happens that a bearing has been recorded in the reverse direction so that no area is enclosed by the boundaries. Sometimes an entire chain-length has been omitted in one of the lines and by supplying this the description is made consistent. Other inconsistencies are to be dealt with in the same general manner, or as suggested in the preceding article.

153. How to Look Up a Recorded Deed. — In all the states of the Union the transfer of real property must be recorded in the respective county Registry of Deeds or in the office of the city or town clerk. At the Registry of Deeds is kept an exact copy of the deed, which can be examined by any one. It is frequently necessary for the surveyor to make use of these copies when it is not convenient to obtain the deed from the owner of the property or when it is necessary to look up the deed of adjacent property or previous transfers of any of them.

In every Registry of Deeds an index of the deeds is kept, which is divided into two parts, the *grantor* index and the *grantee* index; the grantor being the party who sells the land and the grantee the one who buys it. These indexes are frequently divided by years and for this reason the surveyor should know not only the name of the party who bought or sold the property (both if convenient to get them), but also the approximate date of the transaction. With this information he can readily find

in the proper index the name of the party, opposite which will appear the date of the transaction and the number of the deed book and page on which the copy of the deed is recorded. He then finds the deed book, from which he can copy whatever data he desires from the deed; usually the description of the property is all that concerns the surveyor. In the deed book is usually a reference number in the margin or in the text of the deed which refers to the next preceding transfer of the same property or to any attachments, assignments, and the like which may have been made on it. This method of indexing and filing deeds is used in the New England States and in many of the other states; in fact the general principles are the same throughout the country although the details may differ to some extent.

THE UNITED STATES SYSTEM OF SURVEYING THE PUBLIC LANDS.

154. The System. — The United States System of Surveying the Public Lands, which was inaugurated in 1784, and modified since by various acts of Congress, requires that the public lands "shall be divided by north and south lines run according to the true meridian, and by others crossing them at right angles so as to form townships six miles square," and that the corners of the townships thus surveyed "must be marked with progressive numbers from the beginning." Also, that the townships shall be subdivided into thirty-six sections, each of which shall contain six hundred and forty acres, as nearly as may be, by a system of two sets of parallel lines, one governed by true meridians and the other by parallels of latitude, the latter intersecting the former at right angles, at intervals of a mile.

Since the meridians converge it is evident that the requirement that the lines shall conform to true meridians and that townships shall be six miles square, is mathematically impossible. In order to conform as nearly as practicable to the spirit of the law, and also to make its application both uniform and effective, an elaborate system of subdivision has been worked out. This system will be described in this chapter, first in its general and afterward in its more detailed features; this will

then be followed by a discussion of the ways in which the work of present-time county and other local surveyors is related to the Public Lands System.

The work of the Public Lands Surveys is and has been carried on under the direction of the Commissioner of the General Land Office. Usually the area comprised in each State or Territory has been denominated a District, and has been placed in direct charge of a Surveyor General. The functions that the Surveyor General exercises in his District may be likened to those of a division engineer on construction work; he examines the Deputy Surveyors, approves their contracts, and inspects their fieldwork. The maps, field notes and other records are kept at his office until all the subdivision work in his district is completed, when they are turned over to the State to which they pertain, and the office of the Surveyor General is then discontinued. (See Art. 175, p. 153.)

The actual surveying operations are performed by Deputy Surveyors, who run the lines in the manner specified in the Manual * or as directed in detail by the Surveyor General. This work was formerly done under contract, at stipulated prices per mile for lines of various degrees of importance or difficulty. These prices varied from time to time, with the demand for and supply of deputies, the relative degree of accuracy with which the work was required to be done, and with other conditions. Those prescribed by law † are shown in the Table on p. 123.

It will be observed from the schedule of prices given that higher rates are paid for *standard* lines, which constitute the general framework or control for the subdivision work, and that the *township* lines in turn are rated higher than the *section* lines. It is the obvious intention, and has been the general practice, to secure a somewhat higher degree of accuracy for the more important lines by awarding them to the more experienced and skilful deputies, while inexperienced or less skilful surveyors were employed on subdivision work. It follows from this that

* Manual of Surveying Instructions for the Survey of the Public Lands issued by the Commissioner of the General Land Office, Washington, D. C.

† Act of Congress approved, March 3, 1905.

in the relocation of lost corners more weight may properly be given to the more important lines.

TABLE SHOWING PRESCRIBED RATES OF PAYMENT PER LINEAR MILE FOR SURVEYING PUBLIC LANDS.

	Standard and Meander Lines.	Township Lines.	Section Lines.
Minimum rates: to be used under ordinarily favorable conditions.	$ 9	$ 7	$ 5
Intermediate rates: to be applicable to lands "heavily timbered, mountainous, or covered with dense undergrowth, but not exceptionally difficult to survey."	$13	$11	$ 7
Maximum rates: to be allowed only in cases of exceptional difficulties in the surveys.	$18	$15	$12
Special maximum rates: to be allowed in cases of exceptional difficulties in the surveys, in certain remote districts, at the discretion of the Secretary of the Interior.	$25	$23	$20

In the following named States and Territories the surveying of Public Lands is still (1915) in progress, the work being under the supervision of Surveyors General.

Alaska.	Louisiana.	South Dakota.
Arizona.	Montana.	Utah.
California.	Nevada.	Washington.
Colorado.	New Mexico.	Wyoming.
Idaho.	Oregon.	

155. Process of Subdivision. — It will be convenient to consider the process of subdivision as separated into several distinct operations, to be carried out in sequence. It must be understood, however, that one operation, for instance, the division of the area into 24-mile tracts, is rarely or never completed over the entire

area to be covered before the next operation in order is begun; a single surveying camp may be carrying on two or three different operations before removing from the neighborhood, for example, running township exteriors and immediately afterward subdividing the townships into sections.

Briefly stated, the subdivision work is carried on as follows:

FIRST. The establishment of

(a) An *Initial Point* by astronomical observations.

(b) A *Principal Meridian* conforming to a true meridian of longitude through the Initial Point, and extending both north and south therefrom, and

(c) A *Base-Line* conforming to a true parallel of latitude



FIG. 57. SHOWING DIVISION INTO 24-MILE BLOCKS.

through the Initial Point, and extending both east and west therefrom. This initial operation is indicated in Fig. 57.

Evidently the principal meridian will be marked out on the ground as a straight line, while the base-line will follow the curve of a due east and west line, being at every point at right angles to

the meridian through that point. The field methods prescribed for running out the principal meridian and the base-line on the ground are described in detail in Arts. 159–60, pp. 129–31.

SECOND. The division of the area to be surveyed into tracts approximately 24 miles square (Fig. 57) by the establishment of

(a) *Standard Parallels* conforming to true parallels of latitude through the 24-mile points previously established on the principal meridian, and extending both east and west therefrom, and

(b) *Guide Meridians* conforming to true meridians of longitude through the 24-mile points previously established on the base-line and standard parallels, and extending north therefrom to an intersection with the next standard parallel or to the base-line.

Since the guide meridians converge, these 24-mile tracts will be 24 miles wide on their southern and somewhat less than this on their northern boundaries. Theoretically, both the east and the west boundaries should be just 24 miles in length, but, owing to discrepancies of field measurements, this is rarely or never the case.

THIRD. The division of each 24-mile tract into *Townships*, each approximately 6 miles square, by the establishment of

(a) Meridional lines, usually called *Range Lines*, conforming to true meridians through the standard township corners previously established at intervals of 6 miles on the base-line and standard parallels, and extending north therefrom to an intersection with the next standard parallel, or to the base-line, and

(b) Latitudinal lines, sometimes called *Township Lines*, joining the township corners previously established at intervals of 6 miles on the principal meridian, guide meridians, and range lines. The division resulting from the first three operations is indicated in Fig. 58.

It will be apparent that, neglecting the effect of discrepancies and irregularities in measurement, both the east and the west boundaries of all townships will be just 6 miles in length, but the north and south boundaries will vary in length from a maximum at the standard parallel or base-line forming the southern limit of the 24-mile tract to a minimum at that forming its northern limit.

FOURTH. The subdivision of each township into *Sections*, each approximately 1 mile square and containing about 640 acres, by the establishment of *Section Lines*, both meridional and latitudinal, parallel to and at intervals of 1 mile from the eastern and southern boundaries of the township. (See Fig. 63, p. 147.)



FIG. 58. SHOWING SUBDIVISION OF 24-MILE BLOCKS INTO TOWNSHIPS.

Assuming all fieldwork to be done with mathematical exactness, this subdivision would result in sections exactly 80 chains (1 mile) on each of the four sides,* except the most westerly range of 6 sections in each township, which would be less than 80 chains in width by an amount varying with the distance from the southern boundary of the 24-mile tract. The extent to which this condition is realized in practice is indicated in Art. 167, p. 139, wherein the usual field methods of subdividing a township are described in detail.

* These theoretical Sections would not be exactly square, as may be readily perceived, but would be rhomboids.

156. Methods of Designating Lines and Areas. — The various principal meridians and base-lines of the Public Lands Surveys are designated by definite names or by number, as, for example, "The Fifth Principal Meridian and Base-Line," or "The Cimarron Meridian."

The standard parallels are numbered in order both north and south from the base-line, and are so designated. The guide meridians are numbered in a similar manner east and west from the principal meridian. Fig. 57 illustrates the method.

Any series of contiguous townships or sections situated north and south of each other constitutes a *range*, while such a series situated in an east and west direction constitutes a *tier*.

The tiers of townships are numbered in order, to both the north and the south, beginning with number 1 at the base-line; and the ranges of townships are numbered to both the east and the west, beginning with number 1 at the principal meridian. A township is designated, therefore, by its serial number north or south of the base-line followed by its number east or west of the principal meridian, as "Township 7 south, Range 19 east, of the Sixth Principal Meridian." This is usually shortened to "T. 7 S., R. 19 E., 6th P. M."

6	5	4	3	2	1
7	8	9	10	11	12
18	17	16	15	14	13
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36

FIG. 59. DIAGRAM OF A TOWNSHIP ILLUSTRATING METHOD OF NUMBERING THE SECTIONS.

The sections of a township are numbered commencing with No. 1 at the northeast angle of the township, and proceeding west to No. 6, and then proceeding east to No. 12, and so on, alternately, to No. 36, in the southeast angle as illustrated by Fig. 59. In all cases of surveys of fractional townships the sections will bear the same numbers they would have if the township were complete.

The regular subdivisions of a Section are indicated by stating

briefly the aliquot part of the section intended together with its location in the section, as "the N. $\frac{1}{2}$ of the S.W. $\frac{1}{4}$ of Sec. 27, T. 12 N., R. 5 W."

157. Field Methods. — The work of subdivision of the Public Lands has already been largely completed, and the surveyor of to-day is usually concerned only with the retracing of old lines, the relocation of lost corners, or with the subdivision work that comes with increase in population. For all these, however, a thoroughgoing knowledge of at least the common field processes and methods that have been used in the original surveys is essential. Certain details of field practice have varied somewhat from time to time, but the leading features have remained fairly constant for all those areas that have been surveyed since the system became well established.

In the following pages is given a somewhat detailed description of the methods commonly employed in carrying out the operations briefly indicated in Art. 155. Inasmuch, however, as certain of the east and west lines are required to be established as true parallels of latitude, the two commonly accepted methods of accomplishing this will first be described.

158. To Establish a Parallel of Latitude. — A parallel of latitude on the surface of a sphere is a curved line. This may be understood from the facts that the meridians converge toward the pole, and that a parallel is at every point at right angles to the meridian at that point. If vertical lines are drawn through every point on a parallel of latitude they will form a conical surface, the apex of the cone being at the center of the sphere. In the case of a straight line all of the verticals would lie in the same plane, and this plane would intersect the sphere in a great circle.

A parallel of latitude may be run out by means of the solar attachment to the transit, since by using this instrument the direction of the meridian may be quickly found whenever the sun is visible (Art. 85, p. 66). A line which at every point is at right angles to the meridian will be a true parallel of latitude. This method, however, is found to give results less accurate than are required, chiefly on account of the errors in the adjustment of the solar attachment.

A better method of establishing a parallel is by taking offsets from a straight line. Two methods of doing this, known as the *Secant Method* and the *Tangent Method*, are used in the Public Lands Surveys.

159. The Secant Method.* — (Fig. 60.) "This method consists of running a connected series of straight lines, each six miles long, on such courses that any one of the lines will intersect the curve of the parallel of latitude in two points, separated by an interval of four miles; and from this line thus established, measuring north or south, as the case may be, to attain other required



FIG. 60. SECANT METHOD FOR ESTABLISHING A PARALLEL OF LATITUDE.

points on the latitude curve." The 0 and 6 mile points of a parallel will be north of the secant, and the 2, 3, and 4 mile points will be south of the secant.

The instrument is set up south of the township corner where the survey is to begin, the distance from the corner being found in Table 4 in the column headed "0 miles." For example, in latitude 40° the transit would be set 2.79 feet south of the corner. The direction of the first secant at its initial point is found by observing on Polaris (Chapter VIII) to obtain the true meridian and then laying off the azimuth angle found in Table 4 under "0 miles." (See Fig. 60.) This angle should be repeated several times to determine accurately the direction of the secant. This direction is then prolonged 6 miles. At each mile and half-mile point an offset is measured to establish a point on the curve, the distance and direction of the offset being shown in Table 3.

* The quotations are from the "Manual of Surveying Instructions for the Survey of the Public Lands of the United States," prepared by the Commissioner of the General Land Office in 1902.

TABLE 3.

Azimuths of the Secant, and Offsets, in Feet, to the Parallel.

Latitude in left-hand column and distance from starting point at top or bottom of the table.

Latitude	Azimuths and offsets at —							Deflection Angle and nat. tan. to Rad. 66 ft
	0 miles.	½ mile.	1 mile.	1½ miles.	2 miles.	2½ miles.	3 miles.	
°								
30	89° 58′.5 1.93 N.	89° 58′.7 0.87 N.	89° 59′.0 0.00	89° 59′.2 0.67 S.	89° 59′.5 1.15 S.	89° 59′.7 1.44 S.	90° (E. or W.) 1.54 S.	3′ 00″.2 0.69 ins.
31	89° 58′.4 2.01 N.	89° 58′.6 0.91 N.	89° 58′.9 0.00	89° 59′.2 0.70 S.	89° 59′.5 1.20 S.	89° 59′.7 1.50 S.	90° (E. or W.) 1.60 S.	3′ 07″.4 0.72 ins.
32	89° 58′.4 2.09 N.	89° 58′.6 0.94 N.	89° 58′.9 0.00	89° 59′.2 0.73 S.	89° 59′.5 1.25 S.	89° 59′.7 1.56 S.	90° (E. or W.) 1.67 S.	3′ 15″.0 0.75 ins.
33	89° 58′.3 2.17 N.	89° 58 .5 0.97 N.	89° 58′.8 0.00	89° 59′.1 0.76 S.	89° 59′.4 1.30 S.	89° 59′.7 1.62 S.	90° (E. or W.) 1.73 S.	3′ 22″.6 0.78 ins.
34	89° 58′.2 2.25 N.	89° 58′.5 1.01 N.	89° 58′.8 0.00	89° 59′.1 0.79 S.	89° 59′.4 1.35 S.	89° 59′.7 1.69 S.	90° (E. or W.) 1.80 S.	3′ 30″.4 0.81 ins.
35	89° 58′.2 2.33 N.	89° 58′.5 1.05 N.	89° 58′.8 0.00	89° 59′.1 0.82 S.	89° 59′.4 1.40 S.	89° 59′.7 1.75 S.	90° (E. or W.) 1.87 S.	3′ 38″.4 0.84 ins.
36	89° 58′.1 2.42 N.	89° 58′.4 1.09 N.	89° 58′.7 0.00	89° 59′.0 0.85 S.	89° 59′.4 1.46 S.	89° 59′.7 1.82 S.	90° (E. or W.) 1.94 S.	3′ 46″.4 0.87 ins.
37	89° 58′.0 2.51 N.	89° 58′.3 1.13 N.	89° 58′.6 0.00	89° 58′.9 0.88 S.	89° 59′.3 1.51 S.	89° 59′.7 1.89 S.	90° (E. or W.) 2.01 S	3′ 55″.0 0.90 ins.
38	89° 58′.0 2.61 N.	89° 58′.3 1.17 N.	89° 58′.6 0.00	89° 58′.9 0.91 S.	89° 59′.3 1.56 S.	89° 59′.7 1.95 S.	90° (E. or W. 2.08 S.)	4′ 03″.6 0.93 ins.
39	89° 57′.9 2.70 N.	89° 58′.2 1.21 N.	89° 58′.6 0.00	89° 58′.9 0.94 S.	89° 59′.3 1.62 S.	89° 59′.7 2.02 S.	90° (E. or W.) 2.16 S.	4′ 12″.6 0.97 ins.
40	89° 57′.8 2.79 N.	89° 58′.1 1.25 N.	89° 58′.5 0.00	89° 58′.9 0.98 S.	89° 59′.3 1.68 S.	89° 59′.7 2.10 S.	90° (E. or W.) 2.24 S.	4′ 21″.6 1.00 ins.
41	89° 57′.7 2.89 N.	89° 58′.0 1.30 N.	89° 58′.4 0.00	89° 58′.8 1.02 S.	89° 59′.2 1.74 S.	89° 59′.6 2.17 S.	90° (E. or W.) 2.32 S.	4′ 31″.2 1.04 ins.
42	89° 57′.7 3.00 N.	89° 58′.0 1.35 N.	89° 58′.4 0.00	89° 58′.8 1.05 S.	89° 59′.2 1.80 S.	89° 59′.6 2.25 S.	90° (E. or W.) 2.40 S.	4′ 40″.8 1.08 ins.
43	89° 57′.6 3.11 N.	89° 58′.0 1.40 N.	89° 58′.4 0.00	89° 58′.8 1.08 S.	89° 59′.2 1.86 S.	89° 59′.6 2.33 S.	90° (E. or W.) 2.48 S.	4′ 50″.8 1.12 ins.
44	89° 57′.5 3.22 N.	89° 57′.9 1.45 N.	89° 58′.3 0.00	89° 58′.7 1.12 S.	89° 59′.2 1.93 S.	89° 59′.6 2.41 S.	90° (E. or W.) 2.57 S.	5′ 01″.0 1.16 ins.
45	89° 57′.4 3.33 N.	89° 57′.8 1.50 N.	89° 58′.3 0.00	89° 58′.7 1.16 S.	89° 59′.1 2.00 S.	89° 59′.5 2.49 S.	90° (E. or W.) 2.66 S	5′ 11″.8 1.20 ins.
46	89° 57′.3 3.44 N.	89° 57′.7 1.55 N.	89° 58′.2 0.00	89° 58′.6 1.21 S.	89° 59′.1 2.07 S.	89° 59′.5 2.59 S.	90° (E or W.) 2.76 S.	5′ 22″.8 1.24 ins.
47	89° 57′.2 3.57 N.	89° 57′.6 1.61 N.	89° 58′.1 0.00	89° 58′.6 1.25 S.	89° 59′.1 2.14 S.	89° 59′.5 2.67 S.	90° (E. or W.) 2.86 S.	5′ 34″.2 1.28 ins.
48	89° 57′.1 3.70 N.	89° 57′.5 1.66 N.	89° 58′.0 0.00	89° 58′.5 1.30 S.	89° 59′.0 2.22 S.	89° 59′.5 2.78 S.	90° (E. or W.) 2.96 S.	5′ 46″.2 1.33 ins.
49	89° 57′.0 3.82 N.	89° 57′.5 1.72 N.	89° 58′.0 0.00	89° 58′.5 1.34 S.	89° 59′.0 2.30 S.	89° 59′.5 2.87 S.	90° (E. or W.) 3.06 S.	5′ 58″.6 1.38 ins.
50	89° 56′.9 3.96 N.	89° 57′.4 1.78 N.	89° 57′.9 0.00	89° 58′.4 1.39 S.	89° 59′.0 2.38 S.	89° 59′.5 2.97 S.	90° (E. or W.) 3.17 S.	6′ 11″.4 1.43 ins.

Latitude.	6 miles.	5½ miles.	5 miles.	4½ miles.	4 miles.	3½ miles.	3 miles.	Deflection Angle and nat. tan. to Rad. 66 ft.
	Azimuths and offsets at —							

When the 6-mile point is reached the direction of a new secant is found by turning off to the north the deflection angle given in the right-hand column of Table 3. The offsets are then measured from this line as from the preceding one. The chief advantage of this method is that the offsets are short and hence much cutting is saved in wooded regions.

"With ordinary field instruments, usually reading to single minutes only, fractional parts of the 'least count' are generally estimated by the eye. Greater accuracy may be attained by making use of a linear measure to lay off deflection angles." In the right-hand column of Table 3 are given linear dimensions



FIG. 61. TANGENT METHOD FOR ESTABLISHING A PARALLEL OF LATITUDE.

suitable for use in laying off the deflection angles corresponding to the various latitudes noted. In using this extremely valuable method of laying off small angles, a point is first carefully marked, by double centering, at a distance of one chain (66 feet) from the instrument. A scale divided to decimals of an inch is then used to measure off toward the north the appropriate distance taken from the Table, and the vertical cross-wire of the transit is moved through the angle subtended. The reading of the vernier will check the measurement and guard against large errors. The direction thus determined is then prolonged in the usual manner.

160. "The Tangent Method." — This method consists in laying off from a true meridian, established by observations on Polaris at elongation, an angle of 90°, producing the direction thus determined, a distance of 6 miles, in a straight line, and

TABLE 4.

AZIMUTHS OF THE TANGENT TO THE PARALLEL.

[The azimuth is the smaller angle the tangent makes with the true meridian and always measured from the north and towards the tangential points.]

Latitude.	1 mile.	2 miles.	3 miles.	4 miles.	5 miles.	6 miles.
°	° ′ ″	° ′ ″	° ′ ″	° ′ ″	° ′ ″	° ′ ″
30	89 59 30.0	89 58 59.9	89 58 29.9	89 57 59.9	89 57 29.9	89 56 59.8
31	89 59 28.8	89 58 57.5	89 58 26.3	89 57 55.0	89 57 23.8	89 56 52.5
32	89 59 27.5	89 58 55.0	89 58 22.5	89 57 50 0	89 57 17.5	89 56 45.0
33	89 59 26.2	89 58 52.5	89 58 18.7	89 57 44.9	89 57 11.2	89 56 37.4
34	89 59 24.9	89 58 49.9	89 58 14.8	89 57 39.7	89 57 04.6	89 56 29.6
35	89 59 23.6	89 58 47.2	89 58 10.8	89 57 34.4	89 56 58.0	89 56 21.6
36	89 59 22.2	89 58 44.4	89 58 06.8	89 57 28.9	89 56 51.1	89 56 13.4
37	89 59 20.8	89 58 41.6	89 58 02.5	89 57 23.3	89 56 44.1	89 56 05.0
38	89 59 19.4	89 58 38.8	89 57 58.2	89 57 17.5	89 56 36.9	89 55 56.3
39	89 59 17.9	89 58 35.8	89 57 53.7	89 57 11.6	89 56 29.6	89 55 47.5
40	89 59 16.4	89 58 32.8	89 57 49.2	89 57 05.5	89 56 21.9	89 55 38.3
41	89 59 14.8	89 58 29.6	89 57 44.4	89 56 59.3	89 56 14.1	89 55 28.9
42	89 59 13.2	89 58 26.4	89 57 39.6	89 56 52.8	89 56 06.0	89 55 19.2
43	89 59 11.5	89 58 23.1	89 57 34.6	89 56 46.2	89 55 57.7	89 55 09.2
44	89 59 09.8	89 58 19.6	89 57 29.5	89 56 39.3	89 55 49.1	89 54 58.9
45	89 59 08.0	89 58 16.1	89 57 24.1	89 56 32.1	89 55 40.2	89 54 48.2
46	89 59 06.2	89 58 12.4	89 57 18.6	89 56 24.8	89 55 31.0	89 54 37.2
47	89 59 04.3	89 58 08.6	89 57 12.9	89 56 17.1	89 55 21.4	89 54 25.7
48	89 59 02.3	89 58 04.6	89 57 06.9	89 56 09.2	89 55 11.5	89 54 13.8
49	89 59 00.2	89 58 00.5	89 57 00.7	89 56 00.9	89 55 01.2	89 54 01.4
50	89 58 58.1	89 57 56.2	89 56 54.3	89 55 52.6	89 54 50.5	89 53 48.5

Latitude.	7 miles.	8 miles.	9 miles.	10 miles.	11 miles.	12 miles.
°	° ′ ″	° ′ ″	° ′ ″	° ′ ″	° ′ ″	° ′ ″
30	89 56 29.8	89 55 59.8	89 55 29.8	89 54 59.7	89 54 29.7	89 53 59.7
31	89 56 21.3	89 55 50.0	89 55 18.8	89 54 47.6	89 54 16.3	89 53 45.1
32	89 56 12.5	89 55 40.0	89 55 07.6	89 54 35.1	89 54 02.6	89 53 30.1
33	89 56 03.6	89 55 29.9	89 54 56.1	89 54 22.3	89 53 48.5	89 53 14.8
34	89 55 54.5	89 55 19.4	89 54 44.4	89 54 09.3	89 53 34.2	89 52 59.1
35	89 55 45.2	89 55 08.8	89 54 32.3	89 53 55.9	89 53 19.5	89 52 43.1
36	89 55 35.6	89 54 57.8	89 54 20.0	89 53 42.3	89 53 04.5	89 52 26.7
37	89 55 25.8	89 54 46.6	89 54 07.4	89 53 28.2	89 52 49.1	89 52 09.9
38	89 55 15.7	89 54 35.1	89 53 54.5	89 53 13.9	89 52 33.2	89 51 52.6
39	89 55 05.4	89 54 23.3	89 53 41.2	89 52 59.1	89 52 17.0	89 51 34.9
40	89 54 54.7	89 54 11.1	89 53 27.5	89 52 43.8	89 52 00.2	89 51 16.6
41	89 54 43.7	89 53 58.5	89 53 13.4	89 52 28.2	89 51 43.0	89 50 57.8
42	89 54 32.4	89 53 45.6	89 52 58.8	89 52 12.0	89 51 25.2	89 50 38.4
43	89 54 20.8	89 53 32.3	89 52 43.8	89 51 55.4	89 51 06.9	89 50 18.5
44	89 54 08.7	89 53 18.5	89 52 28.4	89 51 38.2	89 50 48.0	89 49 57.8
45	89 53 56.3	89 53 04.3	89 52 12.3	89 51 20.4	89 50 28.4	89 49 36.4
46	89 53 43.4	89 52 49.5	89 51 55.7	89 51 01.9	89 50 08 1	89 49 14.3
47	89 53 30.0	89 52 34.3	89 51 38.6	89 50 42.9	89 49 47.2	89 48 51.4
48	89 53 16.1	89 52 18.4	89 51 20.7	89 50 23.0	89 49 25.3	89 48 27.6
49	89 53 01.7	89 52 01.9	89 51 02.1	89 50 02.4	89 49 02.6	89 48 02.8
50	89 52 46.6	89 51 44.7	89 50 42.8	89 49 40.9	89 48 39.0	89 47 37.1

TABLE 5.

Offsets, in Feet, from Tangent to Parallel.

Latitude.	1 mile	2 miles	3 miles.	4 miles.	5 miles.	6 miles.
30°	0.38	1.54	3.46	6.15	9.61	13.83
31	0.40	1.60	3.60	6.40	10.00	14.40
32	0.42	1.66	3.74	6.65	10.40	14.97
33	0.43	1.73	3.89	6.91	10.80	15.56
34	0.45	1.80	4.04	7.18	11.22	16.16
35	0.47	1.86	4.19	7.45	11.65	16.77
36	0.48	1.93	4.35	7.73	12.09	17.40
37	0.50	2.01	4.51	8.02	12.53	18.05
38	0.52	2.08	4.68	8.32	12.99	18.71
39	0.54	2.15	4.85	8.62	13.47	19.39
40	0.56	2.23	5.02	8.93	13.95	20.09
41	0.58	2.31	5.20	9.25	14.46	20.81
42	0.60	2.40	5.39	9.58	14.97	21.56
43	0.62	2.48	5.58	9.92	15.50	22.33
44	0.64	2.57	5.78	10.28	16.06	23.12
45	0.67	2.66	5.99	10.64	16.62	23.94
46	0.69	2.75	6.20	11.02	17.21	24.79
47	0.71	2.85	6.42	11.41	17.83	25.67
48	0.74	2.95	6.65	11.81	18.46	26.58
49	0.76	3.06	6.88	12.24	19.12	27.53
50	0.79	3.17	7.13	12.68	19.81	28.52

Latitude.	7 miles.	8 miles.	9 miles.	10 miles.	11 miles.	12 miles.
30	18.83	24.59	31.13	38.43	46.50	55.33
31	19.59	25.59	32.39	39.99	48.39	57.58
32	20.38	26.61	33.68	41.58	50.32	59.88
33	21.18	27.66	35.00	43.22	52.29	62.23
34	21.99	28.73	36.36	44.88	54.31	64.63
35	22.83	29.82	37.74	46.59	56.38	67.09
36	23.69	30.94	39.16	48.34	58.49	69.61
37	24.57	32.09	40.61	50.13	60.66	72.19
38	25.47	33.27	42.10	51.98	62.89	74.85
39	26.40	34.48	43.63	53.87	65.18	77.57
40	27.35	35.72	45.21	55.82	67.54	80.38
41	28.33	37.01	46.83	57.82	69.96	83.26
42	29.34	38.33	48.51	59.89	72.46	86.24
43	30.39	39.69	50.24	62.02	75.04	89.31
44	31.47	41.10	52.02	64.22	77.71	92.48
45	32.58	42.56	53.86	66.50	80.46	95.76
46	33.74	44.07	55.78	68.86	83.32	99.16
47	34.94	45.63	57.76	71.30	86.28	102.68
48	36.18	47.26	59.81	73.84	89.35	106.33
49	37.48	48.95	61.95	76.48	92.54	110.13
50	38.82	50.71	64.17	79.23	95.87	114.09

measuring north therefrom, at half-mile intervals, distances of correct length, taken from Table 5 (interpolated if necessary), for the given latitude, to attain other points on the latitude curve passing through the tangential or initial points.

"The azimuth or bearing of the tangent at successive mile points will be taken from Table 4 to the nearest whole minute only, and will be inserted in the field notes, no interpolation being required, except when test sights are taken. The true bearing between two points on a standard parallel will be derived from Table 4 by taking it in the column headed with one-half the distance between said points. The offsets at intervals of one mile are inserted in Table 5; to obtain the length of offsets at the half-mile points, take one-fourth of the offset corresponding to twice the distance of the half-mile point from the tangential point.

"This method is suitable for running standard parallels and latitudinal township lines in a level open country, where no intersections with topographical features will be required; but in all cases the secant method will be found most convenient."

"**161. Initial Points.** — Initial points from which the lines of the public surveys are to be extended will be established whenever necessary, under such special instructions as may be prescribed in each case by the Commissioner of the General Land Office. The locus of such initial points will be selected with great care and due consideration for their prominence and easy identification, and must be established astronomically.

"An initial point should have a conspicuous location, visible from distant points on lines; it should be perpetuated by an indestructible monument, preferably a copper bolt firmly set in a rock edge; and it should be witnessed by rock bearings, without relying on anything perishable like wood."

162. Base-Line. — From the initial point the base-line is extended both east and west on a true parallel of latitude, one of the methods described in the foregoing paragraphs being used. Great care is taken to secure instrumental accuracy. Two back and two fore sights are taken at each setting of the instrument, the horizontal limb being revolved 180° in azimuth between the observations, in one method, taking the mean of observations. Another method, called double back and fore

sights, is still more exact, and therefore preferable. In this process the vertical cross-wire is fixed upon two transit points at some distance apart, in the rear, and then reversed to set one or two new points in advance. This not only insures a straight line, if the transit is leveled, but also detects the least error of collimation. (See Art. 64, p. 52.)

"Where solar apparatus is used in connection with a transit, the deputy will test the instrument, whenever practicable, by comparing its indications with a meridian determined by Polaris observations; and in all cases where error is discovered he will make the necessary corrections of his line before proceeding with the survey. All operations will be fully described in the field notes.

"In order to detect errors and insure accuracy in measurement, two sets of chainmen will be employed; one to note distances to intermediate points and to locate topographical features, the other to act as a check. Each will measure 40 chains, and in case the difference is inconsiderable, the proper corner will be placed midway between the ending points of the two measurements; but if the discrepancy exceed 8 links on even ground, or 25 links on mountainous surface, the true distance will be found by careful re-chaining by one party or both.

"The deputy will be present when each corner is thus established, and will record in the body of his field notes the distances to the same, according to the measurement by each set of chainmen.

"To obviate collusion between the sets of chainmen, the second set should commence at a point in advance of the beginning corner of the first set, the initial difference in measurement thus obtained being known only to the deputy."

The proper township, section, and quarter-section corners are established at the appropriate intervals, and meander and witness corners (Arts. 171–3, pp. 148–9). are set wherever the line crosses such streams, lakes, bayous, or other objects as may make their use necessary. Stones or posts used to mark the positions of the township or section corners are marked on their north face with the letters *SC*, for "standard corner," for

the purpose of easily distinguishing them from the "closing corners," to be set later.

163. Principal Meridian. — The principal meridian is extended as a true meridian of longitude both north and south from the initial point. The methods used for the determination of directions, and the precautions observed to secure accuracy of measurement, are the same as those described in the preceding article, under the subject of "Base-Line."

Also, as in the case of the base-line, all township, section, quarter-section, and other necessary corners are established in the proper places as the survey proceeds.

164. Standard Parallels. — Standard parallels, which are also sometimes referred to as *correction lines*, are extended both east and west from every fourth township corner previously established on the principal meridian. Sometimes, however, the distance between them is more or less than 24 miles, depending upon the requirements of the particular survey in question. For example, in Kansas the correction lines occur at regular intervals of 30 instead of 24 miles. In all cases deviations from the regular order are made only under the written special instructions of the Surveyor General. The Manual provides further that "where gross irregularities (in previous surveys) require additional standard lines, from which to initiate new, or upon which to close old surveys, an intermediate correction line should be established to which a local name may be given, e.g., 'Cedar Creek Correction Line'; and the same will be run, in all respects, like the regular standard parallels."

Standard parallels are established as true parallels of latitude, and are run in the same manner and with the same precautions for accuracy as in the survey of the base-line.

Appropriate corners are established at the proper intervals, and the township and section corners are marked *SC* on their north face, the same as those on the base-line.

165. Guide Meridians. — Guide meridians are extended north from the base-line, or standard parallels, at intervals of 24 miles east and west from the principal meridian. They are run as true meridians of longitude, and are extended to an intersection with the next correction line north. At the point of intersection

of the guide meridian with the correction line a *closing corner* is established, and the stone or post is marked on its south face with the letters *CC*, to distinguish it from the standard corners already in place. Also, the distance of the closing corner from the nearest standard corner is measured and recorded in the field notes. This correction offset will vary with the latitude and with the distance of the corner from the principal meridian. At a distance of 15 or 20 ranges from the principal meridian it may be so great that the closing corner will be nearer to the adjacent quarter-section corner than to the standard township corner. Furthermore, it is obvious that the closing corners will be west of the corresponding standard corners on the east side of the principal meridian, and east of them on the west side.

The mile and half-mile distances on the guide meridians are made full 80 and 40 chains in length until the last half-mile is reached, into which all excess or deficiency due to discrepancies of measurement is thrown.

The general method of running the guide meridians is the same as that used in running the principal meridian, and all the provisions for securing accuracy of alignment and measurement, and for establishing corners, prescribed for the latter apply to the former also.

Provision is made for running guide meridians from north to south where existing local conditions require this departure from the usual practice. In such a case the closing corner is first established on the correction line by calculating the proper correction distance and laying it off from the standard corner; and then the guide meridian is run due south from this point. This method may be used in case the standard corner from which the guide meridian would ordinarily originate is inaccessible, or for other adequate reasons.

The Manual also provides that " where guide meridians have been improperly placed at intervals greatly exceeding the authorized distance of 24 miles, and standard lines are required to limit errors of old, or govern new surveys, a new guide meridian may be run from a standard, or properly established closing corner, and a local name may be assigned to the same, e.g., 'Grass Valley

Guide Meridian.' These additional guide meridians will be surveyed in all respects like regular guide meridians."

166. Township Exteriors. — The usual method of subdividing a 24-mile tract into townships is as follows (see Fig. 58).

Beginning at the standard corner at the southeast corner of the southwest township in the tract, the surveyor runs north on a true meridian of longitude a distance of 6 miles, setting all necessary corners by the way. From the township corner thus established he runs due west on a random line (Art. 199, p. 177) to intersect the guide meridian (or the principal meridian, in case he is working in Range 1 East), setting temporary section and quarter-section corners as he goes. When he intersects the meridian, he notes the "falling" * of his random line, and, in case this is within the limit prescribed, he then calculates the course of the true line joining the two township corners and runs back on it, setting permanent corners opposite the temporary ones previously set on the random line. In this way all the deficiency due to the convergence of the meridional boundaries of the township, together with whatever excess or deficiency may arise from inaccuracies in measurement, are thrown into the most westerly half-mile of the latitudinal boundary.

The range line is now continued as a true meridian for another 6 miles, permanent corners being set as before. Then another random line is thrown across to the western boundary of the range of townships, and is corrected back to the true line, in the same manner as that just described. This process is continued until the most northerly township in the 24-mile tract is reached, when the range line is merely continued as a true meridian to an intersection with the correction line, at which point a closing township corner is established. The half-mile intervals on the range line are made full 40 chains for the entire 24 miles, except the most northerly half-mile, into which all excess or deficiency due to irregularities of measurement is thrown.

The two other range lines of the 24-mile block are run in a similar manner, the latitudinal township lines being extended to

* That is, the distance of the point at which the random line intersects the meridian from the objective corner.

the westward at the proper intervals and made to connect with the township corners previously established. From the township corners on the last range line, however, random lines are run also to the eastward to meet the guide meridian, and are then corrected back to the westward on a true line between the township corners. This is done in such a way that the excess or deficiency of this line also is thrown into the most westerly half-mile.

"In cases where impassable obstacles occur and the foregoing rules cannot be complied with, township corners will be established as follows:

"In extending the south or north boundaries of a township to the west, where the southwest or northwest corners cannot be established in the regular way by running a north and south line, such boundaries will be run west on a true line, allowing for convergency on the west half-mile; and from the township corner established at the end of such boundary, the west boundary will be run north or south, as the case may be. In extending south or north boundaries of a township to the east, where the southeast or northeast corner cannot be established in the regular way, the same rule will be observed, except that such boundaries will be run east on a true line, and the east boundary run north or south, as the case may be. Allowance for the convergency of meridians will be made whenever necessary."

The Manual provides for a maximum allowable limit for closing the random line upon the township corner, as follows: "If in running a random township exterior, such random exceeds or falls short of its proper length by more than 3 chains, allowing for convergency, or falls more than 3 chains to the right or left of the objective point (or shows a proportionate error for lines of greater or less length than 6 miles), it will be re-run, and if found correctly run, so much of the remaining boundaries of the township will be retraced, or resurveyed, as may be found necessary to locate the cause of misclosure." A lateral displacement of 3 chains in a distance of 6 miles is equivalent to an angular deviation of 21 minutes.

167. Subdivision of Townships. — In the subdivision of a township into sections the following routing is followed in the field. The surveyor sets up his instrument at the southeast

corner of the township, observes the meridian, and retraces the range line northward for a distance of one mile, and the township line westward for the same distance. This is for the purpose of comparing his own meridian and needle observations and the length of his chain with those of the previous surveyor who laid off the township exteriors.* Then from the southwest corner of Section 36 he runs north on a line parallel with the east boundary of the township, setting a quarter-section corner at 40 chains and a section corner at 80 chains. Then from the section corner just set he runs east on a random line, parallel to the south boundary of the section, setting a temporary quarter-section corner at 40 chains. When he intersects the range line he notes the falling of his random and also the distance it overruns or falls short of the length of the south boundary of the section. If the falling is not more than 50 links (33 feet, representing an angular deviation of 21 minutes), and if the distance overruns or falls short of the length of the southern boundary of Section 36 by not more than the same amount, a return course which will join the two section corners is calculated; this new line is then run toward the west, the permanent quarter-section corner being set at its middle point.

From the section corner just regained the survey is now continued north between Sections 25 and 26, the direction being changed slightly to the east or west according to whether the latitudinal section line just completed exceeded or fell short of the desired length. At 40 and 80 chains on this line the quarter-section and section corners, respectively, are set, and from the section corner a random is run across to the range line, and a return course is calculated and run as before. This process is continued until five of the six sections in the series are inclosed. Then, if the north boundary of the township is not a correction line, from the section corner last established a random is run north to the township boundary, and from the data thus secured a true line is calculated and run from the section corner on the township line back to the initial corner. If the north boundary of the township is a correction line, however, the point at which

* See specimen field notes, p. 144.

the random intersects this boundary is established as a **closing corner** and its distance from the nearest **standard corner** is measured and recorded. In either case the permanent quarter-section corner is established at 40 chains north of the initial corner, the excess or deficiency being thrown into the most northerly half-mile.

In a similar manner the succeeding ranges of sections are enclosed, randoms being run across eastward to the section corners previously established and true lines corrected back. From the fifth series of section corners thus established, however, random lines are projected to the westward also, and are closed on the corresponding section corners in the range line forming the western boundary of the township. In correcting these lines back, however, the permanent quarter-section corners are established at points 40 chains from the initial corners of the randoms, thereby throwing all fractional measurements into the most westerly half-miles. Reference to Figs. 62 and 63 will help toward an understanding of this method of subdivision.

Table 6, taken from the Manual, gives (to the nearest whole minute) the angular convergency of meridians from one to five miles apart. The meridional section lines, therefore, by reason of being (theoretically) parallel to the range line on the east boundary of the township, will depart from true meridians by the amounts indicated in the table.

TABLE 6.

CORRECTIONS FOR CONVERGENCY WITHIN A TOWNSHIP.

Latitude.	Correction to be applied to bearing of range lines at a distance of —				
	1 mile.	2 miles.	3 miles.	4 miles.	5 miles.
° °	′	′	′	′	′
30 to 35	1	1	2	2	3
35 to 40	1	1	2	3	3
40 to 45	1	2	2	3	4
45 to 50	1	2	3	4	5
50 to 55	1	2	3	5	6
55 to 60	1	3	4	5	7
60 to 65	2	3	5	7	8
65 to 70	2	4	6	8	10

From a consideration of the foregoing it will be apparent

(1) That interior meridional section lines are 80 chains in length, except those next to the north boundary of the township; and that the south half of these is 40 chains.

(2) That interior latitudinal section lines are within 50 links of the length of the line forming the southern boundary of the range of sections, except those section lines next to the west boundary of the township; and that the east half of these is 40 chains.

(3) That interior section lines, whether meridional or latitudinal, are ordinarily straight for one mile only.

(4) That except in those section lines next to the north and west boundaries of the township, the quarter-section corners are placed equidistant from the two section corners on either side.

(5) That meridional section lines are intended to be parallel to the range line forming the eastern boundary of the township; and similarly, that latitudinal section lines are intended to be parallel to the township line forming its southern boundary.

(6) That the cumulative deficiency in latitudinal lines due to the convergence of the meridians is thrown into the most westerly half-mile of the township.

(7) That no quarter-section closing corners are established on correction lines for the use of the sections south of these lines.

168. Fractional Sections. — In sections made fractional by rivers, lakes, or other bodies of water, lots are formed bordering on the body of water, and numbered consecutively through the section. The boundaries of these lots usually follow the quarter lines of the section, and contain, as nearly as may be, forty acres each. Fig. 62 indicates the method. Also, the quarter quarter sections along the north and west boundaries of a township, into which the discrepancies of measurements or the deficiencies due to the convergence of the range lines are to be carried when the sections are subdivided, are usually numbered and sold as lots. (See Art. 177, p. 157.) These lot lines are not actually run in the field, but, like the quarter-section lines, are merely indicated on the plates, and the areas by which the lots are sold are computed in the office.

Field notes taken in connection with the survey of public lands are required to be returned to the General Land Office in the narrative form. A sample page of notes, somewhat condensed from those given in the Manual, is herewith presented



FIG. 62. SHOWING PART OF A TYPICAL TOWNSHIP; ALSO SHOWING METHOD OF FORMING LOTS IN FRACTIONAL SECTIONS.

for its value not only as an illustration of a section line survey but also as an instructive example of this very valuable method of note keeping.

Fig. 62, taken from the Manual, shows the nine sections in the southeastern part of a typical township, and illustrates the specimen notes given on the following page.

SPECIMEN OF FIELD NOTES.

SUBDIVISION OF T. 15 N., R. 20 E.

Chains.	
	From the Tp. cor. already described,* I run
	North, on the 5th Guide Meridian and E. bdy. of sec. 36; and, at 40.01 chs., intersect the ¼ sec. cor.; and, at 79.98 chs., fall 1 lk. W. of the cor. of secs. 25, 30, 31, and 36; therefore, the line bears north.
	From the Tp. cor. I run N. 89° 57′ W., on the S. bdy. of sec. 36; at 39.99 chs., fall 0½ lk. N. of the ¼ sec. cor.; and at 80.01 chs. fall 1 lk. S. of the cor. of secs. 1, 2, 35, and 36, on S. bdy. of the Tp.; consequently, the S. bdy. of the sec. 36 bears N. 89° 57′ W.
	Therefore, the bearings are as stated by the surveyor general, and my chaining practically agrees with the field notes of the original survey.
	I commence at the cor. of secs. 1, 2, 35, and 36, on the S. bdy. of the Tp., which is a sandstone, 6 × 8 × 5 ins. above ground, firmly set, and marked and witnessed as described by the surveyor general.
	Thence I run
	N. 0° 01′ W., bet. secs. 35 and 36.
	Over level bottom land.
4.50	Wire fence, bears E. and W.
20.00	Enter scattering cottonwood timber, bears E. and W. F. G. Alexander's house bears N. 28° W.
29.30	Leave scattering cottonwoods, bearing E. and W.; enter road, bears N.
30.00	SE. cor. of F. G. Alexander's field; thence along west side of road.
39.50	To crossroads, bears E. to Mound City; N. to Lake City. F. G. Alexander's house bears S. 40° W. The ¼ sec. cor. point will fall in road; therefore
	Set a cedar post, 3 ft. long, 3 ins. sq., with quart of charcoal, 24 ins. in the ground, for witness cor .to ¼ sec. cor., marked W C ¼ S 35 on W. and 36 on E. face; dig pits, 18 × 18 × 12 ins. N. and S. of post, 3 ft. dist.; and raise a mound of earth 3½ ft. base, 1½ ft. high. W. of cor.
40.00	Point for ¼ sec. cor. in road.
	Deposit a marked stone, 24 ins. in the ground, for ¼ sec. cor.
	The SE. cor. of Pat. Curran's field bears W., 5 lks. dist.
40.50	Set a limestone, 15 × 8 × 6 ins. 10 ins. in the ground, for witness cor. to ¼ sec. cor., marked W C ¼ S on W. face; dig pits, 18 × 18 × 12 ins. N. and S. of stone, 3 ft. dist.; and raise a mound of earth, 3½ ft. base, 1½ ft. high, W. of cor.
	Thence along E. side of field.
50.50	NE. cor. of Pat. Curran's field, bears W. 4 lks. dist.
51.50	Leave road; which turns to N. 70° W., leads to ferry on Yellowstone River; thence to Lake City.
57.50	Enter dense cottonwood and willow undergrowth, bears N. 54° E. and S. 54° W.
72.50	Leave undergrowth, enter scattering timber, bears N. 60° E. and S. 60° W.
80.00	Set a locust post, 3 ft. long, 4 ins. sq., 24 ins. in the ground, for cor. of secs. 25, 26, 35 and 36, marked T 15 N S 25 on NE., R 20 E S 36 on SE., S 35 on SW., and S 26 on NW. face; with 1 notch on S. and E. faces; from which An ash, 13 ins. diam., bears N. 22° E., 26 lks. dist., marked T 15 N R 20 E S 25 B T. A sycamore, 23 ins. diam., bears S. 71¼° E., 37 lks. dist., marked T 15 N R 20 E S 36 B T. A walnut, 17 ins. diam., bears S. 64° W., 41 lks. dist., marked T 15 N R 20 E S 35 B T. A cottonwood, 13 ins. diam., bears N. 21¼° W., 36 lks. dist., marked T 15 N R 20 E S 26 B T.

* Description omitted. A description of the determination of a true meridian by both solar and Polaris observations is also omitted.

169. "Summary of objects and data intersected by the line or in its vicinity, to be noted. — 1. The precise course and length of every line run, noting all necessary offsets therefrom, with the reason for making them, and method employed.

"2. The kind and diameter of all bearing trees, with the course and distance of the same from their respective corners; and the precise relative position of witness corners to the true corners.

"3. The kind of materials of which corners are constructed.

"4. Trees on line. The name, diameter, and distance on line to all trees which it intersects.

"5. Intersections by line of land objects. The distance at which the line intersects the boundary lines of every reservation, town site, donation claim, Indian allotment, settler's claim, improvement, or rancho; prairie, bottom land, swamp, marsh, grove, and windfall, with the course of the same at all points of intersection; also, the distances at which the line begins to ascend, arrives at the top, begins to descend, and reaches the foot of all remarkable hills and ridges, with their courses, and estimated height in feet, above the level land of the surrounding country, or above the bottom lands, ravines, or waters near which they are situated. Also, distance to and across large ravines, their depth and course.

"6. Intersections by line of water objects. All rivers, creeks, and smaller streams of water which the line crosses; the distances measured on the true line to the bank first arrived at, the course down stream at points of intersection, and their widths on line. In cases of navigable streams, their width will be ascertained between the meander corners, as set forth under the proper head.

"7. The land's surface — whether level, rolling, broken, hilly, or mountainous.

"8. The soil — whether rocky, stony, sandy, clay, etc., and also whether first, second, third, or fourth rate.

"9. Timber — the several kinds of timber and undergrowth, in the order in which they predominate.

"10. Bottom lands — to be described as wet or dry, and if subject to inundation, state to what depth.

"11. Springs of water — whether fresh, saline, or mineral, with the course of the streams flowing from them.

"12. Lakes and ponds — describing their banks and giving their height, and whether it be pure or stagnant, deep or shallow.

"13. Improvements. Towns and villages; houses or cabins, fields, or other improvements with owners' names; mill sites, forges, and factories, U. S. mineral monuments, and all corners not belonging to the system of rectangular surveying; will be located by bearing and distance, or by intersecting bearings from given points.

"14. Coal banks or beds; peat or turf grounds; minerals and ores; with particular description of the same as to quality and extent, and all diggings therefor; also salt springs and licks. All reliable information that can be obtained respecting these objects, whether they be on the line or not, will appear in the general description.

"15. Roads and trails, with their directions, whence and whither.

"16. Rapids, cataracts, cascades, or falls of water, with the estimated height of their fall in feet.

"17. Precipices, caves, sink holes, ravines, remarkable crags, stone quarries, ledges of rocks, with the kind of stone they afford.

"18. Natural curiosities, interesting fossils, petrifactions, organic remains, etc.; also all ancient works of art, such as mounds, fortifications, embankments, ditches or objects of like nature.

"19. The magnetic declination will be incidentally noted at all points of the lines being surveyed, where any material change in the same indicates the probable presence of iron ores; and the position of such points will be perfectly identified in the field notes."

170. MARKING CORNERS. — Corners are marked on the ground by various kinds of monuments, depending upon the character and importance of the corner to be perpetuated, the soil, the materials available, and upon other local and special conditions. In places where stone is plentiful monuments of this material are usually set. In timbered districts where suitable stones are difficult to obtain, posts are driven to mark the points. In prairie regions where neither stones nor timber are available

a mound of earth may be raised over the corner, a small marked stone, a charred stake, a quart of charcoal, or some other permanent and distinguishable mark being deposited beneath it. Occasionally in the timber the corner falls on a spot occupied by a tree, in which case the tree itself may stand as the monument.



FIG. 63. SHOWING THE SUBDIVISION OF A TOWNSHIP INTO SECTIONS AND THE METHOD COMMONLY USED FOR MARKING TOWNSHIP AND SECTION CORNERS.

In case stones or posts are set they are marked with notches as shown in Figs. 63 and 64, in order to indicate their respective positions in the township. Section corners on range lines, including under this term principal and guide meridians, are marked with notches on their north and south faces, the number

of notches being equal to the number of miles to the next adjacent township corner north or south. In a similar manner the section corners on the township lines, including base-lines and standard parallels, are notched on their east and west faces. Township corners, being located on both range and township lines, are marked with six notches on each of the four sides. In addition to being notched as just indicated, corners on correction lines are marked *SC* on their northern or *CC* on their southern faces, depending upon whether they are standard or closing corners. Section corners in the interior of a township are given notches on their east and south faces corresponding to the number of miles to the east and south boundaries of the township. Thus, the corner common to sections 20, 21, 28, and 29 would have two notches on the south and four on the east face, as sketched in Fig. 64. Quarter-section corners are marked with the fraction "$\frac{1}{4}$", those on meridional lines on their west and those on latitudinal lines on their north faces.



FIG. 64. SKETCH OF STONE MONUMENT, SHOWING NOTCHES.

171. Witnessing Corners. — Wherever possible the monument set at a corner is witnessed by several nearby objects, which may be easily found by anyone looking for the corner itself, which are not readily moved or obliterated, and which are comparatively permanent. In timbered country the stone or post is usually witnessed by "bearing trees" located near the corner. The process of establishing a witness tree is to take its bearing and distance from the corner, then to blaze off the bark from a short section of the trunk on the side facing the corner and to cut into the wood with scribing tools certain letters and numerals indicative of the section in which the tree is located. For example, the tree northeast from the corner shown in Fig. 64 might be marked

T 7 S
R 15 E
S 21
B T,

the letters and figures being abbreviations of "Township 7 south, Range 15 east, Section 21, Bearing Tree." Usually one tree is marked in each of the sections to which the corner refers, provided suitable trees can be found within a reasonable distance of the corner.

In prairie regions small rectangular pits are dug near to the corner, the earth taken from them being used to form a mound. These pits are placed either on the section lines leading from the corner or at angles of 45 degrees with these lines, depending on the kind of corner witnessed; and the mound may be either alongside the monument or, in case the monument is merely a deposit beneath the surface of the ground, may be placed immediately over it. Fig. 65, adapted from illustrations given in the Manual, indicates the manner of using this method of witnessing corners of the several classes. Marks of this kind are of much greater value than might at first be supposed, for, although the sharp outlines are quickly worn away, the grass sod soon covers the mound and grows down into the pits and preserves them from entire obliteration. In many places on the plains four slight depressions in the prairie sod with a little mound between have perpetuated the location of the section corner for a generation or more, until the country has been settled up and the fence lines strung. Under other prevailing conditions corners have been witnessed by mounds of stone, by prominent boulders, and by various other suitable objects.

172. Witness Corners. — In case a regular corner falls in a creek, pond, or in any other place where it is impracticable to set or maintain a monument, *witness corners* are set on all the lines leading to this corner. These are marked with the letters *WC* in addition to the markings that would be appropriate to the corner of which they are witnesses. Witness corners are, in turn, referenced by bearing trees, pits and mounds, and other objects, the same as true corners.

173. Meander Corners. — Where a surveyed line intersects the bank of a stream whose width is more than three chains, or of a lake, bayou or other body of water having considerable extent, a *meander corner* is established. The distance from the nearest section or quarter-section corner is measured and recorded


Standard Township Corners.
Standard Section Corners.
Closing Township Corners.
Closing Section Corners
Corners common to 4 Townships
Corners common to 4 Sections
Standard Quarter Section Corners
Perspective
Of Standard T'p Cor., with Closing T'p Cor., in the distance.
Meanderable Body of Water
Meander Corners
Quarter Section Cor. on a Meridional line
PLANS OF CORNERS
■ = Corner Stone or post.
M = Mound.
M' = Mound with deposit.
P = Pit.

FIG. 65. SHOWING SCHEME FOR DESIGNATING CORNERS BY MEANS OF MOUNDS AND PITS.

in the notes, and the stone or post set as a monument is marked *MC* on the side facing the water, and the point is referenced by bearing trees or by mounds of earth in much the same manner as a quarter-section corner. If practicable, the line is then carried across the stream or other body of water by triangulation to another meander corner set in line on the further bank, and the survey is continued.

174. MEANDERING. — After the regular subdivision work has been done traverses are run, usually by the needle, joining the successive meander corners along the banks of the streams or lake. A traverse of this kind, or a *meander line*, as it is called, originates at a meander corner and follows as closely as may be practicable the various sinuosities of the bank until the next meander corner is reached. Here the traverse is checked by calculating the position of the new meander corner and comparing this with its known position on the surveyed line, and the meandering is then continued. Fig. 66 illustrates the relation of meander corners and lines to the regular lines of the survey. These meander lines are used in plotting the stream on the map and in calculating the areas of the sections or quarter-sections made "fractional" by the presence of the body of water.

The following quotation from the Manual indicates the location of meander lines, their functions in the survey, and their authority as boundaries.

"Lands bounded by waters are to be meandered at mean high-water mark. This term has been defined in a State decision (47 Iowa, 370) in substance as follows: High-water mark in the Mississippi River is to be determined from the river-bed; and that only is river-bed which the river occupies long enough to wrest it from vegetation.

"In another case (14 Penn. St. 59) a bank is defined as the continuous margin where vegetation ceases, and the shore is the sandy space between it and low-water mark.

"Numerous decisions in State and U. S. Supreme Courts assert the principle that meander lines are not boundaries defining the area of ownership of tracts adjacent to waters. The general rule is well set forth (10 Iowa, 549) by saying that in a navigable stream, as the Des Moines River in Iowa, high-water

mark is the boundary line. When by action of the water the river bed changes, high-water mark changes and ownership of adjoining land changes with it. The location of meander lines does not affect the question.

"Inasmuch as it is not practicable in public land surveys to meander in such a way as to follow and reproduce all the minute



FIG. 66. SHOWING THE RELATION OF MEANDER CORNERS AND MEANDER LINES TO THE SECTION LINES.

windings of the high-water line, the U. S. Supreme Court has given the principles governing the use and purpose of meandering shores, in its decision in a noted case (R. R. Co. *v.* Schurmeier, 7 Wallace, 286–7) as follows:

"In cases where the deputy finds it impossible to carry his meander line along mean high-water mark, his notes should state the distance therefrom, and the obstacles which justify the deviation.

"Proceeding down stream, the bank on the left hand is termed the left bank and that on the right hand the right bank. These

terms will be universally used to distinguish the two banks of a river or stream.

"Navigable rivers, as well as all rivers not embraced in the class denominated 'navigable,' the right-angle width of which is three chains and upwards, will be meandered on both banks, at the ordinary mean high-water mark, by taking the general courses and distances of their sinuosities, and the same will be entered in the field book. Rivers not classed as navigable will not be meandered above the point where the average right-angle width is less than three chains, except that streams which are less than three chains wide and which are so deep, swift, and dangerous as to be impassable through the agricultural season, may be meandered, where good agricultural lands along the shores require their separation into fractional lots for the benefit of settlers."

175. ACCESS TO RECORDS AND MAPS OF THE PUBLIC LANDS SURVEYS. — Field notes taken in the survey of public lands are required to be returned to the General Land Office and in narrative form giving complete data of alignment, measurement, and of all characteristic topographical features crossed or near the lines. (See p. 144.) In the following States the original notes have been transferred to the State authorities, to whom application should be made for such copies of the original plats and field notes as may be desired, viz.:

Alabama: Secretary of State, Montgomery.
Arkansas: Commissioner of State Lands, Little Rock.
Florida: Commissioner of Agriculture, Tallahassee.
Illinois: Auditor of State, Springfield.
Indiana: Auditor of State, Indianapolis.
Iowa: Secretary of State, Des Moines.
Kansas: Auditor of State and Register of State Lands, Topeka.
Louisiana: Register of the State Land Office, Baton Rouge.
Michigan: Commissioner of State Land Office, Lansing.
Minnesota: Secretary of State, St. Paul.
Mississippi: Commissioner of State Lands, Jackson.
Missouri: Secretary of State, Jefferson City.
Nebraska: Commissioner of Public Lands and Buildings, Lincoln.
North Dakota: State Engineer, Bismarck.
Ohio: Auditor of State, Columbus.
Wisconsin: Commissioners of Public Lands, Madison.

In many if not all these States named either the original records or copies of the same have been distributed among the

various Counties of the State, and are kept for reference and inspection in the office of the County Register of Deeds, County Surveyor, or other official.

Photolithographic copies of township plats and field notes of surveys of the area covered by the Public Land Surveys in the above states may also be obtained from the General Land Office at Washington, at nominal prices. In other public land states copies of the records can be procured on application to the Surveyors General located at the Capitols, except in California and Oregon, whose Surveyors General are at San Francisco and Portland respectively.

Township maps of much of the area covered by the Public Lands Surveys may be obtained from the General Land Office at Washington, at nominal prices.

176. RELOCATING LOST CORNERS. — It has been the common experience that many of the monuments and marks originally established on the lines of the Public Lands Surveys become lost or obliterated by the time the country has been settled for a generation or two. Witness and line trees * are cut down when the land is cleared, the pits and mounds marking the corners on the prairie are quickly destroyed when the sod is broken up, posts rot away, and no one takes the trouble to see that new and more durable marks are set to perpetuate the location of the points. Largely owing to the fact that in the areas covered by the Public Lands Surveys the public roads are usually located along the section lines, even substantial stone monuments oftentimes are carelessly knocked out of place and eventually are thrown into the ditch or the fence corner.

An act of Congress, approved February 11, 1805, specifically provides that corners actually located in the field shall be established as the proper corners of the sections or quarter-sections which they were intended to designate, **irrespective of whether they were properly located in the first place or not.** A further

* "Line trees" are those directly on a line of the survey. They are blazed on opposite sides, the blazes facing backward and forward along the line. Trees near the line are scored with two blazes "quartering" toward the line; the further the trees are from the line the nearer together the two blazes are placed, and vice versa. These blazed trees are of great service in marking the approximate position of the line through the timber.

provision is that "the boundary lines actually run and marked" (in the field) "shall be established as the proper boundary lines of the sections, or subdivisions, for which they were intended, and the length of such lines as returned by . . . the surveyors aforesaid shall be held and considered as the true length thereof." These are the principles upon which is based the present practice in the relocation of the corners of the original survey.*

The General Land Office distinguishes between an **obliterated** and a **lost** corner, as follows:

"An **obliterated** corner is one where no visible evidence remains of the work of the original surveyor in establishing it. Its location may, however, have been preserved beyond all question by acts of landowners, and by the memory of those who knew and recollect the true situs of the original monument. In such cases it is not a **lost** corner.

"A **lost** corner is one whose position cannot be determined beyond reasonable doubt, either from original marks or reliable external evidence."

In the case of a corner that is merely obliterated the method of procedure, obviously, is to establish a new monument in the same location as the old one, this location being determined by the evidence presented, which should be adequate for the purpose. Instances of this kind occur when old witness trees, or their stumps, or the depressions left in the forest floor by their decay, may be identified; or when the point is marked by the intersection of hedge or stone or other permanent fences which admittedly were constructed on line when the monument was still in place; or when the "true situs of the monument" is testified to by other competent witnesses. (See Art. 151, p. 116.)

In the case of lost corners the true location must ordinarily be determined from data obtained by actually rerunning the old lines, as nearly as may be. But here, in accordance with the principle first stated above, the aim should be to relocate the

* The General Land Office publishes a Circular on the Restoration of Lost or Obliterated Corners and Subdivision of Sections, which states these principles and suggests methods of procedure in conformity therewith. Many of the methods referred to in the following paragraphs are condensed from this Circular.

corner at the exact point at which it was originally established, irrespective of whether it was properly located in the first place or not. As a help toward this end the following suggestions are offered, taken mainly from the Circular of the General Land Office to which reference was made in the earlier part of this Article.

A lost corner on a principal or guide meridian or range line will be located by proportional measurements from the nearest original corners in place north and south of the lost corner. It will be located on the straight line joining these original corners, irrespective of whether the measurements to corners east or west of the lost corner correspond with the original field notes or not.

A lost standard corner on a base-line or standard parallel or other correction line will be located by proportional measurements to the nearest original corners east and west of the lost corner, and will be located on the true line joining them, irrespective of whether the required distances to corners north or south would tend to pull it off this line or not. In like manner, a lost corner on an interior latitudinal township line will be recovered by proportional measurements to corners in place east and west of it.

In other words, **a lost corner is to be relocated by proportional measurements from corners which were established at the same time and with the same degree of care as the lost corner.** It sometimes happens that errors are discovered which throw a doubt upon the accuracy of the field notes of the line upon which the corner in question was located, in which case the lateral measurements might prevail and the corner be located in accordance with them; but ordinarily the rule as stated is the one to be observed.

A lost section corner in the interior of a township is to be located by proportional measurements from the corners nearest to it in all four directions. It is sometimes found, however, that the meridional section lines have been run with greater care than the latitudinal lines, owing to the operation of certain routine methods in use on some surveys. In case this is found to be true, the measurements on the meridional section lines may be given a certain precedence over those on the latitudinal lines.

A lost closing corner on a correction line should be located at

the intersection of the correction line with the meridional line closing upon it, even though the distance called for would place the corner north or south of the correction line. It is even held true of a closing corner actually in place, if it happens to be a little off the correction line, that such corner is to be construed as establishing merely the **direction** and not the **termination** of the meridional line upon which it is located. This is one of the very few cases in which the statutory provision quoted in the early part of this Article is not rigidly adhered to.

A lost quarter-section corner is always to be established at the middle point of the section line upon which it was originally located, except those next to the west and north boundaries of the township. On correction lines the quarter-section corners referring to the sections south of the line* are to be located midway between the adjacent closing section corners, except that in the north boundary of Section 6, which is to be placed forty chains west from the east boundary of the section.

177. Subdivision of Sections. — When the Public Lands were parceled out to settlers the quarter-section was usually the unit area granted as a "homestead." To locate the lines of a "quarter," however, obviously required the establishment of the quarter-section corner at the center of the section. Also, the subsequent division of the original "quarters" into "eighties," "forties," or other minor subdivisions has necessitated the location of numerous corners in addition to those originally established by the Government. Much of the routine work of the present day surveyor is in connection with subdivisions of this kind. In the following paragraphs a number of typical examples will be given, illustrating common practice in the location of subdivisional corners. It will be noted that the methods given are based upon those employed in the original surveys of the sections.

The interior quarter-section corner of a section is always to be located at the intersection of straight lines joining the quarter corners on opposite sides of the section. This method holds wherever the section may be located within the township; that is,

* It will be remembered that these corners were not established on the original survey.

it applies to those in the north and west tiers as well as to the other sections of the township. For example, the center of Section 19, in Fig. 67, would be properly located at the intersection of *ab* and *ef*. This rule would still hold even though, through some error in the original fieldwork, the corner *f*, for instance, had been set too far east by one chain-length. If the corner is still in the place at which it was actually set by the Deputy Surveyor, this location is established for all time as the proper corner for the northern quarters of the section, and the line from *e* will be run to it.



FIG. 67. ILLUSTRATING METHODS OF LOCATING INTERIOR QUARTER-SECTION CORNERS.

In case one or more of the exterior quarter-section corners are not accessible, lines are run through the interior of the section from whatever quarter corners are in place, having as nearly as possible the same directions as they would have were all the exterior corners actually in place, and the interior quarter-section corner is located at their intersection. For example, in Fig. 67 the corner at the center of Section 21 would be located by the intersection of a line run north from *d* in a direction which is a mean between that of *ED* and that of *FC*, with a line run east from *c* having a direction which is a mean between those of *CD* and *FE*. In case only one of the interior lines can be run, the corner may be established by proportionate measurements along that line. For example, the center of Section 20 would be located by measuring out from *c* on the line *cb* a distance equal to half the mean length of *CB* and *FG*. A modification of this method is required in the west and north tiers of sections

in a township. In the case of sections lying in the west tier the meridional line run from the quarter corner on the north or south boundary of the section is run parallel to the east line of the section; and similarly, in the case of sections lying in the north tier the latitudinal interior line initiated at the quarter corner on the east or west boundary is run parallel to the south line of the section. The reasons for this method of procedure in these special cases are easily apparent from a consideration of the methods previously described for the establishment of the original quarter-section corners in these sections.

For subdivisions smaller than quarter-sections the same general methods are employed. For example, to subdivide the northeast quarter of Section 10 (Fig. 68) into quarter-quarters or



FIG. 68. ILLUSTRATING THE SUBDIVISION OF A QUARTER OF AN INTERIOR SECTION.

NOTE. — Figures on the outside lines of the illustration are those of the original survey.

"forties," straight lines are run connecting the middle points of the opposite sides of the quarter. In case one or more of these starting corners are inaccessible, the quarter will be subdivided by the application of methods similar to those just outlined for the location of the quarter-section corner at the center of a section. In the subdivision of quarter-sections adjacent to the west or

north boundaries of the township the excesses or deficiences originally thrown into these quarters are not divided up between the different subdivisions, but are carried forward into the western or northern tiers of forty-acre lots. Fig. 69 illustrates this point by showing an ideal subdivision of the northwest quarter of Section 6, in a township not immediately south of a correction



FIG. 69. SHOWING THE SUBDIVISION OF THE NORTH-WEST QUARTER OF SECTION 6.

NOTE. — Figures on the outside lines of the illustration are those of the original survey.

line. In order to make them apparent in the Figure, the original excesses and deficiences are shown on an exaggerated scale. The tract marked 4 might be properly described as "the northwest quarter of the northwest quarter of Section 6," or simply as "Lot 4, of Section 6," of the appropriate township and range.



FIG. 70.

178. **CONVERGENCE OF THE MERIDIANS.** — The angular convergence of the meridians, given in Table 6, may be computed as follows. In Fig. 70 AB is an arc of a parallel of latitude and EQ the arc of the equator intercepted by the meridians through A and B. AT and BT are lines tangent to the meridians at A and B, meeting the earth's axis, prolonged, at T. It will be seen that the angle BTO equals the angle BOQ, which is the latitude of points A and B. The angle AOB is the difference in longitude of points A and B. The angle between the meridians at A and B is the angle ATB.

In the sector $AO'B$,

$$\frac{AB}{BO'} = \text{angle } AO'B$$

In the sector ATB,

$$\frac{AB}{BT} = \text{angle } ATB \text{ (approximately)}$$

But
$$BT = \frac{BO'}{\sin BTO'} = \frac{BO'}{\sin BOQ}$$

$$\therefore \text{angle } ATB = \frac{AB}{BO} \sin BOQ$$
$$= \text{angle } AOB \sin BOQ,$$

i.e., the angular convergence equals the difference in longitude times the sine of the latitude.

The *linear* convergence of two meridians equals the distance run (N. or S.) times the sine of the angular convergence.

Example. — To find the angular convergence between two meridians 6 miles apart in latitude 37°. The length of 1° of longitude in latitude 37° is 55.30 miles (Table 7).

$$\frac{6}{55.30} \times \sin 37^\circ \times 60 = 3'.9.$$

TABLE 7.

LENGTH OF A DEGREE OF LONGITUDE.

Lat.	Degree of Longitude Statute Miles.	Lat.	Degree of Longitude. Statute Miles.	Lat.	Degree of Longitude. Statute Miles.
0	69.160	30	59.944	60	34.666
1	.150	31	.334	61	33.615
2	.119	32	58.706	62	32.553
3	.066	33	.060	63	31.481
4	68.992	34	57.396	64	30.399
5	68.898	35	56.715	65	29.308
6	.783	36	.016	66	28.208
7	.647	37	55.300	67	27.100
8	.491	38	54.568	68	25.983
9	.314	39	53.819	69	24.857
10	68.116	40	53.053	70	23.723
11	67.898	41	52.271	71	22.582
12	.659	42	51.473	72	21.435
13	.400	43	50.659	73	20.282
14	.120	44	49.830	74	19.122
15	66.820	45	48.986	75	17.956
16	.499	46	.126	76	16.784
17	.158	47	47.251	77	15.607
18	65.797	48	46.362	78	14.425
19	.416	49	45.459	79	13.238
20	65.015	50	44.542	80	12.047
21	64.594	51	43.611	81	10.853
22	.154	52	42.667	82	9.656
23	63.695	53	41.710	83	8.456
24	.216	54	40.740	84	7.253
25	62.718	55	39.758	85	6.048
26	.201	56	38.763	86	4.841
27	61.665	57	37.756	87	3.632
28	.110	58	36.737	88	2.422
29	60.536	59	35.707	89	1.211

CHAPTER VI.

TRAVERSE LINES. — LOCATION OF BUILDINGS. — MISCELLANEOUS SURVEYING PROBLEMS.

TRAVERSE LINES.

179. Traverses which do Not form Closed Figures. — A great many surveys, such, for example, as the preliminary surveys for railroads or pipe lines, call for traverses which do not return to the starting point. In this work the line is usually measured continuously from one end to the other, and the form of notes is commonly as follows. The starting point of the traverse is called "Station 0," the next station 100 ft. away is "Station 1," the next "Station 2," etc. Every 100-ft. length is a *full station* and any fractional distance is called the *plus*. The distance from Station 0 to any point, **measured along the traverse line,** is the station of that point and is recorded always by the number of the last station with the plus station in addition, e.g., the station of a point at 872.4 ft. from Station 0 is $8+72.4$.

At the angle points it is customary to measure the **deflection angles** rather than the interior angles because the former are usually the smaller. These should be checked in the field by "doubling" the angles. (See Arts. 143–5, pp. 108–10.)

The notes are kept so as to read **up the page.** The left-hand page is for the traverse notes and the right-hand page for the sketch, the stations in the sketch being opposite the same station in the notes. Fig. 71 is a set of notes illustrating this type of traverse. Frequently no notes are kept in tabular form, all of the data being recorded on the sketch.

180. Methods of Checking Traverses which do Not form Closed Figures. — **Checking by Astronomical Methods.** — The angles of any traverse can be checked by determining the azimuth of the first and last lines by astronomical methods. (See Chapter VIII.) But since the meridians converge it is neces-

sary to make proper allowance for this convergence, the amount of which can be obtained from Table 6, p. 141.

181. Checking by Cut-Off Lines. — The angles may also be checked in some cases by cutting across from one point on the traverse to another at a considerable distance ahead, and measuring the angles from the traverse line at each end of this cut-off

(LEFT-HAND PAGE.) (RIGHT-HAND PAGE.)



FIG. 71. TRAVERSE NOTES.

line, thereby obtaining all the angles of a closed traverse in which the length of one side only (the cut-off line) is missing. Sometimes the angle at only one end of the cut-off line can be measured, in which case the calculations for checking are not so simple as in the former case. When both angles have been measured the check consists in simply obtaining the algebraic sum of the deflection angles, while in the latter case the traverse must be computed.

182. Checking by Angles to a Distant Object. — A practical and very useful method of checking the azimuth of any line of the traverse is as follows. At intervals along the line, measure carefully the angle from the traverse line to some well-defined distant object, such as a distinct tree on a hill or the steeple of a church. If the survey is plotted and it is found by laying off the angles taken to the distant object that these lines do not meet at one point on the plan there is a mistake in the angles, and a study of the plot will show the approximate location of the mistake. If convenient, an angle to the distant object should be taken at every transit point. When plotted, if these lines meet at the same point in one section of the traverse and in another section meet at another point, then there is a mistake in the line which connects these two parts of the traverse. Frequently this distant point is so far away that it cannot be plotted on the plan. In this case as well as when it is desired to check more accurately than by plotting, the location of the distant point with reference to the traverse line can be computed by using these measured angles, as explained in Art. 443, p. 420. Plotting will not disclose minor errors of a few minutes only.

183. Checking by Connecting with Triangulation Points. — An accurate and practical method of checking both the angles and distances of a traverse is to connect the traverse with reliable *triangulation points* which can be easily identified. (See Art. 313, p. 291.) The latitude and longitude of these triangulation points and the distances between them can be obtained from the proper authorities. Sometimes the distances between them are not known but they can be computed. Then by connecting the traverse lines with these triangulation points by angles and distances a closed traverse is obtained, which serves as a good check.

Many surveyors fail to appreciate the value of this method of checking and do not realize how many such points are available. The information concerning such triangulation points can be obtained from The U. S. Coast and Geodetic Survey, The U. S. Geological Survey, State surveys, and frequently from City or Town surveys.

LOCATION OF BUILDINGS FROM TRANSIT LINE.

184. METHODS OF LOCATING BUILDINGS. — Many objects, such as buildings, are plotted directly from the survey line. In this case the measurements taken should be such as will permit the most accurate and rapid plotting. Sometimes where it is desirable to shorten the amount of fieldwork, the methods used are such as to gain time at the expense of accuracy or of simplicity in plotting. The accuracy with which such locations are made will depend upon the purpose of the survey. In city plans the accurate location of buildings is of great importance, while in topographic maps a rough location is often sufficient. There are so many different cases which will arise that this work requires considerable skill and judgment on the part of the surveyor.

185. GEOMETRIC PRINCIPLES. — Whether the locations are accurate or only rough, the principles involved are the same. In order to make clear the various methods used in the location of buildings it will be well to enumerate the geometric principles involved before giving particular cases occurring in practice.

A **point** may be located: —

(1) By rectangular coördinates, i.e., by its station and perpendicular offset.
(2) By two ties from known points.
(3) By an angle and a distance from a known point.
(4) By an angle at each of two known points.
(5) By a perpendicular swing offset from a known line and a tie from a known point.
(6) By perpendicular swing offsets from two known lines.

A **line** may be located: —

(1) By two points on the line.
(2) By one point on the line and the direction of the line.

186. TIES, OFFSETS, SWING OFFSETS, AND RANGE LINES. — In the above, the word *tie* is used as meaning a direct horizontal measurement between two points.

An *offset* is the distance from a line, usually at right angles.

A *swing offset* is the perpendicular distance to a line and is found by trial. The zero end of the tape is held at the point to be located and the tape is swung in a short arc about the point as a center, the tape being **pulled taut and kept horizontal.** The tape is read from the transit in various positions, and the shortest reading obtainable is the perpendicular distance desired.

A *range line* is a line produced to intersect the transit line or some other line.

187. GENERAL SUGGESTIONS. — By whatever method the buildings are located the following suggestions should be carried out.

(1) All the sides of the building should be measured and checked by comparing the lengths of opposite sides.

(2) Other things being equal, a long side of a building should be located in preference to a short side.

(3) Ties should intersect at an angle as near 90° as practicable, and never less than 30°.

(4) One or more *check measurements* should be taken in every case.

(5) In order to secure the best location the surveyor should keep constantly in mind how the building or other object which is being located is to be plotted.

In most work of this character it is customary to record the measurements to tenths of a foot. How precisely the measurements should be taken, however, depends upon the scale to which they are to be plotted.

188. TYPICAL CASES. — Although each case will have to be dealt with according to circumstances there are certain typical cases which will serve as guides. These are illustrated by the following examples.

189. Example I. Building Near Transit Line and Nearly Parallel to it. — As will be seen in Fig. 72 swing offsets are taken at the two front corners which, together with the tie from *A* to station *1* and the length of the front of the building locate points *A* and *B*. Then the general dimensions of the building are sufficient to plot and check the remaining sides. It is assumed that the corners of the building are square unless it is

obvious that they are not. The tie from C to station 2 is a check against an error in the other measurements.

PLOTTING. — This building would be plotted thus: — scale the distance AX perpendicular (estimated) to the transit line



FIG. 72.

and draw a line with triangles parallel to the transit line; then scale $A1$ from station 1 to this parallel line. Point A is then located. Point B is located in the same way, AB being used as the tie from A. Then by means of triangles and scale the building is completed and the distance $C2$ scaled and compared with the notes. Another way to plot point A would be to set on the compass the distance $1A$ and swing an arc about 1 as a center; then, keeping the scale perpendicular to the transit line, find where the distance XA will cut this arc, thus locating point A. Point B can be similarly located after A has been plotted. For the same degree of accuracy distances can be measured more rapidly with a scale than they can be laid off with a compass, therefore the former method is usually more practicable.

This building might have been located by four ties AO, $A1$, $B1$, and $B2$. The plotting in this case would be slow because at least two of the ties must be swung by use of a compass, and inaccurate because the intersections would be bad.

190. Example II. Building Near Transit Line and Making a Slight Angle with it. — Fig. 73 illustrates two ways of locating a building in such a position that the intersection of the transit line by the long side (produced) can be readily obtained.

The left-hand building is located by the method of Example I. The tie $B1$ could have been taken instead of $B2$. It would have given a better intersection at B, but since it is a longer tie than $B2$ the fieldwork necessary is slightly greater. If $B2$ is

taken *B1* might be measured as a check tie although *A1* would make a better check tie since it will also check the measurement of the side *AB*.

The right-hand figure illustrates another method of locating such a building. The front and side of the building are ranged out by eye, a method which is thoroughly practical and sufficiently precise for all ordinary purposes, and the plus station of points *E* and *F* are measured. The range lines *CE* and *DF* are also measured and the check tie *C3*. *C2* could have been taken as a check tie ; it would have given a better intersection at *C* than the tie *C3*, but it is much longer.



FIG. 73.

PLOTTING. — The left-hand building is plotted as described in Example I. In plotting the right-hand building the plus stations on the transit line are first scaled. Then with the compass set at the distance *EC* an arc is swung from *E* as a center. From *F* the distance *FC* is scaled to intersect the arc, which locates point *C* and the direction of the side *CD*. The building is then plotted with triangles and scale. The check tie *C3* should scale to agree with the notes and the line *GC* produced should strike point *E*.

There is little difference between these two methods in the amount of fieldwork, there being only one more measurement in the right-hand than in the left-hand figures, but one extra check is thereby obtained. In plotting, the method used in the right-hand figure is shorter.

191. Example III. Building Located Entirely by Direct Ties. — Any building not far from the transit line can be located and checked by four ties as in Fig. 74. This method has the advantage of being very simple and direct, especially in the field, but the plotting of the building calls for the use of the compass in two of the ties and hence is less rapid and accurate than where swing offsets or ranges can be used.

PLOTTING. — The plotting of this building is done by swinging the tie from one station to a corner of the building and scaling from the other station the tie to the same corner. Then the



FIG. 74.

other corner is plotted in the same way or by using the side of the building as one of the ties in case it gives a better intersection.

192. Example IV. Building Located at a Considerable Skew to the Transit Line. — A building which is at a considerable skew to the transit line can best be located by range ties as illustrated in Fig. 75. The range ties through A are sufficient to



FIG. 75.

locate the building, provided AE and AF are not too short in comparison with the sides of the building. If these ranges are long enough, then $B3$ is a check tie ; but if the ranges are short $B3$ must be depended upon to determine the position of point B and in this event one of the range ties becomes a check. But if A is within two or three feet of the transit line it will be well to omit one of the ranges and take the additional tie $2C$ or the range tie DC produced.

PLOTTING. — If the ranges are of fair length the building is plotted as explained for the right-hand building in Art. 190, but if the range ties are short point B is located either by swinging the arc with radius EB and scaling $B3$ or by arc $3B$ and scaling EB. Then the direction of AB is determined and the building is plotted. CA produced should strike at F, and AF should scale the measured distance.

193. Example V. Buildings at a Long Distance from the Transit Line. — It is evident that in this case (Fig. 76) the tape



FIG. 76.

is not long enough to allow the use of swing offsets. Range ties may be used provided the building is not so far away that the eye cannot judge the range line with reasonable accuracy. Sometimes the only methods available are long ties or angles or a combination of the two. In any specific case there may be some objections to any of these methods, and the surveyor will have to decide according to circumstances which method he will use. For example, where there are obstacles to the measurement of ties, the corners of the building may have to be located entirely by angles from two points on the transit line. Location by angles is objectionable because it is difficult to plot an angle quickly and at the same time accurately. It often happens, however, that when a building is at a considerable distance from the transit line its accurate position is not required, since as a rule the features near the transit line are the important ones. This method of "cutting in" the corners of the building by angle is often used in rough topographic surveying and is decidedly the quickest of all methods so far as the fieldwork is concerned.

PLOTTING. — The angles are laid off from the transit line

with a protractor and the proper intersections determine the corners of the buildings. If the building is measured the side between the corners located will be a check tie.

In some cases, e.g., in making a topographic map on a small scale, the buildings are not measured at all, their corners being simply "cut in" by several angles from different transit points, and the shape of the building sketched in the notes.

194. Example VI. Buildings Located from Other Buildings. — Buildings which cannot be conveniently located from the transit line on account of intervening buildings may be defined by ties from the ones already located. Fig. 77 shows several ways



FIG. 77.

in which such buildings may be located. Any of the preceding methods are applicable, using the side of the house as a base-line, but it will be found that range ties are almost always preferable. For example, the barn is located by the distance BK, the range tie KC and the tie BC, and checked by the tie BE. Another location of the barn is the distance AK or BK, the range tie KC, and the two range ties AJ and CJ. By this latter method the directions of both sides of the barn are checked. Still another location of the point C would be to substitute in the place of the range tie CK a swing offset from C to the house. The shed is located by the range ties AF and FG and by the tie AG. The check tie HD in general checks the location of both the barn and the shed. If the side HL is ranged out instead of the opposite side it will be seen that the tie AL will give a

poorer intersection at L. If convenient a tie from L to 4 or the range GF continued to the transit line may be measured as a check.

195. Example VII. Buildings of Irregular Shape. — Occasionally a building of irregular shape has to be located. For example, the shop in Fig. 78 is located on the front by ties and



FIG. 78.

swing offsets like Example I; then the direction of AB is determined by the range tie BC. The back corner E is determined by the ranges FH and EH, and by the dimensions of the building; FA is assumed parallel to GB. If the angle F is a right angle the tie EF may be taken instead of the range ties FH and EH, but even when F is a right angle it will be well if time will permit to take these range distances as they give valuable checks on the other measurements which the single tie EF does not furnish. ED is scaled along HE produced and the rest of the building plotted by its dimensions and checked by AD.

The ties shown on Fig. 78 to locate the factory chimney will locate its sides even if they do not form a regular polygon. If such a structure is situated at a considerable distance from the transit line probably the best way to locate it is by angles and distances to the corners, by the measurements of the sides, together with a few such ranges as NJ or KJ.

196. Example VIII. Large City Buildings. — Fig. 79 illustrates the location of several buildings in a city block where the transit line runs around the block. The fronts of the buildings are located from the transit line and the rear corners are tied together. The range ties are shown by dotted lines and other ties by dashes. The angles measured are marked by

arcs. At the curve AB, the side lines of the building are ranged out to point C which is located from the transit line by an angle



FIG. 79.

and distance and checked by a swing offset; CD is also measured to locate point D on the curve.

Frequently large buildings have their walls reinforced by pilasters, and care should be taken in such cases not to confuse the neat line of the wall with the line of the pilasters.

197. Example IX. Location of Buildings by Angles and Distances. — It will be seen from Figs. 79 and 80 that some of the buildings have been located by angles and distances from transit points. Any of the buildings in the above examples could be located by this method, and on account of the rapidity with which the work can be done in the field many surveyors prefer to use it almost exclusively.

198. Location of Buildings and Fences from Transit Line. — Fig. 80 is a sample page from a note-book illustrating the above principles. It will be noticed that in the field notes the letter R appears where the lines are ranges.


St. Line
High
Church Street
Transit
House
Barn
Shed
R-45.7
R-72.0
R-69.0
R-23.0
R-29.2
R-31.1
R-49.2
114.1
110.4
144.5
82.2
17+15.6

FIG. 80.

PROBLEM.

Indicate the best method of locating the fences and buildings shown below, by means of tape measurements.



MISCELLANEOUS SURVEYING PROBLEMS.

199. RANDOM LINE. — Not infrequently in attempting to run a straight line between two points A and B (Fig. 81) it is impossible to see one point from the other or to see both points A and B from an intermediate set-up on a straight line between them. When this condition exists it is necessary to start at one point, e.g., A, and run what is called a trial, or *random*, line AC by the method explained in Art. 64, p. 52, in the direction of the other end of the line as nearly as can be judged.

Where the random line passes the point B the perpendicular offset YB is measured and also the distance to point Y along AC. Unless the random line is very close, say, within about two feet of the line AB, the point Y where a perpendicular to AC will pass through B cannot be accurately chosen by eye. The method resorted to in this case is one which has very general application in all kinds of surveying work, and is as follows.



FIG. 81.

With the transit at A point X is set carefully on the line AC and as nearly opposite point B as possible. Then the instrument is set up at X and 90° turned off in the direction XZ. If this line does not strike B (and it seldom will exactly) the distance BZ is carefully measured by a swing offset as described in Art. 186, p. 166. The distance BZ is equal to the distance XY which is added to AX giving the length of the long leg AY of the right triangle AYB. The distance YB is then measured, and AB and angle YAB are easily calculated.

Angle DAY has been measured from some previous course

such as AD and the addition of the angle YAB together with the known distance AB makes the traverse complete to the point B without any further fieldwork. If the transit is now moved to B with a view to carrying on the survey it will be found that, since A cannot be seen from B, there is no point on the line BA to use as a backsight. But any point such as E can be readily set on the line AB by making the offset $ME = BY\frac{AM}{AY}$. Another point can be similarly set on AB as a check on the backsight.



FIG. 81.

This random line method is sometimes employed when AB is a boundary which is covered with shrubs. In such cases, although the view from A to B may not be obstructed, it may be so difficult to measure the line AB that its length can be more easily obtained by the use of the random line while the angle DAB may be measured directly at A. If it is desired to mark the line AB by several intermediate points these may be established by means of perpendicular offsets calculated as described above.

200. OBSTACLES ON LINE. — When an obstacle of limited extent, such as a building or a small pond, lies on the transit line various methods are resorted to for prolonging the line through such obstructions; the most useful of these methods will be explained.

201. Offsetting Transit Line. — This method is illustrated by Fig. 82. It is desired to produce the line AB beyond the house. Point B is set on line and as near as is practicable to the house.

The instrument is then set up at B and a right angle ABF laid off with the transit. BF is made any convenient distance which will bring the auxiliary line beyond the building. Similarly point E is set opposite point A, and sometimes a second point E' opposite A', points A and A' being **exactly** on the transit line. These points E and E' need not be set by means of a transit set up at A and at A' unless AE is quite long.

The instrument is then set up at F and backsighted on E, the sight is checked on E', the telescope inverted, and points G, H', and H set on line. Leaving the telescope inverted, another backsight is taken on E, and the process repeated as described in Art. 64, p. 52. Then the transit is moved to point G, and a right angle turned off, and point C set on the right angle line, the distance GC being made equal to BF.



FIG. 82.

Then by setting up at C and sighting ahead on D, ($DH = GC$), and checking on point D', ($D'H' = GC$), the transit line is again run forward in its original location. The distance FG is carefully measured which gives the distance BC, and thus it appears why it is so necessary that the lines BF and GC shall be laid off at rigth angles by means of the transit. The other offsets AE, $A'E'$, DH, and $D'H'$ are not in any way connected with the measurement along the line; they simply define the direction of the line so that if convenient it is often only necessary to show these distances as swing offsets for the transitman to sight on. From what has been said it will be seen that offsets $A'E'$ and $D'H'$ are not absolutely necessary, but they serve as desirable checks on the work and in first-class surveying they should not be omitted. For obvious reasons the offsets AE and DH should be taken as far back from the obstacle as is practicable.

Should the house be in a hollow so that it is possible to see over it with the instrument at A, the point D, or a foresight of some sort (Art. 64, p. 52) should be set on line beyond the house

to be used as a foresight when the transit is set up again on the original line. The distance may be obtained by an offset line around the house or by slope measurements to the ridgepole. Sometimes it is possible to place exactly on line on the ridgepole of the house a nail or a larger wooden sight which gives an excellent backsight when extending the line on the other side of the building.

If the building has a flat roof it may not be out of the question to set a point on the roof exactly on line, move the instrument to this point on the roof, and prolong the line in this way. Under these conditions the transitman will have to be extremely careful in the use of his instrument as it will be set up on an insecure foundation. If he walks around the transit he will find that it affects the level bubbles and the position of the line of sight; it is therefore well for him if possible to stand in the same tracks while he backsights and foresights. Sometimes two men, one in front and one behind the transit, can carry on the work under these conditions more accurately and conveniently. This method insures an accurate prolongation of the line, but the distance through the building must be measured by an offset method, unless it can be done by plumbing from the edge of the flat roof.

202. SHORT TRANSIT SIGHTS. — Sometimes the offset BF (Fig. 82) does not need to be more than 2 or 3 feet. The shorter this offset line can be made, and still clear the building, the better. But to lay off the short line BF will require a method somewhat different from any that has been heretofore explained. As the ordinary transit instrument cannot be focused on a point much less than about 5 ft. distant it is impossible to set point F directly. The method employed is to set a temporary point, say 10 ft. distant, on which the transit can be focused, and on a line perpendicular to the original transit line. From the transit point to this auxiliary point a piece of string may be stretched and the point F set at the required distance from B and directly under the string.

203. Bisection Method. — A method which is economical in fieldwork but not very accurate is the following. In Fig. 83 the instrument is set up at A, backsighted on the transit line, and equal angles turned off on each side of the transit line pro-

duced. Points B' and C' are carefully set on one of these lines and at convenient distances from A, and on the other line points



FIG. 83.

B'' and C'' are set at the same distances from A. Then point B is placed midway between B' and B'', and similarly point C is set midway between C' and C''. The line BC is the prolongation of the transit line. Of course the distance $B'C'$ should be made as long as practicable. The inaccuracy in this method lies entirely in laying off the two angles. (See Art. 61, p. 50.)

In this case the distance AB can be computed from the formula

$$AB' - AB = \frac{\overline{BB''}^2}{2AB} \text{ (approximately).}$$ (See foot-note, p. 13.)

204. Measuring Around a Small Obstacle. — In Fig. 84 the



FIG. 84.

line AB runs through a tree, and points A, D, and B have been set on line. DE is made equal to some convenient short distance and laid off at right angles to the transit line by eye. Then AE and EB are measured. The distance

$$AB = AE - \frac{\overline{DE}^2}{2AE} + EB - \frac{\overline{DE}^2}{2EB}.$$ (See foot-note, p. 13.)

When DE is taken as some whole number of feet the computation of the above is extremely simple.

This method of measuring around a small obstacle might be applied much more generally than it is at present if its accuracy and its simplicity were more fully realized by surveyors.

205. Equilateral Triangle Method. — While this method requires much less fieldwork than the offset method described above it is at the same time less accurate. Point B (Fig. 85) is set on the transit line as near the building as practicable but so that a line BC at 60° with the transit line can be run out. The instrument is set up at B, backsighted on A, and an angle of 120° laid off; the line BC is made long enough so that when the instrument is set up at C and 60° is laid off from it, CD will fall outside the building. BC is measured and CD is made equal to BC. If the instrument is set up at D and angle CDE laid off equal to 120° the line DE is the continuation of the original transit line,



FIG. 85.

and the line $BD = BC$. This method is subject in three places to the errors incident to laying off angles and, when BC and CD are small, it has in two of its intermediate steps the disadvantages due to producing a short line.

206. INACCESSIBLE DISTANCES. — If the obstruction is a pond, points on the far side of it can be set and these should be used in producing the transit line. When the line can be produced across the obstacles the following methods may be used.

207. Inaccessible Distance by Right Triangle Method. — In Fig. 86 the line AB is made any convenient length and at any convenient angle to the transit line. The line BC is laid off at 90° to BA and is intersected with the transit line and the distance BC measured. AC is calculated from AB and cos A and checked by BC and sin A. Also the angle ACB can be measured which will check the transit work.



FIG. 86.

208. INTERSECTING TRANSIT LINES. — In many kinds of surveying work it is necessary to put in points at the intersection of two transit lines. It would be an easy matter to set the point if two transits could be used, one on each line, and the sight simultaneously given by each transitman. As it is seldom practicable to use more than one transit in a surveying party the following method is resorted to.

An estimate is made by eye where the lines will cross each other and temporary points not more than 10 ft. apart are set on one of the transit lines by means of the instrument, enough points being marked to make sure that the second line will cross somewhere among this set of temporary points. A string is then used to connect two of these temporary points and the transit is set up on the other transit line and the point where the second line cuts the string is the intersection point. Sometimes when the lines cross each other at nearly 90° the intersection point can be estimated so closely that only two temporary points need be placed on the first line. In other cases, where the two transit lines cross at a very small angle, it is impossible to tell by eye within several feet where the lines will intersect and a number of points must be used because in practice the stretching line is seldom applicable for distances much over 15 ft. For short distances the plumb-line can be used as a stretching line.

209. Inaccessible Distance by Swing Offset Method. — If the distance across a pond or river is not great the following method

may be used. It has the advantage of requiring the minimum amount of fieldwork. With the instrument at A (Fig. 87) point C is set on the transit line on the far side of the river. The instrument is then set up at C and the angle ACB measured between the transit line and a 100-ft. swing offset from point A.

A pencil is held vertically at the 100-ft. mark of the tape and while the zero point is held firmly at A the tape, which is constantly kept horizontal and taut, is swung slowly in an arc ab. The transitman, using the tangent screw, can follow the pencil with the vertical cross-hair of the transit, stopping the cross-hair when the pencil is in its farthest position



FIG. 87.

from A. Then as the tape is swung the second time he can check his setting and when this is established the angle ACB is read. The distance AC then is very easily calculated. It should be noted, however, that if AC is several times as long as AB the resulting error in AC may be so great as to prohibit the use of this method where very precise results are required. There is no reason why the swing offset could not be made at C with the instrument at A if more convenient.

210. Inaccessible Distance by Tangent Offset Method. — In the method described above the distance across the pond may be so great that 100 ft. will be too short a base to use, or point A may be situated on ground sloping upward towards B so that a swing offset

cannot be made. In such cases the line AB (Fig. 88) can be laid off at right angles to the transit line and of any convenient length.



FIG. 88.

Then the angle ACB is measured and the line AC computed. By another set-up of the instrument the angle B can be measured as a check, and if the line BC does not cut across the pond its length can also be measured as a further check.

211. Inaccessible Distance by Oblique Triangle Method. — Often the shores of a stream are covered with trees so that none



FIG. 89.

of the above methods are applicable. It may be convenient to measure a line AB (Fig. 89) in but one direction along the shore. In this case the point C is first carefully set on the opposite side, the line AB measured along the shore, and the angles at A and

at C are measured. The distance AC can then be computed. It will be well also to set up at B and measure the angle B as a check on the work. At the time when point C is set it is also good practice to set a point further ahead on the line, to use as a foresight to check the transit line when the instrument is moved across the river.

212. To Obtain the Distance Between Two Inaccessible Points by Observation from Two Accessible Points.— In Fig. 90 the points A and B are inaccessible and it is desired to obtain the distance AB and the angle that AB makes with the transit line. From the point D the distance DC and the angles BDA and ADC are measured, and similarly at C the angles ACB and BCD are measured. AB can then be calculated as follows: — in the triangle CBD compute CB; in triangle ACD compute AC; and in the triangle ACB calculate AB, the inaccessible distance. In the tri-



FIG. 90.

angle ACB, angle ABC can be computed, which, together with the measured angle BCD, will give the difference in direction between AB and CD. It is not at all necessary that DC should have been measured as one straight line in the traverse; the traverse might have run as indicated by the dotted lines, but in such an event the distance CD and the necessary angles could have been easily figured so that it could be reduced to the above problem.

This problem occurs when the distance between two triangulation stations, A and B, and the azimuth of AB are desired and when it is inconvenient or impossible to measure the line AB or to occupy the points with the transit.

213. To Obtain the Inaccessible Distance Between Two Accessible Points by Observations on Two Inaccessible Points of Known Distance Apart. — In this case (Fig. 90) A and B are the two accessible points and C and D are the two inaccessible points but the distance DC is known; the distance AB is required. With the transit at A, the angles CAD and DAB are measured; at B the angle CBD and ABC are measured. The length of the line CD is known. While it is simple to obtain CD in terms of AB, it is not easy to directly determine AB in terms of CD; it will be well therefore to use an indirect method. Assume AB as unity. Then by the same process as described in the preceding problem the length of CD can be readily found. This establishes a ratio between the lengths of the lines AB and CD, and the actual length of CD being known the distance AB can be computed.

A problem of this sort would occur under the following circumstances. If the distance CD between two church spires were accurately known (from a triangulation system) and it is desired to use this line CD as a base-line for a survey, two points A and B could be assumed, and the distance between them and the azimuth of AB could be found by this method.

CHAPTER VII.

THE STADIA METHOD.*

This chapter includes the general theory of stadia measurements and the application of the method to simple surveys. Chapter IV, Vol. II, describes fully the application of the stadia method to topographic surveys and includes many rapid field and office methods commonly employed; it also treats of certain special applications of stadia measurements.

214. Stadia Method of Measuring Distances. — The stadia method of locating points is one in which distances are measured by observing through the telescope of a transit the space, on a graduated rod, included between two horizontal hairs called *stadia hairs*. If the rod is held at different distances from the telescope different intervals on the rod are included between the the stadia hairs, these intercepted spaces on the rod depending upon the distances from the rod to the instrument, so that the intercepted space is a measure of the distance to the rod.

Owing to the fact that in making a stadia measurement the intervening country does not have to be traversed, as is necessary when making a tape measurement, distances can be taken across ravines and water surfaces, and over rough as readily as over smooth ground. This gives the stadia a great advantage over the tape in point of speed. Another advantage of this method over that of tape measurements is that the errors of stadia measurements are compensating while those of tape measurements are cumulative. (Art. 23, p. 14.) Furthermore, the accuracy of the stadia measurements is not diminished in rough country, so that the results obtained by this method are, under some conditions, as accurate as tape measurements. While surveys of property boundaries ordinarily demand the use of transit and tape, still the stadia method is well adapted to the survey of cheap land, such as marsh or timber land. In many

* The word *telemeter* is sometimes used instead of *stadia*.

cases the boundaries of such properties are so uncertain that the latter method is sufficiently accurate. In highway or railroad surveys preliminary plans must often be prepared in a limited time, for which purpose the stadia method is adapted. Furthermore, where an accurate tape and transit survey is being made it is often desirable to locate also physical features which may not be closely related to the purpose of the survey in hand; these may properly be located by stadia measurements, and the use of stadia for locating such details is rapidly increasing. The stadia method is also exceptionally well adapted to topographical surveying. (See Vol. II, Chap. IV.)

215. Instruments. — The only equipment needed for this work in addition to the ordinary engineer's transit is a set of stadia hairs in the telescope, and some form of graduated rod on which distances may be read from the instrument. The two stadia hairs are usually placed on the cross-hair diaphragm parallel to and equidistant from the horizontal cross-hair. In some instruments they are so arranged that the distance between them is adjustable. For exact work the fixed hairs are to be preferred as they do not get out of adjustment; the instrument maker can readily set them at the desired distance apart with sufficient accuracy. Sometimes the stadia hairs and the ordinary cross-hairs are placed on separate diaphragms or in different planes so that when the eyepiece is focused on the ordinary cross-hairs the stadia hairs are invisible, and *vice versa;* these are called *disappearing* stadia hairs. If the cross-hairs are arranged in this manner there sometimes is also a pair of inclined hairs (forming a letter X) set in the same plane as the stadia hairs to define the center line of sight. By this means vertical and horizontal angles may be measured without re-focusing on the ordinary cross-hairs. This arrangement of cross-hairs is open to the objection that when it is desired to read half a stadia interval, as is explained later, it cannot be done conveniently or accurately; for this reason some prefer to have a second set of vertical and horizontal cross-hairs, instead of the diagonal hair, placed in the same plane as the stadia hairs.

The telescope of a transit intended for stadia work should have a magnifying power of from 20 to 30 diameters, and should

give a clear, well-defined image. It is desirable, although not necessary, that the instrument should be provided with a compass needle. Stadia instruments should have a vertical arc reading to the nearest minute. Since vertical angles are often required in stadia work it will prove to be a great saving in time to have the vernier and a spirit level mounted on a separate arm (Fig. 91), so that the index correction can be made zero



FIG. 91. VERNIER LEVEL ON TRANSIT.

each time a vertical angle is read. (See Vol. I, Art. 67, p. 54, and Fig. 57, p. 193 of Vol. II.)

216. Stadia Rods. — There are many patterns of stadia rods both as regards the construction of the rod itself and the style of diagram used to mark the graduations. The diagrams for ordinary work should be simple, so that long distances may be read quickly. Complicated diagrams are to be avoided except where all of the sights are short and where greater precision is desired than is usually required in stadia work. In the rods shown in Fig. 92 the diagrams are made so that the .05-ft. or .10-ft. spaces can be easily distinguished and the hundredths of a foot estimated.

The rods on which these graduations are painted consist of wooden strips from 3 to 5 inches wide and 10 to 15 feet in length. For convenience in carrying the rods they are usually made in two sections joined by hinges, but in some cases the two parts are separate and are clamped together when in use.

In Fig. 92 rods (*a*) and (*b*) are particularly useful for reading distances up to about 500 ft. Rod (*c*) is useful up to about 1000 ft. and rod (*e*) is particularly applicable to distant readings. Rod (*d*) is useful both for short and medium distances. Other styles of stadia rods and different types of hinges and clamps used on them are shown in Fig. 47, p. 149, Vol. II.



(The cross-hatched portions are painted red.)

FIG. 92. STADIA RODS.

The ordinary Philadelphia leveling rod graduated to hundredths is suitable for moderately short sights, say 300 feet.

217. Principle of the Stadia. — The fundamental principle upon which the stadia method depends is the simple geometric proposition that in two similar triangles homologous sides are proportional. Suppose that the telescope is level and is sighted at a vertical rod, then a certain space on the rod will apparently be intercepted between the stadia hairs, the length of this space

on the rod depending upon the distance from the instrument to the rod.

In Fig. 93 let L be the optical center * of the objective, a and b the stadia hairs, and A and B the points on the rod where the stadia hairs appear to cut it. AB is then the intercepted space when the rod is at the distance LX. If the rod were moved to the position Y, where the distance is one-half LX, then the intercepted space $A''B''$ would be one-half AB. That is, **the space on the rod is proportional to the distance.** Let $Lp = f_1$



FIG. 93.

and $LX = f_2$ (these distances being known as conjugate foci) and also let $AB = s$, and $ab = i$.

Then from the similar triangles,

$$f_2 : f_1 = s : i \qquad [1]$$

When the rod is moved from X to Y, however, it becomes necessary to alter the focus of the objective, i.e., the distance between the objective and the cross-hairs must be increased. In some telescopes this is accomplished by moving the tube containing the eyepiece and the cross-hairs, and in others by moving the objective. In the figure let L remain fixed and suppose the cross-

* Strictly speaking the lines representing the rays of light should not be drawn straight through the optical center as in the figure but should be bent at the surfaces of the lens. As a result the vertices of the two triangles ALB and aLb do not fall at L but fall at two points L' and L'' inside the lens. The same ratio will be seen to exist between the sides of these triangles ($AL'B$ and $aL''b$) as exists in case of the triangles discussed in the text. The error introduced by neglecting the distance $L'L''$ is entirely inappreciable in stadia measurements.

hairs to move to the position $a'b'$. If the rod is now viewed through the telescope the cross-hairs will not appear to strike at A'' and B'' but at A' and B'. The lines AA' and BB' continued will meet at some point V on the optical axis, in front of L.

In determining the position of this point it is necessary to make use of the "Law of Lenses," namely,

$$\frac{I}{f_1} + \frac{I}{f_2} = \frac{I}{F} \qquad [2]$$

in which F is the *focal length* of the objective, i.e., the distance from the optical center to the cross-hairs when the telescope is focused on a distant object. (Art. 46, p. 35.) Solving equations [1] and [2] simultaneously,

$$f_2 = \frac{F}{i}s + F \qquad [3]$$

i.e., the distance LX is made up of two parts, — the variable distance VX, or $\frac{F}{i}s$, and the constant LV, or F. Since equation [3] was derived from a general case, LV is a constant for all stadia readings made with the same instrument, and the distance VX is a variable depending upon the rod interval. Hence all stadia distances (from the objective) are obtained by multiplying the space on the rod by a constant, $\frac{F}{i}$ and adding to this result the focal length, F. The distance desired, however, is from the center of the instrument to the rod. This is found by adding to the above result the distance CL from the objective to the center of the instrument, which will be called c. The complete expression for the distance is then

$$\text{Distance} = \frac{F}{i}s + (F + c) \qquad [4]$$

218. Stadia Constants. — In equation [4] the ratio $\frac{F}{i}$ is a constant for any given instrument in which the stadia hairs are not adjustable. The quantity $(F + c)$ is practically a constant for any given instrument. F is strictly a constant, and c

is constant when the telescope is focused by moving the eyepiece; if the focusing is done by moving the objective, c will vary only about a hundredth of a foot in ordinary stadia sights, a negligible quantity in stadia measurements.

The distance between the cross-hairs is generally made equal to one one-hundredth part of the focal length, so that the distance VX may be found by multiplying the space on the rod by 100, i.e., every hundredth of a foot on the rod corresponds to a foot in distance. In practice it is customary to read the rod interval to the nearest hundredth of a foot only, so that distances are obtained to the nearest foot. If the stadia hairs are not set at exactly this interval the error may be determined by measuring a base-line with a steel tape and taking several readings on a rod held at two different distances, say 100 feet and 600 feet. In order to obtain these rod intervals accurately it is advisable to use a leveling rod with two targets, the lower hair being set on the lower target and the upper target being set opposite the upper hair. When the rod intervals have been carefully determined at both of the distances, the constant may be found by substituting these values and the measured distances in equation [4], thus forming two equations of the same form in which $\frac{F}{i}$ and $(F + c)$ are the only unknowns. Solving these two equations simultaneously will give an accurate value for the constant $\frac{F}{i}$.

This, however, is not a satisfactory method for determining the constant $(F + c)$, since errors in the readings cause a comparatively large error in the result. The constant F is the distance from the objective to the cross-hairs when the telescope is focused for a distant object, and c is the distance from the objective to the center of the instrument when focused for an average length of sight, both of which distances may be directly measured.

The constant $(F + c)$ varies from about 0.75 to about 1.35 in different transits, but it is customary and sufficiently accurate to regard it as 1 foot, since the distances are usually read to the nearest foot only.

219. Formulas for Inclined Sights. — In practice it is customary to hold the rod **plumb** rather than perpendicular to the line of sight, because the former position can be readily and accurately judged, while it is not easy to determine when the rod is perpendicular to the line of sight. On inclined sights, when the rod is plumb, the vertical and horizontal distances evidently cannot be found by solving a single right triangle. In Fig. 94 let AB be the intercept on the rod when it is held vertical, $A'B'$ the intercept when the rod is perpendicular to the line of



FIG. 94.

sight, i.e., $A'B'$ is perpendicular to CO. * In the triangle AOA', $\angle O = \angle \alpha$, the measured vertical angle; $\angle A' = 90^\circ + m$; and $\angle A = 90^\circ - (\alpha + m)$, m being half the angle between the stadia hairs. In the triangle BOB', $\angle O = \angle \alpha$; $\angle B' = 90^\circ - m$; and $\angle B = 90^\circ - (\alpha - m)$.

Then
$$\frac{AO}{A'O} = \frac{\sin (90^\circ + m)}{\sin \{90^\circ - (\alpha + m)\}}$$

and
$$\frac{BO}{B'O} = \frac{\sin (90^\circ - m)}{\sin \{90^\circ - (\alpha - m)\}}$$

$$AO + OB = AB = \tfrac{1}{2} A'B' \left\{ \frac{\cos m}{\cos (\alpha + m)} + \frac{\cos m}{\cos (\alpha - m)} \right\}$$

* This demonstration is nearly the same as that given by Mr. George J. Specht in "Topographical Surveying," published by Van Nostrand Company, New York.

from which may be obtained

$$A'B' = AB \cos \alpha - AB \frac{\sin^2 \alpha}{\cos \alpha} \tan^2 m$$

The value of the second term is very small; for $AB = 15.00$ feet, $\alpha = 45°$, and $m = \tan^{-1} 0.005$, this term is only 0.0002 feet, and hence it may always be neglected. In other words it is always sufficiently accurate to regard the angles A' and B' as right angles.

$$\therefore A'B' = AB \cos \alpha$$



FIG. 94.

The difference in elevation between the center of the instrument and the point O on the rod is derived as follows:

$$DO = CO \sin \alpha$$

$$= \left\{ \frac{F}{i} A'B' + (F + c) \right\} \sin \alpha$$

$$= \frac{F}{i} AB \sin \alpha \cos \alpha + (F + c) \sin \alpha$$

$$= \frac{F}{i} AB \cdot \tfrac{1}{2} \sin 2\alpha + (F + c) \sin \alpha \qquad [5]$$

For the horizontal distance from the transit point to the rod we have

$$CD = CO \cos \alpha$$
$$= \left\{ \frac{F}{i} A'B' + (F + c) \right\} \cos \alpha$$
$$= \frac{F}{i} AB \cos^2 \alpha + (F + c) \cos \alpha \qquad [6].$$

220. Most of the stadia tables, diagrams, and stadia slide rules in common use are based upon these two formulas, [5] and [6]. Table VIII, p. 557, contains the value of $\frac{F}{i} . AB . \frac{1}{2} \sin 2 \alpha$ for values of α varying from 0 degrees to 40 degrees, and for a rod interval (AB) of one foot. $\frac{F}{i}$ is taken as 100, the usual ratio. The vertical height for any rod interval can be obtained by multiplying the tabular number by that rod interval. The table of horizontal corrections (Table VIII) contains the number of feet to be subtracted from the distance read, $100 \times AB$, and is given for different distances up to 1000 feet and for angles from 0 degrees to 40 degrees. It is ordinarily possible to interpolate mentally and to obtain the correction to the nearest foot, which is sufficiently accurate for most stadia work.

To allow for the constant $(F + c)$ when obtaining the vertical height the term $(F + c) \sin \alpha$ should be added to the result found from the table. Strictly speaking this term should be computed separately, but the error is almost always negligible if the constant $(F + c)$ is first added to the distance $100 \times AB$, which is equivalent to adding $\frac{F + c}{100}$ to the rod interval, and then obtaining the vertical height from the table as before. In allowing for this constant when determining the horizontal distance the term $(F + c) \cos \alpha$ is always so nearly equal to $(F + c)$ that the true horizontal distance may be found by adding $(F + c)$ to $100 \times AB$ and then subtracting the horizontal correction.

221. For small vertical angles, say under 3°, the horizontal correction may be omitted and if in this case the constant $(F + c)$ is also omitted, it will be observed that since one of these is positive and the other negative the resulting error will usually

be smaller than either of these corrections. Care should be taken, however, that the constant $(F + c)$ is not omitted when computing or plotting a traverse, for in this case the error tends to accumulate and may seriously affect the accuracy of the map. In very rough work or on small-scale plans where errors of one or two feet cannot be plotted the constant $(F + c)$ may be omitted.

222. Fieldwork. — In surveying by the stadia method points are located by means of (1) the azimuth, (2) the angle of elevation or depression, and (3) the distance. When the survey does not involve the determination of elevations the vertical angles are simply read close enough for computing the horizontal correction to the distances read. But when a topographical survey is made, the determination of elevations becomes necessary and all vertical angles must be read closer, usually to the nearest minute. The azimuths and distances are read in both kinds of surveys with a precision that is consistent with the accuracy required in the final result.

Traverse lines which form the control of the survey are run out either by means of the transit and tape or by stadia, according to the accuracy demanded. Where a number of transit points are to be distributed over a large area this can be most rapidly done by laying out a small system of triangulation, in which a base and a few additional lines are measured with the tape and the lengths of all of the lines in the system are computed; the additional measured lines will serve as checks on the accuracy of the work. Where the survey is controlled by such a triangulation or by tape traverses the stadia work is confined to filling in details. Where no great accuracy is required the main traverse may be measured by stadia alone; in this case the distances should be read on both forward and back sights.

From the traverse line as a control, points taken for the purpose of locating details are determined by angles and stadia distances. These observations are commonly called "side shots." The accuracy with which these measurements are taken need not be so great as that of the traverse measurements, because any error in the measurements will affect only a single point, whereas an error in the traverse line will be carried through

the rest of the traverse. The side shots are usually numbered consecutively in the note-book.

In locating points as above described the readings are conveniently taken in the following order. The vertical hair is first set on the rod and the upper plate clamped; the distance is then read by setting one stadia hair on a whole foot-mark and reading the position of the other stadia hair (Fig. 92); finally the middle horizontal hair is set on the point on the rod to which the vertical angle is to be taken. After making this setting the transitman signals the rodman to proceed to the next point and in the meantime he reads the azimuth and the vertical angle.

223. Azimuth Angles. — Azimuths are usually reckoned from the south point through the west up to 360 degrees in accordance with geodetic practices. If the true azimuth of any line is known, or if observations for the true meridian have been made, all the azimuths of the survey may be referred to the meridian. If the direction of the true meridian is not known an initial azimuth may be taken from the magnetic bearing of some line and all azimuths referred to the magnetic meridian. The latter method has the advantage that all azimuths may be directly checked (roughly) by reading magnetic bearings in addition to the azimuth indicated by the vernier. If for any reason the magnetic meridian cannot be used, any direction may be arbitrarily assumed as a meridian and all azimuths referred to this direction. In case a transit and tape traverse has been previously run it is often convenient to assume one of the transit lines as the 0° line of azimuths, a new traverse line being taken as a reference line for the azimuths at each set-up if desired.

In running traverses by stadia it is necessary to carry forward the direction of the meridian from one transit point to the next; there are two methods in common use, each of which has its advantages. Suppose that the work at point A is completed, all of the azimuth angles about A having been referred to the meridian which was chosen as the 0° direction, and that the transit is to be moved to a new station B. Before leaving A the transit point B is located from A by its distance and azimuth. The transit is then set up at B and the azimuth of any line (BC) is determined in either of the following ways.

(1) Backsight on A with the telescope inverted, the horizontal circle remaining at the same reading it had at A (the azimuth of line AB); clamp the lower plate, turn the telescope into its direct position, and, loosening the upper plate, turn toward C. The circle will then read an angle which will be the azimuth of BC referred to the same meridian as the azimuth of AB. It is evident that this method does not eliminate any error that may exist in the line of collimation, so that the error in the azimuth will accumulate. The advantage of this method is the rapidity with which the instrument can be oriented.

(2) Add 180 degrees to the azimuth of AB, set this off on the plate, and sight on A with the telescope direct. Sight the telescope toward C, and the angle read will be the azimuth of BC. The disadvantages of this method as compared with the former are that time is consumed in setting the circle at each new set-up of the instrument, and that there is an opportunity for mistakes in calculating and in making the setting on the vernier.

224. Vertical Angles. — When vertical angles are to be taken the middle horizontal cross-hair is sighted at a point on the rod whose distance above the foot of the rod is equal to the distance from the center of the transit to the ground (or the stake) beneath. This distance is known as the *height of instrument* (H.I.); it is not the same as the H.I. used in ordinary leveling, which is the height of the instrument above the datum plane. If the cross-hair is sighted at this H.I. point on the rod, it is evident that the line of sight is parallel to the line from the transit point to the foot of the rod, and that the difference in elevation between the center of the instrument and the H.I. on the rod is the same as the difference in elevation between the point under the transit and the foot of rod. It is common practice to fasten a rubber band on a strip of red cloth on the rod so that it can be set on the new H.I. point on the rod at each set-up.

225. Distances. — The distance is read by setting one of the stadia hairs on a whole foot-mark and counting the feet and tenths between the stadia hairs, the hundredths of a foot being estimated. If a Philadelphia leveling rod is used and the distances are short, the hundredths of a foot may be read directly. Great care should be taken not to mistake the middle horizontal

cross-hair for one of the stadia hairs. This mistake is likely to occur when the telescope is of high power, because the stadia hairs appear to be far apart in the field of view and consequently the eye does not readily see all three hairs at once. In counting the number of feet in the rod interval between the stadia hairs great care should be taken to obtain this interval correctly. It can be checked by reading the interval between the middle hair and a stadia hair and observing if this is approximately one half of the whole interval. (Fig. 92, p. 191.)

It is customary in reading the distance to set the lower stadia hair on that foot-mark which will bring the middle cross-hair in the vicinity of the H.I. In finding the horizontal correction to apply to the distance read it is customary to use the vertical angle read when the middle cross-hair is on the H.I. Theoretically a slight error is thus introduced because when the distance is read with a stadia hair on a whole foot-mark the inclination of the line of sight is not quite equal to the vertical angle read. The middle hair, however, need not be more than half a foot above or below the H.I. when the distance is read, and in this case it is easy to show that the error in horizontal distance produced by sighting exactly on the H.I. is negligible.

Whenever a portion of the rod is obscured, by leaves for instance, or when the distance is so great that the two stadia hairs do not both fall on the rod at the same time, an approximate value of the reading may be obtained by reading first the interval between the upper and middle hairs and then the interval between the middle and lower hairs, and taking the sum of the two readings. If the two spaces are found to be exactly equal it will be sufficient to take one reading and double it, but it should never be assumed that the two are equal.

It is of great importance that the rod should be held plumb when the distance is being read, as any inclination of the rod will evidently introduce an error into the observed distance. This error becomes greater as the inclination of the line of sight increases. In some classes of stadia work it is desirable to plumb the rod by means of a rod level whenever highly inclined sights are taken.

226. STADIA TRAVERSES. — In a stadia traverse the instrument is set at the first station and the telescope set on the meridian (or reference line) with the vernier reading 0°. The position of the second station is located by reading the distance, azimuth, and vertical angle. In determining the azimuth of the line it is well for the rodman to show the narrow edge of his rod as a foresight, so that the transitman can make a more exact setting of the vertical cross-hair. The transit is then moved to the second station and placed in position by backsighting on the first point as explained in Art. 223; at the same time the vertical angle and the distance are again read, thus checking the distance between the two points and also the difference in elevation if stadia levels are also being taken. In reading the distances both ways there is also an opportunity to guard against an inaccurate reading due to poor illumination of the rod. By sighting both directions with the telescope erect the index error of the vertical circle is eliminated; this process is similar in principle to the peg method of testing a level. (See Art. 128, p. 92.)

227. Checks on the Traverse. — In running a closed stadia traverse the azimuths may be checked by redetermining the azimuth of the first line from the last and noting whether this value checks the azimuth of the first line as determined at the beginning of the traverse. If these differ by less than 5 minutes of angle the result will be sufficiently accurate for most topographical purposes. The azimuths may be roughly checked at any point by reading the magnetic bearings of the lines. Where there are triangulation points connected with the survey the known azimuths of these triangle sides will furnish a complete check.

In running stadia traverses for several miles where no other check on the azimuths can be obtained it is advisable to make observations on the sun for azimuth. (Art. 240, p. 225.) Such observations can be quickly taken and if made in the morning or afternoon, when the sun is not very near the meridian, will give the azimuth within about one minute of arc, which is as accurate as is required for this purpose.

228. Stadia Notes. — To the beginner the taking of good stadia notes presents great difficulties. The general instructions

Stadia Survey of Pasture Land of L. K. Miller
Jan. 15, 1915
King ⊼ Stone

⊼ at	Sta.	Dist.	Az. ∠ 0° on Mag. S	Obs. Bearing	Vert. ∠	Remarks
A	E	717			-2° 15′	
	B	642	211° 21′	N. 31° 15′ E.		
B	A	642				
	C	786	272° 47′	S. 87° 15′ E		
C	B	784				
	D	971	359° 03′	S. 1° 00′ E	+4° 40′	Cedar Post
D	C	973			-4° 30′	
	E	897	76° 05′	S. 77° 00′ W		Stake and Stones
E	D	895				
	A	718	157° 34′	N. 22° 15′ W.	+2° 00′	Stake and Stones
A			211° 20′ "check"			
A	1	467	199° 00′			
A	2	491	199° 50′			



FIG. 95. STADIA SURVEY FOR AREA.

with regard to transit notes apply equally well to notes for stadia surveys. (Art. 148, p. 112.) A large amount of sketching or description of details is required in order to convey sufficient information to enable the draftsman, who may not be familiar with the locality, to plot the results. Furthermore it is necessary to locate a large number of points in order to be sure of sufficient data to correctly sketch the details. If the map can be plotted soon after the fieldwork is done and by the person who made the survey, and especially if the map can be afterward taken into the field and the sketching there completed, then much greater accuracy in regard to details can be secured; this field sketching on the map is important and should be done whenever it is practicable.

The notes for the survey of a lot of land are shown in Fig. 95. The notes given above in tabular form show in the first column the station at which the instrument was set up; the second column indicates the station to which it was sighted; the distances read are in the third column. The azimuth angles are read to the nearest minute because they are to be used for purposes of calculation, the observed bearings are taken as a check upon the azimuths. The vertical angles are taken only on those lines where the horizontal correction would change the distances as much as a foot, and they are read only to the nearest quarter or half degree because for the distances and the vertical angles occurring in these notes this will give the horizontal correction to the nearest half-foot. Evidently there is no necessity in this case for indicating whether the angles were plus or minus. The traverse was measured in a right-hand direction around the field beginning at A, and finally the instrument was set up at A again, backsighted on E, and the azimuth of the line AB redetermined from the backsight on E. The notes indicate that an error of one minute was found in the azimuths. The notes also indicate that two shots, Nos. 1 and 2, were taken to the corners of a barn merely for the purpose of obtaining data for plotting it on the map. The figure in the lower part of the page is a sketch of the property, on which are lettered the names of the abutting owners, and the physical features which define the boundaries.

It will be observed that the distances on the traverse were measured both forward and backward, two independent readings being taken. Before computing the area of this field the average of these two readings should be taken as the correct distance and to this distance should be added, of course, the constant of the instrument (1 ft.). The horizontal correction should be applied to all inclined distances if the correction amounts to more than half a foot.

Fig. 96 is a double page of stadia notes of a survey where elevations were required. The survey in this case was made for the purpose of obtaining a preliminary map of a grade crossing. The traverse was run by transit and tape along the center line of the straight track and at curves running to the point of intersection of the tangents or else cutting across on long chords. The points occupied by the instrument are numbered and are designated by a ⊡, the usual symbol for a stadia station. The side shots are numbered consecutively either throughout the entire survey or through each day's work; the vertical angles are designated + or − to indicate whether they are upward or downward angles. If the middle cross-hair is sighted at any point other than the H.I. it should be noted directly under the vertical angle; such a case occurs on the sight to side shot 41. The first five columns only are entered in the field; most of the values in the last two columns are computed in the office; those which are recorded with inclined figures were computed in the field for the purpose of checking elevations and for establishing station elevations which were used later in the same day's fieldwork. The erect figures were computed in the office.

Referring to the notes on the left-hand page of Fig. 96 it will be seen that the elevation of ⊡ 6 where the transit was first set up was obtained by means of a level reading of 5.26 taken on the B.M. The elevation of ⊡ 6 equals $57.62 + 5.26 - 4.6 = 58.3$. A rectangle is drawn about this figure 58.3 because it is used for all computations of elevation of points which were sighted when the instrument was at ⊡ 6. After all necessary side shots were taken at ⊡ 6 the elevation of ⊡ *A* was determined by the stadia method as 95.3. The azimuth angles were checked by sighting again on Sta. 1 + 62.47. The instrument was then

Survey for Elimination of Grade Crossing at Westwood, A. & B. R.R.

Sta.	Dist.	Az. Ang.	Bear.	Vert. Ang.	Diff. El.	Elev.
℄ at ⊡6,		0° on 1+62.47,			H.I. = 4.6	58.3
B.M.	Top S.	B. at P.T. 3+24.94		0° 00′ on 5.26		57.62
1	298 -1	221° 20′		+3° 27′	+18.0	76.3
2	238 -1	217° 15′		+2° 44′	+11.4	69.7
3	183	205° 10′		+1° 37′	+ 5.2	63.5
4	165	180° 00′		+0° 31′	+ 1.5	58.8
5	167	115° 40′		-0° 16′	- 0.8	57.5
6	177	142° 25′		-0° 42′	- 2.2	56.1
7	212	111° 00′		-1° 22′	- 5.1	53.2
8	323	80° 15′		-1° 57′	-11.0	47.3
9	426	70° 05′		-1° 47′	-13.3	45.0
10	409 -2	67° 30′		-3° 36′	-25.7	32.6
Etc.						
⊡A	825 -2	221° 23′		+2° 34′	+37.0	95.3
1+62.47	437	0° 00′				
℄ at ⊡A,		0° on ⊡6,			H.I. = 4.7	95.1
⊡6	823 -2		S. 7° 15′ E.	-2° 33′	-36.7	58.3
39	312	357° 10′		-1° 25′	- 7.7	87.4
40	133 -1	17° 35′		-3° 46′	- 8.8	86.3
41	156	22° 05′		-2° 46′ on 6.7	- 9.6	85.5
42	274 -1	3° 20′		-2° 24′	-11.5	83.6
Etc.						
⊡12+14.37	547 -2	48° 02′	S. 41° 00′ W.	-3° 07′	-29.8	65.3
⊡6		0° 01′				
℄ at ⊡12+14.37,		0° on ⊡6,			H.I. = 4.8	65.2
⊡6		0° 00′		0° 00′ on 11.7	- 6.9	58.3
⊡A	546 -2	269° 25′		+3° 08′	+29.9	95.1
52	640 -3	56° 25′		-3° 40′	-40.9	24.3

FIG. 96. STADIA SURVEY REQUIRING ELEVATIONS.



FIG. 96. STADIA SURVEY REQUIRING ELEVATIONS.

moved to ⊡ *A* and a backsight taken on ⊡ 6. The elevation of ⊡ 6 was determined above as 58.3 by direct leveling from the bench-mark. It is therefore recorded below opposite station ⊡ 6 as 58.3 and by means of difference in elevation of 36.7 the new elevation of ⊡ *A* is 58.3 + 36.7 = 95.0, but as its elevation was determined above from ⊡ 6 as 95.3 there has been entered in these notes in the last column opposite "Instrument at ⊡ *A*" the figure 95.1, which is the mean (to the nearest tenth) of 95.0 and 95.3.

The side shots at ⊡ *A* are then taken and then Sta. 12 + 14.37 has its elevation established by stadia as 65.3. Before picking up the instrument, ⊡ 6 was sighted to check the azimuth. If this azimuth is correct it indicates that the azimuths of all the side shots are probably correct.

The instrument was then taken to Sta. 12 + 14.37, backsighted on ⊡ 6 and instead of using the elevation 65.3 previously obtained for the elevation of Sta. 12 + 14.37, its elevation is obtained by direct leveling from ⊡ 6 using 58.3 as the elevation of ⊡ 6 which was obtained at the first of the work by a level reading on a bench-mark. The elevation of Sta. 12 + 14.37 = 58.3 + 11.7 − 4.8 = 65.2; this elevation is more reliable than the one obtained by stadia.

It will be noted that in all cases in these notes the backsight reading was taken on 0° azimuth. The side-shot azimuth angles are all read to the nearest 5 minutes only, which is close enough for plotting purposes. Occasional bearings have been taken to check the azimuths. In the second column the little minus quantities at the right are the horizontal corrections taken from a Table of Horizontal Corrections and entered in this column in the office. The notes, description and sketch are on the right-hand page. The numbers enclosed in circles are the numbers of the points which were located by stadia. These little circles are drawn so that these numbers will not be confused with the dimensions on the sketch.

229. METHODS OF REDUCING THE NOTES.—The computation of the differences in elevation and of the horizontal distances is usually performed in practice by one of the following methods: (1) Stadia tables, (2) stadia slide rule, (3) stadia diagram.

(Art. 160, p. 168, Vol. II.) Table VIII, p. 557, is calculated from formulas [5] and [6] and may be used to reduced stadia readings when the vertical angle does not exceed 40°.

230. Use of Stadia Tables. — To illustrate the use of Table VIII it is assumed that the following readings have been taken.

Station	Observed Rod Intervals	Observed Vert. Angle	Computed Diff. El.	Computed Hor. Dist.
1	311	+ 3° 54′	+ 21.18	311
2	91	− 25° 28′	− 35.71	75
3	240	+ 0° 39′	+ 2.74	241

$(F + c) = 1.0$ foot.

The rod intervals are recorded here as distances (100 × rod interval), which is in accordance with common practice, rather than as actual rod intervals. The constant $(F + c)$ has not been included in the recorded distances in the above example.

To obtain the difference in elevation for Station 1 from the Table of Vertical Heights (Table VIII), in the column headed 3 degrees and opposite 54 minutes, 6.79 feet is found as the difference in elevation for a 1-foot rod interval, i.e., a 100-foot distance. By adding $(F + c)$ to the distance 311 the corrected distance 312 is obtained. Then 6.79 feet (the difference for 100 feet) multiplied by 3.12 gives 21.18 feet as the difference in elevation between the center of the instrument and the point on the rod where the middle cross-hair was sighted when taking the vertical angle. This multiplication may be performed with an ordinary slide rule. Beneath the Table of Vertical Heights is given the Table of Horizontal Corrections. The horizontal correction for 311 feet and 3 degrees 54 minutes is found by interpolating between 3 degrees and 4 degrees and also between 300 feet and 400 feet, the result being 1.4 feet. The horizontal distance, to the nearest foot, is then $311 + 1 - 1 = 311$.

At Station 2 the difference in elevation is $.92 \times 38.82 = 35.71$. The horizontal distance is $91 + 1 - 17 = 75$ feet. At Station 3 the vertical height for 0 degrees 39 minutes and for 100 feet is

taken from the 0 degree column by interpolation between 38 and 40 minutes and is 1.14, the difference in elevation for the rod interval 2.40 being 2.74 feet. The horizontal correction is only 0.1 and is therefore neglected. Suppose that at Station 3 the vertical angle + 0° 39′ had been taken at a point on the rod 4 feet **below** the H.I., the difference in elevation would then be + 2.74 + 4.00 = 6.74. Had the sight been taken on the rod 4 feet **above** the H.I. the difference in elevation would be + 2.74 − 4.00 = − 1.26.

231. METHODS OF PLOTTING STADIA NOTES. — Stadia notes are usually plotted by means of a circular protractor and a scale. If the main traverse is a transit and tape survey, or if the scale of the map is such that a protractor would not be sufficiently accurate, the traverse may be plotted by some more accurate method and the side shots put in afterward by the protractor and scale. In general, however, any measurement taken by stadia may be plotted with sufficient accuracy by means of a protractor. (See Chap. XVI for methods of plotting traverses.)

In setting the protractor in position for plotting it should be centered with care and turned to the proper azimuth as defined by a 0° line drawn through the point and extending each way beyond the circumference of the protractor. It is not safe to depend upon a line extending only one way, because the center of a protractor is usually marked in such a way that it is difficult to place it exactly over the transit point on the plan. Many protractors which are accurately graduated have the center point carelessly marked. The most accurate way to use a protractor is to draw two lines at right angles to each other, one of them being the meridian or reference line. These lines may be drawn at right angles as explained in Art. 486, p. 450. The protractor is then **oriented,** i.e., turned in the proper direction by means of the cardinal points on the circumference of the circle, without regard to the position of the center mark on the protractor.

The usual process is to place the protractor in position and plot all of the azimuths first, marking each by a light dot or a short radial line in the proper azimuth and writing opposite the mark the number of the shot. This work can be conveniently

done by two persons, one reading the azimuths and the numbers while the other plots the angles. When all of the azimuths have been plotted the protractor is removed and the distances are scaled off, the proper elevation being written opposite each point. Sometimes the plotted position of the point is indicated by a dot enclosed by a small circle, the height being written at one side. Another way, which is convenient when the plotted points are close together, is to write the whole number of feet of the elevation to the left of the point and the tenths to the right, the plotted point itself serving as the decimal point. (For special methods of plotting stadia notes see Vol. II, Chap. IV.)

PROBLEM.

COMPUTE THE HORIZONTAL DISTANCES AND THE ELEVATIONS IN THE FOLLOWING STADIA SURVEY.

Pt.	Dist.	Azimuth	Observed Bearing	Vert. Angle	Diff. El.	Eleva.
		Instr. at ⊡ 4		H.I. = 4.29		133.1
81	61	168° 20′		− 13° 40′		
82	90	84° 30′		− 5° 45′		
83	140	218° 10′		− 5° 40′		
84	101	343° 10′		− 2° 16′ on 9.3		
85	185	310° 05′		− 4° 56′ on 5.3		
86	276	301° 25′		− 5° 26′ on 2.3		
87	373	277° 05′		− 4° 05′		
88	280	261° 45′		− 4° 44′		
89	210	233° 15′		− 5° 13′		
90	220	216° 50′		− 3° 55′		
91	201	202° 30′		− 3° 25′		
⊡5	255	202° 19′	N22° E	− 3° 08′		
		Instr. at ⊡ 5		H.I. = 5.01		
92	88	85° 30′		− 1° 55′		
93	157	113° 20′		− 2° 55′		
94	183	169° 10′		− 1° 36′		
95	90	205° 20′		+ 0° 09′		
96	193	194° 25′		− 0° 06′		
97	218	222° 15′		+ 2° 06′		
98	115	228° 40′		+ 2° 30′		
99	39	230°		+ 2° 56′		
100	90	283° 40′		+ 1° 32′		
101	122	255° 20′		+ 3° 18′		
102	185	279° 00′		+ 2° 10′		
103	213	261° 30′		+ 3° 14′		
104	308	272° 00′		+ 0° 55′		
105	353	279° 10′		+ 0° 05′		
106	225	284° 50′		+ 0° 46′		
107	288	290° 30′		− 0° 20′		

CHAPTER VIII.

OBSERVATIONS FOR MERIDIAN AND LATITUDE.*

OBSERVATIONS FOR MERIDIAN.

232. To Establish a True Meridian Line by Observation on Polaris with the Transit. — On account of the earth's daily rotation on its axis all heavenly bodies **appear** to revolve once a day around the earth. Stars in the south appear to revolve in large circles parallel to the daily path of the sun. As we look farther north the apparent size of the circles grows smaller. The center of these circles is the *north pole* of the *celestial sphere*, a point in the sky in the prolongation of the earth's axis. The pole-star *(Polaris)* revolves about the pole in a small circle whose radius is less than a degree and a quarter (Fig. 97). This angular distance from the pole to a star is called its *polar distance.*



FIG. 97.

When the star is directly above the pole its bearing is the same as that of the pole itself and the star is said to be at *upper culmination.* At this instant it is **in the true meridian.** About twelve hours later it will be below the pole at *lower culmination* and will be again in the true meridian. About half-way between these two positions the star reaches its greatest east or west bearing,

* See also Chapter II, Volume II.

and at such times is said to be at its greatest *elongation.* At either *eastern* or *western elongation* the star's bearing is not changing perceptibly because it is moving almost vertically, a


Position of the Constellations when Polaris is at Upper Culmination.
δ
Cassiopeia
Direction of Apparent Motion
POLARIS
POLE
Ursa Minor
Pointers
Ursa Major
β
Position of the Constellations when Polaris is at Western Elongation.
Position of the Constellations when Polaris is at Eastern Elongation.
Position of the Constellations when Polaris is at Lower Culmination.

FIG. 98. RELATIVE POSITION OF THE CONSTELLATIONS NEAR THE NORTH POLE.

condition which is most favorable for an accurate observation. At culmination the star is changing its bearing at the maximum rate, and therefore this is not as good a time to make an accurate observation as at elongation. This star moves so slowly, however, that even at culmination its bearing can be obtained with sufficient accuracy for determining the declination of the needle. Polaris can be easily found by means of two conspicuous constellations near it, *Cassiopeia* and *Ursa Major*. The seven most conspicuous stars of the latter form what is commonly known as the "*Great Dipper*" (Fig. 98). The two stars forming the part of the bowl of the Dipper farthest from the handle are called the "*pointers*" because a line through them points almost directly at the pole. On the opposite side of Polaris is Cassiopeia, shaped like the letter W. A line drawn from δ* *Cassiopeiæ*, the lower left-hand star of the W, to ζ *Ursæ Majoris*, the middle star of the Dipper handle, passes very close to Polaris and also to the pole itself.

233. OBSERVATION FOR MERIDIAN ON POLARIS AT ELONGATION. — When the Dipper is on the **right** and Cassiopeia on the **left**, Polaris is near its **western elongation**; when the dipper is on the **left** Polaris is near **eastern elongation.** When the constellations are approaching one of these positions the transit should be set over a stake and leveled, and the telescope focused upon the star.† Unless the observation occurs at about sunrise or sunset it will be necessary to use an artificial light to make the cross-hairs visible. If the transit is not provided with a special reflector for throwing light down the tube a good substitute may be made by cutting a small hole in a piece of tracing cloth or oiled paper and then fastening it over the end of the telescope tube by a rubber band. If a lantern is then held in front and a little to one side of the telescope the cross-hairs can be plainly seen. The star should be bisected by the vertical wire and followed by means of the tangent screw in its horizontal motion until it no

* The Greek Alphabet will be found on p. 570.

† It is difficult to find a star in the field of view unless the telescope is focused for a very distant object. The surveyor will find it a convenience if he marks on the telescope tube the position of the objective tube when it is focused for a distant object.

longer changes its bearing but moves vertically. (It will be seen from Fig. 97 that when the star is approaching eastern elongation it is moving **eastward** and **upward**; when approaching western elongation it is moving **westward** and **downward**.) As soon as this position is reached the telescope should be lowered and a point set in line with the vertical cross-hair at a distance of several hundred feet from the transit. Everything should be arranged beforehand so that this can be done quickly. Immediately after setting this point the instrument should be reversed and again pointed on the star. A second point is then set at one side of the first. The mean of these two points is free from the errors of adjustment of the transit. If the instrument is in adjustment, of course, the first and second points coincide. On account of the great difference in altitude between the star and the mark the elimination of instrumental errors is of unusual importance (Art. 79, p. 61). For 10 minutes of time on either side of elongation the bearing of the star does not change more than 5 seconds of arc and therefore there is sufficient time to make these two pointings accurately.

After the direction of the star at elongation has been found, the meridian may be established by laying off an angle equal to the azimuth, or true bearing of the star. Since this angle to be laid off is the **horizontal** angle between the star and the pole, it is not equal to the polar distance but may be found from the equation: —

$$\text{Sin Star's True Bearing} = \frac{\text{Sin Polar Distance of Star}}{\text{Cos Latitude}} \quad *$$

The mean polar distances for the years 1906 to 1920 may be

---

* This equation may be derived as follows; in Fig. 83, let P represent the pole, Z the zenith, and E the position of the star at elongation. Then by spherical trigonometry,

$$\frac{\sin PZE}{\sin ZEP} = \frac{\sin PE}{\sin ZP}.$$

But PZE is the angle between the two vertical circles and equals the bearing. $ZEP = 90°$ because ZE is tangent to the circle $WUEL$, which represents the path of Polaris. PE is the polar distance and ZP may be shown to be equal to 90° − latitude.

Hence,

$$\sin PZE = \frac{\sin PE}{\cos \text{lat.}}.$$

TABLE 8

MEAN POLAR DISTANCES OF POLARIS.*

Year.	Mean Polar Distance.			Year.	Mean Polar Distance.		
	°	′	″		°	′	″
1906	1	11	41.05	1914	1	09	12.07
1907	1	11	22.37	1915	1	08	53.51
1908	1	11	03.71	1916	1	08	34.97
1909	1	10	45.07	1917	1	08	16.45
1910	1	10	26.44	1918	1	07	57.94
1911	1	10	07.82	1919	1	07	39.45
1912	1	09	49.22	1920	1	07	20.98
1913	1	09	30.64	....	..	..	..

found in Table 8. The latitude may be obtained from a reliable map or by observation (Arts. 242–3, p. 230).

When the transit is set up at the south end of the line the angle thus computed must be laid off to the **right** if the elongation is **west**, to the **left** if the elongation is **east**. A convenient and accurate way of laying off the angle is by measuring the distance between the two stakes *A* and *B* (Fig. 99), and calculating the perpendicular distance *BC* which must be laid off at the north stake *B* to give a meridian *AC*.



FIG. 99.

* The above table was derived from data furnished by the Superintendent of the United States Coast and Geodetic Survey. The Mean Polar Distance is the polar distance the star would have at the beginning of the year, if unaffected by small periodic variations.

In taking the polar distance from the table for the purpose of looking up its sine the student should keep in mind the degree of precision desired in the computed azimuth. If the azimuth is to be within about one minute of the true value the polar distance need be taken only to the nearest minute, but if the azimuth is to be correct within a few seconds the polar distance should be taken to the nearest second. It should be noted however that since the values given in the table take no account of the variations during the year, there will in general be an error of a few seconds due to neglecting the variation of the polar distance during the year. The exact value for every day in the year may be found in the "American Ephemeris and Nautical Almanac," published by the Bureau of Equipment, Navy Department.

234. Observation for Meridian on Polaris at Culmination. — At the instant when Polaris is above the pole the star ζ *Ursæ Majoris* will be almost exactly underneath Polaris. When Polaris is below the pole δ *Cassiopeiæ* will be almost directly below Polaris (Fig. 98). In order to know the instant when Polaris is exactly on the meridian it is necessary first to observe the instant when one of these two stars is vertically below Polaris. From this the time when Polaris will be on the meridian can be calculated by adding a certain interval of time, and the meridian line can thus be directly established. This interval of time was, for ζ *Ursæ Majoris*, about 2^m36^s in the year 1900, and it increases about 21^s per year. The intervals computed by this rule are only approximate, but are sufficiently accurate for many purposes and, as the change is very slow, the rule is good for many years. It may also be used for any latitude in the United States. When ζ *Ursæ Majoris* cannot be used, as is the case in the spring of the year, especially in northern latitudes, a similar observation can be made on δ *Cassiopeiæ*. The interval for this star was 3^m24^s for 1900, with an annual increase of about 20^s.

The observation to determine when the two stars are in the same vertical plane is at best only approximate, since the instrument must be pointed first at one star and then at the other; but since Polaris changes its azimuth only about 1 minute of angle in 2 minutes of time, there is no difficulty in getting fair results by this method. The vertical hair should first be set on Polaris, then the telescope lowered to the approximate altitude of the other star to be used. As soon as this star comes into the field the vertical hair is again set carefully on Polaris. As it will take the other star about 2 minutes to reach the center of the field there will be ample time for this pointing. Then the telescope is lowered and the instant when the star passes the vertical hair is observed by a watch. This will be the time desired, with an error of only a very few seconds. The time of culmination should then be computed as described above and the vertical hair set on Polaris when this computed time arrives. The telescope is then in the meridian which may be marked on the ground.

It will be seen that in this method the actual error of the watch has no effect on the result since it is used only for measuring the interval of a few minutes. The error in the meridian obtained by this method will seldom exceed one minute of angle.

235. To Find the Standard Time of Culmination and Elongation. — The approximate times of culmination and elongation of Polaris for the 1st and 15th of each month in the year 1915 may be found in Table 9.

TABLE 9

APPROXIMATE TIMES OF CULMINATION AND ELONGATION OF POLARIS COMPUTED FOR THE 90TH MERIDIAN WEST OF GREENWICH, FOR THE YEAR 1915.

Date.	Upper Culmination.	Western Elongation.	Lower Culmination.	Eastern Elongation.
1915	*h m*	*h m*	*h m*	*h m*
Jan. 1...	6 47	12 42	18 45	0 52
" 15...	5 52	11 47	17 50	23 53
Feb. 1...	4 44	10 39	16 42	22 45
" 15...	3 49	9 44	15 47	21 50
Mar. 1...	2 54	8 49	14 52	20 55
" 15...	1 59	7 54	13 57	20 00
Apr. 1...	0 52	6 47	12 50	18 53
" 15...	23 53	5 52	11 55	17 58
May 1...	22 50	4 49	0 52	16 55
" 15...	21 55	3 54	9 57	16 00
June 1...	20 49	2 48	8 51	14 54
" 15...	19 54	1 53	7 56	13 59
July 1...	18 51	0 50	6 53	12 56
" 15...	17 56	23 51	5 58	12 01
Aug. 1...	16 50	22 45	4 52	10 55
" 15...	15 55	21 50	3 57	10 00
Sept. 1...	14 48	20 43	2 50	8 53
" 15...	13 54	19 49	1 56	7 59
Oct. 1...	12 51	18 46	0 53	6 56
" 15...	11 56	17 51	23 54	6 01
Nov. 1...	10 49	16 44	22 47	4 54
" 15...	9 54	15 49	21 52	3 59
Dec. 1...	8 51	14 46	20 49	2 56
" 15...	7 56	13 51	19 54	2 01

To find the time for any other date interpolate between the values given in the table, the daily change being about 4 minutes.

In order to find the exact time of culmination or elongation for any observation it would be necessary to take into account the latitude and longitude of the place and the exact date of the observation. The times given in Table 9 are only approximate in any case and are to be regarded merely as a guide so that the surveyor may know when to prepare for his observations.

The times are computed for mean local astronomical time at the 90th meridian west of Greenwich and for the year 1915. These numbers increase about $\frac{1}{3}$ minute per year on the average, so that this table will give approximate results for other years. Astronomical time begins at noon of the civil day of the same date and is reckoned from 0^h to 24^h, e.g., 18^h would mean 6^h A.M. The tabular numbers are nearly correct for the Standard Meridians, i.e., the 75th, 90th, 105th, and 120th west of Greenwich. All watches keeping "railroad time," or "standard time," are set to the local mean time of one of these four meridians (Art. 86, p. 68). To find the watch time of culmination or elongation for any other meridian, first find the difference in longitude in degrees between the place of observation and the standard meridian, and then convert this into minutes and seconds of time by dividing by 15, since 15° of longitude are equivalent to one hour of time. The standard, or watch, time of the observation is then obtained by **adding** this correction to the time taken from the table if the place is **west** or by **subtracting** it if the place is **east** of the standard meridian.

236. Meridian Observations on Polaris with the Compass. — In determining a meridian with the compass the observations are made as described for the transit except that the following modifications will be necessary. Suspend a long plumb-line a few feet away from the point where the instrument is to be set. Since the rear sight is the only part of the compass to be used in the observation it may be unscrewed from the compass and fastened to a piece of board. This board should be placed on a table. The compass sight may then be shifted to the right or left to bring it in line with the star and the plumb-line. The plumb-line should be illuminated by means of a lantern. The direction of the star may be marked by setting stakes in line. If the observation is made at elongation the

meridian should be laid out as described in Art. 233. In finding the declination of the needle the compass is set up over one of the meridian stakes and sighted at the other, when the declination can be read off directly. In order to obtain as nearly as possible the mean value of the declination this should be done at about 10 A.M. or 5 to 6 P.M. because at these times the needle is in its mean position for the day.

237. MERIDIAN OBSERVATION ON POLARIS AT ANY TIME WITH THE TRANSIT. — In order to make this observation, it is necessary to know the local time very closely. As in most cases the time which the surveyor carries is "standard time" it is assumed that such is the case here. The observation itself consists in either marking the direction of the star, as previously described, and noting the time by the watch when the star is sighted; or in repeating the angle between the star and some reference mark, the time of each pointing on the star being noted. In the latter case, take the average of the observed times and assume that it corresponds to the average angle. This is very nearly true if the observations extend over a few minutes of time only.

After finding the standard time of the observation, the next step is to compute the *hour angle* of the star at the time of the observation. Take from the Nautical Almanac: (1) the *right ascension* of Polaris for the date; (2) the *right ascension* of the "*mean sun*" for the date; (3) the *increase* in the *sun's right ascension* since Greenwich noon, which is found in Table III in the Appendix to the Nautical Almanac. Remember that the dates in the Almanac are in Astronomical time (Art. 235, p. 218). Reduce the standard time to local time by adding or subtracting the difference in longitude expressed in hours, minutes, and seconds, remembering that if the place is west of the standard meridian the local time is earlier than standard time and *vice versa*. To the local time add the sun's right ascension and the correction from Table III, Appendix, Nautical Almanac. The result is the *sidereal time*. From this subtract the star's right ascension, and the result is the hour angle of the star reckoned from the meridian from 0h to 24h in the direction of the star's apparent motion. Convert this angle into degrees, minutes, and seconds. The azimuth of the star may now be computed from the formula,

$$* \tan Z = \frac{\sin t}{\cos L \tan D - \sin L \cos t}$$

where Z = the azimuth, or true bearing; t = the hour angle; L = the latitude; D = the declination = 90° − the polar distance. If the hour angle is between 0h and 12h the star is west of the meridian; if between 12h and 24h it is east of the meridian (see Example below).

In the "Manual of Surveying Instruction" issued by the General Land Office a set of tables is given which will enable the surveyor to perform all of the above work by simple inspection and without the aid of the Nautical Almanac.

---

* See Hayford's Geodetic Astronomy, p. 211, Art. 193.

Example.

Observation on Polaris for azimuth April 15, 1908. Latitude 38° 58′. Longitude 92° 25′. Angle between a mark (approximately N.W.) and Polaris is repeated 6 times. Watch $1^m\ 13^s$ fast. The times are

	8h	35m	40s
	8	37	20
	8	38	50
	8	39	59
	8	41	30
	8	43	00
Mean of 6 readings	8	39	26.2
Watch fast		1	13
True Central time	8	38	13
Longitude of Standard Meridian	6		
Greenwich time	14h	38m	13s

From Nautical Almanac, Right Ascension of "Mean Sun" at Greenwich Mean Noon = $1^h\ 32^m\ 57^s.82$; Right Ascension of Polaris = $1^h\ 25^m\ 01^s.47$; Declination of Polaris = + 88° 48′ 52″; Correction from Table III (Nautical Almanac) for Greenwich Time = $14^h\ 38^m = 2^m\ 24^s.2$

92° 25′ =		6h 09m	40s
∴ longitude correction =		09m	40s
Mean of observed times		8h 38m	13s
Longitude correction		9	40
Local time		8 28	33
Right Ascension "Mean Sun"		1 32	58
Correction (Table III)		2	24
Sidereal time		10 03	55
Right Ascension Polaris		1 25	01
Hour Angle Polaris	=	8h 38m	54s
	t =	129° 43′	30″

$\log \cos L = 9.89071$	$\log \sin L = 9.79856$
$\log \tan D = 1.68413$	$\log \cos t = 9.80558$ (n) *
1.57484	9.60414 (n)

37.570	− .4019
.402	
37.972	

$\log \sin t = 9.88600$
$\log \text{denominator} = 1.57946$
$\log \tan Z = 8.30654$
$Z = 1°\ 09′\ 37″$ W. of N.

* The *n* after the logarithm indicates that the number corresponding is negative.

238. SOLAR OBSERVATIONS. — Where great accuracy is not required many surveyors prefer solar observations because they can be made without much additional work, while star observations have to be made at night and require special arrangements for illuminating the field of view and the mark. If it is sufficient for the purpose in view to obtain the azimuth within $\frac{1}{2}$ minute of angle solar observations will answer. In making these observations with the ordinary transit it is necessary to have some means of cutting down the sun's light so that it will not be too bright for the eye while making pointings. This is usually effected by placing a dark glass over the eyepiece. A dark glass in front of the objective will introduce error into the pointings unless the faces of this glass have been made plane and exactly parallel. If the instrument is not provided with a dark glass the observation may be made by holding a white card back of the eyepiece while the telescope is pointing at the sun. If the eyepiece tube is drawn out the sun's disc and the cross-hairs can both be sharply focused on the card. By this means pointings can be made almost as well as by direct observation. It is also well to cut down the amount of light entering the objective by having a cap with a hole in the center or by using a piece of tracing cloth as explained in Art. 233, p. 214.

239. OBSERVATION FOR MERIDIAN BY EQUAL ALTITUDES OF THE SUN IN THE FORENOON AND AFTERNOON. — This observation consists in measuring in the forenoon the horizontal angle between the sun and some reference mark at the instant when the sun has a certain altitude, and again measuring the angle when the sun has an **equal** altitude in the afternoon. If the distance of the sun from the equator were the same in the two cases the horizontal angles between the sun and the meridian would be the same in both observations, hence the mean of the two readings of the horizontal circle would be the reading for the meridian. But since the sun is changing its distance from the equator the measured angles must be corrected accordingly. The correction is computed by the equation

$$X = \frac{d}{\cos L \sin t}$$

in which X = the correction to the mean vernier reading, d = the hourly change in declination of the sun taken from Table 10 and multiplied by half the number of hours between the two observations, L = the latitude, and t = half the elapsed time converted into degrees, minutes, and seconds. Since the hourly change for any given day is nearly the same year after year an almanac is not necessary but the table given below is sufficient.

TABLE 10.

HOURLY CHANGE IN THE SUN'S DECLINATION.

	1st.	10th.	20th.	30th.
January	+12″	+22″	+32″	+41″
February	+43	+49	+54	....
March	+57	+59	+59	+58
April	+58	+54	+49	+46
May	+45	+39	+39	+23
June	+21	+12	+02	−09
July	−10	−19	−28	−36
August	−38	−44	−49	−54
September	−54	−57	−58	−59
October	−58	−57	−54	−49
November	−48	−42	−34	−25
December	−23	−14	−02	+10

The observation is made as follows: — * at some time in the forenoon, preferably not later than 9 o'clock, the instrument is set up at one end of the line the azimuth of which is to be found, and one vernier is set at 0°. The vertical cross-hair is then sighted at the other end of the line and the lower plate clamped. The upper clamp is loosened and the telescope turned until the sun can be seen in the field of view. The horizontal cross-hair is to be set on the **lower** edge of the sun and the vertical cross-hair on the **left** edge. Since the sun is rising and also changing its bearing it is difficult to set both of the cross-hairs at once and it will be found easier to set the horizontal hair so that it will cut across the sun's disc leaving it clamped in this position while the vertical hair is kept tangent to the left edge of the sun by means of the upper tangent screw. When the sun has risen until the lower edge is on the horizontal hair

* The nearer the sun is due East or due West, the better the result.

the instrument is in the desired position and after this position is reached the upper tangent screw should not be moved. As soon as this position is reached the time is noted. Both the vertical and the horizontal circles should now be read and the angles recorded.

In the afternoon, when the sun is found to be nearly at the same altitude as at the forenoon observation, the instrument should be set up at the same point and again sighted on the mark. The observation described above is repeated, the pointings now being made on the **lower** and **right** edges of the disc. The telescope is inclined until the vernier of the vertical circle reads the same as it did at the forenoon observation. When the sun comes into the field the vertical hair is set on the right edge and kept there until the lower edge is in contact with the horizontal hair. The time is again noted and the verniers are read. If desired, the accuracy may be increased by taking several pairs of observations. The mean of the two circle readings (supposing the graduations to be numbered from 0° to 360° in a clockwise direction) is now to be corrected for the sun's change in declination. The correction as obtained by the formula given on p. 222 is to be added to the mean vernier reading if d is minus, and subtracted if d is plus, i.e., if the sun is going south the mean vernier reading is east of the south point, and *vice versa*. When the circle reading of the south point is known the true bearing of the mark becomes known and the bearings of other points may be found (see Example below).

The disadvantage of this method is that it is necessary to be at the same place both in the forenoon and afternoon, whereas in many cases the surveyor might in the afternoon be a long distance from where he was working in the forenoon.

EXAMPLE.

Latitude 42° 18′ N. April 19, 1906.

A.M. Observation.	P.M. Observation.
Reading on Mark, 0°00′00″	Reading on Mark, 0°00′00″
Pointings on Upper and Left Limbs.	Pointings on Upper and Right Limbs.
Vertical Arc, 24°58′	Vertical Arc, 24°58′
Horizontal Circle, 357°14′15″	Horizontal Circle, 162°28′00″
Time $7^h19^m30^s$	Time $4^h12^m15^s$

½ elapsed time $= 4^h\ 26^m\ 22^s$
$= 66°\ 35'\ 30''$

log sin t 9.96270
log cos L 9.86902
9.83172
log 230″.9 2.36342
2.53170
correction 340″.2 = 5′40″.2

Increase in declination in $4^h\ 26^m\ 22^s$ =
52″ × 4.44 = 230″.9

Mean circle reading = 79° 51′ 08″
5 40
S 79° 45′ 28″ E

Azimuth of mark = 280° 14′ 32″

240. Observation for Meridian by a Single Altitude of the Sun. — The most convenient method of obtaining the azimuth of a line is by measuring an altitude of the sun and computing the sun's azimuth by spherical trigonometry. This observation may be made in a few minutes time while the survey is in progress and is therefore preferred by many sur-



(A.M. Observations.) (P.M. Observations.)

Fig. 100. Position of Sun's Disc a Few Seconds before Observation.

veyors to the observation on Polaris, which consumes more time and usually requires a special trip to the point of observation.

To make this observation set up the transit at one end of the line whose azimuth is to be determined and set the plate vernier to read 0°. Sight the vertical cross-hair on the point marking the other end of the line; using the lower clamp and tangent screw. Place the colored shade glass over the eyepiece, loosen the upper clamp and point the telescope toward the sun. Before attempting to make the pointings focus carefully so that the edge of the sun is distinct, and then examine the field to be certain which is the middle horizontal hair. The three horizontal hairs cannot all be seen at once through the colored screen and there is danger of using one of the stadia hairs by mistake. When making observations in the forenoon in the northern hemisphere it is best to observe first the right and lower edges of the sun's disc, and then the left and upper edges as shown at the left in Fig. 100. In the afternoon the positions would be as shown at the right in Fig. 100.* In order to avoid the necessity of setting on both edges at the same instant the forenoon observations may be made as follows. Set the horizontal hair so that it cuts a small segment from the lower edge of the disc, and the vertical hair tangent to the right edge.† Since the sun is now rising and moving to the right it is only necessary to keep the vertical hair tangent to the right edge with the upper plate tangent screw; the apparent motion of the sun itself will set the horizontal hair after a lapse of a few seconds. At the instant both hairs are tangent to the disc stop following the sun's motion and note the time by the watch. Read the vertical and horizontal circles, and record all three readings. The second observation is made in a similar manner except that the vertical hair is set a little way in from the left edge of the sun and the horizontal hair is kept tangent to the upper edge by

* In the diagram only a portion of the sun's disc is visible on account of the small angular diameter of the field of the telescope. In a telescope having a very large field the whole disc may be seen.

† It should be kept in mind that if the telescope has an inverting eyepiece the direction of the sun's apparent motion is reversed. If a reflecting prism is attached to the eyepiece, the upper and lower edges of the sun are apparently interchanged, but the right and left edges are not affected.

means of the tangent screw on the standard. If it is desired to increase the precision several such observations may be made in each position, being careful to take the same number of pointings in each. If the transit has a full vertical circle the telescope should be inverted between the two observations thus eliminating errors of adjustment of the cross-hairs and the horizontal axis. Before the plate is unclamped the index correction should be determined and recorded. After the pointings on the sun are completed the telescope should be sighted again along the line whose azimuth is being determined and the vernier read to be certain that the plate has not moved during the observations.

The mean of all the vertical circle readings, corrected for index error, is the apparent altitude. This altitude decreased by the correction for atmospheric refraction (Table 11) is the true altitude, h, in the formula given below.

TABLE 11

REFRACTION CORRECTION.

Altitude.	Refraction.	Altitude.	Refraction.
10°	5′ 19″	20°	2′ 39″
11	4 51	25	2 04
12	4 27	30	1 41
13	4 07	35	1 23
14	3 49	40	1 09
15	3 34	45	0 58
16	3 20	50	0 49
17	3 08	60	0 34
18	2 57	70	0 21
19	2 48	80	0 10

In order to compute the azimuth it is necessary to know the latitude of the place. The latitude may be obtained from a reliable map; or, in case this is likely to be in error a half minute or so, it may be observed directly as described in Arts. 242–3, p. 230: It is also necessary to know the declination of the sun at the instant of observation; this is found as described in Art. 86, p. 68. The azimuth may then be computed by the formula

$$\cot^2 \tfrac{1}{2} Z = \frac{\sin (s - L) \sin (s - h)}{\cos s \cos (s - p)}$$

in which Z is the azimuth of the sun east or west of the south point; L, the latitude of the place; h, the true altitude of the sun's center; p, the sun's north polar distance (= 90° Declination); and $s = \frac{1}{2}(L + h + p)$.

In making this computation five place logarithms will always be found sufficiently precise. Five place tables will define the angle within 5″ to 10″, which is a greater degree of precision than can be expected from such an observation. After the angle Z has been computed it is combined with the readings of the horizontal circle to obtain the azimuth of the line.

In order to determine the azimuth as accurately as possible by this method the observation should be made when the sun is nearly due east or due west, because the trigonometric conditions are then most favorable. Observations made near to noon are not reliable because small errors in the observed altitude cause large errors in the computed azimuth. Observations should also be avoided when the sun is less than 10° above the horizon, even though the sun is nearly east or west, because the correction for atmospheric refraction is uncertain. The table gives values of the correction for an average temperature and pressure of the air; any deviation from these average conditions will produce changes in the correction, especially near the horizon.

Ross's Meridiograph * is an instrument containing an arrangement of movable concentric scales on discs of cardboard or of metal, for solving mechanically the spherical triangle to obtain the azimuth of the sun. Its operation consists in making two simple settings on different scales, the results being values of the two terms of the formula

$$\cos Z = \frac{\sin D}{\sin L \sin h} - \tan L \tan D \dagger$$

The sum or difference of these two numbers gives, by reference to another scale, the desired angle Z. The instrument will give results to about the nearest minute of angle, which is often amply accurate for checking the azimuth of a survey.

* See Engineering News, Feb. 26, 1914, Vol. 71, p. 468.

† This formula is a convenient one to use when both natural and logarithmic functions are available. It gives the angle with great precision and does not require the computation of auxiliary quantities. It may be derived directly from the fundamental formula of spherical trigonometry by a simple transformation.

Example.

Observation on Sun for Azimuth.

Latitude 42° 21′ N. Longitude 4h 44m 18s W
Time, Nov. 28, 1905, A.M.

	Horizontal Circle Vernier *A*	*B*	Vertical Circle	Watch A.M.
Mark	238° 14′	14′		
Right and Lower Limbs	311 48	48.5	14° 41′	8h 39m 42s
" " " "	312 20	20	15 00	8 42 19
The inst. reversed				
Left and Upper Limbs	312 27	26.5	15 55	8 45 34
" " " "	312 52	51.5	16 08	8 47 34
Mark	238 14	14		
Mean reading on Mark =	238° 14′.0		Mean = 15° 26′	Mean = 8h 43m 47s
" " " Sun =	312 21 .7			7
Mark N. of Sun =	74. 07′.7		Greenwich Mean Time *	= 1h 43m 47s
Observed Altitude	15° 26′.0		Sun's apparent declination at	
			Greenwich Mean Noon	= −21° 14′ 54″.4
Refraction	3.5		Difference for 1 hour	= − 26″.81
True Altitude	15° 22′.5 = *h*		− 26″.81 × 1h.73	= − 0′ 46″.4
			Declination	= − 21° 15′ 40″.8
			Polar Distance	= 111° 15′ 40″.8

L = 42° 21′.0
h = 15° 22′.5
p = 111° 15′.7
s = 84° 29′.6

$s - L$ = 42° 08′.6
$s - h$ = 69° 07′.1
$s - p$ = −26° 46′.1

log sin $(s - L)$ = 9.82671
log sin $(s - h)$ = 9.97049
log sec s = 1.01791
log sec $(s - p)$ = 0.04923
2) 0.86434
log cot ½ Z = 0.43217
½ Z = 20° 17′.3
Z = 40° 34′.6
Mark N. of Sun = 74° 07′.7
114° 42′.3
Mark N. 65° 17′.7 E.

241. Observation for Meridian by Means of the Solar Attachment. — This observation has been described in detail in Art. 85, p. 66.

* See Art. 86, p. 68.

OBSERVATIONS FOR LATITUDE.

242. (1) **BY THE ALTITUDE OF POLARIS AT UPPER OR LOWER CULMINATION.**—When Polaris is approaching either culmination (see Art. 232, p. 212, and Fig. 97) set up the transit and point the horizontal hair on the star. Keep the cross-hair pointed on the star until the culmination is reached. Read the vertical arc and determine the index correction. The altitude is to be corrected for refraction by Table 11, p. 227. This gives the true altitude. If Polaris is at upper culmination subtract from the true altitude the polar distance of the star at the date of the observation (Table 8, p. 216). If the star is at lower culmination the polar distance is to be added. The result is the latitude of the place of observation.

243. (2) **BY THE ALTITUDE OF THE SUN AT NOON.**—The observation consists in finding the greatest altitude of the sun's lower limb. This will occur when the sun is on the meridian (very nearly). Begin the observation a little before *apparent* noon, remembering that this differs sometimes more than 16^m from *mean* noon.* Furthermore it should be remembered that standard time may differ a half hour or so from *mean* time. When the maximum altitude is found the following corrections are to be made: first, the refraction correction is to be subtracted (Table 11, p. 226); second, the sun's semi-diameter (found in the Nautical Almanac) is to be added; third, the sun's declination is to be subtracted if plus or added if minus. The result, subtracted from 90°, is the latitude.

---

* *Apparent* noon occurs when the sun is on the meridian. *Mean* noon is the instant when the sun would be on the meridian if it moved at a uniform rate along the equator. The difference between the two is known as the *Equation of time* and may be found in the Nautical Almanac. For example, on November 1st, the sun passes the meridian $16^m\ 18^s$ before *mean* noon, i.e., when it is $12^h\ 00^m\ 00^s$ *apparent* time it is $11^h\ 43^m\ 42^s$ *mean* time.

Example.

Observed maximum altitude of the sun's lower limb on Jan. 8, 1906. = 25° 06′ Index Correction = + 1′

Observed altitude	25° 06′.0	
Index Correction	1′.0	
	25° 07′.0	Declination of sun at
Refraction	2′.0	Greenwich app. noon = − 22°19′33″ (S)
	25° 05′.0	+ 1 33
Sun's semi-diameter	16′.3	− 22° 18′00″ (S)
Altitude of sun's center	25° 21′.3	Longitude = $4^h\,44^m\,18^s$ W.
Declination	− 22° 18′.0	$= 4^h.74$
	47° 39′.3	
Latitude	42° 20′.7	Diff. 1^h = + 19″. 59
		+ 19″.59 × $4^h.74$ = + 1′ 33″

PROBLEMS.

1. (a) What was the azimuth of Polaris at its greatest western elongation at Boston when the polar distance of the star was 1° 14′ 12″? The latitude of Boston is 42° 21′ N.

(b) In making an observation for meridian two stakes were set 329 feet apart, marking the direction of the star at elongation. Compute the length of the perpendicular offset to be laid off at one end of the line to obtain the true meridian.

2. What is the approximate Eastern Standard Time of the eastern elongation of Polaris on August 10th at a place in longitude 72° 56′ West?

3. Observation on May 15, 1906, for determining the azimuth of a line from an altitude of the sun. Reading of vernier A of the horizontal circle while pointing on the azimuth mark = 0° 00′. At first pointing on sun, lower and right limbs, vernier A, horizontal circle read 168° 59′; vertical arc read 43° 36′; the Eastern Standard Time was $2^h\,52^m\,45^s$ P.M. At second pointing on the sun, upper and left limbs, vernier A, read 168° 52′; vertical arc, 42° 33′; time, $2^h\,55^m\,37^s$ P.M. The second pointing on the mark = 0° 00′, the mark being to the left of the sun. The sun's declination at Greenwich Mean Noon was + 18° 42′ 43″.6 (North). The change for 1 hour was + 35″.94 (sun going north). The latitude of the place was 42° 17′ N.; The longitude was 71° 05′ W. Find the azimuth of the mark.

4. Observation for latitude. The observed altitude of Polaris at upper culmination was 43° 27′. The polar distance of the star was 1° 12′. What was the latitude of the place?

5. Observation for latitude. The observed maximum altitude of the sun's lower limb on August 10th, 1906, was 66° 29′. The Eastern Standard Time was approximately $11^h\,50^m$ A.M. The semi-diameter of the sun was 15′ 48″.7. The declination of the sun at Greenwich Mean Noon was North 15°46′ 13″.3 (+). The difference for 1 hour was −43″.46 (sun going south). What was the latitude of the place?

CHAPTER IX.

LEVELING.

244. DEFINITIONS. — Leveling consists in ascertaining differences in elevation; there are two kinds, *Direct Leveling*, and *Trigonometric Leveling*. The former alone will be considered in this book, as trigonometric leveling is used only in advanced surveying work.

Wherever extensive leveling operations are to be carried on it is necessary to have a system of reference points called *bench marks* (*B.Ms.*), the relative heights of which are accurately known. These heights are usually referred to some definite zero plane, such, for instance, as *mean sea-level* or *mean low water*, and the height of a point above this plane is called its *elevation*. This plane is called the *datum*. (See Art. 263, p. 245, and Art. 276 p. 261.) Strictly speaking it is not a plane but a level surface, i.e. it is at every point perpendicular to the direction of gravity. I mean sea-level is not known a datum can be arbitrarily assumed

245. LEVELING TO ESTABLISH BENCH MARKS. — When it i necessary to run a line of levels to establish new bench mark the rod is first held on some bench mark the elevation of whic is accurately known, and a backsight taken (Art. 116, p. 85). I this backsight is added to the known elevation of the benc mark it gives the *height of the instrument* (*H. I.*) above th datum. A *turning point* is then selected ahead on the route (t be traversed), and a foresight taken on it. (See Art. 250, p. 236. If the foresight is subtracted from the height of the instrumen the elevation of the turning point is obtained. When a targe rod is used it is customary to take readings on bench marks an turning points to thousandths of a foot, and in this case ofte more than one rod-reading is taken on each point. If the firs and second readings agree within 0.002 ft. it is unnecessary t take more readings; if they differ by a greater amount it ma be necessary to take three or four or even more readings t properly determine the correct value. The object of takin

more than one reading is not so much to increase the precision as to check the former readings.

When it is desired to establish a bench mark a suitable point is selected and **used as a turning point**. The elevation of this bench mark could be obtained by simply taking a foresight upon it and not using it as a turning point, but by making the bench mark also a turning point it becomes a part of the line of levels and if the levels check, the elevation of the bench mark is also checked. Each bench mark established should be carefully recorded by a description or a sketch, or both. The elevations of the remaining turning points are as accurate as the elevations of the bench marks themselves, so that any of the turning points might be used as a bench mark. Consequently it is advisable to describe those turning points which can be readily identified so that they may be used when it is not convenient or possible to use one of the established bench marks.

In leveling up or down slopes the levelman should be able to judge quickly where to set his instrument in order to have it the desired height above the turning point. In going downhill the rod-reading of the backsight should be as small as possible in order to overcome the height with the minimum number of set-ups of the level. But while the levelman may waste much time by having large backsights necessitating additional set-ups, it is also possible for him to waste quite as much time in attempting to place his instrument so as to get very small backsights. The proper way to handle the instrument is as follows. Set up roughly (without pressing the tripod legs into the ground), turn the telescope toward the rod and then level it, approximately, in that direction. By sighting along the outside of the telescope, the approximate place where the line of sight will strike the rod can be noted and the distance the instrument should be moved up or down the slope can readily be estimated. Then move to the new position, level up carefully, and proceed to take the backsight. This general procedure should be followed whether leveling up or down a slope.

246. In this work it is very important to eliminate as far as possible errors of adjustment in the instrument. If at every set-up of the level the foresight and its corresponding backsight are

taken at points which are equally distant from the instrument such errors will be eliminated. If the level is not in perfect adjustment the resulting error in any reading is proportional to the distance. At equal distances from the instrument the errors are equal, and, since it is the difference of the rod-readings that gives the difference in elevation, the error is eliminated from the final result by this method. By making the length of foresights and backsights equal on turning points it is possible to eliminate not only the error due to non-adjustment of the bubble but also any error due to non-adjustment of the objective tube, since this will occupy the same position in the telescope in each sight. The distance to the backsight is determined by the place where the instrument is set up, and the rodman, as he passes from one turning point to the next, can by pacing make the foresight distance approximately equal to that of the backsight. The line of levels should be "closed" by continuing the leveling until the original bench mark, or some other bench mark whose elevation is well established, is reached.

247. The notes for this work may consist of five columns, as shown in Fig. 101. The height of instrument is obtained by adding the backsight to the elevation of the point on which it is taken. The elevation of any point is found by subtracting the foresight for that point from the height of the instrument. Notice that the

LEFT-HAND PAGE. RIGHT-HAND PAGE.

B.M. Leveling for Eastern Intercepting Sewer. B. Jones ✕ M. Brown Oct. 30, 1905.

Point	B.S.	H.I.	F.S	Elev.	Remarks.
B.M.1	4.122	93.139		89.017	Top S.E. cor. granite foundation S.E. cor. City Hall.
T.P.1	3.661	90.611	6.189	86.950	Curb.
T.P.2	4.029	89.630	5.010	85.601	N.E. bolt top hydrant opp. 42 Main St.
B.M.2	3.901	86.161	7.370	82.260	S.W. cor. S.B. on N.W. cor. Main and Broad Sts.
B.M.3	3.512	83.056	6.617	79.544	N.W. cor. lower stone step 62 Broad St.
T.P.3	6.007	80.348	8.715	74.341	Cobble stone.
B.M.4			9.070	71.278	Chisel cut N.W. cor. C.B. curb S.W. cor. Broad and State Sts. True elev. B.M. = 71.274 Book 27, P. 36.

FIG. 101. BENCH MARK LEVEL NOTES.

calculations may be checked by adding the foresights and the backsights. The difference of these sums should be the same as the difference in elevation between the first and last points.

248. Double Rodded Lines. — A good check on the line of levels may be secured by running a double line of turning points. Instead of taking a foresight on a single turning point, foresights may be taken on two different points near together, from the same set-up of the instrument. When the level is set up again a backsight is taken on each turning point and two independent values of the new height of instrument are obtained. In ordinary bench mark leveling these two values should not differ by more than 0.002 or 0.003 ft. from the previous difference, i.e., if the two heights of instrument differed by 0.013 at a certain set-up they should not differ by more than 0.016 nor less than 0.010 at the next set-up. If the two turning points of a pair are so chosen that their difference in elevation is more than a foot then any mistake of a foot in the computations or in reading the rod will be immediately detected.

In this way, by little additional work the accuracy of the levels may be checked as the work progresses. This method of using double turning points is particularly useful in running long lines of levels where no established bench marks are available for checking.

249. A set of notes illustrating double turning points is shown in Fig. 102. It will be noticed that the higher and lower

LEFT-HAND PAGE. RIGHT-HAND PAGE.

B.M. Levels – Bridge "67 to Mile Post "45 A & B. R.R. — April 17, 1906. Smith, Lowe & Rich

Sta.	B.S.	H.I.	F.S.	Elev	Description
B.M.$_{16}$	4.691	50.965		46.274	N.E. cor. W. Bridge seat bridge "67 A.&B.RR.
T.P.$_1$ L.	6.040	49.721	7.284	43.681	
T.P.$_1$ H.	4.441	49.719	5.687	45.278	
T.P.$_2$ L.	10.641	53.621	6.741	42.980	
T.P.$_2$ H.	7.902	53.617	4.004	45.715	
B.M.$_{17}$ L.	4.805	54.748	3.678	49.943	S.E cor stone step S. side Jamaston Sts.
T.P.$_3$ H.	2.972	54.747	1.842	51.775	
T.P.$_4$ L.	4.959	55.027	4.680	50.068	
B.M.$_{18}$ H.	3.489	55.029	3.207	51.540	d.h. S.W cor. first step W. wing N. abut. bridge "70 A.&B.R.R.
B.M.$_{19}$			2.709	52.318	
				52.320	52.319 Top Mile post "45.

FIG. 102. BENCH MARK LEVEL NOTES, DOUBLE RODDED LINES.

turning points of a pair are arranged in a systematic order. The readings in this case have been taken on the lower turning point first at each set-up. It is very important that some definite system shall be followed so that the two lines of levels will not be confused.

250. Bench Marks and Turning Points. — Both the bench marks and the turning points should be such that their elevations will not change during the time they are needed. The only difference between the two is that turning points may be of use for only a few minutes while bench marks may be needed for many years. Bench marks should be very carefully and accurately described, and their heights should be checked before being accepted as correct. They are frequently taken on such points as these: — stone bounds, tops of boulders, spikes in trees, and on sills, stone steps, or underpinning of buildings. Curb stones or tops of hydrants are also used but are not so permanent. As it is often impossible in a new country to find existing points where bench marks can be established, it is usual in such cases to set stone monuments or iron rods and to carefully determine their elevation. The U. S. Geological Survey, for example, sets an iron pipe with a cap on the top of it; or in some cases a plate with a horizontal line across it in the masonry wall of a building. Some of the bench marks of the U. S. Coast and Geodetic Survey and of the Missouri River Commission consist of stones buried 3 or 4 ft. under ground. The exact bench is the top of a spherical headed bolt set in the top of the stone. This is reached by lowering the rod through an iron pipe which extends to the surface of the ground.

Bench marks should be established at frequent intervals for convenience in dependent work. Some surveyors consider it advisable to have two bench marks in the same locality to serve as checks on each other. In choosing a bench or a turning point it is best to select a point which is slightly raised so that the rod will always rest on exactly the same point. A rounded surface is better than a sharp point, especially when it is on a rock, as the rod may chip off a small piece and alter the elevation. If a turning point is taken on a flat surface it is difficult to get the rod at exactly the same height each time. Bench

marks are, however, sometimes established on flat level surfaces such as the coping stone of a masonry structure, because permanence is of more importance than great precision. Bench marks are not only described in the notes, but are themselves frequently marked by red chalk, by chisel marks, or drill-holes.

251. LEVELING FOR PROFILE. — Profile leveling is for the purpose of determining the changes in elevation of the surface of the ground along some definite line. The line is first "stationed," i.e., marked at every hundred feet or such other interval as is desired. The level is set up and a backsight taken on a bench mark to determine the height of the instrument. Foresights are then read on as many station points on the line as can be conveniently taken from the position of the instrument. Intermediate sights are taken at any points where marked changes of slope occur, and the plus stations of these intermediate points are recorded with the rod-readings. It will be noticed that here the terms foresight and backsight do not refer to the **forward** and **backward** directions. **A backsight is a reading taken on a point of known elevation for the purpose of obtaining the height of the instrument. A foresight is a reading taken on a new point to determine its elevation.** For this reason backsights are frequently called *plus sights* ($+S$), and foresights are called *minus sights* ($-S$). When it is necessary to move the level to a new position in order to take readings on stations ahead, a turning point is selected and its elevation determined. The level is then taken forward and its new height of instrument determined by taking a backsight on the turning point. This general process is continued until the end of the line is reached.

A line of levels should be checked by connecting with some reliable bench mark if possible. If there are any bench marks along the line of levels they should be used as turning points if convenient, or at least check readings should be taken on them in order to detect mistakes. In such a case it is evident that the reading taken on the bench mark is really a foresight since its elevation is being found anew from the height of instrument. Readings on bench marks and turning points should be taken to thousandths or to hundredths of a foot, depending upon the accuracy desired. If the elevations of the profile are de-

sired to the nearest hundredth of a foot, as in the case of a railroad track, the turning points should be taken to thousandths of a foot. Elevations on the surface of the ground will not usually be needed closer than to tenths in which case the T. Ps. are taken only to hundredths. In calculating the elevations the results **should not be carried to more decimal places than the rod-readings themselves,** otherwise the results will appear to be more accurate than they really are.

LEFT-HAND PAGE. RIGHT-HAND PAGE.

Profile of Meadow Park Road. *Sept. 16, 1904.* Howe, Harkins, Jacobs

Sta.	+S	H.I.	−S	Elev.	B.M. & T.P. Elev.	Description
B.M.3	12.23	34.98			22.748	d.h. in wall near Sta. 0
0			9.8	25.2		
1			6.6	28.4		
2			3.0	32.0		
T.P.1	11.18	44.73	1.43		33.55	Stump
3			6.1	38.6		
+65			2.7	42.0		
4			3.7	41.0		
+20.7			5.2	39.5		
5			6.7	38.0		
6			11.2	33.5		
T.P.2	3.48	42.59	5.62		39.11	Nail in stump 80' W. Sta. 6+80.
7			10.2	32.4		
8			8.6	34.0		
9			7.6	35.0		
+62.4			4.0	38.6		
10			2.4	40.2		
+43			1.1	41.5		
11			2.6	40.0		
12			8.0	34.6		
T.P.3	0.42	31.89	11.12		31.47	Boulder
13			2.8	29.1		
14			8.7	23.2		
+23.8			11.2	20.7		
B.M.4	0.63	27.79	4.73		27.16	Elev. = 27.14 (Book 12. p 26) Highest point large isolated boulder 200' E. Sta 16.
15			6.8	21.0		
16			7.2	20.6		
17			8.1	19.7		
18			9.0	18.8		
+54			9.2	18.6		



FIG. 103. PROFILE LEVEL NOTES.

252. Profile notes are kept as shown in Fig. 103. In this case also the heights of instrument and the elevations of turning points may be checked by means of the sums of the fore sights and backsights, provided only the sights on turning points and the initial and final benches are included. If it seems desirable the elevations of stations may be checked by means o

differences in foresights. The difference between the elevations of any two points, which are obtained at the same set-up of the instrument, is equal to the difference between the foresights taken on these points. For example, if the difference between the foresights on stations 4 and 5 is 3 ft. this should also be the difference between their elevations. In these notes the elevations of B. Ms. and T. Ps. are put in a different column from the surface elevations simply for the sake of clearness, but many surveyors prefer to put all the elevations in the same column. Another arrangement of columns which will be found convenient when plotting the notes is to place the station column immediately to the right of the elevation column.



FIG. 104.

Fig. 104 represents a rough plan and profile of the line of levels shown by the notes in Fig. 88. Angle points in the transit line are shown in the plan, but they do not appear in the profile of the line. It will be noticed that the T. Ps. and B. Ms. are not on the transit line in plan, and that they consequently do not appear on the profile. It is not customary to introduce

any sketches into the profile notes except those used in describing bench marks or turning points.

253. CROSS-SECTIONING. — If it is desired to know the shape of the surface of a piece of ground, the area may be divided into squares and the elevation taken at each corner of these squares and at as many intermediate points as seem necessary to determine the changes of slope. These surface elevations are obtained to tenths of a foot. The squares which may be anywhere from 10 ft. to 100 ft. on a side are laid out with the transit and tape, stakes being driven at the corners. It is well to choose some long line of the traverse as the primary line from which the cross-section system is to be laid out. The points are usually designated by a system of rectangular coördinates, one set of parallel lines being marked by letters and the other by numbers, as shown in Fig. 105. For example, the

LEFT-HAND PAGE. RIGHT-HAND PAGE.

Cross-Sections for Grading the A.M.Cole Estate, Westfield.

March 10, 1906. *Hatch, Allen, Rolfe*

Sta.	+S.	H.I.	−S	Elev.
B.M.	3.02	124.92		121.90
A4			1.2	123.7
A5			1.7	123.2
A6			2.4	122.5
B6			2.9	122.0
B5+40			2.8	122.1
B5			2.0	122.9
B4			1.8	123.1
B+60,4			1.8	123.1
C4			3.0	121.9
B+80, 4+35			0.8	124.1
C5			5.0	119.9
C6			7.2	117.7
D6			8.9	116.0

100 f. Squares.



FIG. 105. CROSS-SECTION LEVEL NOTES.

point p would be called $(C, 7)$; the point s, $(D, 5)$; the point r, $(B+80, 4+35)$; etc. The notes are kept as in profile leveling except as to designation of points. (See Art. 331, p. 312.)

254. Use of the Tape Rod in Cross-Section Work. — In this work, where there are a large number of elevations to be calculated, it will save much time to use a tape rod (Art. 100, p. 81), which is so arranged that no elaborate figuring is required. In this rod the numbers increase from the top toward the bottom, the opposite way from ordinary rods. The level

set up at a convenient point and the rod held on a bench mark. The tape, or band, on the rod is then moved up or down as directed by the levelman until he reads the feet, tenths, and hundredths which are the same as those of the elevation of the bench mark, e.g., if the elevation of the B. M. is 195.62, the tape will be moved until it reads 5.62. If the rod is then held on a point 1.61 ft. lower than the bench, the rod-reading will be 4.01, since with this rod the readings decrease as the rod is lowered. The elevation of the point is then 194.01 ft., or sufficiently precise for topographic work, 194.0 ft. In this way the elevations are read directly on the rod to feet and decimals of feet, the tens and hundreds of feet being supplied mentally. Obviously the only notes kept are the columns of stations and elevations.

255. CROSS-SECTIONING FOR EARTHWORK. — Whenever it is desired to ascertain the quantity of earthwork in an excavation or an embankment, it is necessary to take levels to determine the vertical dimensions, and to obtain the horizontal dimensions by means of the transit and tape. The three general cases where the quantity of earthwork is to be estimated by the engineer are: (1) an excavation or embankment having a known base and side slopes as in the construction of a railroad or a highway, (2) an irregular excavation from a bank of earth called a *borrow-pit*, (3) a trench excavation such as is used for sewer construction.

256. (1) Road Cross-Sections. — Cross-sections for estimating the earthwork in highways or railroads are usually taken at full station points (sometimes oftener) and at right angles to the center line of the road.* By this method is obtained a section of the general shape shown in Figs. 106 and 107. These cross-sections are taken in the field before the construction begins so that a proper record of the surface heights can be obtained before the ground is disturbed.

From the plan of the proposed road its alignment is staked out and a profile is taken along the center line, which is subsequently plotted (Art. 251, p. 237). On this profile the *grade line* is drawn, which corresponds to the finished surface of the road. Roads are usually first finished to *sub-grade*, which is below the

* For a more complete treatment of this subject see "Railroad Curves and Earthwork," by Professor C. F. Allen, published by McGraw-Hill Book Company, New York.

completed surface by an amount equal to the thickness of the road covering, i.e., the pavement of a highway or the ballast in the case of a railroad. The width of the base of the road and the inclination of the side slopes are known. For ordinary gravel the slope is usually $1\frac{1}{2}$ ft. horizontal to 1 ft. vertical, called "a slope of $1\frac{1}{2}$ to 1."

For construction work the engineer sets grade stakes at every full station or oftener on the center line and at both sides where the finished slope intersects the surface of the ground, e.g., at points *A*, *B* and *C* on Figs. 91 and 92. All of these



FIG. 106. EXCAVATION.



FIG. 107. EMBANKMENT.

stakes are marked, giving the amount of "cut" or "fill" to be made at these points. The cut or fill marked on the stakes at *B* and *C* is the vertical distance from the base of the road to the surface of the ground at these points, e.g., the distance *bC*.

These cuts and fills are determined in the field by the following method. The level is set up and the height of instrument obtained from some convenient bench mark. Then, the elevation of the finished grade being known (from the profile prepared in the office), the difference between the height of instrument and the elevation of the finished road will give what is called the *rod-reading for grade*, i.e., the rod-reading which would be obtained if the foot of the rod could be held on the finished surface of the road. Then the rod is held on the surface of the ground at the center stake and a reading is taken (to the nearest tenth of a foot), and the difference between the rod-reading for grade and the rod-reading on the surface will give the cut or fill at that point, and this is marked on the center grade stake thus, C5.2 or F4.7.

257. SETTING SLOPE STAKES. — The points where the side slopes intersect the surface of the ground are found by trial as follows. Hold the rod at a point where it is estimated that the side slope will cut the surface, and take a rod-reading. The difference between this rod-reading and the rod-reading for

grade will give the cut or fill at this point, from which the distance out from the center of the section to the point on the side slope having this cut can be computed. This distance out equals ($\frac{1}{2}$ *base* + *cut* × *slope*). Then the distance is measured from the center to the rod, and if the measured distance equals the computed distance the rod was held at the right place and the stake should be driven and marked with the cut or fill at that point (distance *bC*, Fig. 107). If the measured distance does not agree with the calculated distance a second trial must be made by holding the rod at another point and repeating the operation. The difference between the measured and calculated distances is an aid in judging where the rod should be held at the second trial. After a little practice it will be possible to set the slope stake at the second or third trial.

258. EARTHWORK NOTES FOR ROAD CROSS-SECTIONS. — The notes for this work will contain the cut or fill at the center, the cut or fill at either side, and the corresponding distances out. A cut is usually written in the notes as a plus (+) height and a fill as a minus (−) height; but the stakes

Cross-Section for Jamestown Road — Aug. 17, 1906 — Hatch Wood Appleton

Sta.	Surface Elev.	Grade Elev.	Cross-Sections.-Base 40'- Slope 1½ to 1				
12	99.5	96.50	29.0 / +6.0	12.0 / +4.5	+3.0	15.0 / +4.0	22.4 / +1.6
+50	98.7	96.25	27.2 / +4.8	20.0 / +4.0	+2.4	20.0 / +3.0	24.8 / +3.2
11	97.6	96.00	26.0 / +4.0		+1.6		25.4 / +3.6
10	97.5	95.50	23.0 / +2.0		+2.0		23.0 / +2.0

FIG. 108. CROSS-SECTION NOTES FOR A ROAD.

are marked *C* or *F* rather than + or −. If the surface is irregular levels are taken at intermediate points and are recorded as shown opposite Sta. 11 + 50, and Sta. 12 in the notes, Fig. 108. Where the surface of the ground is parallel to the

base of the road, as in Sta. 10, the section is called a *Level Section*. Where the surface of the ground is not parallel to the base and where three cuts or fills only are recorded, as at Sta. 11, the section is called a *Three Level Section*. If, besides the three readings which are taken for a three level section, two more intermediate readings are taken one directly over each end of the base, as at Sta. 11 + 50, the section is called a *Five Level Section*. If intermediate readings (one or more of them) are taken anywhere except over the ends of the base, as in Sta. 12, the section is called an *Irregular Section*. For methods of computing the amount of earthwork see Chapter XIII.

It will be noticed that in the column of the notes headed "Cross-Sections" the distances out appear above and the corresponding cuts below the lines. Besides this set of notes there is a simple set of level notes similar to Fig. 101, p. 234, from which the height of instrument is determined. This is conveniently kept in another part of the note-book, often at the back of the book.

259. (2) Cross-Sections for Borrow-Pits. — The ground is first staked out in squares or rectangles and the elevation at each corner and at every change in slope is determined as explained in Art. 253, p. 240. Then the work of excavating is carried on, and when it is desired to determine the amount that has been excavated, the same system of cross-sections is again run out and the new elevations at the corners and at the necessary intermediate points are determined.

The notes are kept as shown in Fig. 105, p. 240. For methods of computing the earthwork in borrow-pits see Art. 408, p. 390.

260. (3) Cross-Sections for Trench Excavation. — The surface elevations are determined by making a profile of the line. The grade of the bottom of the trench is obtained either from the plan or by direct leveling. The width of the trench is measured wherever it changes and the stations of these places noted. For methods of computing the quantity of earthwork see Chapter XIII.

261. LEVELING TO ESTABLISH A GRADE LINE. — The level may be used for setting points at desired elevations as, for example, in establishing the grade line of a sewer. To set any point at a given elevation, set up the level and take a backsight

on a bench mark, thus determining the height of instrument. Subtract the given elevation from the height of instrument and the result is the rod-reading for grade. Raise or lower the rod until the horizontal cross-hair indicates this reading. The foot of the rod is then at grade. This is usually set for construction work to hundredths of a foot; for some purposes tenths of a foot will be sufficiently exact. If a target rod is used the target is set at the proper reading, and the bottom of the rod is at grade when the cross-hair bisects the target.

If the grade line comes beneath the surface of the ground and cannot be reached a point may be set a convenient whole number of feet above grade and the depth marked on a stake, or *vice versa* if the grade line comes far above the surface.

262. "Shooting in" a Grade Line. — To save time and to diminish the liability of mistakes, grades are often set by a method known as "shooting in" the grade. First set a point at the proper elevation at each end of the straight grade line. The instrument (usually a transit with a telescope bubble) is set up 6 or 8 inches to one side of the first point, and the distance from the top of the first stake to the axis of the telescope is measured with the tape or rod.* Then the rod, which is set at this reading, is carried to the last point on the straight grade line, and, while it is held vertical on this point, the instrument man raises or lowers the telescope until the horizontal cross-hair is on the target, clamping the instrument in this position. If a level is used the horizontal cross-hair is set by means of the leveling screws; but if the transit is used the cross-hair is set by means of the clamp and tangent screw of the vertical motion. The line of sight is then along an inclined line parallel to the grade line. All intermediate points on the grade line are then set by raising or lowering the rod until the target coincides with the horizontal cross-hair.

263. To Establish a Datum Plane by Means of Tidal Observations. — Whenever it is necessary to establish a datum from tidal observations it may be determined as follows. Set up

* Where the grade is flat some surveyors prefer to set the instrument just behind the point instead of to one side of it.

a vertical staff, graduated to feet and tenths, in such a manner that the high and low water can be read. Read the positions of high and low water for each day for as long a period as practicable. The mean value obtained from an **equal** number of high and low water observations will give the approximate value of mean sea-level. If the observations extend over just one lunar month the result will be fairly good, whereas in less than one month a satisfactory result cannot be obtained; to determine this accurately will require observations extending over several years.

The proper location of the gauge is an important factor in obtaining the true mean sea-level. The place chosen for setting up the gauge should be near the open sea, so that local conditions will not influence the tide. It should be somewhat sheltered against bad weather. The water should be deep so that at the lowest tide the water will stand at some height on the gauge.



Fig. 109. Staff Gauge

At the beginning of the series the zero of the staff and some permanent bench marks should be connected by a line of levels. This should be tested occasionally to see if the staff is moved. After the reading of the rod for mean sea-level is found the elevation of the bench mark can be computed.

264. The Staff Gauge. — This is a form of gauge (Fig. 109) which can be easily constructed, and which is sufficient where only a short series of observations is to be made. If made in sections not over 3 feet long, as described below, it can easily be packed in a box for transportation. Each section consists of two strips of wood about $1\frac{1}{2}$ inches square, and 3 feet long, fastened together at the ends by strips of brass, leaving a space between them of about 1 inch. In this space is placed a glass tube of about $\frac{3}{4}$ inch diameter and held in place by brass hooks. On one side of the tube is a red strip blown into the glass. When the gauge is set up for observations the sections are screwed to

a long vertical piece of joist. The ends of the tube are nearly closed by corks, in which small glass tubes of approximately 1 mm. (inside) diameter have been inserted. When the water rises in the main tube, the red strip appears to be much wider than it really is on account of the refraction of light by the water. Above the water surface the strip appears its true width. By observing the position of the wide strip the height of the water surface can be read within a hundredth of a foot. The heights are read on a scale of feet painted on the wooden strips. If the size of the small glass tube is properly chosen, the fluctuations of the water surface outside will not disturb the water in the tube, so that the reading is a fair average of the water surface. A gauge of this sort may be read by means of a transit telescope or field glass at a distance of several hundred feet.

When a long series of observations is to be made a self-registering tide gauge should be used. A description of such a gauge may be found in the Reports of the U. S. Coast and Geodetic Survey.* (See Volume II, Arts. 258–9, p. 288–91.)

265. LEVELING ACROSS A RIVER. — While the effect of curvature and refraction (Art. 118, p. 87) is usually negligible in leveling operations, it may in certain special cases become of great importance to eliminate this error. For example, it is sometimes necessary to carry a line of levels across a river of considerable width, say, half a mile. In this distance the correction for curvature and refraction amounts to about 0.143 ft. under normal conditions, which in a line of bench levels is too large a quantity to neglect. If the correction as derived from formulas could be depended upon under all circumstances it would be sufficient to compute and apply it to the rod-reading. But the amount of the refraction correction is so variable that the actual value often differs considerably from the computed value.

If it is desired to obtain the difference in elevation between two distant points with great accuracy it will be necessary to use a method which will eliminate the effects of curvature and refraction no matter what their actual amount may be. In Fig. 110 suppose a backsight were taken on T. P.1 with the instrument

* Report for 1897, pp. 315–320 and pp. 480–489.
Report for 1853, pp. 94–96.

at A and then a foresight taken on T. $P._2$ The elevation of T. $P._2$ as computed from T. $P._1$ will be too low by the amount ab, since the foresight on T. $P._2$ is too great by this amount. If the difference in elevation is determined by the instrument at B the backsight on T. $P._1$ is too large by the amount cd. Hence the H. I. of the instrument at B is too great, and consequently



FIG. 110. LEVELING ACROSS A RIVER.

the elevation of T. $P._2$ too great by the amount cd. The mean of the two determinations would give the true elevation of T. $P._2$ if $ab = cd$, but this occurs only when the two sights are taken under the same atmospheric conditions. Therefore it will be seen that the two sights must be taken **simultaneously.** In order to eliminate the errors of adjustment * in the instrument it is necessary to use the same instrument at both ends of the line. To accomplish both of these results at once it is necessary to take simultaneous readings with two instruments and then to repeat the operation with the instruments interchanged. The magnifying powers of the two telescopes and the sensitiveness of the two spirit levels should be about equal in order to give the best results. It will be noticed that this process is similar to that of the peg adjustment (Art. 128, p. 91).

* Errors due to non-adjustment are of unusual importance because the sight is much longer than that used in adjusting the instrument.

PROBLEMS.

1. Compute the following set of level notes.

Sta.	+ S.	H. I.	− S.	Elev.
B. $M._1$	4.702			16.427
B. $M._2$	11.846		6.727	
T. $P._1$	7.276		9.689	
B. $M._3$	8.760		4.726	
T. $P._2$	0.687		11.000	
B. $M._4$	1.607		8.496	

2. Compute the elevations in the following set of level notes.

Sta.	B. S.	H. I.	F. S.	Elev.
B. $M._{12}$	6.427		4.273	62.473
20			6.2	
21			7.4	
+42			5.2	
22			4.7	
T. $P._{27}$	4.724		9.976	
23			11.2	
+63			10.4	
B. $M._{22}$	0.409		7.482	
24			11.2	

3. Compute the elevations in the following set of level notes.

Sta.	+S.	H. I.	−S.	Elev.
B. $M._{24}$	6.214			84.238
T. $P._1$ L.	3.515		9.280	
T. $P._1$ H.	2.152		7.919	
T. $P._2$ L.	2.971		8.263	
B. $M._{25}$ H.	2.338		7.629	
T. $P._3$ L.	4.278		7.529	
T. $P._3$ H.	2.646		5.894	
B. $M._{26}$ L.	5.721		6.072	
T. $P._4$ H.	4.837		5.187	
B. $M._{27}$			5.817	

4. Make up a set of cross-section notes for road construction which shall be consistent with the following data: width of road, 50 ft., slopes $1\frac{1}{2}$ to 1; grade elevation of Sta. 0 = 107.20; grade, + 1.4. Show complete notes from Sta. 0 to Sta. 3 inclusive as follows: Sta. 0, a level section; Sta. 1, a three level section; Sta. 2, a five level section; Sta. 3, an irregular section.

PROBLEMS.

5. Compute the elevations in the following set of level notes.

Sta.	+ S	H. I.	− S	Elev.
B. M.$_1$	8.21			47.19
T. P.	11.01		3.07	
T. P.	9.61		4.19	
0			9.0	
+ 50			8.1	
1			6.0	
+ 50			4.5	
2			1.0	
T. P.	12.00		0.17	
+ 50			11.0	
3			8.8	
B. M.$_2$			7.91	

6. Compute the elevations in the following set of level notes.

Sta.	+ S	H. I.	− S	Elev.
B. M.$_6$	8.21			207.33
0			4.0	
1			8.1	
2			11.2	
+ 50			11.9	
T. P.	4.01		12.19	
2			6.9	
+ 10.90			1.0	
3			2.6	
4			2.9	
B. M.			5.27	

7. Compute the elevations in the following set of level notes.

Sta.	+ S.	H. I.	− S.	Elev.
B. M.$_{21}$	0.27			1164.20
T. P.	1.16		12.41	
T. P.	1.01		10.91	
T. P.	2.16		7.99	
T. P.	0.79		11.32	
B. M.$_{22}$	4.71		4.90	
T. P.	3.02		8.00	
T. P.	0.64		9.69	
T. P.	2.26		11.49	
B. M.$_{23}$			10.20	

CHAPTER X.

CITY SURVEYING.

266. INSTRUMENTS USED. — Owing to the comparatively high value of land in cities and to the fact that a large proportion of city surveying is the establishing of lines and grades for construction work, the chain and compass are discarded entirely and the steel tape and transit are used.

267. Tapes and Tape Measurements. — The tape most commonly employed is the light 100-ft. steel tape, graduated to hundredths of a foot, described in Art. 7, p. 5. All ordinary measurements are taken in the usual manner, the pull and the horizontal position of the tape being judged by the men taking the measurements. But frequently it is necessary to obtain results with a greater degree of accuracy than is afforded by this ordinary method of measurement. For example, in measuring the base-line for triangulation work or in the survey of the valuable portions of large cities, there is call for an accuracy of measurements which can only be obtained by using a method which will insure a uniform pull on the tape, a careful alignment, little or no sag in the tape, and some means by which its temperature can be taken and its correction applied. (Arts. 19–22, pp. 12–3.) In such cases the pull is measured by use of a tension handle (ordinary spring balance) which can be attached by a clamp to any part of the tape, the alignment is given with the transit, and, where feasible, just enough pull is given so that the stretch in the tape equals the shortage due to sag. The correction for temperature can be computed from the difference between the temperature of the tape taken in the field and the temperature at which it is standardized (Art. 20, p. 12). The tape should be compared with the *City Standard* (Art. 269, p. 253), at a definite tension, and the temperature noted at the time. From this information all of the field measurements can

be reduced to agree with the City Standard and very accurate results may be obtained.

Where the ground is not level and there is call for frequent plumbing it is impossible to obtain accurate results unless the plumbing is carefully done by experienced tapemen. For very accurate work it may be desirable to entirely eliminate the plumbing. This is sometimes done by measuring directly on the surface (on the slope) from point to point, and by means of leveling the relative elevations of these points are obtained and the horizontal projection of the slope distances computed. A more common method is to measure the inclined distance from the telescope axis of a transit set up at alternate points which are a little less than a tape-length apart, obtain the inclination of the tape by measuring the vertical angle to the adjacent points and then compute the horizontal distances by the method explained in Art. 13, p. 9.

The government Bureau of Standards at Washington will, for a nominal charge, standardize tapes; and city and private engineers frequently avail themselves of this opportunity. This Bureau will give the exact length of the tape at a given temperature or the temperature at which the tape is of standard length, whichever is desired by the engineer. It is well to have the tape also tested at a few intermediate points, e.g., the 25 ft., 50 ft., and 75 ft. marks. One tape which has been standardized should be kept in reserve, with which tapes in service can be compared both when new and after being mended.

Steel or metallic tapes reading to tenths of a foot are used in taking measurements for making approximate estimates of construction and for measuring earthwork, paving, and the like.

268. Transits and Levels. — The transits usually employed in city work read to 30″ or to 20″. With these instruments angles to the nearest 5″ can be obtained by repeating the angles as explained in Art. 59, p. 48. If much of this precise work is required it will be of advantage to use an instrument reading to 10″. It is well also to have transits equipped with stadia hairs for use on certain classes of surveys.

Much of the city work, such as the staking out of new streets paving, sewers, or curbs, requires the establishment of both lines

and grades. Since this class of work does not as a rule call for precise results, the measurements and rod-readings are usually taken to hundredths of a foot. It is not convenient, for the ordinary surveying party of three men, to carry both a transit and a level instrument in addition to the ordinary equipment of sighting-rods, level-rod, stakes, tape, etc., so the engineer's transit, with a level attached to the telescope, is extensively used in setting grades as well as in establishing lines. For this reason several of the transits in a city office should be equipped with telescope levels and some of them with vertical arcs. The degree of precision possible with an engineer's transit is entirely satisfactory for all ordinary leveling.

Where leveling work alone is to be done the ordinary wye or dumpy level instrument is used together with target or self-reading rods. (See Chapter IV.) For bench leveling it is customary, in large cities at least, to use a *precise level*, an instrument which is similar in principle to the ordinary level but which has a more delicate bubble and a telescope of higher power, and is therefore capable of yielding more accurate results. (See Chap. III., Vol. II.)

269. CITY STANDARD.* — It is customary in some cities to maintain a standard of length, usually 100 ft. long, established in some convenient place, often near the office of the City Engineer. It sometimes consists of two brass plugs set in a stone pavement, or it may be a long steel rod supported on rollers on the side of a wall or building in such a way that the rod can expand or contract freely. The end points and the 50-ft. point are so marked that they can be readily used for testing tapes.

A city standard is often established by carefully transferring the length of some other standard, by means of different tapes and under different weather conditions; or it can be established by means of a tape which has been standardized by the U. S. Bureau of Standards (Art. 241, p. 216). The City Standard is

* See a paper entitled "The 100-foot Standard of Length of the Boston Water Works at Chestnut Hill Reservoir," by Charles W. Sherman, published in the Jour. Assoc. Eng. Soc., Vol. XVIII, No. 4, April, 1897. See also description of standard presented to City of Chicago by Western Soc. C. E. in Eng. News, Vol. 72, p. 748, Oct. 8, 1914.

generally placed where it will not be exposed to the direct rays of the sun, and with this end in view it is sometimes covered with a wooden box.

When a tape is tested it should be stretched out at full length beside the standard and left there until it acquires the same temperature as the standard before the comparison is made, to avoid the necessity of applying a temperature correction.

CITY LAYOUTS.

270. In laying out or extending a city it is the duty of the surveyor to consider the future needs of its population and to design the general plan of the city accordingly. Nearly all of our large cities show examples of lack of forethought relative to future growth, which have necessitated the outlay of millions of dollars for revision of street lines, sewer systems, water works, and the like.

Occasionally the engineer is called upon to plan a new city or to design the general layout of the suburbs of an existing city. The basis for such work should be a topographic map of the entire area, for the topographic features of a locality will influence its development to a marked degree.

271. STREETS. — In planning the arrangement of the streets for a city such features as a water front, a river or lake, the location of an existing railroad, or the probable location of some projected railroad line will determine to a large degree where the business section of the city will be located. This section should then be so divided as to yield the greatest convenience for business purposes. Other sections will be reserved for residential districts, and their design will be of a different character. Easy access should be provided from the business to the residential districts and to outlying towns or adjacent cities.

The streets must be of the proper width to accommodate the traffic they are to carry, and their alignment and grades must be carefully studied with the topographic map as a guide. Adequate drainage of the streets is, of course, one of the most

important features, for which ample provision must be made in establishing the alignments and grades.

In the business section the traffic will move in certain directions, e.g., to and from important points such as a river, railroad station, or freight yard, and this traffic must be provided for by wide streets with easy grades. In the residential portions, narrower streets and steeper grades are permissible when made necessary by the topography of the district.

272. Location of Streets. — In establishing the location of city streets in hilly districts it is probable that to obtain the essential requisites of easy grades and good drainage the topography will govern the street layout. Whereas in a practically level country, with no steep grades in any direction, the street layout can be such that the most direct communication between different parts of the city is secured.

Fig. 111 shows the location of a rectangular system of streets laid out without reference to the topographic features. The lower portion is on rolling ground where this system may be properly applied; but from a study of the contours it will be seen that in the upper portion this method introduces very steep grades on all of the streets which cross the valley and also leaves a hollow in these streets which is difficult to drain. Fig. 112 shows a layout which will obviate this difficulty to some extent, the diagonal streets being located in the valleys to take the surface drainage of surrounding property. It is obvious that the construction of a sewer through these diagonal streets will be much more economical than through the streets as laid out in Fig. 111, for a sewer must have a continual drop toward its outlet, and cannot be laid uphill and downhill like a water pipe.

With reference to directness of communication between different parts of a city the two general systems which have been used in this country are the rectangular block system and a combination of rectangular blocks with diagonal streets, running in the direction of the greatest traffic.

The rectangular system gives the maximum area for private occupation and is consistent with the general style of rectangular building construction. Where the topography admits of it, this system of streets is advisable. Many of our large cities,



FIG. 111. LAYOUT OF STREETS WITHOUT REGARD TO TOPOGRAPHY.



FIG. 112. LAYOUT OF STREETS WITH REGARD TO TOPOGRAPHY.

like Philadelphia, for example, have been laid out in this manner. The streets frequently run parallel and perpendicular to the shore of a lake or river. More often, however, they are laid out in north and south, and east and west directions. When diagonal streets also are introduced they should connect the points between which the traffic is the heaviest. Indianapolis is planned in this manner, having four broad diagonal avenues running from a central park; but the city of Washington (Fig. 113) is the best example of this system in the United States.

273. Size of Blocks and Lots. — No definite size of blocks and lots can be prescribed which will fit all conditions. Experience has shown that the depth of lot most convenient for both business and residential districts is from 100 to 150 feet. In business districts particularly, it is well to provide an alley from 15 to 25 ft. wide running lengthwise through the block. This makes the width of blocks from 215 to 325 feet, which is about the range in existing cities.

The length of the blocks should be in the direction of greatest travel, and this dimension will therefore depend upon the necessity for cross-streets to accommodate the traffic which moves at right angles to the principal line of traffic. In business districts then the cross-streets should be much more frequent than in residential portions of the same city. The length of blocks therefore varies considerably in different cities and in different parts of the same city; ranging all the way from 400 to 900 feet. In New York the typical blocks are 200 × 900 ft., and 200 × 400 ft.; in Boston they vary in width from 125 to 252 ft. and in length from 200 to 700 ft., depending upon the locality.

The frontage of lots is frequently 25 ft. in business and congested residential districts and 50 feet or more in suburban districts, but these dimensions are by no means universal.

274. Width of Streets. — The widest streets should in general be the ones which have the greatest traffic. Important business streets should be from 100 to 150 ft. in width, while streets of secondary importance in business districts may be from 60 to 80 ft. wide. In residential districts the main streets



FIG. 113. MAP OF A PORTION OF THE CITY OF WASHINGTON.

should be 60 to 80 ft. wide, but those of lesser importance are often made 50 ft. These widths, however, are more liberal than have been used in many of our older cities, e.g., such cities as Boston, Baltimore, and New York which are especially afflicted with narrow streets.

The alleys which are run through the middle of city blocks should be made from 15 to 25 ft. wide. If they are made narrower than 15 ft. two teams cannot pass each other unless certain parts of the alley are widened for this purpose. Alleys furnish a convenient place for the location of water pipes and sewers.

The width of sidewalks varies greatly with the locality. In business districts, where there is usually a necessity for ample width, some cities devote two-fifths of the entire width of the street to sidewalks; while in residential districts, the sidewalks are frequently much narrower in proportion to the width of the street. In Boston the general rule is to make each sidewalk one-sixth the width of the street. Sidewalks 8 ft. wide are ample for most residential districts. In some localities walks as narrow as 4 ft. are laid out with a liberal grass-plot between the sidewalk and the roadway, which not only gives a pleasing appearance to the street, but also lessens the width of sidewalk and of roadway to be paved and maintained, thereby decreasing the burden of taxation and leaving room for an increase in width of roading if afterwards needed.

275. STREET GRADES. — In connection with the layout of a new city or suburb the grade of the streets is of quite as much importance as the street alignment. While, in the residential districts of some cities, street grades as steep as 10 and 15 per cent. are not uncommon, still it is considered advisable, if possible without excessive cost, to keep the grades down to about 5 or 6 per cent., especially those which extend for any considerable distance. In business districts, where heavy loads are to be hauled, it is desirable that the grades should not exceed 3.5 or 4 per cent. In any case where one street crosses another the grade should be flattened between curb lines to 2 or 3 per cent. if the grade of either street is greater than this amount.

On account of drainage it is well to build a street with a slight grade rather than level. A grade of 6 inches in 100 feet is a good working minimum for proper drainage, and if the street does not have this gradient the gutters must be made of varying depth so as to properly carry off the water. Other elements which govern the rate of grades are the cost of earthwork and the proper balancing of the excavation and embankment in the construction, the effect on abutting property, and the general appearance of the street.

At points where there is a decided change in grade it is customary to introduce a parabolic vertical curve. (Art. 294, p. 277.)

For the purpose of "establishing" street grades, profiles are made of each street. Levels taken for the purpose of establishing a profile should include elevations at the center of the street and along both side lines, and it is often desirable to have a plan of the entire area of the vicinity where the street is to be located. A description of the street grade is put in written form for acceptance by the proper municipal authorities. When this description has been formally accepted by an order of the City Government the grade is said to have been "established." Such an order may refer to the profile by title or recorded number, instead of a written description of the grade. The profile of each street should contain one or more cross-sections on which is indicated to what part of the cross-section the profile refers, i.e., whether the profile grade is the grade of the center of the street, the curb, or the sidewalk at the property line.

The following is an example of a description of an established street grade: —

"Beginning at Station 146 (Maple St.) at the junction of the center lines of Maple St. and Ocean Ave., at grade * 52.00, the grade line falls 0.50 per 100 for 726 ft. to grade 48.37— thence rises 0.82 per 100 for 322 ft. to grade 51.01 — thence

---

* The word *grade* is frequently used to mean the *elevation* of a point. In such a case care should be taken not to confuse the meaning of *grade* with *rate of grade*. The latter is sometimes called *gradient*, a word which has some advantages but is not entirely satisfactory.

falls 0.50 per 100 for 122 ft. to grade 50.40 — thence falls by a vertical curve for 100 ft. as follows:

Sta.	Elev.
157 + 60	50.40
157 + 85	49.90
158 + 10	49.30
158 + 35	48.55
158 + 60	47.70

thence falls 3.60 per 100 for 239 ft. to Station 160 + 99 (Maple St.), grade 39.10."

276. THE DATUM PLANE. — One of the first tasks of the surveyor in laying out a town site is to establish a datum plane to which all elevations may be referred. It is customary to choose a datum that bears an intimate relation to the topography of the locality. For example, if the town is located on the seashore a series of tidal observations may be taken to determine the mean sea-level or mean low water either of which is often used as a datum (Art. 263, p. 245). The mean level of lakes is used as a datum for many inland cities. Frequently the elevation of some point not far from the town site has been established by the U. S. Geological Survey, the U. S. Coast and Geodetic Survey, or by the line of levels of a railroad; and by careful leveling the elevation of some permanent point in the town site can be established which will serve as the starting point for all the elevations in the town. Where nothing of this sort is available, the elevation of some point is found by barometer so that the recorded elevation may approximate the actual height above sea-level.

277. ESTABLISHING BENCH MARKS. — When the datum has been determined, bench marks are established by the method explained in Art. 245, p. 232. The establishment, at the start, of a reliable system of bench marks is of utmost importance, in order that the elevations of all parts of the city shall refer to the same datum. In laying out construction work it is absolutely necessary that bench marks which can be relied upon shall be available and sufficiently numerous to be of use in any section of the city without requiring several set-ups of the level to connect a bench mark with the level work that is to be done.

Another advantage in having them close together is that they may serve as ready checks on each other as well as on the work at hand. It is not uncommon for a bench mark to be disturbed, and, if the level work is not occasionally checked on some other bench mark, an error will surely enter into all of the level work which was started from that bench.

STAKING OUT CITY WORK.

278. STAKING OUT A NEW DISTRICT. — In staking out a new district the information at hand is usually a plan of the proposed layout which has been approved by the municipal authorities, the street lines as they appear on the plan being the "established lines."

It is the surveyor's duty to stake out these lines on the ground, connecting them properly with the street lines of the older portion of the city, and in short, to produce on the ground a layout exactly like that on the plan. As soon as the plan is accepted the street lines should be marked by monuments (Art. 279), so that there may be no difficulty in retracing the lines as they were originally laid out and accepted. If considerable grading work is to be done in building the new streets it may not be practicable to set many of the corner bounds at first on account of the likelihood of their being disturbed. In such cases it is the duty of the surveyor to properly reference the points by cross transit lines or otherwise before construction work begins; for it is important that the layout, as recorded in the city order, shall be accurately and definitely fixed so that when the streets are brought to the proper grade and the monuments are finally set they will mark the exact position of the original layout.

279. MONUMENTS. — It is important and at the same time customary to define street lines by setting stone bounds, often called *monuments*, at the street corners and at angles in the street lines. The bounds are set sometimes on the side lines, sometimes on the center lines, and sometimes in the sidewalks.

At street intersections, one monument at the intersection of the center lines will suffice to mark both street lines, but since this point will come in the center of the road pavement where it is likely to be disturbed by traffic or by street repairing it is sel-

dom placed there. The more practicable method is to define the street lines by marking the side lines at the angles or, in the case of rounded corners, at the beginning and end of the curves. It is not necessary that all four corners of a street intersection shall be marked, as a bound on one corner will define the side lines of the two streets and, the width of the streets being known, the other sides can easily be determined. Nor is it necessary to place a bound at one of the corners of every street intersection, provided a street is straight for several blocks, although it is good practice to do so. On account of the liability of bounds which are placed on the side lines of the street being disturbed by building operations, some surveyors prefer to place them on an offset line, say 2 ft. from the street line. All monuments should be placed with extreme care as regards both their accuracy of position and their stability. If any bounds are set with more care than others, they should be the ones which occur at angle points in the street lines rather than the intermediate bounds which are set along a straight line.

Monuments are usually roughly squared stone posts about 4 to 8 inches square and 3 to 4 feet long, the length depending upon the severity of the climate, e.g., in New England a monument less than 4 ft. long is likely to be disturbed by frost action. They are carefully squared on top and a drill-hole in this end marks the exact point. This drill-hole may be made either before the stone is set in place, or else after it has been so placed that its center is about in position when the exact point may be defined by drilling a hole in its top. Frequently the hole is filled with lead and a copper nail set in the lead is used to mark the exact point. For nice definition of the point, a copper bolt is inserted and two lines scratched across it; the intersection marks the exact point. When the stone bound is placed at the intersection of the side lines of the streets it is sometimes located entirely in the sidewalk in such a way that its inside corner is exactly on the intersection of the street lines. In such a case the three other corners of the bound are usually chipped off so that there may be no mistake as to which corner defines the line, but the line corner frequently becomes worn off and this practice is therefore not recommended. Some surveyors

use, in the place of stone bounds, a piece of iron pipe or iron plug with a punch-hole in the top of it, driven into the ground or embedded in cement concrete. Long heavy stakes are employed to temporarily define intermediate points or points of secondary importance.

280. Setting Stone Bounds. — When the street lines are laid out the corners are marked by tacks in the top of ordinary wooden stakes. The monuments which are to take the place of the stakes should be set before the frost has entered the ground or before any other disturbance of the stakes has taken place. When the bound is ready to be set the first thing to do is to drive four temporary stakes around the corner stake about two feet from it and in such a way that a line stretched from two opposite stakes will pass over the tack in the head of the corner stake (Fig. 114). Then tacks are carefully set in the tops of these temporary stakes in such positions that a stretching line running from the tack on one stake to the tack on the opposite stake will pass exactly over the tack in the corner stake.



FIG. 114. SETTING A STONE BOUND.

Then the corner stake is removed and the hole dug for the stone bound. Care should be taken not to dig the hole any deeper than is necessary so that the bound may be set on firm earth. As to the position of the top of the bound with reference to the surrounding ground, surveyors disagree. Some prefer that the monument should stick out of the ground so that it can be readily found; while others claim that if it projects above the surface the bound is likely to become misplaced by traffic, and therefore that it is better to set it just flush with the ground or slightly below the natural surface. If any grading is to be done in the vicinity the bound should be set so that it will conform to the proposed grade. When the hole for the

bound has been dug to the proper depth it is well to stretch the strings across between the temporary stakes and plumb down roughly into the hole to determine where the center of the bound will come, so that when the monument is dropped into the hole it can be placed so that it will set plumb.

The bound having been set in the hole, the next operation is to fill around it. This should be done with considerable care, the material being properly rammed as the filling proceeds and the bound kept in such a position that the drill-hole in the top of it, if there is one, shall be **exactly** under the intersection of the strings. It is sometimes desirable to put in a foundation of concrete and to fill with concrete around the monument to within a foot of the surface, as shown in Fig. 115, where a very substantial bound is required, or where the ground is so soft as to furnish an insecure foundation. If the top of the bound is plain and the hole is to be drilled after the bound is in place, care should be taken to place the monument so that this hole will come practically in the center of the top in order that it may present a workmanlike appearance. After the bound is set exactly in place the temporary stakes are removed.



FIG. 115. STONE BOUND WITH CONCRETE FOUNDATION.

Some surveyors prefer to use only two opposite stakes and one stretching line, the position of the monument being determined by a measurement along the stretching line from one or both of the temporary stakes. Still another method of temporarily tying in the stone bound, and one which many surveyors use, is to set two stakes such as A and B in Fig. 114, and either measure the distance from them to the bound or set them at some even distance from the bound. This process of using temporary stakes and the stretching line is employed also in setting other types of bounds such as gas pipes or iron rods.

In the construction of buildings or fences, monuments are frequently disturbed and too often they are reset by the owner of the property without the services of a surveyor. In rerunning a street line, therefore, a surveyor should be on the lookout for such conditions, and he should be cautious in the use of any monument which he has any reason to suspect may have been misplaced.

281. CURVED LAYOUTS. — It is not unusual for streets to be laid out with curved lines. In the design of boulevards, parks, and residential sections a landscape architect is often called in and the plan he presents is sometimes almost devoid of straight street lines. (See Fig. 116.) The surveyor must



FIG. 116. CURVED LAYOUT FOR RESIDENTIAL PART OF A CITY.

take this plan and from the design there given stake out th layout and obtain the necessary dimensions to definitely locat all parts of it.

As a rule the landscape architect simply draws on the top graphic map his scheme of layout with very few dimensions an leaves the rest to be worked out by the surveyor. Occasionall

the radii of the curves are noted on the plan, but the street widths are often the only dimensions given. If the radii are not given the surveyor must determine from the plan either these radii or some other distances, such as the tangent lengths, so that he can go into the field, and, beginning with some known street line, run out the new street lines in such a way that when the data he determines are plotted the lines will coincide with those on the plan prepared by the landscape architect. As a rule these curved lines can be made up of a combination of circular curves.

282. ELEMENTS OF A CIRCULAR CURVE.— Before considering how to stake out a curve it will be well first to refer to the elements of a simple circular curve. In Fig. 117 which represents a simple circular curve

OB = Radius $= R$
AHB = Length of Arc $= L_c$
AB = Long Chord $= C$
$VA = VB$ = Tangent Distance $= T$
VH = External Distance $= E$
HF = Middle Ordinate $= M$
I = Intersection Angle, or Central Angle
V = Vertex
$P.C.$ = Point of Curvature
$P.T.$ = Point of Tangency



FIG. 117. CIRCULAR CURVE.

From simple geometric and trigonometric relations,

$$\text{Tan}\ \frac{I}{2} = \frac{T}{R}, \qquad T = R \tan \frac{I}{2}$$

$$\text{Exsec}\ \frac{I}{2} = \frac{E}{R}, \qquad E = R\ \text{exsec}\ \frac{I}{2}$$

$$\text{Vers}\ \frac{I}{2} = \frac{M}{R}, \qquad M = R\ \text{vers}\ \frac{I}{2}$$

$$\text{Sin}\ \frac{I}{2} = \frac{C}{2R}, \qquad C = 2R \sin \frac{I}{2}$$

$L_c = R \times$ Circular measure of I.*

* The curves used in railroad engineering are usually very flat, so that there is little difference between the chords and their corresponding arcs. This fact

283. STAKING OUT CIRCULAR CURVES. — In Fig. 117 the two lines *BC* and *EA* are produced in the field and a point is set at their intersection *V*, as described in Art. 208, p. 183. The instrument is then set up at *V* and the central angle *I* carefully measured, or if point *V* is inaccessible other angles such as *VEC* and *VCE* may be measured from which *I* can be easily computed. Then the radius *R* which is determined from the plan being known, the tangent distance *T* is obtained by the formula, $T = R \tan \frac{1}{2} I$. Points *P.T.* and *P.C.* are then set and the curve is usually laid out by the method of *deflection angles* as explained in the following article.



FIG. 117. CIRCULAR CURVE.

284. DEFLECTION ANGLES. — A deflection angle is usually referred to as an angle between a tangent and a chord, e.g., in Fig. 118 angles *VAb*, *VAc*, etc., are deflection angles. Since



FIG. 118. DEFLECTION ANGLES.

---

makes it possible to compute the *length of curve* by a simple approximate method, which, however, is sufficiently exact for most railroad work.

The *Degree of Curve*, which is the angle at the center subtended by a chord of 100 ft., is an element of the circular curve which is used extensively in railroad en-

the angle between a tangent and a chord is measured by half the included arc these deflection angles must be equal to half the angle at the center subtended by the same chord or arc.

If the total length of the curve is divided into an even number of parts, n, the angle at the center under each of these arcs will be $\frac{I}{n}$, and the deflection angle for one chord will be $\frac{I}{2n}$, which in Fig. 103 is the angle VAb. Angle bAc = angle VAb, both being measured by one-half of equal arcs. It follows then that the deflection angle to point

$$c = 2 \times \frac{I}{2n} = \frac{I}{n}$$

$$d = 3 \times \frac{I}{2n} = \frac{3I}{2n}$$

$$e = 4 \times \frac{I}{2n} = \frac{2I}{n}$$

etc.

Evidently, after the first deflection VAb is found, the other deflections can be obtained by simply adding the increment $\frac{I}{2n}$ to the preceding deflection angle, and this is the method which should be used. The deflection angle from the $P.\ C.$ to the $P.\ T.$ should be equal to $\frac{I}{2}$, and this check should always be applied to the computations before they are used in laying out the curve.

The chords Ab, bc, cd, etc. are equal since their arcs are equal. With the radius and the central angle $\left(\frac{I}{n} \text{ for one chord}\right)$ given, the chord length can readily be found from the formula,

---

gineering. The central angle divided by the degree of curve will give the number of 100-ft. chords in the length of the curve, i.e., $\frac{I}{D} = L$ (in 100-ft. stations). Therefore L (in feet) $= \frac{100I}{D}$. For a complete discussion of railroad curves see "Railroad Curves and Earthwork," by Professor C. F. Allen, published by McGraw-Hill Book Company, New York.

$c = 2\,R \sin\frac{I}{2n}$. Since the angle at the center is usually small and the radius large the angle will have to be carried out in some instances much closer than to the nearest minute in order that the length of the chord may be obtained to hundredths of a foot (Art. 406, p. 389). An approximate value for the chord length corresponding to a given arc may be obtained by the useful formula,

$$l_c - c = \frac{c^3}{24R^2}, \text{ or } = \frac{l_c^3}{24R^2} \;*$$

in which l_c is the length of the arc, c is the chord length, and R the radius.

Most of the engineer's handbooks contain tables of chords and corresponding arcs for curves of different radii, which assist greatly in shortening these computations.

When the deflection angles have been computed and checked and the chord length found, the instrument is set up at A, (Fig. 118) a foresight taken on the vertex with the vernier reading 0°, and the point b set by measuring Ab and placing b on line by means of the transit on which the first deflection angle VAb has been laid off. Point c is set by measuring bc and placing c on line with the transit on which the second deflection angle has been laid off, and so on, until the last point ($P.T.$) has been set.

It is evident that with the transit at the $P.C.$ the curve could have been laid out just as well by taking the measurements from the $P.T.$ end, and some surveyors prefer to do it this way. Similarly the instrument might just as well have been set up at the $P.T.$ instead of the $P.C.$ and the measurements started from the $P.C.$ if it were found to be more convenient.

* The following will give some idea of the accuracy of this formula.

With $R = 100$ and $c = 25$, the formula gives $l_c = 25.065$, (correct value is 25.066).

With $R = 100$ and $c = 50$, the formula gives $l_c = 50.521$, (correct value is 50.536).

With $R = 1000$ and $c = 100$, the formula gives $l_c = 100.042$, (correct value is 100.042).

This formula will be found very useful if a slide rule is employed for the computation.

It is sometimes necessary to set **definite station points** on the curve rather than to cut the curve up into several **equal** parts as suggested above. The principle is exactly the same as described above; but in figuring the deflection angles and the chord lengths to be used the computations are not quite so simple. No trouble will be experienced, however, if it is borne in mind that **the total deflection angle to any point is equal to half the central angle to that point from the** *P.C.*, **and that the central angle for any arc bears the same relation to the entire central angle that the arc does to the entire length of curve.**

285. Keeping the Notes. — In a curved street the notes of alignment generally refer to the center line, the two side lines being parallel to the center line. All three of these lines have to be run out by the use of chords and deflection angles; Fig. 119 is an example of a concise form of notes for this work. In

Description of curve	Station	Distance (Arc)	Chords			Deflection Angles	Remark
			Left	Center	Right		
			Width of Street 70 Feet.				
To Right	18+52.50	30.08	35.31	30.05	24.79	25°-47'-40"	P.T.
R=200	18+22.42	50.00	58.59	49.87	41.14	21-29-10	
T=96.66	17+72.42	50.00	58.59	49.87	41.14	14-19-20	
I=51°-35'-20"	17+22.42	50.00	58.59	49.87	41.14	7-09-40	
L_c=180.08	16+72.42						P.C.

FIG. 119. NOTES OF A CIRCULAR CURVE.

the first column is a description of the curve, which refers to the center line of the street. This particular curve is marked "To Right" meaning that it deflects to the right while passing around it in the direction in which the stations run. In the third column are the distances measured on the actual arc along the center line. The next three columns headed "Chords" are the chord measurements across the curve from station to station on the left side line, the center line, and the right side line of the street, the terms left and right meaning left and right looking in the direction in which the stations run. In the column headed "Deflection Angles" are the total deflections to be laid off with the instrument set up at the *P.C.* These same deflection

angles are used in running out the side lines for the chords which have been computed for the side lines run between points which are radially opposite the corresponding points on the center line. The computation of these notes will be found in Art. 406, p. 389.

286. When the Entire Curve Cannot be Laid Out from One End. — It is often impossible to see from the *P.C.* to the *P.T.* of a curve on account of intervening obstructions. In such a case the curve is run from the *P.C.* as far as is practicable and a point is carefully set on the curve; then the transit is brought forward and set up at the point thus fixed, and the curve extended beyond. There are two different methods employed in this case.

287. FIRST METHOD. — Assume the circular curve in Fig. 120 to be laid out from *A* to *d* as described above. Point *d* is



FIG. 120. INTERMEDIATE SET-UP ON CURVE.

carefully set and the instrument then taken to that point and set up. The vernier is turned back to 0° and beyond 0° by the value of the deflection angle *VAd*. Then by using the lower clamp and tangent screw the telescope is sighted on point *A*. The upper plate is then unclamped and, if the telescope is turned so that the arc reads 0° the instrument will be pointing along the direction of an auxiliary tangent *df*, for angles *VAd* and *Adf* are equal. It is well to note whether the instrument appears to point in the direction of the tangent. Then reverse the telescope, set off on the vernier the angle $gde = \frac{I}{2n}$, and lay out the

curve from d to B just as though it were an independent curve beginning at d and ending at B.

288. SECOND METHOD. — When the transit has been set up at d, the vernier is set at 0° and a backsight taken on A. Then an angle equal to the deflection angle VAe is laid off on the arc; this will cause the telescope to point in some such direction as dh. The line of sight is reversed and point e set on hd produced, making the chord de of the proper length. Then point B is set by laying off on the vernier an angle equal to VAB and measuring the chord eB. This method is correct for

$$VAe = VAd + dAe$$
$$= fdA + hdf, \text{ being measured by half of equal arcs.}$$

This second method is sometimes to be preferred since the original deflection angles figured can be used throughout the curve. The first method calls for the calculation of a few more angles; but this is so simple a process that there is probably little choice between the two methods.

289. CURVED STREET CORNERS. — It is the practice in many cities to curve the corners of the streets by introducing a circular curve of short radius. Where both street lines are straight the problem is handled as explained in Art. 283, p. 268.



FIG. 121.

290. * **One Street Line Straight, the Other Curved.** — In Fig. 121 the curved street line DEF intersects the straight street line AV and at this point the circular curve whose center is C' and with a given radius r is to be introduced to round off the corner. It is required to stake out the curve GE on the ground. In

* The authors are indebted to I. T. Farnham, formerly City Engineer of Newton, Mass., for the solution of the problems given in Arts. 290–1.

the field any tangent line, such as FV, is run off from some known point on the curve and intersected with AV, and the angle β and the distance FV are measured. In the right triangle CFV in which R and T are known, compute angle α and distance CV. In the right triangle CAV, CV and $\gamma = \beta - \alpha$ being known, compute CA and AV. $CA' = CA - r$; $CC' = R - r$. In the right triangle $CA'C'$, CA' and CC' being known, compute $A'C'$ and $A'CC' = GC'E$. Angle $ACF = 180° - \beta$. Angle $ECF = ACF - A'CC'$, from which the length of the arc FE can be readily computed, which locates the point E. $VG = AV - A'C'$, which locates point G of the curve GE, and any intermediate points can be located as explained in the previous articles.



FIG. 121.

As the radius $C'E$ is often quite short the center of the curve can be located from either its *P.C.* or *P.T.* or both, and any intermediate points on the curve can be easily swung in from its center.

291. Both Street Lines Curved. — In Fig. 122 the two curved street lines ABD and $A'B'D'$ intersect each other and the curve whose center is E and with a given radius r is introduced at the intersection of the two street lines. It is required to locate the curve $B'B$ on the ground. In the field the tangent DV is run off from some known point D on the curve ABD and intersected with a tangent $D'V$ from the curve $A'B'D'$ and angle α and distances T and T' are measured. In the right triangle CDV, R and T being known, compute angle CVD and distance CV. Similarly in the triangle $C'VD'$ compute angle $C'VD'$ and distance $C'V$. In the oblique triangle CVC', CV, $C'V$ and angle $CVC' = 360° - (\alpha + CVD + C'VD')$ being known, compute CC' and the angle $CC'V$ and $C'CV$. In the oblique tri-

angle $CC'E$, $CE = R + r$, $C'E = R' - r$, and CC' being known, compute the angle $C'CE$, $CC'E$ and $C'EC$, which is the supplement of the central angle of the curve $B'B$. Angle $DCB = DCV + VCC' - C'CE$, from which arc DB can be com-



FIG. 122.

puted. Similarly angle $D'C'B' = D'C'V + VC'C - CC'E$, from which arc $D'B'$ is computed. These locate the $P.C.$ and $P.T.$ of the small curve whose center is E.

292. INTERSECTION OF CIRCULAR ARC AND STRAIGHT LINE. — This problem occurs wherever a straight property line cuts a curved street line. In the survey sufficient data must be obtained so that the distance along the curve and also the distance along the property line can be computed to the point where it cuts the curve. The usual method is to lay out a line tangent to the arc at some known station A on it, intersect that tangent with the property line, measure the distance from

A to the point of intersection and measure also the angle at the point of intersection.

In Fig. 123, AC is the curved street line, EF the property line, AD an auxiliary tangent. Distance AD and angle α are measured in the field; the radius R is known. Arc AB and distance DB are required. In triangle DOB, $OB = R$, $OD = \frac{R}{\cos I'}$, $BDO = 180° - \alpha - (90° - I') = 90° - (\alpha - I')$. Angle I' is found through the known distances DA and R. Solve triangle DOB for angle β and BD, using special precautions because angle β is so small (see Art. 388, p. 374, and p. 502). Arc $BC = R \times$ angle $(I + \beta)$.



FIG. 123.

Sometimes R is so small that its position can be readily sighted from the arc, in which case line CF and angles EFC and FCO are measured in the field. In triangle COF solve for OF and all angles. Then in triangle FOB, OF, OB and BFO being known, solve for FB and FOB. Arc $CB = R \times$ angle $(COF + FOB)$.

293. STAKING OUT STREET GRADES. — The fieldwork necessary in setting grade stakes is explained in Arts. 261–2, pp. 244–5. When new streets are constructed the excavation or embankment is first brought to sub-grade, i.e., to the grade of the bottom of the road covering or pavement. The grade stakes set for this work are usually the center and the two side slope stakes, properly marked with the cut or fill, as described in Arts. 256–8, pp. 241–4.

As the work progresses the center stake is dug out or covered up and when the construction has progressed nearly to the sub-grade it is customary to set additional stakes marking the elevation of the sub-grade along the center line and on each side line of the roadway. If sidewalks with curbstones are to be constructed the curbs are first set to grade, and the roadway grades are marked on the face of the curb as well as on stakes in the center of the roadway. (See Arts. 295 and 278.)

294. Vertical Curves. — Where the rate of grade of a street changes, in order to avoid an abrupt transition from one grade to the other, a vertical curve, usually from 30 ft. to 200 ft. long, is introduced which is tangent to both grade lines. The simplest curve to locate for this purpose is the parabola.

In Fig. 124 LV and VM represent two grade lines intersecting at V. The parabola AHB is tangent to these lines at A and B. Fig. 124 represents a vertical curve 200 ft. long on



FIG. 124. VERTICAL PARABOLIC CURVE.

which the elevation of nine points, 25 ft. apart, must be determined. The equation of the parabola is

$$y^2 = 4\,px, \quad \text{or} \quad y^2 = (\text{constant})\,x,$$

the x dimensions being parallel to VK (vertical) and the y dimensions being along AV. From the equation it is readily seen that **the offsets from the tangent vary as the squares of the distances along the tangent,** or $x_1 : x_2 = y_1^2 : y_2^2$. The lines VP and NQ are vertical and AQ is horizontal. Since the curve extends an equal distance each side of V, $AP = PQ$; and therefore $AK = KB$. $NB = 4VH$; $VH = 4CC'$; $CC' = 4DD'$; etc. (from equation 1.)

Let g and g_1 represent the rate of grade of LV and VM, and n the number of 25-ft. stations (in this case 4) on each side of the vertex V, then $NB = (g + g_1)$,

and $$KV = \frac{NB}{2} \text{ (from similar triangles)}$$

but $$NB = 4VH \text{ (from above)}$$

therefore $$KV = 2HV,$$

or point H is midway between V and K.

The elevation of V is determined from the established grade. The number of 25-ft. stations will determine the distance VA and VB. The elevation of A and of B can be readily computed along their respective straight grade lines.

$$\text{Elev. } K = \frac{\text{Elev. } A + \text{Elev. } B}{2}$$

$$\text{Elev. } H = \frac{\text{Elev. } V + \text{Elev. } K}{2}$$

$$VH = \text{Elev. } H - \text{Elev. } V.$$



FIG. 124. VERTICAL PARABOLIC CURVE.

Elevations of all the other intermediate points along the curve can be computed by finding the elevation of the points D', C', E', F', G', and J' and by adding to these elevations the ordinates $D'D$, $C'CE'$ E, etc.

$$D'D = J'J = \frac{VH}{16}$$

$$C'C = G'G = \frac{VH}{4}$$

$$E'E = F'F = \frac{9VH}{16}$$

295. CROSS-SECTION OF STREET. — On account of the necessity for draining the surface of a road the center is raised or "crowned" above the grade of the gutters by an amount depending on various conditions. The shape of the road surface is sometimes two planes, running straight from the gutter to a summit or ridge in the center of the street, this ridge being

rounded off by rolling; but more frequently it is a curved surface in the form of a parabola or a circle. The ordinary width and crown of streets are such that the parabola and the circle are practically coincident.

When a street is to be paved the curbstones are first set to proper line and grade, then stakes are set for the finished grade of the roadway. The center grade stake is frequently the only grade given and a templet, or form, which can be set on the curbs and on this center stake is used to give the form of the cross-section. The form of the templet for this work is laid out by the surveyor. If no templet is used he should put in intermediate grade stakes between the center and the curb lines. In either case the surveyor must compute the necessary ordinates to give the proper shape to the surface.

Usually the mean transverse slope of the pavement is given either in the form of a ratio thus:

$$\text{Mean Transverse Slope} = \frac{\text{Crown}}{\text{Half the Width of Carriageway}} = \frac{1}{30}$$

or, Mean Transverse Slope $= \frac{2}{5}''$ per ft.

296. Gutters at Same Elevation. — Fig. 125 represents the cross-section of a pavement and sidewalks. The crown AB is



FIG. 125. CROSS-SECTION OF PAVEMENT; GUTTERS AT SAME ELEVATION.

computed from the mean transverse slope and the width of the pavement.

The ordinate DD' at any other point on the parabola $= C'C \times \frac{l^2}{\left(\frac{W}{2}\right)^2}$ since in a parabola the offsets from a tangent vary as the square of the distance out along the tangent (Art. 294, p. 277). But $C'C = AB$; hence, if D' is half-way from

the center to the curb, $DD' = \frac{AB}{4}$.

297. One Gutter Higher than the Other. — When one gutter is higher than the other and when it is also desirable to adhere to



FIG. 126. CROSS-SECTION OF PAVEMENT: ONE GUTTER HIGHER THAN THE OTHER.

a certain mean transverse slope the following application of the parabola can be used. In Fig. 126 the maximum ordinate x is at a distance a from the lower gutter. The first step is to find this distance a from the formula $a = \frac{\frac{1}{2}W}{1 - \frac{b}{2Ws}}$ and then x is readily found from the desired mean transverse slope, since $\frac{x}{a}$ = Mean transverse slope. The other offsets can be computed as explained in the previous article.

At A the offset $= \frac{x}{4}$; at $B = x - b$; at $C = \frac{x - b}{4}$

The formula for a is based upon the assumption that the crown is the arc of a circle. The term W = width of pavement, and s = mean transverse slope expressed as a ratio of crown to half the width of pavement.

298. If, instead of assuming the mean transverse slope of the pavement, the elevation of the center of the pavement D



FIG. 127.

(Fig. 127) with respect to the elevation of A or B is assumed, then DC is readily found and the elevation of such points as E or F, which are midway between D and the gutters, are computed from the method explained in Art. 296, eE and fF both being equal to $\frac{DC}{4}$.

Similarly, Elevation E = Elevation $G + \frac{3DC}{4}$

Elevation F = Elevation $H + \frac{3DC}{4}$

Elevation J = Elevation $K + \frac{7DC}{16}$

Elevation L = Elevation $M + \frac{7DC}{16}$ etc.

299. Irregular Shaped Blocks. — There is a wide variance of practice in the method of dividing irregular shaped blocks into lots. One good general rule in such cases is to give



Fig. 128. Arrangement of Lots in a Wedge-Shaped Block.

each lot as much street front as is possible consistent with making the side lines of the lots at right angles to the street lines. If the side lines do not run at right angles to the street there will be portions of the lot which are not available for the customary rectangular style of building construction and which are therefore not so desirable for business purposes. This is not of

so much importance in residential districts where the rectangular system is often purposely avoided to some extent, to obtain a layout which has an attractive appearance, as illustrated by Fig. 116, p. 266.

Fig. 128 is an example of an irregular shaped block in which rectangular lots have been planned, the wedge-shaped remnants being thrown into the corner lots.

300. STAKING OUT CITY LOTS. — In staking out the lots of a rectangular block, the corners of which have been established, the most direct method is as follows. The transit is set up on the S. B. at *A* (Fig. 129), a sight is taken on *B*, and the front



FIG. 129. RECTANGULAR CITY BLOCK.

corner stakes of lots 1, 2, 3, 4, etc., are set, with a tack, exactly on line, in the top of each stake. All such work should be done to the nearest 0.01 ft. It will be well first to measure the line *AB*, to see that it is just 600 ft. long. Since it is assumed that considerable care was used in setting the S. Bs. exactly in the correct position, if it is to be found to be a few hundredths over or under 600 ft., it is probable that this discrepancy is due to the difference between the length of the tape on the present work and that used in the original layout. In such a case the twelve lots must be laid out with equal frontages. For example,

it may be a hot day when the lots are to be staked out and the tape may give a distance from A to B of 599.88 ft. In this case each lot should measure 49.99 ft. wide.

With the instrument still at A and sighted on C, point D is set by measuring 66 ft. from C, and then point E is placed midway between A and D. Whatever slight discrepancy there may be in the distance between the S. B. at A and that at C is thrown into the depth of the lots rather than the width of the street.

By setting up the instrument at B and sighting on H, points F and G are set. Then by setting up at F and sighting on D the front corners of lots 13, 14, 15, etc., are determined. Another set-up of the transit at G with the line of sight on E will allow the "back bone" to be run out and the back corners of all the lots established. The check on the lines AB, EG, and DF is their total length. The depth of the lots can easily be checked by taking direct measurements from the front to their rear corner stakes. If a further check is desired the transit can be set up at each of the front corner stakes of the lots on one street and a right angle turned off to check the position of the rear corner stakes and the front corner stakes of the lots on the street beyond.

By the method suggested above the street lines are made straight and the slight inaccuracies which may occur in the field-work are put into the back and side lines of the lots.

Some surveyors prefer, after the front stakes on both streets are located, to set up the instrument at each front corner and locate the back corner stakes by turning a 90° angle and laying out the depth of the lot, at the same time checking the position of the front stakes on the street on the other side of the block. Then the distances along EG are measured to check this field-work.

301. Staking Out Curb* Lines and Grades. — If the line stakes which are set for the curbstones are placed directly on the line of the curb they will be disturbed when the trench is excavated. For this reason they are usually set in the sidewalk on an offset line, say, 3 ft. from the outside edge of the

* Called edgestones in some localities.

curb, and at intervals of about 25 ft. The grade stakes are set at about the same interval, with their tops at grade or at some even distance (6 inches or 1 foot) above or below the grade of the curb. Sometimes the grade stakes are not driven so that their tops bear any relation to the finished grade, but a horizontal chalkmark is made on the side of the stake marking the proper grade. A stake can be marked much more quickly than the top can be driven to the exact grade.

When new curbstones are being set in an old street, stakes cannot as a rule be used. The sidewalks are too hard to permit the driving of stakes, and even if they could be driven those projecting above the surface of the sidewalk would be a source of danger to pedestrians. In such cases it is customary to use heavy spikes about 6″ long. These are driven into the sidewalk on the offset line and the elevation of their tops determined by leveling. The difference between the elevation of each spike and the grade of the curb opposite it is calculated. A list of the stations and the distances the spikes are above or below the curb is given to the foreman in charge of the work. These distances should always be transposed into feet and inches (to the nearest $\frac{1}{8}$″) before being given to the foreman, as it is seldom that the men employed to lay the curbstones have any conception of the meaning of tenths and hundredths of a foot. (See Art. 7, p. 3.)

Where there are trees growing in line with the curbs, a nail can sometimes be set in the side of a tree on the line of the curb as well as at its grade. Points like these, of course, should be set in preference to offset stakes or spikes wherever possible, as there is little liability of the workmen misinterpreting such marks. They can fasten their string directly to the nail and set the curb to agree with it.

Before the curbstones are ordered the surveyor usually measures the distances between trees and locates driveways, and then makes out a list of the lengths of straight, of curved, and of chamfered stones (opposite driveways) to be used on the job. This list is used in ordering the stones, and when they are delivered they should be found to fit the conditions without the necessity of cutting any of them.

302. STAKING OUT SEWERS. — The lines and grades of sewers are sometimes run out in the same way as those described for curbstones. The stakes or spikes (in hard paving) are set on an offset line and the grades figured as described in Art. 301.

Another method which is extensively used is to spike out the center line of the sewer and, from the profile of the street, determine the depth of digging. When the excavation is completed the surveyor again runs out the center line and places batter-boards at the proper grade and line. This eliminates the errors which are likely to creep in during the leveling from the offset spikes as is required in the previous method.

303. STAKING OUT STREET RAILWAY TRACKS. — The lines and grades for street railway tracks are given usually by the use of an offset line of spikes. The spikes are frequently placed on an offset line 5 ft. from the center, or on a line 3 ft. from the gauge of the nearer rail, and at every 50-ft. station or oftener. The differences between the desired elevation of the track and the spikes is calculated, and this information is given to the foreman in charge, usually in the form of printed "grade sheets."

304. RERUNNING STREET LINES AND GRADES. — There is a constant call for lines and grades of streets. All kinds of work, such as the construction of fences, buildings, and street improvements, call for rerunning the street lines and grades.

The work of running out the line is simple enough if the original S. Bs. are in place. It is not uncommon, however, to find that in excavating a cellar on a corner lot the corner bound has been disturbed or that it has been removed entirely; and before the line can be properly staked out it may be necessary to begin at some reliable S. B. farther down the street or even on some other nearby street line.

When the line has finally been rerun it is customary to take and record swing offsets from the corners of the underpining of several of the buildings located along the street and near to the line. By this record of offsets, then, this street line can very easily and quickly be run out at any future time, and any disturbance of the S. Bs. at the corners can readily be detected. **Several offsets to substantial buildings are often of more permanent value than stone bounds.** In some offices these offsets to

buildings are recorded directly on the street plans. Whenever a street line or grade is rerun full notes should be made showing all measurements taken for redetermining the lines or grades.

Sometimes the original street lines have been so completely obliterated that it is necessary to resurvey them and make a new record plan and description of them and have these new lines "established" by a city ordinance. Such work, for example, has been done by the City of Providence, R. I. since 1857, when a state law was passed requiring that accurate street lines be marked where the adjacent land was about to be built upon. To properly carry out this law the resurvey of a number of the principal streets was required and the policy then originated has been continued.

When a new building is to be constructed the owner generally requests the City Engineer to define the street grade in front of his property. The surveyor who has charge of this work levels from the nearest B. M. to the site of the new building. He has in his possession the established grade of the street and its cross-section giving the relation of the curb grade to the established grade of the crown of the street, and the rate of slope of the sidewalk. From these he can compute the elevation of the sidewalk grade at those points along the street line where the grades are desired. On the fence or on stakes set on the side line of the street he marks the grade of the sidewalk at the property line, usually to a hundredth of a foot.

305. REVISING STREET LINES. — In older cities much is being done toward straightening some of the crooked streets, and widening the narrow streets. A survey of existing structures is made and plotted, and the new street lines are then studied with reference to existing conditions. Several proposed lines are sometimes considered and run out on the ground. The line finally selected is carefully run out and offsets to existing structures determined so that if it may be definitely located, and the areas of all property taken from each abutter are then surveyed, computed, and described. This layout is then accepted by city ordinance, usually after an advertised hearing has been held, and the fences are then changed in accordance with the revision.

306. REVISING STREET GRADES. — Sometimes the established grades of city streets have been laid down in the early days of the city, and it is subsequently found that these grades need revision. In such a case the surveyor will make a profile of the center line of the street, of each curb (if there are any) and sometimes along the side lines of the street. He will also take all necessary elevations on the steps of buildings which lie near the street lines, and a few levels in the front yards of abutting property. From a study of these grades together with a plan of the street the new grade line is laid out with a proper regard for existing improvements on abutting property. When this grade line has been accepted it is staked out and the street regraded. Stakes for final grading are set to hundredths of a foot.

307. LAYOUT OF CEMETERIES. — In the layout of new cemeteries or the extension of old ones it is customary to prepare a topographic map of the district on a scale of 1 inch = 20 feet. These surveys may be carried on by the usual transit and tape methods but the plane table may be used to advantage. If the latter is used the distances are measured by means of the tape, although the directions are determined in the usual manner. In laying out the new district particular attention must be given to under-drainage and to surface drainage. The roads and paths are usually narrow and are constructed of the rocks, boulders and other acceptable material which has been excavated from the lots where the interments are to be made. The size of the lots depends upon the desirability of the location; if the lots are in a very desirable portion of the cemetery, the larger and more expensive lots would be laid out. The common sizes of lots are 20 ft. × 20 ft., for about a dozen interments, 20 ft. × 10 ft., for 6 interments, and 10 ft. × 10 ft., for 3 interments. Lots for single interments are usually 4 ft. × 8 ft. The lot corners are usually marked by stone bounds. As a rule a grass plot is left between the avenue lines and the lot lines. The avenues and paths are often curves of short radii. (See Arts. 281–92, pp. 266–75.)

308. ACCIDENT PLANS. — When a city is sued for damages due to an accident occurring on a highway the City Engineer frequently has to prepare so-called "Accident Plans." These

are prepared on a large scale, such as 1 inch = 4 feet, 1 inch = 8 feet and 1 inch = 10 feet; the two former scales are convenient for use by the layman who is familiar only with the use of the ordinary scale divided into inches and eighths. These plans should be shaded and colored so as to show very clearly the physical features which are claimed to have caused or contributed to the accident. They are often used as wall maps to be viewed by a jury and care should be taken that they do not contain unnecessary details. The measurements made for this sort of a map should be accurately taken and carefully recorded, especial attention being paid to keeping the note-book in neat form as it is often introduced as evidence as well as the plan.

309. MISCELLANEOUS CITY SURVEYING PROBLEMS.— The park systems of a city are laid out by the City Engineer. The playground should be divided in a logical manner, with the base ball diamond, tennis courts and other recreation spaces so oriented with reference to the sunlight as to give the players as little trouble as possible from that source.*

Public Service corporations are required in most municipalities to file with the City Engineer, for his approval, plans of the location of their pipes, underground conduits and poles. It is necessary for him to prepare maps showing the location of sewers, water pipes and other underground structures so as to pass intelligently upon the plans presented by the public service corporation. It is conceded to be good practice so far as possible to locate trolley and other poles with their faces 10 inches back of the face of curbstones and opposite a boundary between properties.

The elimination of grade crossings in municipalities brings in a special line of work in which the street lines in those vicinities must be accurately defined. These problems often involve changes of grade of the street, revisions of drainage systems, and the taking of private property on either side of the street for slope easements.

Surveys by water departments of the ponds, reservoirs,

* See Art. 21, Sec. 3, American Civil Engineers' Pocket Book for dimensions of ball grounds, tennis courts, croquet grounds and other layouts for outdoor sports.

conduits and pipe lines of the water department are other branches of city surveying; as well as the survey of lands for takings after they have been condemned by the city for municipal purposes or for sale by the city.* The sewers, brooks and conduits within the city limits are usually under the care of the City Engineer.† Surveys frequently have to be made for bridging these brooks and revisions of their lines and grades.

311. SETTING BATTER-BOARDS FOR A BUILDING. — One of the most common tasks of the surveyor is to set the batter-boards for the excavation and construction of the cellar of a new building. The dimensions of the building and the elevation at which to set it are usually obtained from the architect, although sometimes the elevation of the ground floor of the building is recorded on the plan itself. In a brick or stone building the lines to be defined are the outside neat lines of the building, and the elevation desired is usually the top of the first floor. In the case of a wooden building the line usually given is the outside line of the brick or stone underpinning and the elevation given is the top of this underpinning on which the sill of the house is to rest. Sometimes the outside line of the sill instead of the underpinning is desired. There should be a definite understanding in regard to these points before the work of staking out is begun.

Generally there is no elevation marked on the plan and the surveyor is simply told to set the top of underpinning a certain distance above the sidewalk or above the surface of some portion of the lot. If there is an elevation referred to City Datum marked on the plan, he should level from the nearest B. M. and set the batter-boards at the grade given.

The location of the building on the lot is given either by plan or by orders from the architect or owner. Not infrequently the surveyor receives the directions to place the building so that its front line is on line with the other buildings on the street and so that it will stand a certain number of feet from one of the side lines of the lot.

* See Public Water Supplies by Tourneaure and Russell, published by John Wiley & Sons, New York.

† See Sewerage, by Professor A. P. Folwell, published by John Wiley & Sons, New York.

His first work is to stake out the location of the building by accurately setting temporary stakes at all of the corners of the building, e.g., in Fig. 130, at *A*, *B*, *C*, *D*, *E*, and *F*. A stake should be set at *G* also so that the entire work can be checked by measuring the diagonals *AG* and *FB*, and *GD* and *EC*. These checks should **always** be applied where possible. Then the posts for the batter-boards are driven into the ground 3 or 4 ft. outside the line of the cellar so that they will not be disturbed when the walls are being constructed. On these posts, which are usually of 2″ × 4″ scantling, 1″ boards are nailed. These boards are set by the surveyor so that their top edges are level with the grade of the top of the underpinning or for whatever other part of the building he is giving grades. After the batter-boards are all in place they should be checked roughly by sighting across them; they should all appear at the same level. Sometimes, however, on account of the slope of the ground some of them have to be set a definite number of feet above or below grade.



FIG. 130. SETTING BATTER-BOARDS FOR A BUILDING.

Then the lines are to be marked by nails driven in the top of these batter-boards. The transit is set up on one of the corner stakes of the house at *A* (Fig. 130), for example, and a sight is taken on *F*. This line is then marked on the batter-board beyond (at *f*) and on the one near the transit (at *a*). If the batter-board is so near the transit that the telescope cannot be focused on it, then point *a* can be set within a hundredth

of a foot by eye if the surveyor will stand outside of the batter-board and sight point *a* in a line determined by point *f* and the plumb-line on the instrument. Then a sight is taken along *AB* and this line is produced both ways and nails set on the batter-boards at *h* and *j*. In a similar manner all of the lines are marked on the batters. These points should be marked with nails driven in the top edges of the batter-boards and there should be some lettering on the boards to make clear which lines have been given. It is well for the surveyor also to show these marks to the builder or inspector and have it clearly understood just what parts of the structure these lines and grades govern.

It is customary to set batters for the jogs in the building as well as for the main corners; but small bay windows of dwellings are not usually staked out, but are constructed from wooden patterns made and set by the builder.

As soon as the excavation is begun the corner stakes are dug out and the building lines are then obtained by stretching lines between the nails in the opposite batter-boards. These batter-boards are preserved until the sills or first floor are in place, when they may be removed.

312. CITY PLANS AND RECORDS. — Every city has a large number of valuable plans and records in its possession. Too frequently these are not kept with anything like the care consistent with the amount of money that has been expended to obtain them. For suggestions regarding the filing and indexing of plans and records see Arts. 518–22, pp. 479–81.

RECTANGULAR COÖRDINATE SYSTEM OF SURVEYING CITIES.

313. GENERAL DESCRIPTION. — It is customary to disregard the effect of curvature of the earth in the survey of a city on account of its limited extent, and to use a system of rectangular coördinates based upon plane surveying. In a coördinate system two arbitrary lines are chosen for coördinate axes, one usually coinciding with some meridian and the other at right angles to it. All points in the city are located by distances from these two axes, these distances being known as X's and Y's, or sometimes

as latitudes and longitudes. The axes are sometimes chosen entirely outside the area to be surveyed, and where they meet (their *origin*) is designated as (0, 0.). Sometimes they are taken through some conspicuous point, such as the tower of the city hall, and are considered as being certain distances from the zero lines as (10 000, 10 000). By either of these arrangements negative values for coördinates are avoided. The coördinates are usually considered positive toward the north and the east, in accordance with the custom of analytic geometry, as is the case in ordinary land surveying. The convergence of the meridians is neglected and all points having the same X coördinate therefore lie on a straight line parallel to the initial meridian and are **not** all on the same true meridian line.

In the survey of the city of Baltimore (Fig. 131) the origin of coördinates was taken through the Washington Monument in the central part of the city, and the map divided into squares 1000 feet on a side. Each square mile is shown on a separate page of the atlas of the city and these squares are designated by their number north or south, and east or west of the origin, as 1S2W, 3N4E, etc. Any point is designated by the distance in feet north or south, and east or west, as (1000 E, 2000 N).

One of the chief advantages of any coördinate system is that if any point is lost it can be exactly replaced by means of the known coördinates. This would be especially true in case a large section of the city were destroyed by fire.

314. TRIANGULATION SCHEME.— The principal points of the survey are usually located by a system of *triangulation.* Prominent points are selected in such positions that the lines joining them form well shaped triangles, i.e., preferably triangles which are not far from equilateral. These points may be signals on tops of hills, church spires, and the like. If the cupola of the city hall, or some such point is chosen as the origin of coördinates it should also be one of the triangulation points. Points which can be occupied by an instrument are in general to be preferred. Such points as steeples or flag poles are definite enough, but where no definite object exists on which to sight the instrument signals are erected for this purpose. Such a signal usually consists of a pole placed carefully over the exact



FIG. 131. TRIANGULATION SCHEME FOR SURVEY OF

(Printed by permission of Major Joseph W. Shirley, Chief Engineer of the Topo

point and braced in a vertical position by other poles forming a tripod. (See Volume II, Chapter I.)

The system of triangles should cover the entire area but should not contain more lines than are necessary to establish a sufficient number of points to control the subsequent work of the survey.

315. **MEASUREMENT OF BASE-LINE.**— At least one line in the system must be chosen where its length can be very accurately measured; this is called the *base-line*. The lengths of all the other lines are to be computed from this line by means of the measured angles, hence it will be seen how important it is that this line should be measured with great accuracy, and that it should also form well shaped triangles with the connecting triangulation stations.

It should be chosen if possible in some level spot where there are no serious obstacles to the measurement. It is sometimes an advantage to have the ends of the base-line slightly elevated above the general level. The base should be measured with a steel tape the exact length of which is known. The tension should be kept constant by means of a spring balance, and the temperature carefully taken. If the work is done on a cloudy or rainy day the thermometer readings will represent the temperature of the tape much more nearly than when taken in sunshine. The points should be lined in with a transit and the tape held horizontal, or, if the measurements are taken directly from stake to stake, the slope should be determined, by means of a leveling instrument. There should be at least two independent measurements of the line.

316. **MEASUREMENT OF ANGLES.** — If possible all of the angles of each triangle should be measured by repetition. An "inverting" instrument reading to 20″ or to 10″ is to be preferred for this work. The angles are repeated at least six times with the telescope direct and the same number of times with the telescope inverted. Several of these sets of readings are made beginning each time with a different initial setting on the circle. For example, if the first setting was at 0° and four sets are to be taken the second would begin with a setting of 45°, and so on. In each case both verniers should be read and the mean

of the two taken. Sometimes the direction of the measurement is changed during the set, the first six repetitions being taken from left to right, and the second six from right to left. In this work it is important that the instrument should be carefully centered over the point, and that the signals are also carefully centered. It is also important to keep the instrument carefully leveled, especially if there is great difference in the angular elevation of the points sighted.

317. Adjustment of the Angles. — The test of the accuracy of the angle measurements is in the "closure" of the triangles. In good work the sum of the angles of a triangle should not differ from 180° by more than about 5 seconds, under fair conditions. After the angles have been measured the errors in the closure of the triangles should be distributed equally among the angles, thus making the sum of the angles in each triangle exactly equal to 180°. If the best results are desired all of the discrepancies due to errors of measurement can be removed by adjusting the system in accordance with the "Method of Least Squares." In ordinary work, however, where the errors have been kept small, the expense of such a computation is not warranted. After all of the angles have been corrected the sides of the triangles may be computed.

318. AZIMUTH. — If the coördinate lines are to run N and S and E and W it is necessary to know the astronomical azimuth of at least one line of the triangulation system before the coördinates can be computed. This may be determined by observation on Polaris as described in Chapter VII, or, in case there are other triangulation points already established in the vicinity, the new system can be connected with them and the azimuths computed from one of these lines. Azimuths are reckoned in this work from lines parallel to the initial meridian, from the south point right-handed, i.e., in the direction S-W-N-E, and from 0° to 360°. When the azimuth of one line is known all of the others may be computed. With the azimuth and length of each line known the difference of the latitudes and departures, i.e., the difference of the Xs and Ys of the ends can be found, and with the coördinates of some one

point given, or assumed, the coördinates of all of the other points can be computed as explained in Art. 445, p. 421.

319. SECONDARY AND TERTIARY TRIANGULATION. — After the principal triangles have been completed, forming a system of control, smaller triangles are selected, locating a system of points of lesser importance so far as the survey is concerned. This is called the *secondary system.* Sometimes a third (*or tertiary*) system is introduced, the triangles being still smaller. The tertiary triangles are the ones that would be used for locating the city boundaries, street corners, and important monuments.

It frequently happens that, owing to the large number of angle measurements and the consequent accumulated error, the lengths of the sides of the small triangles become much less accurate than they would be if measured directly; and since many of these lines naturally lie in places where the distance can easily be measured, this measurement should be made as a check, in which case this line becomes a *secondary base-line.* It is a good plan to introduce these measurements frequently, where it can be conveniently done without great expense, in order to prevent the errors of the survey from accumulating unnecessarily.

320. TRAVERSES. — After all of the triangulation is completed the system is extended by running traverses with the transit and tape, from one known point to another. The triangulation points are regarded as fixed and the errors of closure of the traverses are assumed to be entirely in the traverse surveys, the traverses being made to fit in exactly between the triangulation points.

All street lines, or parallel offset lines, are connected with the coördinate system so that the azimuth of every street line in the city may be known, and the coördinates of all important points, such as street corners and lot corners, are computed.

321. METHOD OF LOCATING PROPERTY LINES AND BUILDINGS. — Since the coördinates of the property corners are to be computed it is advisable to locate them by angle and distance from the transit points, for with these data the calculation of the coördinates is simple. The buildings are located from the transit line by methods explained in Chapter VI.

CHAPTER XI.

TOPOGRAPHICAL SURVEYING.

322. In making a survey for a topographical map the methods used will depend upon the purpose for which the map is made and the degree of accuracy which is required. But whatever the purpose of the map may be it is not necessary to locate points in the field more accurately than they can be represented on paper, whereas in surveying for an area measurements are made with far greater precision than would be necessary for the purpose of plotting.

While most of the details of topographical surveying can be filled in more economically by the use of the *transit* and *stadia* or by the *plane table* it is thought best to describe here only the more elementary methods, and to reserve the complete treatment of the stadia and plane table for an advanced work.

323. TRIANGULATION FOR CONTROL.— In all cases where the area is large it will be advisable to use a system of triangulation to control the survey, as this is the cheapest method of accurately determining the relative position of a few points which are a considerable distance apart. The details of this triangulation work have already been described under the head of "Rectangular Co-ordinate System of Surveying Cities," Chapter X. One line of the survey, the base-line, must be carefully measured. The precision with which the angles of all the triangles must be measured depends upon the use to be made of the map. After the principal triangulation points have been established their positions are plotted on the map. This may be done conveniently by the method of rectangular coördinates described in Art. 313, p. 291. The extension of the system to smaller systems of triangles, called *secondary* and *tertiary*, may be made if necessary. After the triangulation system has been extended far

enough to furnish a sufficient number of points for controlling the accuracy of the map, traverses may be run wherever convenient or necessary for locating topographic details. In all cases the traverses should be connected with the triangulation points at frequent intervals in order that the relative positions of all points may be kept as nearly correct as possible. Where a high degree of accuracy is necessary these traverses should be run with a transit and tape; if, however, errors of a foot or two would not be appreciable on the map it will be sufficiently accurate to use the stadia method of measuring the distances and thus save time. (See Volume II, Chapters I, IV, and V.)

324. Location of Points from the Transit Line.— Where a tape is used for measuring the distances, such objects as fences, walls, and buildings may be located as described in Chapter VI, but it will not be necessary to make the measurements with as great precision. Fig. 132 is a sample page of notes of a topographical survey where the transit and tape were used. On city plans, which are frequently drawn to a scale of 40 feet to an inch, a fraction of a foot can easily be shown. On a topographic map the scale is often such that an error of a fraction of a foot becomes insignificant in the side measurements from the transit line, where such errors cannot accumulate. In some cases it may be sufficient to obtain the distances by pacing, and the angles or directions by means of a pocket compass. Locations may frequently be checked by noting where range lines intersect the transit line. In making a series of measurements it is well to take each measurement with a little more precision than is actually needed for plotting, in order to be sure that the accumulated error does not become too large.

In taking measurements the surveyor should constantly keep in mind how the notes can be plotted; this will often prevent the omission of necessary measurements. No matter whether an accurate or only a rough survey is desired **check measurements** should be taken on all important lines.

325. Contour Lines.—There are two general systems of representing on paper the form of the surface of the ground.



FIG. 132. FIELD NOTES OF A PORTION OF TOPOGRAPHICAL SURVEY WITH TRANSIT AND TAPE.

In one of these systems (Fig. 133) slopes are represented by *hachure lines,* i.e., lines which always run in the direction of the steepest slope of the ground. In the other system (Fig. 134) *contour lines,* lines joining points of equal elevation, are used. In the latter system elevations may be read directly from the map, and for this reason it is much more used by surveyors.



FIG. 133. HACHURE LINES.

FIG. 134. CONTOUR LINES.

A contour line is the intersection of a level surface with the surface of the ground. A clearer conception of a contour line may be obtained from the following. Imagine a valley, or depression in the surface of the ground, partly filled with water. The shore line of this body of water will then be a contour line, since it is the intersection of a level surface with the surface of the ground. If the water stands at an elevation of 50 feet the shore line is the 50-ft. contour. If the surface of the water were raised 5 feet the new shore line would then be the 55-ft. contour. Contour lines if extended far enough will therefore be closed curves, and all of the points on any one contour will have the same elevation above the datum. It is customary to take contours a whole number of feet above the datum, spacing them in regard to height, so as to make the *contour intervals* equal, e.g., a contour may be taken at every 5 feet or every 10 feet of elevation. Since the contours are equidistant in a vertical direction their distance apart in a horizontal direction shows the steepness of the slope.

Fig. 135 illustrates contour maps of simple solids.



FIG. 135. CONTOUR MAPS OF SIMPLE SOLIDS.

326. Characteristics of Contours. — The chief characteristics of contours are illustrated in Fig. 136, and may be summed up as follows.

1. All points on any one contour have the same elevation, as at *A*.

2. Every contour closes on itself, either within or beyond the limits of the map. In the latter case the contour line will not end within the limits of the map but will run to the edge of the map, as at *B*.

3. A contour which closes within the limits of the map indicates either a summit or a depression. In depressions there will usually be found a pond or a lake; but where there is no water the contours are usually marked in some way to indicate a depression, as at *C*.

4. Contours can never cross each other except where there is an overhanging cliff, in which case there must be two intersections, as at *D*. Such cases as this seldom occur.

5. On a uniform slope contours are spaced equally, as at *E*.

6. On a plane surface they are straight and parallel to each other, as at *F*.

7. In crossing a valley the contours run up the valley on one side and, turning at the stream, run back on the other side, as at *G*. Since the contours are always at right angles to the lines of steepest slope they are at right angles to the thread of the stream at the point of crossing.

8. Contours cross the ridge lines (watersheds) at right angles, as at *H*.



FIG. 136. ILLUSTRATING CHARACTERISTICS OF CONTOURS.

Fig. 137 shows a contour across an ordinary city street with sidewalks and curbstones, the street being located on a steep grade. In order to trace out the position of a contour it is necessary to keep in mind that it is a line all points on which are at the same elevation. It will be noticed that the contour from A to B crosses the sidewalk in a straight line but not perpendicular to the street line because the sidewalk is sloped toward the gutter. Turning at B it runs straight along the face of the curbstone until it strikes the gutter at D, and returns on the other side of the gutter along the surface of the road, the point E being where it swings around and travels back toward the other gutter. The other half of the street is similar. If the center of the road is at the same elevation as the top of the curb opposite, then E will be opposite B. This illustrates how contours run around valleys (gutters) and ridges (crown of street).



FIG. 137. CONTOUR CROSSING A STREET.

If the side of the street to the right (HF) were at a lower elevation than the left side then the contour at the point where it crosses the gutter, F, would be farther up the road from E, i.e., the contour would be unsymmetrical, EF being longer than DE.

327. RELATION BETWEEN CONTOUR MAP AND PROFILE. — If a line is drawn across a contour map the profile of the surface along that line may be constructed, since the points where the contours are cut by the line are points of known elevation and the horizontal distances between these points can be scaled or projected from the map. The profile shown in Fig. 138 is constructed by first drawing, as a basis for the profile, equidistant lines, corresponding to the contour interval, and parallel to AB. From the points where AB cuts the contours lines are projected

to the corresponding line on the profile. Conversely, if the profiles of a sufficient number of lines on the map are given it is possible to plot these lines on the map, mark the elevations, and from these points to sketch the contours as described in Art. 331, p. 312.



FIG. 138. PROFILE CONSTRUCTED FROM A CONTOUR MAP.

328. RELATION BETWEEN CONTOUR MAP AND SIDE ELEVATION OR PROJECTION. — A photograph of a landscape represents approximately a side elevation of the country. To

construct such a projection from a contour map (Fig. 139), lines



FIG. 139. SIDE ELEVATION CONSTRUCTED FROM A CONTOUR MAP.

are drawn perpendicular to AB, the plane of projection, and tangent to the contours. These tangent points show the limits between the visible and invisible portions of the landscape, the observer being assumed to stand on the line AB and to look in a direction perpendicular to AB.

329. DRAINAGE AREAS. — The drainage area that supplies a stream or pond is limited by the *divide line*, which is a line drawn on the ridges surrounding a depression as indicated by the dotted line on Fig. 140. Since the perpendicular to the contour at any point is the direction of steepest slope the direction in which water will flow at any point can be determined at once by examining the contours. On the ridge there is a line (its summit) on one side of which water will flow down one of the slopes and on the other side of which it will flow down the other slope. This line is the divide line or *watershed line*.

If a dam were built as shown in Fig. 140, its elevation being 960 ft., the area actually flooded by the water at full height of dam is the area included within the 960-ft. contour, which is indicated by the shaded section. The drainage area for the portion of the stream above the dam is the area included within the heavy dotted line, which follows the line of the divide.

330. SKETCHING CONTOURS FROM STREAMS AND SUMMITS. — The present topography of some parts of the country is due almost entirely to erosion by streams. Consequently the position and fall of the streams give more information regarding the position of the contours than any other topographic features. If a definite position of the contours is desired it will be necessary to obtain the elevation of a few governing points on the ridges as well as the location and elevation of the streams, as shown in Fig. 141. (See Volume II, Chapter VII.)

In sketching in contours from these data it should be borne in mind that the contours cross the stream at right angles to its thread and that they curve around from the hill on either side so as to represent the valley of the stream. The contours are farther apart at the top and bottom of the slope of an eroded hill than near the middle, because in these portions the slope is somewhat flatter. A stream is usually steeper near its source than in the lower portion and therefore the contours are closer together near the source. This is true of most cases but the shape of the contours in any particular case will depend upon the geological formation. Fig. 142 represents the same country as Fig. 141 but with the contours sketched on it, following out the general suggestions which have just been mentioned.



FIG. 140. ILLUSTRATING FLOODED AREA AND DRAINAGE AREA.



FIG. 141. MAP SHOWING THE LOCATION AND ELEVATION OF STREAMS AND SUMMITS.



FIG. 142. CONTOURS SKETCHED FROM THE DATA GIVEN IN THE MAP ABOVE.

331. SKETCHING CONTOURS FROM KNOWN ELEVATIONS. — A portion of the country can be cross-sectioned as described in Art. 253, p. 240, or profiles can be run on any desired lines as explained in Art. 251, p. 237. From these known elevations contours can be sketched by interpolation. This is usually done by estimation and the principle involved is the same whether the elevations were obtained by cross-sectioning or by profiles.

Fig. 143 illustrates how contours can be sketched from cross-



FIG. 143. CONTOUR SKETCHED FOR CROSS-SECTION NOTES.

section notes. The points at which elevations are taken in the field should be so chosen that the slope of the ground is practically uniform between any two adjacent points. Then by simple interpolation the contours may be accurately sketched. This interpolation may be done by geometric construction, but for most topographic work it is accurate enough to interpolate by eye.

332. MISTAKES IN SKETCHING CONTOURS. — Fig. 144 shows several examples of impossible and incorrectly sketched contours; the streams are assumed to be correctly located. The numbers on the figure refer to the tabulation made in Art. 326, p. 304, and will assist in detecting the type of error present.



FIG. 144. CONTOURS INCORRECTLY SKETCHED.

333. LOCATING CONTOURS. — Contours are often most economically located by means of the *transit and stadia* or by an instrument called the *plane table*. In this chapter, however, only those methods will be considered which call for the use of the transit and tape. A complete discussion of the Stadia Method will be found in Chapter VII of this volume and in Chapter IV of Volume II. The Plane-Table Method is treated in Chapter V of Volume II.

334. Locating Contours by Cross-Sections. — A very common as well as expensive method of locating contours is that of taking cross-sections. Elevations on the surface of the ground are usually taken to tenths of a foot. From these elevations the contours may be sketched by interpolating between these known elevations as explained in Art. 331. The accuracy may be increased by taking a larger number of intermediate points. The size of the squares used should depend upon the roughness of the surface.

335. Locating Contours by Profiles. — In some cases where the ground is fairly smooth it is sufficient to take a few profiles on known lines, not necessarily at right angles to each other. These lines are stationed and elevations are taken at every full station and at the points of marked change in slope. From these data the contours are sketched on the map by interpolation as described in Art. 331.

336. Locating Points on the Contours. — Where the contour interval is small, say one or two feet, and the topography is to be determined with considerable accuracy, it is advisable to find, in the field, points actually on the contours and thus avoid the errors of interpolation. The rodman moves up or down the slope until the rod-reading indicates that the foot of the rod is on a contour. The position of the rod may then be located by an angle and a distance from some known line, the distance being taken with a tape.

337. Locating Contours by the Hand Level. — A more rapid but less accurate way of putting in contours is by means of the hand level. The work is done by making profiles of lines whose positions on the map are known. A point on some contour is found in the following manner.

The first step to take is to measure to the nearest tenth of a foot the distance from the ground to the eye of the leveler, which may be, say, 5.4 ft. If the B. M. is at elevation 143.43 and it is desired to locate a point on the 140-ft. contour, the rodman holds the rod (or a tape) on the B. M. while the leveler attempts to place himself on the 140-ft. contour. When he is on the 140-ft. contour the elevation of his eye (H.I.) is 145.4

and the rod-reading at the B. M. must be 145.4 — 143.43 = 1.97, or 2.0 to the nearest tenth of a foot. The leveler therefore travels along the line on which the point is to be located until he reads 1.97 on the rod. His feet are then on the 140-ft. contour, the position of which is located from some known point on the line. Sometimes this is done by measurement and sometimes by pacing. A point on the 145-ft. contour could have been located first by applying the same principle, but if the 140-ft. contour is established it is very easy to locate a point on the 145-ft. contour as follows. The distance from the leveler's feet to his eye being 5.4 ft., if he stands on the 140-ft. contour and reads 0.4 ft. on the rod, the bottom of the rod must be on the 145-ft. contour. By trial then the point is found where the rod reads 0.4 ft.* Then the leveler walks up the hill and, standing on the point just found, places the rodman on the next higher contour by the same process.

In working down the hill to locate the 135-ft. contour, if the leveler is standing on the 140-ft. contour, the rod will be on the 135-ft. contour when it reads 10.4 ft. Or, when the 140-ft. contour has been found by the leveler the rodman comes forward and holds the rod on this spot and the leveler backs down the hill until he reads 0.4 ft. on the rod; he is then standing on the 135-ft. contour. Some surveyors prefer to cut a stick just 5 ft. long and hold the hand level on the top of it in taking sights.

The points thus found at regular contour elevations are then plotted on the corresponding lines and the contours sketched by joining points of equal elevation. Where the lines which are profiled are far apart or where the country is very rough it is frequently necessary to obtain the correct position of the contours, to locate extra points on them between these profiled lines. The extra points are located by right-angle offsets from the lines. Most of this work is plotted in the field upon paper ruled in small squares to facilitate sketching. Where practicable it is always well to sketch the contours in the field rather than in the office.

* For very rough work sometimes the rod is not used, the leveler simply estimating where the rod-reading will come on the rodman's body and placing him so that his feet will be on the proper contour.

338. LOCATION OF STREAMS AND SHORE LINES. — Streams or shore lines of ponds may be very rapidly located by stadia measurements. If the shore lines are to be located by tape measurements, however, a convenient way is to run a transit line aproximately parallel to the general direction of the shore line, and to take perpendicular offsets at regular intervals and at all points where there is a marked change in the direction of the shore line, as was done in the notes in Fig. 53, p. 104.

339. CONTOUR PROBLEMS. — There are many surveying problems involving earthwork which can be worked out approximately by use of a contour map. As a rule the smaller the contour interval, the more accurate will be the result of such work. Contour studies occur in a variety of problems, so numerous that it would be useless to attempt to cover the subject fully. Three typical problems, however, are illustrated and explained; and these contain the essential principles applicable to practically all contour studies.

340. EXAMPLE 1. — (Fig. 145.) Given a contour map, the surface being represented by contours shown by full lines, a plane (extended indefinitely) is passed through the straight lines *AB* and *CD*, which are level and parallel, *AB* being at elevation 12.5 and *CD* being at elevation 40. It is required to find where this plane intersects the surface, and to shade the portion which is above the plane.

Since the proposed surface is a plane, contours on it will be parallel to *AB* and *CD*. The elevations of *AB* and *CD* being known, other contours, such as *ef* and *gh*, can be interpolated between *AB* and *CD*. Their interval is made 5 ft. the same as the contour interval for the original surface. Evidently the point where any of these parallel lines crosses an original contour of the same elevation, as *j*, *k*, *l*, *m*, or *n*, is a point on the intersection of the plane with the surface. Joining these points gives the line of intersection of the plane with the original surface, which is indicated by the heavy full line on the figure. Such points as *q*, *s*, or *t* are determined by interpolation. Intermediate contours are drawn at one-foot intervals between the original surface contours; corresponding lines are interpolated between the straight contours which show the plane; additional

intersections obtained, and in this way the point p is determined. Again it will be seen that point t, with reference to the parallel straight contours, is at about 18.5; with reference to the original



FIG. 145.

contours, it will be seen that wt is about three-tenths of wr, the distance between contours, and this makes the elevation of point t equal to 18.5.

341. EXAMPLE 2. — (Fig. 146.) Given a contour map which includes a road, and on which the original contours are represented by full lines. It is desired that all of the road between A and B shall be visible from the ground at point C. Sketch on the map and shade the portions which will have to be cut down to fulfill this requirement.

The general method of solving this problem is to sketch a new set of contours on the map, which will represent a uniform

slope from C to the nearer edge of the road. Everything that is above the surface represented by these new contours must be cut away.

First draw lines, such as Ca, Cb, and Cc, the points a, b, and c being points on the upper side of the road between which it may be assumed that the slope is uniform (Art. 331, p. 312). Along these lines interpolate points which will lie on the uniform slope from C to the road and also on the regular 5 ft. intervals which correspond to the contours. For example along the line Ca



FIG. 146.

from the summit which is at elevation 89 to the road at a which is at elevation 55, there is a drop of 34 ft., or a little less than 7 contour intervals. Points c, f, g, h, etc. are therefore plotted so as to divide Ca as follows: ca, cf, etc., are each $\frac{5}{34}$ of AC, and the upper division is $\frac{4}{34}$ of AC. Similarly points i, j, k, etc., are plotted along the line Cb, but the point b, being at elevation 56, is plotted so that the distance ib is four-fifths of the other distances ij, jk, etc. When these points have been plotted on all of the necessary diagonal lines, the contours representing a uniform slope from C to the road are sketched on the map as shown by the dotted lines on the figure. The points, such as m, n, or r, where the new contours cut the old contours of equal elevation, are points of "no cut and no fill." A line connecting these

points encloses portions of either cut or fill. The shaded portions of the figure, where the new contours are nearer C than the corresponding old ones, represent the portions where it will be necessary to excavate to the surface represented by the dotted contours. In the central portion of the figure, from point c to p, the road can already be seen.

342. EXAMPLE 3. — (Fig. 147.) Given a contour map on which are shown the two side lines of a road, the contours being represented by full lines. The road is to be built on a 4% down grade starting at A at elevation 55. Scale 1 inch = 150



FIG. 147.

feet. Side slopes of road to be 1½ horizontal to 1 vertical. It is desired to sketch the new contours on the slopes of the road, to sketch on the map the top and foot of slopes, and to designate the portion in embankment and the portion in excavation.

First, the new contours which are to cross the road are plotted at *ab*, *cd*, *ef*, *gh*. These will be 125 ft. apart, as a 4 % grade falls 5 ft. in a distance of 125 ft. If the road is assumed to be level on top, then these lines will cross the road at right angles to its general direction as shown in the figure. From points *a* and *b*, on either edge of the road, the new contour

lines will follow along the slope, e.g., the line *ao* represents the new 50 ft. contour. Where this contour *ao* passes point *c* it is just 5 ft. above the road. Since the slope of the cut is $1\frac{1}{2}$ to 1, then the distance out from *c* must be $1\frac{1}{2} \times 5 = 7.5$ ft.; opposite *e* it is 10 ft. above the road and similarly the distance out from *e* must be 15 ft. Where this new 50 ft. contour meets the old



FIG. 147.

50 ft. contour at *o*, is a point at the top of the slope. Similarly all of the new contour lines, which are represented on the figure by dash lines are plotted and their intersections with the corresponding contours of the original surface give points of "no cut" or "no fill," or top of slope (in excavated portions) and foot of slope (in embankment portions). These lines are shown in the figure by heavy dotted lines. Where this heavy dotted line crosses the road it marks a "no cut" and "no fill" line, i.e., the road bed cuts the surface of the ground.

CHAPTER XII.

MINE SURVEYING.

343. General Remarks. — In this chapter the usual limitations and difficulties met with in surveying a mine are pointed out and some of the instruments and common methods described. A brief description is also given of the methods of establishing the boundaries of mining claims in the United States.

Mine surveys are made for the purpose of determining the relation of mine workings to the boundaries of the property, obtaining data from which to establish directions for proceeding with the workings, determining the amount of material taken from the mine and the probable amount of available ore that can be worked, obtaining data from which graphical representation of mine workings may be made, and aiding in efficient operation of the mine.

344. Definitions of Mining Terms.—The following terms are in common use in mine surveying.

Adit. An approximately horizontal underground passageway running from the surface into the mine workings and used for drainage and ventilation.

Apex. The portion of the surface of the undisturbed rock formation which is included between the walls or sides of the mineral deposit.

Bed. A stratum in the earth's crust which has been formed or deposited in an approximately horizontal layer.

Back. Top of a passageway (same as roof).

Chute. A narrow, inclined passage used for drawing off broken ore from a stope or raise.

Collar. Timbers around top of shaft.

Compartment. One of the smaller passageways of a large shaft divided by timber partitions. Fig. 153, p. 336, is the plan of a three compartment shaft.

Connection. A passageway which is driven from one accessible part of the mine to another.

Cross-cut. A horizontal passageway across or approximately at right angles to the strike.

Dip. The inclination of any rock plane to the horizon.

Drift. A horizontal passageway following the vein.

Fault. A fracture in the earth's crust along which slipping or shearing has occurred.

Floor. The bottom of the passageway or of a seam or bed.

Heading. Any preliminary passageway driven to explore the mine or to facilitate the future operations.

Heave. The distance between the two parts of the same vein which is divided by a fault, measured along the strike of the fault.

Levels. Horizontal passageways run at different levels along the deposit or adjacent to it for working the mine.

Manhole. A small passage from one level into the next level above or below, or into stopes.

Mill-hole. A passage between a stope and a level through which the ore is conveyed.

Ore Shoot. A rich aggregation of ore within a vein.

Outcrop. That portion of the vein which is exposed on the surface of the ground.

Prop. A piece of timber which prevents any rock in the roof from falling, sometimes called a post.

Raise. A passage driven steeply upward from any portion of the mine.

Roof. The top of a passageway or of a seam or bed.

Room. A place other than a passageway from which material has been extracted. The term usually refers to bed deposits.

Seam. A bed of mineral or a small vein.

Stopes. Rooms formed by the excavation of ore above or below a level, sometimes filled with broken ore or rock.

Strike. The direction (bearing) of a horizontal line in the plane of a deposit. The strike is always at right angles to the dip.

Stull. A piece of timber wedged in crosswise between the side walls of a passageway.

Throw. The vertical distance between the planes representing two parts of the same vein which is divided by a fault. The term is used only in regard to nearly horizontal deposits.

Tunnel. A horizontal working passageway open at both ends.

Vein. (Also *lode*, *ledge*, *lead*, etc.) A mineral body of the flattened shape.

Wall. The rock on each side of the mineral body. The upper wall is called the "hanging wall," and the lower the "foot wall."

Winze. A subsidiary shaft not starting from the surface.

MINING INSTRUMENTS.

Owing to the confined nature and steep inclination of many of the passages in a mine through which the survey lines have to be carried, it is necessary to use specially constructed instruments.

345. MINING TRANSITS. — In modern mining all of the accurate angle measurements are taken with a transit, several forms of which are designed for this purpose. The essential features are lightness and adaptability for measuring accurate azimuths of nearly vertical or of very short sights. If the telescope is of low power the illumination of the field is better and its focal length is usually shorter, both of which are conveniences in mine surveying. The transit should be provided with a full vertical circle which should be enclosed in a metal case to protect the graduations from dripping water which commonly exists in mines. In sighting highly inclined lines a striding level will be found useful, but the horizontal axis of the transit must be so designed that the striding level will fit upon it.

With an ordinary transit one cannot take a downward sight more steeply inclined than 55° or 60° to the horizon. Various attachments have been devised for sighting more steeply inclined lines, the object being to permit a sight to be taken over the edge of the horizontal circle of the instrument. This is usually accomplished by attaching an auxiliary telescope to the side or to the top of the main telescope of the engineers' transit, so that the instrument will afford all the advantages of the ordinary transit and will also make it possible to sight even down a vertical shaft.



FIG. 148. MINING TRANSIT WITH INTERCHANGEABLE SIDE AND TOP TELESCOPE.
(From photographs loaned by C. L. Berger & Sons, by permission.)

346. Eccentric Telescopes. — Some mining transits are constructed so that an auxiliary telescope may be attached to an end extension of the horizontal axis, such an instrument being known as a *side telescope transit*. In another type of transit, called the *top telescope transit*, the auxiliary telescope is mounted above the main telescope. The distance between the centers of the main and auxiliary telescopes is called the

eccentricity. Some instruments (Fig. 148) are made with an interchangeable telescope which can be attached at either the top or the side of the main telescope. In such an instrument no correction for eccentricity of the auxiliary telescope is necessary, provided the horizontal angles are measured with the top telescope and the vertical angles are measured with the side telescope.

In comparing the merits of the various forms of attachment it must be remembered that the object to be accomplished is to transfer the meridian accurately from one station to another, these stations sometimes being close together in plan and distant in elevation.

The side telescope has the merit of being easy to operate. Since this telescope is detachable the transit need not be encumbered with it when the main telescope can be used, which is the case in most of the surveying required in mines. When this attachment is used the effect of eccentricity in the measured azimuths is eliminated by the reversal method described below.

When a top telescope is attached the main telescope cannot be inverted. With such a transit correction for eccentricity must be applied to all altitude readings.

When it is not important to double the angle azimuths may be carried more rapidly by means of the top telescope than with the side telescope, but it is good practice to double all of the angles of a traverse.

The interchangeable side and top telescope is in common use. Some surveyors prefer to use the side telescope only, the vertical angles being measured directly and the horizontal angles being measured by repeating the angles and reversing the telescope at the same time, so that if four angles are read, for example, the result of the fourth reading divided by 4 will give the angle whose vertex is at the point over which the instrument is set. If the instrument is used as just described then the top telescope is used only for lining in points along the shaft. Other surveyors prefer to use the top telescope for all work, in which case the azimuths are measured directly and only the vertical angles require correction.

347. Correction for Eccentricity. — If the side telescope is used in measuring a single azimuth or if the top telescope is used for measuring vertical angles, a correction for eccentricity must be made. The correction in either case may be made by regarding the line between the centers of the eccentric and main telescopes as one of the lines of the traverse. Instead of making this eccentric distance a line of the traverse, it may sometimes be more convenient to eliminate it by sighting the auxiliary telescope at an auxiliary point which bears the same relation to the station point as the center of the auxiliary telescope bears to the center of the main telescope. It is also possible, when the horizontal distance to the point sighted is known, to compute a correction to apply to the angle measured by the auxiliary telescope which will make it equal to the angle which would have been measured had the main telescope been used.



FIG. 149.

348. Vertical Angle Correction for Eccentricity of Top Telescope.— In Fig. 149 the vertical angle V has been taken by means of the top telescope to point C in the bottom of a shaft. The distance AC was measured, A being the horizontal axis of the main telescope. The distances desired are DC and AD. HB and $H'A$ are both horizontal,

$$\text{then } V' = V - v$$

where V is the angle measured by the top telescope, v is the angular correction for eccentricity, and V' is the corrected angle.

$$\text{Since } \sin v = \frac{AB}{AC} = \frac{\text{Distance between telescopes}}{\text{Distance measured}}$$

we may easily construct a table for any instrument giving the values of v for different measured distances.

The vertical and horizontal components of AC are then

$$AD = AC \sin V' = AC \sin (V - v)$$

and

$$DC = AC \cos V' = AC \cos (V - v)$$

Had the measured distance been BC instead of AC then

$$AD = BC \sin V - AB \cos V$$

and

$$DC = CF + FD = BC \cos V + AB \sin V$$

349. Horizontal Angle Correction for Eccentricity of Side Telescope. — In Fig. 150, the center of the small circle represents the center of the instrument, and the line of sight of the eccentric telescope is tangent to this circle. Angle H has been measured with the side telescope and H' is the angle which would have been obtained had it been measured with the main telescope. The difference in direction between the lines from the F.S. to the side telescope and to the main telescope is the angle α, and the difference in direction between the lines from the B.S. to the side and to the main telescope is the angle β. By the construction indicated in the figure the angle formed between the two dash lines is equal to the angle measured with the side telescope. The required true angle H' therefore is equal to $H - \beta + \alpha$. Since the usual practice is to measure all horizontal angles as azimuths in a clockwise direction, the true horizontal angle will equal the angle measured with the side telescope minus the correction angle for the B.S. plus the correction angle for the F.S. These correction angles α and β obviously balance when the horizontal distances from the center of the instrument to the F.S. and the B.S. are equal.



FIG. 150.

The cotangent of the correction angle for either case equals the horizontal distance from the center of the instrument to

the point sighted divided by the distances between the main and side telescopes.

350. ADJUSTMENTS OF MINING TRANSITS. — It is assumed that all ordinary adjustments of the transit have been made. In addition, the adjustment of the object slide (Art. 77, p. 60) is of unusual importance, because often in mining work the azimuth has to be transferred through very short horizontal sights, or inclined sights with short horizontal component. Exceptional care must be taken to make the horizontal axis of the telescope truly horizontal and the line of sight exactly perpendicular to it.

The side telescope is generally adjusted by first making the line of sight parallel to the axis of the side telescope tube. This is done by the cross-hair adjustment and the aid of a pair of fixed wyes in which the tube is rotated; it is the same adjustment as for the level, Art. 121, p. 90. It is assumed that the instrument maker has made the optical axis parallel to the axis of the tube.

Secondly, the line of sight is made parallel to that of the main telescope. In the type of instrument shown in Fig. 148, this adjustment is made by moving the cross-hairs, but there is another somewhat common type which has a trivet placed between the auxiliary telescope and the main part of the instrument, in which case this adjustment is made by the adjusting screws on the trivet. The former type is cheaper, more rigid and less liable to get out of adjustment. To make this adjustment sight on a piece of paper upon which are drawn two vertical marks connected by a horizontal line, the distance between the marks being equal to the distance between the telescopes. The plane of the paper should be placed at right angles to the line of sight and about 200 ft. distant. The vertical cross-hair of the main telescope is sighted at one of the vertical lines by means of the clamp and tangent screw of the plates and then the vertical cross-hair of the side telescope is sighted at the other line by adjusting the vertical cross-hair of the side telescope, if the instrument is of the type shown in Fig. 148. This adjustment of the vertical cross-hair may affect the first adjustment, but its effect is usually so slight that it is negligible.

If, however, the instrument has trivet plates, this adjustment is made by means of the trivet plate adjustment screws on the side telescope.

The side telescope and main telescope are then brought into the same plane at right angles to the vertical plane as follows: The horizontal cross-hair of the main telescope is sighted at some point, preferably a distant one; then the horizontal cross-hair of the side telescope is sighted at the same point by means of the tangent screw on the side telescope.

As the adjustment of the side telescope is not direct, but made by comparison with the main telescope, which may not be in perfect adjustment, the instrument should be used in both the direct and reversed positions when accurate results are required.

The top telescope is adjusted in much the same manner as the side telescope.

351. Combined Solar Attachment and Top Telescope. — A special top telescope is sometimes made to do the duty of a solar attachment; but it is now generally admitted that better meridian determinations can be made by direct single observations with the main telescope, and the surveyor is advised not to get any such complex attachment for mining work.

352. Fittings of Mining Transits. — A mining transit should have a reflector for illuminating the cross-hairs, a diagonal or prismatic eyepiece which makes it possible to take any upward sight not exceeding about 60° above the horizon or to take sights where, because of the close proximity of walls, it is impossible to place one's eye directly behind the eyepiece, a tripod with extension legs; a plumb-bob with an interior reel for adjusting the length of plumb-bob string is a convenience.

The bracket and trivet shown in Fig. 151, although not essential, are very useful attachments, especially for work in shafts and for low set-ups of the instrument. Another form of bracket which is very convenient is one in which the ring which holds the base of the transit can be slid along horizontally on the bracket instead of being fixed at the end as in Fig. 151. This permits greater lateral movement and facilitates setting the transit over or under a point. In the

bracket shown in Fig. 151 it is necessary to attach it at the start in such a position that the center of its circular base is so near the point that the exact setting can be made entirely by the shifting head of the transit.



FIG. 151. BRACKET AND TRIVET USED WITH MINING TRANSITS.
(From the catalogue of C. L. Berger & Sons, by permission.)

353. Compasses used in Mines. — The transit has taken, to a great extent, the place of the old miner's dial in which the compass was the main feature. This is partly because, in modern mines, so much heavy machinery and often electric lights and motor cars are used that the compass needle cannot be depended upon even to its ordinary degree of accuracy, and furthermore the advantages afforded by a transit as compared with a compass are so great as to make the difference in cost of the two instruments a matter of minor importance.

Compasses are often used, however, for reconnoissance sur-

veys and sometimes also for filling in the details. They are made in many sizes and of different designs. A compass with a plain needle is preferable to one with a swinging card, since the former can be brought to rest more quickly and is more accurate by reason of the smaller amount of weight on the center bearing. One of the excellent forms of compass for details and reconnoissance work is the "Brunton pocket transit." The observer looks down on this instrument and the line of sight is reflected upward toward him by a hinged mirror so that the object and the compass box are seen simultaneously. A clinometer is attached, which is suitable either for measuring the dip of a vein or for taking inclined sights.

354. OTHER INSTRUMENTS. — The best kind of level for use in mines is a dumpy level having a low power telescope. It should be equipped with a reflector for illuminating the cross-hairs. Leveling rods for mine work are made similar to ordinary leveling rods, except that they are shorter, the 3-ft. and the 5-ft. lengths being the commonest. These rods are usually of the Philadelphia pattern, the target being employed when there is difficulty in reading the graduations directly. A good form of target for rods used in mine surveys has a slit silhouetted against an illuminated white background. This can be made by cutting a horizontal slit across half the face of the level target so that the light can be held behind it.

The objects sighted at in underground surveying must be illuminated. An ordinary plumb-bob hung in front of a white card or tracing cloth illuminated by a light held in front of and at one side of the plumb-bob makes a good signal. Even when the point is close to the instrument and the atmosphere is clear a white card held behind the plumb-bob string is of great aid to the transitman. Signals in which there is a burning light, such, for example, as a plummet lamp, are sometimes used, the sight being taken on the wick of the lamp.

The equipment should contain at least two tapes, a 50 or 100 foot steel tape graduated to hundredths, and another tape of such length that the longest slope measurements required, such as those from level to level, can be made in one measurement. Tapes 200 or 300 feet in length are suitable for this

purpose. It is frequently impracticable to hold a tape level and obtain the measurement by plumbing because it is so dark in the passages that it is impossible for one to tell when the tape is level. For this reason inclined measurements, which often require long tapes, are more common in mine surveying than in surface surveying. A short tape, however, should always be in the equipment for the purpose of measuring the fractions of a foot, because the long tapes are usually graduated only by foot-marks. The reels for all tapes used in mine surveying should be of the open form shown in the two upper right-hand tapes Fig. 2, p. 4, because tapes used in mines often become wet and dirty. A short pocket tape is useful in measuring the height of instrument, height of points and offsets.

UNDERGROUND SURVEYING.

355. TRANSFERRING A MERIDIAN INTO A MINE. — There are two general methods of transferring a meridian into a mine: first, by means of the main telescope or an auxiliary telescope on the transit, and, second, by means of plumb-lines hung in a shaft. If the mine is entered by an adit or tunnel the passage-way is usually so nearly level that the meridian can be transferred into the mine by setting up the transit at the mouth of the adit and, after taking a backsight on a fixed station on the surface, taking a foresight into the adit and establishing a point within the mine. This furnishes within the mine one line of known azimuth from which surveys may be extended. If the entrance is by a shaft which is highly inclined, but not vertical, the same general method is employed except that the auxiliary telescope will be required in taking the sights.

When the shaft is vertical it is still possible to use the transit and its auxiliary telescope, but a more accurate method is to use long-plumb lines hung in the shaft. In case the mine has but one shaft it is necessary to suspend two plumb-lines (sometimes three or four) in the shaft. If the mine has two or more shafts a point may be located at the bottom of each shaft by plumbing down from the top. Then a traverse can be run in the mine connecting these underground points and another traverse on the surface connecting the corresponding points at

the tops of the shafts; in this way a closed traverse is formed connecting all of the points.

356. Transferring Meridian Down Shaft by Use of Transit. — In transferring the meridian down a shaft by the use of a transit the instrument is set up at the collar of the shaft, a backsight is taken in the ordinary manner and a foresight then taken down the shaft to some selected point, the line of sight being made as much inclined to the vertical as possible. The distance is then measured from the horizontal axis of the instrument to the point sighted; the transit is next set up over the bottom station, a backsight taken on the top station and the survey then carried into the levels of the mine.

In sighting from both ends of the same highly inclined line it will be found that errors of meridian due to the line of sight not being perpendicular to the horizontal axis are eliminated if the readings are made with the telescope in the same position at both sights, whereas errors of meridian due to the horizontal axis not being perpendicular to the vertical axis are eliminated if the readings are made with the telescope direct when at the top and reversed when at the bottom of the shaft, or *vice versa*. Obviously both are eliminated when the direct and reverse position are used at both the top and the bottom of the shaft and the mean readings taken in both cases.

When it is impossible to sight up a shaft on account of its being too wet, two or more points can be set in line at the bottom of the shaft by means of the instrument when at the top, and these will determine a line of known azimuth at the bottom of the shaft.

The great importance in this work of having the horizontal axis truly horizontal should not be overlooked; elimination of the errors by reversing and taking mean readings should not be relied upon without the aid of a more sensitive level than the plate bubbles, because reversing the instrument does not eliminate the errors due to the vertical axis not being truly vertical. If the transit is provided with a striding level, this level should be used in both of its positions as follows: with the main telescope direct the striding level is used in both positions and two azimuths are read, then with the telescope inverted the

striding level is again used in both positions and two more azimuths are read. The means of the two readings of these pairs correspond to two mean lines of sight which are symmetrically placed with respect to the vertical plane passing through the two station points and the correct azimuth reading is therefore the mean of these two mean azimuths. If the transit is not equipped with a striding level, the axis may be made vertical by leveling the plate by means of the telescope bubble as follows. First, level the plate as nearly as possible by means of the plate bubbles, then place the telescope parallel to a pair of opposite leveling screws, and by means of leveling screws center the telescope bubble; then turn the telescope 180° in azimuth and if the bubble moves away from the center bring it halfway back to its central position by means of the leveling screws, and bring it the rest of the way to its central position by means of the tangent screw of the vertical motion. Repeat this process with the telescope in line with the other pair of leveling screws.

In some cases an azimuth is carried into the workings by stretching a horizontal wire across the bottom of the shaft and as far back into the workings as possible, the wire being carefully aligned by the instrument at the top. This method may admit of even more accuracy than that of taking a backsight to the surface from a station established in the bottom of the mine. Errors due to a slight inclination of the horizontal axis are not important when this method is used, and for that reason it is also useful in cases where a sensitive striding level is not to be had. The effect of a slight inclination of the horizontal axis is simply to shift the line slightly to one side of, but parallel to, the true position.

357. Plumbing the Meridian Down a Shaft.* — To the mine surveyor the plumb-line is an instrument of precision, excelling even the transit under some conditions, and the work of transferring the meridian down a mine can generally be accomplished more accurately by means of the plumb-line than by any other method available to the surveyor.

* See Colliery Engineer and Metal Miner, Vol. XVII, p. 23; Colliery Engineer, Vol. XIV, p. 92, and School of Mines Quarterly, Vol. III, pp. 269–77.

The method usually followed is to suspend two bobs from points on the collar of the shaft which have been accurately set as far apart as possible and so located that a horizontal line in their plane can be sighted from below. The transit is set up both above and below in this vertical plane and thus an azimuth connection is established between the surface and the workings. Points are established at the collar of the shaft from which plumb-bobs are suspended by wires. Two wires are generally used, although three or four wires are sometimes employed. The distance between the wires is carefully measured at the surface. The instrument is then taken underground and set up at *C* (Fig. 152) and "jiggled in"; that is, moved until the line of sight *CA* and the two wires *A* and *B* are in the same vertical plane. The distances from the wires to the transit should, if possible, be so chosen that it will be unnecessary to move the objective far when focusing. Since this condition is seldom possible, the objective slide should be in excellent adjustment before these operations are performed. When the instrument is in the same vertical plane as the wires a point is established under or over the instrument and an angle turned into the mine workings, where another point is established.



FIG. 152.

The distance between the wires should be measured at the bottom of the shaft and should check the measurement made at the top. The distance of one or both wires from the instrument should also be measured, as this is one line of the traverse.

The plumb-lines should be as small in diameter as the weight will permit. They are usually of copper, annealed iron or piano wire.* With regard to the size of plumb-bob and wire

* See Eng. and Min. Jour., Vol. LV, p. 179, Feb. 25, 1893; Proc. Inst. of C. E., Vol. CXLII, p. 334; School of Mines Quarterly, Vol. XI, p. 333, and Colliery Engineer, Vol. XVI, p. 31.

a great difference of opinion exists. The plumb-bobs should be heavy enough to straighten out all bends in the wire. They should be immersed in oil or water or an oil emulsion, so as to stop their swinging in the shortest possible time, and the receptacle in which the plumb-bobs are immersed should be covered in order to protect the surface of the liquid from water dripping down the shaft. All air currents should be checked so far as possible, since experience has shown that in deep shafts they have considerable effect upon the plumb-lines. Great care should be taken to see that no part of the wires comes in contact with the shaft.

When once the plumb-lines are hung the meridian may be transferred to all the levels of the mine once and for all time, so that a little extra precaution and time given to this operation are worth while. The surveyor should always keep in mind the fact that in plumbing the meridian down the mine the direction of the meridian is of much more importance than the actual position of the points themselves, because an error due to an incorrect direction of the meridian may be multiplied many hundreds of times in carrying the traverse through the mine.



FIG. 153. TRIANGULATION AT JUNCTION OF SHAFT AND LEVEL.

When the level or cross-cut runs in a direction with respect to the shaft as shown in Fig. 153, then the triangulation method is employed. Points A and B are the plumb-bobs and point C is where the transit is set up. A slight error in the distance AB merely affects the computed lengths of AC and BC, whereas a small error in the direction of AB may produce large error in the positions of distant points in the workings. The point C therefore is chosen as far from the shaft as possible even though the angle C is small.

358. Measurements of Distances down Vertical Shafts.* — If the depth of the shaft is no greater than the length of the tape, then the zero end of the tape may be lowered by having a small weight attached to it, and a vertical measurement taken from a point at the top of the shaft to a level line of sight established by the transit set up in the bottom of the shaft. When the distance is greater than the tape-length it may be measured along the guides for the cage or skip, or it may be measured by means of a long wire. The difficulty in measuring deep vertical shafts by means of long tapes or wires is due to their stretching. The amount the tape stretches may be determined as follows. If a tape is suspended from a spring balance the pointer will register the total weight of the tape, which is twice the average tension in the tape. Consequently if the pull is increased by attaching a weight W to the end of the tape the average tension is $W + \frac{1}{2}$ (weight of tape). Knowing this average amount of pull the actual length of tape can be found by stretching the tape out on a floor and testing it as described in Art. 19, p. 12, giving it the same amount of pull.

359. Transferring a Meridian into a Mine when there are Two Shafts.† — The above methods presuppose that the mine has so far been opened only by one shaft. If there is a second shaft or an adit, it is, of course, only necessary to plumb or otherwise transfer the position down each shaft; the computed distance between these points then becomes a base-line of substantial length. In Fig. 154 the traverse $ABCD$ is run out on the surface to connect the two shafts at A and D. The points A and D are plumbed down the shafts and the corresponding points A' and D' established at the bottom. An underground traverse $A'G'F'E'D'$ is then run out. In the surface traverse the length and azimuth of AD and in the underground traverse the length and azimuth of $A'D'$ are missing. The horizontal length and azimuth of each of these lines can be determined from their respective traverses as explained in Art. 433, p. 415. The surface traverse is referred to the true meridian, and, since

* See Colliery Engineer, Vol. XVI, p. 53.
† See Colliery Engineer, Vol. XIV, p. 53.

nothing is yet known in regard to the direction of the meridian in the mine, the underground traverse is referred to an assumed meridian. The true azimuth of $A'D'$ is the same as the azimuth of AD, provided the plumbing down the shaft has been accurately done. The difference between the true and assumed azi-



Fig. 154

muths of $A'D'$ is a correction to be applied to the azimuths of all of the lines of this underground traverse.

360. UNDERGROUND TRAVERSES. — Surveying in a mine is necessarily a process of traversing, for only the working passages are available for lines of survey. The line of traverse is often run so that the longest possible sight may be taken. In the tortuous passages of a mine it is frequently necessary to take very short sights on the main traverse and since the azimuth is transferred to distant connections through these short lines great care should be exercised; and instrumental errors should be eliminated by reversing the telescope and using the mean of the two results. After the main traverses have been run, the surface boundaries may be accurately established underground and the stopes and working places surveyed by more convenient and less accurate methods, from the stations already established.

It is often very convenient in underground work to take the azimuth from an estimated general direction (or strike) of the vein; for the direction of the meridian is of no importance in the actual working of a mine, while the direction of most of the passages will usually vary only a few degrees from the strike; this will simplify the traverse calculations.

Accurate traverses should be carried into all important workings of the mine, which include the shafts, levels, cross-cuts, raises and winzes. Permanent transit points should be established in the shaft at every level, and in an inclined shaft it is good practice to put in one or two points on line between the levels to hold the direction of the shaft. Offset distances called "rights" and "lefts" are measured on each side of the traverse line within the mine workings for the purpose of locating the limits of the workings. The floor of passages is defined by determining the elevation of the necessary number of points, and the roof by measurements from points located on the floor.* Elevations are defined within the mine either by direct leveling, as in leveling out on the surface, or by means of inclined distances and vertical angles. Secondary openings, such as stopes, are surveyed by running the lines from the main traverse through a chute or mill-hole, from which the necessary dimensions and angles are taken to define the shape and extent of the stope holes.† Sometimes these stopes are surveyed by use of the compass and clinometer. In some cases where long stopes are to be surveyed a transit line is run from a station in a level up through a chute at one end of the stope, carried along through the stope, and then down through another chute at the other end closing on another station in the level.

The field-notes of these details are usually kept in the form of sketches which show the traverse line which forms the skeleton of the survey and the measured offsets and angles which locate the points needed to define the boundaries of the hole.†† It is often necessary to draw sketches showing the opening both in elevation and in plan and to add descriptive remarks sufficient to make the sketch clear to any surveyor even though he is unfamiliar with that particular place in the mine.

361. Traverse Stations and Station Marks. — The places chosen for stations should be in protected places and located

---

* See Colliery Engineer, Vol. XIV, p. 197; also School of Mines Quarterly, Vol. XI, p. 334.

† See Eng. and Min. Jour., Jan. 27, 1900; Proc. Inst. of Mine Surveyors, Vol. II, and Min. and Sci. Press, April 3, 1910.

†† See Colliery Engineer, Vol. XIV, pp. 38 and 197.

where they will not be liable to be tampered with or disturbed. They are often marked by a drill-hole with a plug and spad of some kind, a nail, a spike or a boiler rivet.

A satisfactory station mark may be made by drilling in the roof (or back) of a passageway a hole about $1\frac{1}{2}$ inches in diameter and driving a tight-fitting wooden plug into the hole; a mark of some kind is made on the end of the plug. These marks are commonly a spad (or spud) which is made by flattening the head of a horseshoe nail and drilling a hole about $\frac{1}{8}$ inch in diameter through it. Other roof marks commonly used are an eye pin, a screw-eye, a staple or a bent nail. (See Fig. 155.) These



FIG. 155. STATION MARKS IN ROOF.

station marks can be attached to the caps of the mine timber, but timbers are liable to be moved.

Owing to the workings in the mine these overhead marks sometimes cannot be employed, in which case the stations are established on the floor. Floor station marks are commonly a short stout spike or a sharpened boiler rivet driven into a tie of the track. In the heads of these spikes a small drill-hole is made to distinguish them from other spikes. For a temporary mark a punch mark on the rail, a mark on a block of lead or iron or a chalk mark is often used.

In sighting overhead stations a plumb-line is generally suspended and the angle and distances taken to a mark on the plumb-line, such as to the top of plumb-bob, to a knot in the line, or to a bit of candle grease fastened to the line. When the station is on the floor a pencil may be sighted, and if the

station mark has a small drill-hole in it a small finish nail can be inserted, upon which to sight.

All such points must be illuminated. This may be done by holding a piece of tracing cloth back of the station mark, behind which is a lighted candle which causes the nail or pencil held upon the station mark to be silhouetted against a white surface. Often a candle held to one side of the object sighted will illuminate it sufficiently, especially if a sheet of white paper is held behind it. Many devices such as plummet lamps and special illuminated targets on tripods are used.

Besides the devices which mark the exact station point a white ring is often painted around them to aid in finding the point. Another method is to paint an arrow on the wall, pointing toward the station. It is good practice to paint the number of the station near by, in which case these numbers should be painted either on the hanging wall or on the foot wall. In some mines a small copper, brass or aluminum tag upon which the station number is stamped is attached near the station mark.

The method of numbering stations sometimes depends upon their positions and sometimes it does not.* Where the station number relates to its position in the mine one of the methods is to number all points on the first level from 100 to 199, on the second level from 200 to 299, and so on, as is done in the field-notes on pp. 346–8. Another method is to designate the station as 1206 N or 1318 S, if the workings are about North and South, in which case the first number would mean Station 6 on the 12th level north of the shaft. Where the numbering of the stations has nothing to do with its location they are usually numbered consecutively. A book containing the number, location and description of all stations should be kept up to date, and if the mine has more than one shaft this fact should be indicated in the notes or in the station numbers.

362. Setting up the Transit. — If the point to be occupied is on the floor the transit is set up in the usual manner; if it is in the roof a temporary point can be marked on the floor by plumb-

* See Eng. and Min. Jour., Sept. 8, 1906; also Min. and Sci. Press, Oct. 24, 1903.

ing down from the roof point, and then the transit set up over the temporary floor point. If the point is in the roof, however, the usual method is to suspend the plumb-line from the point and set the instrument up under it. Most instruments have a mark on the telescope barrel over the intersection of the center lines of the horizontal axis and the telescope. This point is set approximately under the plumb-bob and the instrument leveled, the telescope is brought to a horizontal position by the telescope bubble, and then by means of the adjustable head the point is brought directly under the plumb-bob.

363. TRAVERSING. — In running the traverses in levels, drifts and horizontal, or nearly horizontal, passages the work is done the same as on the surface and under these conditions the main telescope of the transit can be used. The angles are measured either as direct angles, and **doubled for a check,** or measured as azimuths. (See Art. 144, p. 109.) Vertical angles are read in the ordinary manner, but care should be taken to determine the index correction. In those cases where the vertical circle is read with the telescope both direct and inverted, the index correction should be determined and applied to each reading to eliminate errors produced by plate bubbles. The mean of these two corrected angles is the true value. Where it is necessary to use an eccentric telescope the proper correction for eccentricity must be applied as described in Arts. 348 and 349, pp. 326–7.

364. The following method is in use in several mines and requires no reduction for eccentricity. The side telescope only is used, the vernier is set on zero and a backsight taken on the first point, the upper motion is unclamped and the second point sighted with the vertical and horizontal cross-hairs; the horizontal and vertical angles are then read. The lower motion is unclamped, the telescope inverted, and the first point sighted again; the upper motion is unclamped and the second point sighted as before. Again the horizontal and vertical angles are read. The first horizontal angle read does not give the true angle, but half of the second angle reading gives the true horizontal angle; and the mean of the two vertical angles read gives the true vertical angle. In practice the vertical angle is gener-

ally read but once, the index correction being applied. The above method is illustrated in the notes on p. 346–8.

365. Since practically all traverse measurements are made as inclined measurements, and since vertical angles are often used together with the distances for obtaining elevations, it is frequently necessary to measure the H.I. (*height of instrument*) and the H.Pt. (*height of point*) above or below the station mark. If the transit is set **above** the station the H.I. is recorded + (plus), and if the transit is set **under** the station the H.I. is recorded − (minus); but if the point sighted is **below** the station



FIG. 156.

the H.Pt. is recorded + (plus), and if it is **above** the station the H.Pt. is recorded − (minus).

The vertical distance is obtained by computing the "sine distance," which is the inclined distance × the sine of the vertical angle, and then applying to that distance the proper correction, depending upon the amount and the sign of the H.I. and H.Pt. distances. For example, Fig. 156 indicates a set-up of the instrument under a point in the roof; the vertical angle was taken to the top of the plumb-bob hung from another point in the roof. Here the H. I. is minus and H.Pt. is plus.

Fig. 157 illustrates a case where the instrument station is in the roof, the station ahead is in the floor, and the vertical angle was taken directly to the point in the floor; here the H.I. is a minus quantity. There are several different combinations which

arise, but no difficulty will be experienced if the case is carefully visualized before the computations are made.

The horizontal distances are usually obtained by computing the "cosine distance," which is the inclined distance × the cosine of the vertical angle. The reason why the cosine instead of the versed sine is so frequently used in obtaining the horizontal distance is because its logarithm can be taken from the tables at the same opening as the log sine which is used for the vertical distance. But when the horizontal distance alone is required and



FIG. 157.

the vertical angles is small, the versed sine method explained in Arts. 13, p. 9, and 390, p. 376 should be used.

The field-notes on p. 346–8 illustrate this common method of running mine traverses.

366. A somewhat less common method of traversing is to use three tripods having leveling heads and centering plates like those of the transit. The transit fits on to any of these heads, and while it is attached to one of them the other two are surmounted by *lamp targets* in which the sighting center has exactly the same position as the sighting center of the transit would have if set on the same tripod. These tripods are placed vertically over or under the stations and the transit is attached to the middle one. When the transit head is moved from the middle to the foremost tripod a target takes its former place and the hindmost tripod is brought ahead of the transit and set up on the new forward station.

367. Traverse Notes. — As in all surveying parties the form of notes differs with local practice and the personal preference of the surveyor. A common and useful form is shown on pp. 346–8. In these notes the first column shows that the instrument was first set up at Sta. 0, the second and third columns state that a B.S. was taken on a monument with the horizontal circle set at 0° 00′, a F.S. taken to Sta. 2 and horizontal angle read as 88° 03′; then without changing the circle reading a B.S. was taken on the Mon., and then another F.S. taken on Sta. 2 and the double angle read was 176° 08′, half of which is the true angle. All horizontal angles are here read as azimuth angles in a clockwise direction from a B.S. on the station designated in the "Pt." column. The fourth column states that the distance 651.01 was measured horizontally instead of on the slope, which latter is the usual custom and would have been used here had the tape been long enough. The fifth, sixth and seventh columns state that the vertical angle was a single reading of a depression angle taken to a point which was distant above Sta. 2 equal to the distance the center of the instrument was above Sta. 0. The description of the points sighted is in the last column.

The next set of readings shows that the transit was set at the same Sta. 0, and the horizontal angle read and "doubled"; the single reading of the angle was considerably different from half of the double reading, which was due to the fact that the sight was down the shaft, as indicated by the vertical angle, and so highly inclined that an auxiliary telescope had to be used, in this case a side telescope. In the column headed "H.Pt." is recorded + 3.27, which means that the vertical angle was taken to a point on a plumb-line hung from Sta. 102, which was 3.27 ft. below the station mark. (Art. 365, p. 343.) Throughout this traverse the main telescope was used except on highly inclined sights when the side telescope was used as indicated in the "Remarks" and by the horizontal angle readings. Had the top telescope been used and the angles accurately measured the first reading of the horizontal angle would have been half of the "double angle," but the vertical angles would all have had to be corrected for eccentricity of the telescope, as explained in

TRAVERSE NOTES OF BEAR CREEK MINE, WEST BOWLDER, MONTANA.

Sta.	Pt.	Hor. Angle.	Slope Dist.	Vert. Angle.	H.Pt.	H.I.	Remarks.
						+ 4.68	Coördinates Mon.
O	Mon.	0° 00′					= Lat. + 1476.82
	2	88° 03′	651.01	− 0° 58′	− 4.68		Dep. − 647.87
	Mon.	" "	(Hor.)				Hor. Dist. O to Mon. = 764.27
	2	176° 08′					Elev. Mon. = 560.28, R.R.
						+ 4.68	= 4.92
*O	Mon.	0° 00′					O = pt. on collar of shaft.
	101	357° 01′	117.38	−80° 10′	+ 3.27		Bearing O to Mon. = due N.
	Mon.	" "					2 = Top of air shaft to 1st level.
	101	355° 40′					101 = Shaft plug 1st level.
						− 6.23	* Side telescope.
101	O	0° 00′					102 = Spad in roof 1st level.
	102	269° 55′	230.83	+ 0° 45′	+ 3.42		
	O	" "					
	102	179° 50′					
						− 6.23	
101	O	0° 00′					201 = Shaft plug 2nd level.
	201	179° 54′	112.65	−80° 09′	+ 4.14		Side telescope.
	O	" "					
	201	359° 52′					
						− 2.85	
102	101	0° 00′					103 = Spad in roof 1st level.
	103	181° 30′	153.51	+ 0° 55′	+ 3.75		
	101	" "					
	103	3° 00′					
						− 2.85	
102	101	0° 00′					107 = Spad in roof 1st level.
	107	181° 25′	75.03	+ 0° 52′	+ 3.16		
	101	" "					
	107	2° 50′					
						− 3.16	
103	102	0° 00′					104 = Spad in roof 1st level.
	104	181° 32′	105.68	+ 0° 30′	+ 4.01		
	102	" "					
	104	3° 04′					
						− 3.75	
104	103	0° 00′					105 = Spad in roof 1st level at
	105	181° 01′	162.13	+ 0° 48′	+ 4.26		foot of air shaft.
	103	" "					
	105	2° 02′					
						− 3.92	
105	104	0° 00′					Side telescope.
	2	270° 30′	92.36	+88° 25′	0.00		
	104	" "					
	2	194° 14′					
						− 3.92	
105	104	0° 00′					
	Breast	179° 50′	15.9	0° 00′			
						− 6.22	
201	101	0° 00′					301 = shaft plug at 3rd level.
	301	180° 00′	115.78	−80° 32′	+ 2.93		Side telescope.
	101	" "					
	301	360° 00′					
						− 6.22	
201	101	0° 00′					202 = Spad in roof 2nd level.
	202	268° 06′	167.48	+ 0° 53′	+ 1.96		
	101	" "					
	202	176° 12′					

TRAVERSE NOTES OF BEAR CREEK MINE, WEST BOWLDER, MONTANA (*Continued*).

Sta.	Pt.	Hor. Angle.	Slope Dist.	Vert. Angle.	H.Pt.	H.I.	Remarks.
201	101	0° 00′				− 6.22	
	205	88° 00′	196.02	+ 0° 47′	+ 3.01		205 = Spad in stull 2nd level.
	102	" "					
	205	176° 00′					
202	201	0° 00′				− 4.92	
	208	182° 28′	138.07	+ 0° 44′	+ 1.09		208 = Spad in roof at raise 2nd level.
	201	" "					
	208	4° 56′					
202	201	0° 00′				− 4.92	
	203	182° 28′	106.37	+ 0° 47′	+ 1.03		203 = Spad in roof 2nd level.
	201	" "					
	203	4° 56′					
203	202	0° 00′				− 3.68	
	204	182° 35′	176.93	− 0° 29′	0.00		204 = Spike in floor at breast 2nd level.
	202	" "					
	204	5° 11′					
208	202	0° 00′				− 3.04	Side telescope.
	107	268° 01′	121.03	+77°59′	+3.26		
	202	" "					
	107	177° 08′					
205	201	0° 00′				− 4.28	
	206	180° 24′	216.87	+ 0° 48′	+ 3.69		206 = Spad in roof 2nd level.
	201	" "					
	206	0° 48′					
206	205	0° 00′				− 4.23	
	209	180° 44′	117.72	+ 0° 41′	+ 3.18		209 = Spad in roof over winze 2nd level.
	205	" "					
	209	1° 30′					
206	205	0° 00′					
	Breast	181° 04′	152.00				
301	201	0° 00′				− 6.78	
	302	268° 34′	304.02	− 0° 10′	0.00		302 = Spad in floor in raise 3rd level.
	201	" "					
	302	177° 08′					
301	201	0° 00′				− 6.78	
	303	268° 34′	315.83	+ 0° 48′	+ 3.16		303 = Spad in roof 3rd level.
	201	" "					
	303	177° 08′					
301	201	0° 00′				− 6.78	
	305	88° 54′	194.63	+ 0° 50′	+ 4.02		305 = Spad in roof 3rd level.
	201	" "					
	305	177° 48′					
301	201	0° 00′				− 6.78	
	401	180°02′	116.82	−80° 10′	+ 3.02		401 = Shaft plug 4th level. Side telescope.
	201	" "					
	401	360° 00′					

TRAVERSE NOTES OF BEAR CREEK MINE, WEST BOWLDER, MONTANA (*Continued*).

Sta.	Pt.	Hor. Angle.	Slope Dist.	Vert. Angle.	H.Pt.	H.I.	Remarks.
302	301	0° 00′				− 4.16	
	208	266° 56′	123.48	+79° 30′	+ 4.03		Side telescope.
	301	" "					
	208	175° 18′					
303	301	0° 00′				− 4.16	
	304	184° 33′	288.92	+ 0° 12	0.00		304 = Spike in floor, breast 3 ft. beyond.
	301	" "					
	304	°9 06′					
305	301	0° 00′				− 4.16	
	306	182° 12′	186.10	+ 0° 46′	+ 2.16		306 = Spad in roof 3rd level.
	301	" "					
	306	4° 24′					
306	305	0° 00′				− 1.52	
	307	180° 56′	150.16	+ 0° 43′	0.00		307 = Spike in floor at winze 3 rd level.
	305	" "					
	307	1° 52′					
307	306	0° 00′				+ 4.77	
	209	87° 11′	120.49	+71° 11′	0.00		Breast 15′ beyond 307.
	306	" "					Side telescope.
	209	175° 02′					
401	301	0° 00′				− 6.72	
	402	268° 02′	219.73	+ 0° 48′	+ 2.08		402 = Spad in roof 4th level.
	301	" "					
	402	176° 04′					
401	301	0° 00′				− 6.72	
	406	90° 24′	116.39	− 1° 02′	+ 1.98		406 = Spike in floor 4th level, breast 2′ beyond.
	301	" "					
	406	180° 48′					
401	301	0° 00′				− 6.72	
	Bot. shft.	180° 00′	49.7	−80° 10′	0.00		
402	401	0° 00′				− 2.01	
	403	184° 08′	84.83	+ 0° 45′	+ 3.24		403 = Sta. in roof at raise 4th level.
	401	" "					
	403	8° 16′					
402	401	0° 00′				− 2.01	
	404	184° 08′	92.62	+ 0° 42′	+ 2.68		404 = Spad in roof 4th level.
	401	" "					
	404	8° 16′					
403	402	0° 00′				− 2.68	
	302	269° 08′	111.68	+81° 24′	+ 2.61		
	402	" "					Side telescope.
	302	179° 56′					
404	402	0° 00′				− 3.01	
	405	182° 49′	217.66	+ 0° 13′	0.00		405 = Spike in floor 4th level breast 3′ beyond.
	402	" "					
	405	5° 38′					

MAP OF

BEAR CREEK MINE

WEST BOWLDER, MONT.

Scale, 1 in. = 50 ft.

Scale of Reduced Plate,
1 in = 150 ft.





TRANSVERSE SECTION
LOOKING WEST

Art. 348. In the method used in these notes no eccentricity correction is necessary.

The measurements which locate the walls of the workings have been purposely omitted from the foregoing notes for the sake of simplicity. A plot of the mine in which this traverse was run is shown in Fig. 158.

368. Station, Computations, and Coördinate Books. — Besides the field note-book, most mining engineers keep three other survey record books, a book containing a description and location of all traverse stations, one containing the computations of all traverses and other surveys, and a coördinate book containing the computed values of the coördinates of station points.

369. Station record books are commonly kept in the form shown below. These notes show that Sta. 1001 is in C shaft,

STATION RECORD.

Station.	Notes.	Coörd.	Comp.	Date.	Remarks.
1001	C shaft	2– 1	60–83	2–10–15	Shaft plug 10th level.
1013	B 10 N	1–19	59–77	2–14–15	Plug in stope

its coördinates are on p. 1 of Coördinate Book No. 2, the computations relating to this point are on p. 83 of Computation Book 60, and that the point was set on Feb. 10, 1915.

370. The computation book is usually a book of unruled pages with pasteboard covers. At the top of the pages should be entered the title of the computation, the coördinates and elevation of the station from which the computations start, the bearing of the B.S. line, where the coördinates used are to be found in the Coördinate Book, the shaft and level under which the data will be found headed in the field-notes, the date and the name of the computer. Fig. 159 is the beginning of the computations of the notes on p. 346–8.

Main Shaft Line.

Coörd. Mon. = { Lat. + 1476.82 / Dep. − 647.87 } Coörd. Bk. 76, p. 43.
Elev. 560.28 Main Shaft Fieldbook.

May 20, 1906.
J. C. Keene.

0 − 2 N 88° 04′ E

Lat.	Dep.	Elev.
8.52810	9.99975	560.28 = Mon.
2.81359	2.81359	+ 4.92
1.34169	2.81334	565.20
		− 4.68
+ 21.96	+ 650.64	560.52 = 0
+ 712.55	− 647.87	− 10.98
+ 734.51	+ 2.77	549.54 = 2

H.D. = 651.01
V ∠ = 0° 58′
8.22720 tan
2.81359
1.04079
V.D. = − 10.98

Bearings.
0 − Mon. = due N
88° 04′
0 − 2 = N 88° 04′ E

0 − 101 N 2° 10′ W

9.99969	8.57757	560.52 = 0
1.30204	1.30204	+ 4.68
1.30173	9.87961	565.20
		− 115.66
+ 20.03	− 0.76	449.54
+ 712.55	− 647.87	+ 3.27
+ 732.58	− 648.63	452.81 = 101

V ∠ = − 80° 10′ 9.23244
S.D. = 117.38 2.06960
1.30204
H.D. = 20.05
9.99357
2.06960
2.06317
V.D. = − 115.66

0 − Mon. = due N
360°
357° 50′
0 − 101 = N 2° 10′ W

101 − 102 N 87° 45′ E

8.59395	9.99967	452.81 = 101
2.36325	2.36325	− 6.23
0.95720	2.36292	446.58
		+ 3.02
+ 9.06	+ 230.63	449.60
+ 732.58	− 648.63	+ 3.42
+ 741.64	− 418.00	453.02 = 102

V ∠ = + 0° 45′ 9.99996
S.D. = 230.83 2.36329
2.36325
H.D. = 230.81
8.11693
2.36329
0.48022
V.D. = + 3.02

101 − 0 = S 2° 10′ E
269° 55′
267° 45′
180°
101 − 102 = N 87° 45′ E

13TH LEVEL NORTH B SHAFT.

Sta.	Bearing	Dist. Hor.	Latitude.		Departure.		Total.		Elev. Plat.	N Bk.		C Bk.		Date.	Sta.	Remarks.
			N	S	E	W	Latitude.	Departure.	Elev.		No.	P	No.	P			
699															699	
	S 29°41′ E	23.40		20.33	11.59		+1266.78	−547.32	−788.95							
801															801	6″ Spike in tie
	S 68 02 E	33.43		12.50	31.00		+1246.45	−535.73	−789.05							" " "
866							+1233.95	−504.73	−789.26						866	" " "

FIG. 159 *a*. COÖRDINATE BOOK.

In computing horizontal distances log cosines of vertical angles are used rather than log vers sines, because the former can be taken from the same page of the tables as the log sines which are used for computing the vertical distances. The vertical distance of the first course from sta. 0 to 2 was obtained through the tangent of the angle, because the distance measured was the horizontal distance.

371. The Coördinate Book may be ruled and columns headed as shown in Fig. 159 *a*. In it are recorded the results of the computations in the proper columns.

Columns headed "Latitude" and "Departure" are computed as explained in Chap. XIV. The minus signs before the numbers in the "Elev." column indicated that the points are below the datum plane.

The column headed "Elev. Plat" is used for recording the elevation of base of rail at the shaft; the following four columns are for recording the field note-book number and page and the computation book number and page.

372. MINE MAPS. — The maps of a mine are frequently the only means of clearly conveying information regarding the shape and extent of the workings.* They should be so made as to show in the clearest possible manner the passages and stope-holes, their extent as well as their location. Since in different mines the veins of deposit have different amounts of dip and different directions of strike, considerable judgment must be exercised in the choice of planes upon which to project the plans of the workings so that their location and extent will be shown in the clearest possible manner.

The usual plans prepared for a mine are

(1) Surface plan.
(2) Underground workings in plan.
(3) Underground workings in longitudinal section.
(4) Underground workings in transverse section.
(5) Map of stopes.
(6) Assay map.
(7) Geological data.

(1) The surface plan should show the boundaries, roads, joining railroad, buildings, mine dump, drains and water supply.

(2) The underground plan is a projection on a horizontal plane. It should show all underground workings such as the shafts, levels, cross-cuts, winzes, raises, stopes, faults, ore shoots, mill-holes, and sometimes the geology; the progress should be shown by different colors, by difference in character of lines or by dates lettered on the plan.

In mines where the dip is 70° or greater the plan is often complicated because lines on one level overlap lines representing other levels. To avoid this confusion each level should be plotted in plan separately. In Fig. 158 all levels are shown on one plan because the stopes are not plotted on that plan and hence there is no overlapping of lines on different levels.

When the dip is less than 60° to 70° the plan of the entire mine can usually be plotted on one sheet, and if the levels are colored differently the plan is more easily understood.

* See article on Accurate Underground Plans, in Canadian Engineer, May, 1902.

(3) The longitudinal section may be either a vertical section, as in Fig. 158, or a section lying in the plane of the dip, in which case it is called a "plan on the vein." In the former the true vertical distance between levels is shown, whereas in the latter the levels are shown at distances apart equal to the slope distances along the shaft. Even though the levels are usually constructed on a grade of about 1 per cent for drainage and haulage they are often plotted on the longitudinal section as level passages.

This longitudinal section should show all workings shown on the plan (see [2] above) and should show the progress of the work in a clear manner, especially in the stopes.

If the vein is fairly regular and the coördinate planes are taken with the assumed north and south along the strike, then the longitudinal section represents the levels in their true lengths.

(4) The transverse section is usually plotted in a plane at right angles to the plan and longitudinal section. It is well in some cases to plot several transverse sections, each one a separate sheet, in order that their lines may not overlap and produce a confusing drawing. If the longitudinal plan is in a vertical plane through the strike, then the transverse plane is at right angles to this plane and on it the shaft would show in its true length.

(5) In some mines stope maps are kept showing in detail the size and shape of each stope as a separate map and indicating upon the plan the progress made. These working plots may be either vertical, horizontal, or parallel to the vein or seam. In any case, the thickness of the deposit is recorded at frequent intervals together with other particulars, such as thickness of waste or value of ore. These thicknesses are all measured at right angles to the plane of the working plan, so that when multiplied by the area on the plot, the cubic contents of any section is obtained. Where the ore occurs in irregular masses, not conforming particularly to any one plane, the above system does not apply and some other method must be devised by the surveyor. The best way of estimating amounts not mined is to sketch their probable extent on such a chart from the data

available and to make use of the area and thickness method as suggested above.

(6) Assay plans are made from the plan and longitudinal section of the mine on which is plotted the location from which assay samples have been removed.*

(7) A plan showing geological data should show the boundaries of the various formations, the planes of bedding and the foliation, the fault planes with their displacement, and all veins and dikes encountered.† These data could of course be shown to some extent by three coördinate planes as in solid geometry, but it is usually better to plot the geological data taken in each level. Any inclined rock surface is then represented by a series of contour lines corresponding to the levels from which the information is actually obtained. Strikes, dips, and intersections may then be determined by use of a protractor, a scale and a table of contangents.

In a metal mine a plan of each level when filled in with all the geological data will have as much detail as can conveniently be shown. It is usual in such cases to make a geological plan of each level separately on thin tracing paper so that any two or possibly three consecutive ones may be superimposed. The particular position, strike, and dip of any ore shoot or surface may then be found as easily as though they were all plotted on the same piece of paper.

The scale of the surface map is usually 100 or 200 ft. to an inch. The general plans of underground workings are often 50 ft. to an inch and the detail stope plans are 20 ft. or 10 ft. to an inch. The general underground plans can be best plotted by the coördinates of the station points. The coördinates can be laid out on the plan and then if it changes scale by shrinking or swelling it does not affect the accuracy of the plan, for the new station points located in workings as they progress are plotted by coördinates from the nearest of the coördinate points originally plotted on the map. Since these maps are used so frequently and for so long a period, it is advisable to plot them on the best quality of mounted paper available.

* See Min. and Sci. Press, Sept. 3, 1904.
† See Mining Reporter, Vol. XLVIII, p. 181.

373. Mine Models. — These may be constructed of wood and glass. A wooden box without a top is first built. Horizontal strips of wood are fastened to the inside of the box at distances apart equal to the vertical distances (to scale) between the levels. On each of these horizontal strips a sheet of glass is placed on which has been accurately painted the horizontal projection of that particular level. The glass should first be treated with a coat of copal varnish or gelatine so that it will take the paint or ink. Strips of glass are inserted between the horizontal sheets to represent a shaft or winze.

374. Laying out Mining Work. — Drifts or cross-cuts are laid out by putting in two nails or hooks in the roof, not too near together, from which the miner can hang two plumb-lines and sight the center of the heading he is to run.

Vertical shafts are carefully plumbed on the inside of the frames, and frame by frame, as these are put in. It is best to hang the plumb-line from several frames above the bottom one, as these upper ones are more likely to have ceased to move. Hang the line an even fraction of an inch each way from the true position of the corners and note any accidental variation in the last frame set, so that in future work, if it is desired to hang the plumb-line from this frame, its error of position can be allowed for. The dimensions of a shaft or drift are given either "in the clear," meaning net measurements inside all timbers, or "over all," meaning gross measurement outside all timber and lagging.

375. Underground Surveying Problems. — In the practice of mine surveying, problems are constantly arising which tax the ability and ingenuity of the surveyor, although the actual solution of most of them is quite simple. A few of the common problems met with in such work are given below.

376. To Find an Ore Shoot by Driving a Level. — The pitch being given by its altitude and azimuth, this serves as a course from any point on the ore shoot whose coördinates are known. The difference in elevation between this point and that of the level to be driven is divided by the sine of the altitude (or vertical angle) of the ore shoot, which gives the slope distance along the ore shoot. The horizontal coördinates of the point where the level will intersect the ore shoot may then be calculated.

377. To Lay Out a Connection in a Mine. — Here the problem is to determine the bearing (or azimuth) and the vertical angle and the distance to run from point A in a mine to point B in another portion of the mine. A traverse can be run from A to B through the passages already cut in the mine, and all the distances reduced to horizontal distances which, together with the azimuths, form a traverse in which the length of the closing line AB (horizontal projection) and its azimuth are missing. These can easily be computed by the method explained in Art. 433, p. 415. The difference in elevation between the actual points A and B together with the length of the horizontal projection of AB will give the vertical angle; from these data the direction and distance between the points A and B can be computed.

378. To Establish a Boundary Line of the Claim Underground. — In Fig. 160 points A and B are on the boundary of the claim.



FIG. 160.

The shaft is located at S, and it is desired to prolong the underground working in the drift $H'J'$ to a point K' vertically under the boundary line. The surface traverse $BADCS$ is run out, point S is plumbed down to S', and the meridian transferred into the mine. Then the underground traverse $S'E'F'G'H'J'$ is run out. The horizontal projections of all the measured lines on both traverses are computed (or measured), and the length of the level line AH' and its bearing can be calculated as described in Art. 433, p. 415. In the horizontal triangle $AH'K'$, AH' and all the angles being known, the line $H'K'$ can readily be computed. If the drift $H'J'$ is not level the distance from H'

along the drift to the boundary plane will be equal to the horizontal distance $H'K'$ divided by the cosine of the vertical angle.

379. BOREHOLE SURVEYING. — The exploration of ore-bearing property is often carried on by drilling deep holes. These may be made for the purpose of determining the character of the rock, as well as to form air passages or drainage holes. The holes sometimes vary considerably from a straight line and their direction can only be plotted by determining at various points in their length their slope depth, bearing and dip.

The length is readily obtained by measuring the length of the rods used in drilling, or a wire with a weight attached may be lowered and then measured.

Many devices have been used for determining the bearing and dip. The simplest consists of a phosphor-bronze shell, similar to a piece of pipe about ten inches long and one and one-half inches outside diameter (the diameter depends to a certain extent on the diameter of the drill-hole). The inside diameter is slightly larger than one and one-eighth inches. One end of this shell is permanently closed, while the other may be closed by means of a plug or left open as desired; when in use this plug is screwed in tightly. On the other end of the plug is a thread to which drill rods may be attached, or a hole through which a wire may be fastened. The device may then be lowered into the hole.

To determine the dip and bearing, a piece of glass tubing is used which is about 6 inches long and whose inside diameter is uniform and whose outside diameter is such that it will just fit in the shell. In the center of this tube is placed a tightly fitting rubber stopper, dividing the tube into two parts. The lower half is partially filled with hydrofluoric acid, and corked. The upper part is partially filled with liquid gelatin, and a small compass needle, suspended in a frame to which a piece of cork is attached, is placed in the gelatin. The tube is then corked and placed in the shell, which can be lowered to any desired depth. This is then allowed to remain in the hole until the acid has had time to act on the glass, and the gelatin to harden. The acid etches the glass, and the angle it makes with the vertical may be measured by placing the glass tube in a special instru-

ment for that purpose. Knowing this angle, the dip may be readily computed.

The bearing is obtained as follows. The cork is of sufficient size so as to float the compass and frame, the compass, however, being always surrounded by the gelatin. The latter should be of such consistency that it will not harden until some time after the instrument is in place. This will then allow the magnetic needle to coincide with the magnetic meridian. When the gelatin hardens it holds the needle in place, and the bearing of the hole at that point may be determined by noting the position of the needle when the tube has been withdrawn from the hole. If several results are obtained at different depths, the coördinates of these points may be computed, and plans made if necessary.

Another instrument used is similar to the above, but both compartments are partially filled with gelatin. A compass is used in one, and a small suspended plumb-bob in the other.

Another instrument used for this purpose, more elaborate than the former, contains a compass and plumb-bob which are photographed when the instrument is at any desired depth. A sensitized paper, a small electric lamp and battery for illuminating the bob and compass, and a watch are lowered with the instrument, the watch being so constructed that it makes the exposure automatically.

380. TUNNEL AND SUBWAY SURVEYS. — The simplest case of tunnel construction is that of an aqueduct built on a straight grade and line. A surface traverse forming a long straight line may be run from portal to portal to establish accurate points on the center line of the tunnel in the vicinity of its portals for the purpose of projecting the tunnel from each end toward the center. On this surface line all points are fixed with great accuracy to insure that the directions of the lines at each end of the tunnel are in the same straight line, and also to locate intermediate shafts when the work is to be carried on from shafts as well as from each portal. The line is transferred down the shafts by the plumbing method described in Art. 357, p. 334. The surface line directly above the center line of the tunnel may be run first as a random straight line and then points set on the center line

by offsets, or it may be necessary to run a traverse between the portals and then compute the closing side, which is the center line. (Art. 433, p. 415.) Large transits which circles 7 to 9 inches in diameter and horizontal circles reading to the nearest 10″ are often used for this work. As the work of tunneling progresses the lines at both portals are extended into the tunnel by means of the transit, and accurate roof points are put in from which plumb-lines are hung to fix the direction for the workmen to follow in carrying on the excavation. The elevations are carried along by means of the ordinary leveling instrument.

A topographic survey is made for the purpose of preparing a profile along the line of the tunnel to show the amount of cover over the tunnel, the best locations for vertical or inclined shafts, and the geological structure through which the tunnel will pierce.

When the tunnel is to extend under a river it is often necessary to establish its alignment by a system of triangulation. This was done in the case of the Hudson River Tunnel of the Pennsylvania Railroad, and in the case of the Simplon Tunnel and St. Gothard Tunnel in Switzerland.

When it is necessary to introduce curves into the tunnel alignment they are laid out by the common method of deflection angles, and are projected forward by use of the largest chords which can be sighted. The deflection angles are laid off and then measured by repetition and corrected as explained in Art. 61, p. 50. These problems frequently occur in city subway layouts, but since there are usually many shafts in such construction there is ample opportunity to transfer surface points into the underground work to serve as checks.

The great variety of conditions existing in tunnel and subway alignments has brought forth a great many special surveying details, too numerous to mention in this treatise. Following are several references to engineering periodicals in which some of the special surveying methods used in typical tunnel and subway projects are described.

Hoosac Tunnel, Massachusetts, on Boston & Maine R.R.
"Manual for Railroad Engineers," by Vose, pp. 69–70.
Colliery Engineer, Vol. XVI, p. 52.

Musconetcong Tunnel, New Jersey, on Lehigh Valley R.R.
Trans. A. I. Mining Engineers, Feb. 1875, Vol. III, p. 231, by H. S. Drinker.

Simplon Tunnel, Italy.
Eng. News, Dec. 21, 1905, Triangulation and Construction Surveys.
Eng. News, Aug. 13, 20 and 27, 1903.
Schweizeriche Bauzeitung, March 14, 1908, by M. Rosenmund.

Lötschburg Tunnel, Switzerland.
Schweizeriche Bauzeitung, Aug. 26, 1911.

Vosburg, Pennyslvania, on Lehigh Valley Railroad.
"The Vosburg Tunnel," by Leo Von Rosenberg, 1887.

Cascade Tunnel, Washington, on Great Northern Ry.
Eng. News, Jan. 10, 1901, by John F. Stevens.

New Croton Aqueduct, New York.
Trans. A. S. C. E., Vol. XXIII, 1890, pp. 17–30, by F. W. Watkins.

New York Rapid Transit Subways.
Trans. A. S. C. E., Vol. XXIII, 1890, p. 31, by Edward Wegmann, Jr.
Eng. Rec. Sept. 19, 1903.
Eng. News, Dec. 4, 1902.
Eng. News, June 11, 1903.

Napean Tunnel, New South Wales.
Proc. Ins. of C. E., 1888, Vol. XCII, pp. 259–67, by T. W. Keele.

Gunnison Tunnel, Uncompahgre Valley Project, Colorado.
Eng. Rec., Aug. 28, 1909, by I. W. McConnell.

Cincinnati Water Works Tunnel.
Eng. Rec. March 4, 1905, by J. A. Hiller.

Hudson River Tunnel, Pennsylvania Railroad, New York.
Eng. News, Dec. 13, 1906, by James Forgie.
Eng. News, Feb. 28, 1907, by James Forgie.

East River Tunnels, New York.
Eng. Rec., July 28, 1906.

Little Tom Tunnel, Norfolk & Western Ry.
Eng. News, Apr. 19, 1900, by Emile Low.

Scranton Tunnel, Pennsylvania, on the Lackawanna & Wyoming Valley R.R.
Trans. A. S. C. E., May 1906, Vol. XVI, p. 221.

SURFACE SURVEYING.

381. SURFACE SURVEYING IN RUGGED MOUNTAIN REGIONS. — In accurate work, such as the surveying of mining claims for patent,* the ordinary mining transit may be used. Measurements are made with a steel wire tape, 300 to 500 feet long and marked every 10 feet (or 20 feet); it is used with a

* By patent proceedings is meant the proceedings necessary to obtain from the government a fee simple deed to the mining claim.

short auxiliary steel ribbon tape which is divided to hundredths of a foot. Over rough ground it is not practicable to measure horizontal distances by use of plumb-lines. Slope measurements are taken from the horizontal axis of the instrument to the point at which the telescope is sighted, care being taken not to overstretch the tape nor to kink it. (Art. 13, p. 9.) The most accurate work is done by stretching the tape with a tension handle (a spring balance) which can be attached by a clamp to any part of the tape. Where it is feasible, just enough tension is given so that the stretch of the tape compensates for the shortage due to sag. In some cases assistants will have to hold the middle point or the points at one-third and two-thirds the length of the tape up to the line of sight, giving at the same time enough pull to make the sag equal in the different sections of the tape.

In making general maps of a mining district, only monuments and important locations need be accurately shown. This accurate work which is the first to be done forms a skeleton on which to make a general map. The topography can be filled in by a transit fitted with stadia hairs and a compass.

The best topograhical data in mountainous country are obtained by running traverses along the ridges and valleys; these are also usually the best places to travel. Much sketching is necessary and the work should be plotted by the surveyor himself each day as the work proceeds. In this work a rough determination of the topography is sufficient, since the plans are usually plotted to the scale of $\frac{1}{10000}$ or smaller, and therefore such instruments as the hand compass, clinometer, and aneroid barometer can be used. With such instruments one man can do the entire work. The plane table cannot be used to advantage in wooded mountain or in mine surveying, but photographic surveying may often prove useful in filling in details of topography.

382. Mine Boundaries. — Appropriations Under United States Laws.* — In most countries mineral rights are defined by vertical planes through lines marked out on the surface. Title to metalliferous lands, however, as granted by the United

* For further information with regard to this subject see the Manual of Instructions for the Survey of the Mineral Land of the United States, issued by the Commissioner of the General Land Office, Washington, D.C.

States, conveys the right to all minerals included in the downward prolongation of the portions of veins cut off by the vertical end bounding planes, i.e., a vein can be worked in the dip indefinitely, but in the direction of the strike it is limited by the end bounding planes of the claim. This law has given rise to much litigation and there are still many unsettled points involved.

The Federal law allows a claim to cover 1500 feet located along the direction of a vein and 300 feet of surface ground on each side of it. These dimensions which constitute the maximum can be reduced by local laws. The ordinary method of locating a claim is shown in Fig. 161. The discovery being



FIG. 161. PLAN OF LODE CLAIM.

made at *D* the center line *WC-D-EC* is run and then the end lines *SE-NE* and *SW-NW* are put in, being made parallel with each other and straight. The side lines need not of necessity be parallel and are not usually run out on the ground.

A monument with explanations is placed at each of the seven points marked. If in a timbered country, the lines run should be blazed, and squared trees may be used as monuments. At *D* (Fig. 161) a location notice is posted, defining the boundaries of the claim and containing such explanation as would identify the claims in case of dispute. The miner usually makes the location survey himself, using approximate courses and distances. There is legally no objection to this work being done roughly, but when a patent survey comes to be made, neither the dimensions specified in the location notice nor the limits of the claim as marked off on the ground can be exceeded. So when the location survey is roughly made certain "fractions" of ground are not included, and these may cause much trouble, especially when "groups" of claims are located.

In such preliminary surveying, traverses may be run along courses where the sights can be conveniently taken; this may save much time and considerably simplify the work, especially in thickly timbered regions. In the description it is sufficient to state the approximate compass bearings of the boundaries. The center line and side lines need not be straight or parallel, but are assumed to be so unless marked with additional monuments. If, on account of the crookedness of the vein, it is advisable to make the center line of the claim a series of straight lines (like a traverse), this can be done, but the above mentioned conditions must be fulfilled with regard to the length and breadth of the claim and the two end lines must be parallel. In order to guard against troublesome litigation, an effort is sometimes made to surround a valuable claim with others, thus forming a "group." The more valuable claim is then protected as regards all "extralateral rights."

Flat deposits, such as coal and placer, are subject only to vertical bounding planes, and, provided the boundaries are approximately north and south lines, marked plainly on the ground, and the legal area is not exceeded, no difficulty need be encountered. The Federal law allows 20 acres to be taken for a placer claim but fixes no limits in regard to breadth or length. Local or state laws can regulate the size, provided the 20-acre limit per claim is not exceeded. The coal lands law is made subject to the general system of public land surveys for agricultural lands. (See Chapter V.)

383. SURVEYING FOR PATENT. — The surveying of claims for patent from the United States Government can only be obtained by those who have received appointment of United States Deputy Mineral Surveyor and they must have an order from the Surveyor General of the state or territory in which the claims are located before making any such survey.

In surveying for patent, much more accurate work has to be done than when merely locating a claim. After the shape of the claim as originally staked has been determined, the positions of the new corners and other boundary marks are computed and laid out on the ground. The original claim cannot anywhere be exceeded and usually has to be cut down so as to make the

end lines parallel and bring the dimensions of the claim within statutory limits. All this must be done accurately, the limit of error allowed being one in two thousand. Besides the marking of the boundaries on the ground, the position of at least one of the corners of each claim must be determined with reference to permanent monuments recognized by the government. The true meridian must also be determined by observations of the sun and all courses must be referred to it. The position of all buildings and surface improvement must be found and shown on the plot, and also the position of all corners of other claims for which a patent has already been applied. The surveyor must also make an estimate of the value of and describe all improvements, such as tunnels, shafts, open-cuts and other mining work done on the ground, and these should amount to not less than $500.00 worth per claim. The Manual of Instructions describes a great many other details which must be known to the Deupty Mineral Surveyor before his survey will be accepted, and defines the penalties attached to poor or dishonest work. Patented claims may overlap, and in fact do, in all mining districts, but in making application for patents to claims which lap on ground previously patented, the exact rights desired on the area of intersection must be defined.

Placer claims may be taken in 20-acre tracts, the bounding lines of which must conform with the general system of survey lines established by the Government, but if such survey has not been extended to the district, they must be bounded by true meridian and east and west lines. The survey of coal land is subject to somewhat similar rules.

PROBLEMS.

1. From a station at the mouth of a tunnel a line is run in the tunnel, azimuth 37° 24′, slope distance 424.34, vertical angle + 2° 10′, H.I. + 4.62, H.Pt. 0.0; thence azimuth 62° 42′, slope distance 278.53, vertical angle + 2° 18′, H.I. + 4.21, H.Pt. + 3.12, to breast. From the same station at tunnel a line is run on the surface, azimuth 98° 33′, slope distance 318.57, vertical angle − 3° 22′, H.I. + 4.87, H.Pt. 0.0; thence azimuth 38° 02′, slope distance 647.82, vertical angle + 14° 13′, H.I. + 4.73, H.Pt. 0.0, to the center of a vertical shaft. How deep must the shaft be to meet a connecting drift run on a grade of + 2.4% from a point in the floor at the breast of tunnel which is 7.0 ft. vertically under the roof point, and what is the slope length and azimuth of this drift?

2. The strike of a certain vein at point of outcrop is N 43° E and the dip is 71° 50′ to S.E. From this point of outcrop a surface line is run, N 83° 15′ E, slope distance 248.12, vertical angle − 12° 34′; thence S 2° 54′ E, slope distance 208.52, vertical angle − 14° 34′, to a point from which the tunnel is to be driven in the direction N 71° W and with a grade of + 3.8% until it intersects the vein. All vertical angles were taken to points above the station sighted equal to the distance the horizontal axis of the transit was above the station point under the instrument.

(*a*) What would be the slope length of such a tunnel?

(*b*) What would be the slope length and bearing of the shortest possible tunnel run on a + 1.3% grade to intersect the vein?

3. A vein has a strike of S 67° W and its dip is 55°. What is the bearing of a line lying in the plane of the vein and having a vertical angle of − 44°?

4. Given the following field notes.

Sta.	Pt.	Hor. Angle.	Slope Dist.	Vert. Angle.	H.Pt.	H.I.	Remarks.
O	X	0° 00′				+ 5.64	O = pt. in collar. X = pt. due S of Sta. O. Bearing O − 100 = due S
	100	0° 00′	106.21	− 67° 40′	+ 14.91		Pt. in roof
O	100	0° 00′				+ 5.64	
	1	89° 40′	308.95	0° 00′	− 5.41		Pt. on collar
100	0	0° 00′				− 15.12	
	101	269° 50′	80.74	+ 1° 04′	+ 2.61		Pt. in roof
101	100	0° 00′				− 3.22	
	102	175° 40′	113.40	+ 0° 27′	+ 2.18		Pt. in roof
1	0	0° 00′				+ 5.41	
	103	90° 20′	105.01	− 67° 07′	+ 15.02		Pt. in roof
103	1	0° 00′				− 13.13	
	104	94° 16′	99.98	− 1° 06′	− 3.71		Pt. in tie in floor

All horizontal angles were measured clockwise, the first pointing being made on the B.S.

Compute the horizontal distance and slope distance, to nearest .01 ft., from Sta. 102 to 104.

Compute the vertical angle and bearing, to the nearest minute, from Sta. 102 to Sta. 104.

5. A vertical winze has been sunk below the level of a tunnel. It is desired to sink a vertical shaft from the surface to connect with the winze. Station X is established at the mouth of the tunnel and Station Y is near the site of the proposed shaft. Y bears S 88° 58′56″ W, 896.79 ft. from X. The following are the notes of the survey reduced to horizontal distances connecting X and the winze corners A, B, C, and D:

Instrument Station.	Mean Deflection.	Horizontal Distance.	Stations Sighted.
X	0° 00′	896.79	Y
X	45° 05′ 34″ R	403.08	1
1	74° 05′ 06″ L	587.20	2
2	32° 23′ 43″ L	67.00	3
3	54° 43′ 47″ R	44.80	4
4	39° 51′ 57″ R	41.07	5
5	31° 10′ 10″ R	19.57	Cor. A
	31° 10′ 10″ R	27.24	Cor. B
	31° 43′ 40″ R	21.47	Cor. C
	24° 02′ 40″ R	25.77	Cor. D

Required the bearings and horizontal distances from Y to points vertically over the winze corners.

6. From Station M at the mouth of a tunnel a traverse is run in the tunnel, azimuth 20° 35′, distance 352.16, vertical angle + 1° 02′, H.I. + 4.71, H.Pt. + 3.42 to point A; thence azimuth 61° 07′, distance 528.24, vertical angle + 0° 40′, H.I. − 3.62, H.Pt. + 4.07, to point B at the breast of the tunnel. From M a surface traverse is run, azimuth 25° 10′, distance 578.34, vertical angle + 4° 25′ to point C; thence azimuth 11° 16′, distance 407.62, vertical angle + 14° 20′ to point D, which is the center of a vertical shaft 120 ft. deep. In sighting surface points the vertical angles were in all cases read to points above the stations sighted equal to the distance the horizontal axis of the telescope was above the station point under the instrument.

Find the azimuth, vertical angle and slope distance of the line from the point at the bottom of the shaft to the roof point at breast of the tunnel.

7. Assuming the transit to be in perfect adjustment what is the error in horizontal angle in sighting down a 500-ft. shaft, when the vertical angle is − 89° and the telescope cannot be sighted closer than 3 seconds along the inclined line?

8. A vein has a dip of 38° to the W. and a strike of N 9° 35′ E. A drift in vein is driven N 14° 30′ E. What is the per cent. of grade of the drift?

9. A drift is constructed N 38° E on a 3% grade in the plane of a vein whose strike is N 57° E. What is the dip of the vein?

10. A vein has a dip of 57°. A drift is driven N 37° W in the plane of the vein on a grade of 5%. What is the strike of the vein?

PART III.

COMPUTATIONS.

PART III.

COMPUTATIONS.

CHAPTER XIII.

GENERAL PRINCIPLES. — MISCELLANEOUS PROBLEMS. — EARTHWORK COMPUTATIONS.

384. GENERAL REMARKS. — The ultimate purpose of many surveys is to obtain certain numerical results to represent quantities such as areas or volumes. In the section on Surveying Methods it has been pointed out that in all surveys there should be a proper relation between the precision of measurement of the angles and distances. To secure final results to any given degree of precision, the measurements in the field must be taken with sufficient precision to yield such results. In computing from a given set of field notes the surveyor should first determine how many places of figures he should use in the computations, the aim being to obtain all the accuracy which the field measurements will yield without wasting time by using more significant figures than are necessary. Professor Silas W. Holman* in the preface to his "Computation Rules and Logarithms" says:— "It would probably be within safe limits to assert that one-half of the time expended in computations is wasted through the use of an excessive number of places of figures, and through failure to employ logarithms."

Final results should be carried to as many significant figures as the data will warrant and no more. In order to insure the desired precision in the last figure of the result it will usually be necessary to carry the intermediate work one place further than is required for the final result.

385. The number of significant figures in the result of an observation is the number of digits which are known. For instance, if a distance is recorded as 24,000 ft. when its value was

* See "Computation Rules and Logarithms," by Professor Silas W. Holman, published by Macmillan & Co., New York.

obtained to the nearest thousand feet only, it contains but two significant figures. The zeros are simply put in to show the place of the decimal point. If, however, the distance has been measured to the nearest foot and found to be 24,000 ft. there are five significant figures, for the zeros are here as significant as the 2 or 4. Similarly a measurement such as 0.00047 contains but two significant figures, the zeros simply designating the position of the decimal point, for, had this same value been recorded in a unit $\frac{1}{100,000}$ as large the result would have been 47.

Again, if a series of rod-readings are taken on different points to thousandths of a foot and three of the readings are 4.876, 5.106, and 4.000 it is evident that each of these readings contains four significant figures; if each of them is multiplied by 1.246 the respective results are 6.075, 6.362, and 4.984. But had the results been measured to the nearest tenth of a foot and found to be 4.9, 5.1, and 4.0 these values when multiplied by 1.246 should appear as 6.1, 6.4, and 5.0. This illustration indicates the proper use of significant figures. Since the rod-readings 4.9, 5.1, and 4.0 are reliable only to about 1.5 to 2 per cent. the multiple 1.246 should be used in this computation as 1.25. Similarly in the use of such a constant as $\pi = 3.1415927$ it is a waste of time to use any more significant figures in the constant than exist in numbers with which the constant is to be combined in the computation.

386. In deciding how many places of decimals to use in the trigonometric functions the student should examine the tabular differences and determine what percentage error is introduced by any error in an angle. For example, suppose an angle of a triangle to have been measured in the field to the nearest minute. There may be an error of 30 seconds in this angle, and it will be seen from the table of natural sines that the tabular difference for one minute in the fourth decimal place varies from 3 for a small angle to less than 1 for a large angle, and that the variation is about the same for cosines, and for tangents and cotangents of angles under 45°. Then for half a minute the difference will be, on an average, about 1 in the fourth place. Therefore, in general, four places will be sufficient when the angles have been measured to the nearest minute only. But if there are several steps in the computations it may be advisable to use

five-place tables. Similarly it can be seen that five-place tables of functions will, in general, give angles to the nearest 10 seconds, and six-place tables to the nearest second. These are only average results and are intended to give the student a suggestion as to how to decide for himself whether to use four, five, or six-place tables. It is obviously a great saving of time to use four-place tables where four places are needed rather than to use six or seven-place tables and drop off the last two or three digits. The amount of labor increases about as the square of the number of places in the tables, i.e., work with 6-place tables: work with 4-place table = 36 : 16.

387. The following simple examples illustrate the uselessness of measuring the distances with a precision which is inconsistent with that of the angles, when the angles are to be used in the computation of other distances. Given the measurements shown on Fig. 162. If the angle B was measured to the nearest minute only there may be an error of 30 seconds in this angle and the tabular difference for 30 seconds for the sine and cosine of this angle in four-place tables is 0.0001; therefore use four-place tables. In this case it is evident that the 0.02 on the hypotenuse distance is of no value whatever in determining the length of the other two sides a and b, that the 0.6 being the fourth significant figure should be retained, and that the resulting length of a or b will not be reliable to more than four significant figures.



FIG. 162.

$$\begin{aligned} \log 773.6 &= 2.8885 & \log 773.6 &= 2.8885 \\ \log \cos 44°12' &= \underline{9.8555} & \log \sin 44°12' &= \underline{9.8433} \\ \log a &= 2.7440 & \log b &= 2.7318 \\ a &= 554.6 & b &= 539.3 \end{aligned}$$

If it is assumed, however, that the angle B is measured by repetition and found to be 44° 12′ 25″ the error in the original angle then was about 25″. By using the same value for the hypo-

tenuse (773.6) and six-place tables to secure greater precision the value of a is 554.5 and of b 539.4 Comparing these results with those obtained above will give a good idea of the error in length of these lines due to reading the angle to the nearest minute only and also a proper conception of the fallacy of computing with tables of more than four places when the angles are read to the nearest minute only. The difference between the values of a and b obtained by use of the angle $44^\circ\ 12'$ and similar results by use of $44^\circ\ 12'\ 25''$ is due entirely to the $25''$ and not to the fact that four-place tables were used in the former case and six-place tables in the latter, for in both cases the result has been obtained to four significant figures only.

It is also evident that when the angle B was measured to the nearest minute it was inconsistent to measure the hypotenuse closer than to the nearest tenth of a foot. But if angle B was measured to the nearest 10 seconds the line AB should have been measured to the nearest hundredth. It should not, however, be assumed that in all cases where angles are only measured to the nearest minute the sides should be recorded to tenths of a foot. The precision of measured distances and angles should be so related that their respective errors should have equal effects upon the computed results. As a general statement it may be said that when the angles are read to nearest minute only, the sides should be measured to four significant figures; with angle to nearest 10 seconds they should be measured to five significant figures; and with angles measured to 1 second the sides should be measured to six significant figures. Where small angles are involved in the computations they must be measured with greater precision. All the sides of a triangle of considerable size might be measured to hundredths of a foot, the angles being recorded to the nearest minute only, and the distances used for the computations, the angles serving merely as checks; this, of course, is practicable at times.

388. In Fig. 163 we are to determine the length of a long line from a short one and the error in the short line is therefore multiplied several times. The same degree of precision should be secured



FIG. 163.

in the measured line BC as is desired in the computed lines AC or AB, which, it is assumed in this case, is required to four significant figures. In order that the measurements of line BC and angle A may be consistent with the precision of the required result, BC should be measured to the nearest hundredth of a foot and angle A to the nearest quarter of a minute, because the tangent of angles of about 4° varies .0003 per minute. In this computation four-place tables should be used and the value obtained for AC or AB should be recorded only to four significant figures.

$$\begin{aligned} \log 12.34 &= 1.0913 \\ \log \tan 3°56' &= \underline{8.8373} \\ \log AC &= 2.2540 \\ AC &= 179.5 \end{aligned}$$

If AC is desired to the nearest hundredth of a foot the angle A must be determined closely by repetition, but this will not give the length AC to the nearest hundredth unless BC has been measured closer than to the nearest hundredth; for, suppose there is an error of 0.005 ft. in the measurement of BC, then the line AC being about 15 times as long as BC will have an error of 0.075 ft. no matter how exact the angle at A may be measured. In other words, if AC is desired correct to five significant figures BC should contain five significant figures. Evidently the practical way of obtaining an exact value for the inaccessible distance AC is to measure AB to the nearest hundredth, and to compute AC from AB and BC, using the angle at A as a check on the measured distances. In both of the above examples it is assumed that the 90° is exact.

389. Logarithmic or Natural Functions. — The question as to whether logarithmic or natural functions shall be used will depend upon the computation in hand. Many surveyors have become so accustomed to using naturals that they will often use them when logarithms would require less work and offer fewer opportunities for mistakes. Each method has its proper place, and the computer must decide which will be the better in any given case. The use of logarithms saves considerable time spent in actual computation because the process is

simpler, but, on the other hand, looking up the logarithms consumes time. The result is in many cases, however, a saving of time over that required to do the arithmetical work of multiplying or dividing. While the multiplication of two numbers of three or four digits each can possibly be done directly more quickly than by logarithms, still it takes more mental effort and there is more opportunity for making mistakes; but in case several such multiplications are to be made logarithms are almost always preferable. Furthermore when there are several multiplications of the same number logarithms will save time since the logarithm of this common number has to be taken from the table but once. Frequently, however, the computation is so simple that the use of logarithms would be almost absurd, e.g., the multiplication of any number by a simple number like 20, 25, 150, or 500. If a function of an angle is to be multiplied or divided by any such number the natural function should of course be used.



$\text{Vers } A = \frac{CD}{AB}$

$\text{Exsec } A = \frac{EB}{AC}$

FIG. 164.

390. SHORT CUTS.—The solution of a right triangle, when one of the angles is small, involving the use of the cosine of this small angle, can often be more easily obtained by the use of the versed sine or external secant of the angle. In Fig. 164

$$AB = 207.42$$
$$A = 7^\circ\ 32'$$
$$AC = 207.42 \cos 7^\circ\ 32' \qquad (1)$$
$$\text{But } AC = AB - CD$$
$$= 207.42 - 207.42 \text{ vers } 7^\circ\ 32' \qquad (2)$$
$$= 207.42 - 207.42 \times 0.00863$$
$$(207.42 \times 0.00863 = 1.79, \text{ by slide rule.})$$
$$= 207.42 - 1.79$$
$$= 205.63$$

Obviously, when the angle is quite small, the result of the multiplication indicated in (2) can be taken from the table to the nearest hundredth of a foot with much less effort than is required for the computation called for in (1). In fact, the computation in (2) can often be done more quickly by the use of natural numbers than by logarithms, and in most cases the slide rule will give results sufficiently exact (Art. 394, p. 378).

Had AC been given (205.63) and the angle A, ($7^\circ\ 32'$) then

$$AB = \frac{205.63}{\cos 7^\circ 32'},$$

$$\text{But } AB = AE + EB$$

$$= 205.63 + 205.63 \quad \text{exsec } 7^\circ 32'$$

$$= 205.63 + 205.63 \times 0.00871$$

$$(205.63 \times 0.00871 = 1.79, \text{ by slide rule.})$$

$$= 205.63 + 1.79$$

$$= 207.42$$

391. There are many "short cuts" in arithmetical work which are of great value to the computer, and the student should endeavor to learn the most common and simple ones. The following are a few illustrations.

$$247 \times 25 = \frac{247 \times 100}{4} = \frac{24700}{4}$$

$$682 \times 50 = \frac{68200}{2}$$

$$694 \times 150 = 69400 + 34700$$

$$927 \times 62.5 = 92700 \times \frac{5}{8}$$

$$672 \times 1002.3 = 672000 + 1344 + 201.6$$

$$547 \times .9968 = 547\ (1 - .0032) = 547 - 5.47 \times .32$$

$$\frac{43}{60} = \frac{4.3}{6} \text{ (reducing minutes to decimals of a degree)}$$

$$\frac{843}{12.5} = 8.43 \times 8$$

The student should cultivate the habit of performing mentally as much of the work as can be done without fatigue, delay, or danger of mistakes. No hard and fast rule can be laid down in this matter, as some persons have more aptitude than others for work of this kind. Such subtractions as $180° - 36° 47' 18''$ should always be performed mentally. Also in taking the co-logarithm of a number from a table of logarithms the result should be written down directly.

392. ARRANGEMENT OF COMPUTATIONS. — All surveying computations should be kept in a special computation book. At the head of the page should appear the title of the work, the number and page of the field note-book from which the data are copied, the names of the computer and checker, and the date. The work should be arranged neatly and systematically so that every part of the computations can be traced by any one who is familiar with such work. Where possible the work should be so arranged that numbers will have to be written but once. Each important value, each column, etc. should be labeled so that it can be readily found.

393. CHECKS. — It is very important that all calculations should be checked, not merely at the end of the computation but also at as many intermediate steps as possible. In this way a great waste of time may be prevented and serious mistakes avoided. One good method of checking is to perform the operations when possible by two independent methods, for example, by the use of logarithms and by natural functions. Very often two men do the computing, one man's work acting as a check on that of the other. The two may each work by the same or by different methods, and the results may be compared at intervals. **Every part of the work should be done independently, from the copying of data out of the note-book to the final results.** It is not uncommon to find two men computing the same area where only one of them looks up the logarithms. In case a mistake is made in looking up the logarithms the results may check but both are wrong. The computer should also check his work roughly by estimating approximately what the result should be.

394. SLIDE RULE. — A valuable aid in checking calculations is an instrument known as the *slide rule*, which enables the computer

to multiply and divide numbers by logarithms by a purely mechanical process. It is really the equivalent of a table of logarithms. It consists of a wooden rule, usually about 10 inches long, having a groove in one side in which runs a small wooden strip called the slide. On one face of the rule are placed two scales, *A* and *D*, Fig. 165, one above and one below the slide *BC*. These are constructed by plotting logarithms of numbers by subdividing a unit of some convenient length, say 10 inches. For example, the log of 1 is 0, so this is taken as the left end of the scale and the number 1 placed at this point. The log of 2, to three significant figures, is 0.301, and a line is placed therefore at a distance equal to .301 of the 10 inches, or 3.01 inches, and marked with the number 2. Similarly at 4.77 (log 3 = 0.477) a line is marked 3. The space between 1 and 2 is subdivided by plotting log 1.1, log 1.2, etc. The subdivision is continued until the spaces are as small as will admit of rapid and accurate reading of the scale.

It is customary to make the spacing on the upper scale just half that on the lower, i.e., if 10 inches is chosen as the unit for the lower scale, then the unit for the upper scale will be 5 inches. Since the length of this upper scale is only half the length of the rule there are usually two scales exactly alike marked on the upper part of the rule, the right end of one coinciding with the left end of the other.

On the slide are two scales, *B* and *C*, exact duplicates of *A* and *D* on the rule. A *runner* is usually attached to the rule for convenience in setting and reading the scales. This runner is a small metal slide which fits over the face of the rule in such a way that it can be slid along the



FIG. 165.



FIG. 166.

rule and set at any reading of the scale. It is usually provided with a fine line running crosswise of the rule which is used in marking the exact setting.

Multiplication or division of numbers is performed by adding or subtracting the scale distances corresponding to these numbers. Adding two scale distances is, in effect, adding two logarithms. For example, if the left end of scale *C*, Fig. 166, is set opposite the number 2 of the scale D, then opposite the number 3 on scale *C*, is found the product, 6, on scale *D*. The distances which have been added are those corresponding to log 2 and log 3 respectively. The sum of these distances is the distance corresponding to log 6. Division is performed by placing the divisor on scale *C* over the dividend on scale *D* and reading the result, opposite the end of the scale *C* on the scale *D*.

Fig. 166 shows the position of the scales for dividing 6 by 3. The scales *A* and *B* may be used in a like manner. It is evident that, by setting the runner on the result of one operation and then moving the slide so that one of its ends coincides with the runner setting, continued multiplication and division can be performed without the necessity of reading intermediate results.

Scale *D* may be used in connection with scale *A* for obtaining squares or extracting square roots. Since the spaces on scale *A* are one-half those on scale *D* the number 4 on scale *A* is opposite number 2 on scale *D*, 9 is opposite 3, and so on, every number on scale *A* being the square of the corresponding number on scale *D*. Other scales, generally log sines and log tangents, are placed on the reverse side of the slide, so that trigonometric calculations can also be performed with this instrument. Results

obtained with the ordinary 10 inch slide rule are usually correct to 3 significant figures, so that this slide rule is the equivalent of three-place logarithm tables.

395. Thacher Slide Rule. — The Thacher slide rule consists of a cylinder about four inches in diameter and eighteen inches long working within a framework of triangular bars. On these bars is fastened a scale corresponding to the scale on an ordinary slide rule, and on the cylinder is marked another scale like that on the bars. The cylinder is the **slide** and the triangular bars form the **rule.** This rule is operated in a manner similar to the one explained above. Results can be obtained with it which are correct to four and usually to five significant figures.

396. REDUCING THE FIELD NOTES FOR COMPUTATIONS. — Before any of the computations are made the measurements taken in the field frequently have to be corrected on account of erroneous length of tape. This correction can usually be made mentally when the distances are transcribed into the computation book. The errors in the angles are balanced by altering the value of those angles which were taken from short sights since the angular errors are most likely to occur in these. In some cases, where it has been found desirable to take measurements on a slope, these distances are reduced to horizontal distances by multiplying them by the versed sine of the vertical angle and subtracting the result from the **corrected** slope distance, the correction for error in the tape being made **before** this is done. Sometimes instead of a vertical angle the slope distance and the difference in elevation between the points are the data contained in the field notes. In this case the formula given in Art. 20, p. 12, should ordinarily be used.

397. CURVED BOUNDARY BY OFFSETS. — The offsets to the brook (Fig. 53, p. 104) were taken at regular intervals in one portion of the survey and in another portion offsets were taken at the points where the direction of the brook changes. The offsets which were taken at regular intervals give a series of trapezoids with equal altitudes the area of which can be obtained by one computation. Although there are several approximate rules for this computation the two most common are what are known as the *Trapezoidal Rule* and *Simpson's One-Third Rule.*

398. Trapezoidal Rule. — If the figure is considered as made up of a series of trapezoids their area can be found by the following rule: —

$$\text{Area} = d\left(\frac{h_e}{2} + \Sigma h + \frac{h'_e}{2}\right)$$

where d = common distance between offsets,
h_e and h'_e = end offsets of the series of trapezoids,
and Σh = sum of the intermediate offsets.

399. Simpson's One-Third Rule. — In the development of this formula the curved line is assumed to be a parabolic curve. It is claimed by some that this affords results more nearly correct than the Trapezoidal Rule, although for most problems of this kind, where the offsets at best can give but an approximate location of the boundary, frequently a brook or crooked wall the center of which must be estimated, it is quite probable that the Trapezoidal Rule is sufficiently exact. Simpson's One-Third Rule is as follows: —

$$\text{Area} = \frac{d}{3}(h_e + 2\Sigma h_{\text{odd}} + 4\Sigma h_{\text{even}} + h'_e)$$

where d = common distance between offsets,
h_e and h'_e = end offsets of the series,
$2\,\Sigma\, h_{\text{odd}}$ = twice the sum of all the odd offsets (the 3d, 5th, 7th, etc., from the end)
$4\,\Sigma\, h_{\text{even}}$ = four times the sum of all the even offsets (the 2d, 4th, 6th, etc., from the end).

For this rule to apply there must be an **even** number of trapezoids; if there is an odd number, an even number of them may be computed by this rule and the extra trapezoid must be computed separately. Or, if there is a triangle or trapezoid at the end of this series, which has a base greater or less than d, it must also be computed separately.

Fig. 167 shows the computation of a series by both methods and also the computation of several trapezoids and triangles at the ends of the series. The data are taken from the field notes in Fig. 53, p. 104.



FIG. 167.

400. STRAIGHTENING CROOKED BOUNDARY LINES. — In Fig. 168, $AEFGH$ represents a curved boundary between two



FIG. 168. STRAIGHTENING A CROOKED BOUNDARY.

tracts of land, and it is desired to run a line from A so as to make the boundary a straight line and to leave each tract of the same area as before.

The trial line AB is first run, and the distance AB, the angles at A and B, and the necessary offsets to the curved boundary are measured in the field. Then the areas of the property between this trial line and the curved line are computed as explained in the previous articles. The sum of the fractional areas on one side of the trial line and the sum of the areas on the other side of it should be equal. If not made so by the trial line, the difference between these sums is the area of a correction triangle ABC which must be taken from one tract and added to the other because the trial line has taken this difference from one of the tracts and it should therefore be restored. The area and the base AB being known the altitude dC can be computed. Then in the triangle ABC, the lines BC and AC and the angle at A are calculated; and the line AC is staked out, its calculated length being checked by measuring the line AC in the field and the angle at A being checked by the measured distance BC.

401. AREA BY TRIANGLES. — If the field has been surveyed by setting the transit in the middle of the field and taking angles between the corners (Art. 138, p. 105), the areas of the triangles may be found by the trigonometric formula:

$$\text{Area} = \tfrac{1}{2}\, a\, b \sin C,$$

where C is the angle included between the sides a and b.

If all three sides of any of the triangles have been measured

or if the field has been surveyed with the tape alone (Art. 139, p. 106), the area of the triangles can be found by the trigonometric formula: —

$$\text{Area} = \sqrt{s\,(s-a)\,(s-b)\,(s-c)}$$

where a, b, and c are the sides and $s = \dfrac{a+b+c}{2}$.

402. AREA OF A QUADRILATERAL BY TRIANGLES. — Most city lots have four sides, and while the Double Meridian Distance Method (Art. 419, p. 400) is often employed in computing their areas, it is not at all uncommon in computing such quadrilateral lots to divide them into triangles, checking the fieldwork and computations, and computing the areas by triangles.

In Fig. 169, $ABCD$ represents an ordinary city lot in which all the sides and angles have been measured. It is evident that the diagonal BC can be computed either from BD, CD, and the angle D, or from AB, AC, and the angle A. These two determinations of BC should check each other. Similarly two independent determinations of AD can be found. These evidently check all the fieldwork and calculations as far as they have gone. In computing these triangles the best way is to resolve all the work into right triangle calculations, as suggested by the dotted lines on the figure.



FIG. 169.

Not only is this method more simple than to use the oblique triangle formulas, but it gives at the same time altitude distances which are useful in computing the area of the lot. The area can be obtained by calculating the area of one pair of triangles and readily checked by calculating the other pair.



FIG. 170.

403. AREA OF CURVED CORNER LOT. — In Fig. 170 *ABFHGDE* is the boundary of a corner lot, all the angles and distances of which have been determined in the field. The area of *ABCDE* can be easily computed by the method explained in Art. 419, p. 400. Then the area of *FCGH* must be subtracted from the traverse area. The angle *I* is known and the radius *KF* of the curve is given or can be computed from data such as *CH* or *CF* obtained in the field (Art. 282, p. 267).

$$KFHG = \frac{FHG \times HK}{2} = \frac{I^\circ \times 0.0174533\,^* \times (HK)^2}{2}$$

$$KFCG = FC \times FK$$

$$FCGH = KFCG - KFHG$$

$$= KG(CG - KHG \div 2)$$

The area of *FCGH* could have been calculated by computing the area of the triangle *FCG* and then subtracting the area of the segment *FHG* from it. The area of this segment, however, cannot be calculated accurately by any short formula. An approximate formula for the area of a segment is

Area of Circular Segment $= \frac{2}{3} MC$ (approximate), where *M* is the middle ordinate and *C* is the chord length.

$$M = \frac{C^2}{8R}\,\dagger \text{ (approximately).}$$

Expressed in terms of *C* and *R*,

$$\text{Area of Circular Segment} = \frac{C^3}{12R} \text{ (approximately).}$$

* The length of the arc of curve whose radius is 1 and whose central angle is 1° is 0.0174533, which will give results to six significant figures, provided *I* and *R* are correct to six significant figures. (See Table VII, p. 556.)

† In Fig. 171, *OB* = Radius of circular curve.
CH = Middle Ordinate for chord *AB*.
CD is drawn tangent to the curve.

These formulas are fairly accurate when M is very small as compared with C. They are most useful, however, as a check on computations made by the prec ding method.

404. ROUGH CHECKS ON AREAS. — If the traverse has been plotted to scale, it can be easily divided into simple figures such as rectangles or triangles, their dimensions scaled from the plan, and their areas computed, thereby giving an independent rough check on the area.

A piece of tracing cloth divided into small squares can be placed over the plan of the traverse and the number of squares counted and the fractional parts estimated, generally to tenths of a square, by inspection. Then the area of one square being known an approximate area of the traverse may be obtained.

405. Planimeter. — One of the commonest ways of checking the area of a traverse is to obtain its area by means of an instru-

---

DB = Tangent Offset for chord CB.
OE is drawn perpendicular to CB.
In the two similar triangles OEB and CBD,

$$DB : CB = BE : OB$$

$$DB : CB = \frac{CB}{2} : OB$$

$$DB = \frac{CB^2}{2\,OB}$$



FIG. 171.

$$\textbf{Offset from Tangent} = \frac{(\textbf{Chord})^2}{2 \times \textbf{Radius}} \quad (1)$$

But $DB = CH$, and $AB = 2 \times CB$ (approximately)

$$\therefore CH = \frac{\left(\frac{AB}{2}\right)^2}{2\,OB} = \frac{AB^2}{8\,OB} \quad \text{(approximately)}$$

$$\textbf{Middle Ordinate} = \frac{(\textbf{Chord})^2}{8 \times \textbf{Radius.}} \quad \text{(approximately)} \ (2)$$

The following will give some idea of the accuracy of this formula:

When radius = 20 ft. and chord = 10 ft., M = 0.625, (correct value is 0.635).
When radius = 100 ft. and chord = 25 ft., M = 0.781, (correct value is 0.784).
When radius = 100 ft. and chord = 100 ft., M = 12.500, (correct value is 13.397).
When radius = 1000 ft. and chord = 100 ft., M = 1.250, (correct value is 1.251).

It is evident from the above that this formula will not give accurate results when the chord is large in comparison with the radius.

ment called the *planimeter*. It is a small instrument consisting of an arm, carrying a tracing point, which is fastened to the frame of the instrument; the arm can be adjusted to any desired length. The frame touches the paper at only three points; the anchor point, the tracing point, and the circumference of a small wheel which is free to revolve. On the rim of this wheel is a scale and beside it is a vernier which is used in reading the scale. The length of the arm can be regulated by setting it at the proper reading on a scale which is marked on the arm, so that a unit on the wheel scale will represent any desired unit area such as a square inch or a square centimeter. (See Appendix A on the Planimeter.)

In using the instrument the anchor point is set at some convenient position on the drawing **outside** of the area to be measured and then the tracing point is run around the perimeter of the area to be determined. The reading on the wheel is recorded when the tracer is at the starting point. The tracer, in passing around the perimeter, should be kept as **closely as possible** on the boundary line and should return **exactly** to the starting point. Then the scale is again read, and the difference between the two readings is the area which has been traced out, expressed in some unit depending on the length of the arm. The result can be easily transposed into the unit of the scale of the map.

Usually the settings for the scale on the arm are furnished by the maker for various units of area. It is safer to test this setting by running the instrument around a known area, such as 4 square inches and determining the interval passed over by the wheel by making several tests and by setting the anchor point at different positions. This interval divided by 4 will be the value of one square inch of plan area and this is equivalent to a certain number of square feet of surface, depending upon the scale of the map. It is important that the sides of the trial square should be laid off so that they agree with the present scale of the map which, owing to swelling or shrinking of the paper, is frequently not quite the same as when it was first drawn (Art. 514, p. 476).*

* When areas are desired from U. S. Geological Survey maps on which are shown parallels of latitude and longitude it is best to refer all planimetered areas to the areas of a quadrilateral, say, 1° on a side. The area of such quadrilateral

406. DEFLECTION ANGLES AND CHORDS FOR A CIRCULAR CURVE. — The computations shown in Fig. 172 refer to the notes in Fig. 119, p. 271. In the discussion of the simple curve as



FIG. 172.

can be taken from a publication entitled Geological Tables and Formulas, by S. S. Gannett, Bulletin No. 232, U. S. Geological Survey, and by simple proportion the desired area found.

applied to city surveying (Art. 284, p. 268) will be found the formulas which have been used in the computations in Fig. 172. The length of the curve L_c is found by taking from Table VII ("Lengths of Circular Arcs: Radius = 1"), the length of an arc for 51°, for 35′, and for 20″ successively and adding them, which gives the arc of a curve whose radius is 1 and whose central angle is 51° 35′ 20″. This is then multiplied by the radius (200) which gives the value of L_c, which is added to the station of the P.C. to obtain the station of the P.T.

407. COMPUTATION OF OBSERVATIONS. — The computations relating to observations for meridian and latitude will be found in Chapter VIII.

COMPUTATION OF VOLUME.

408. BORROW-PITS.* — Fig. 173 is a plan of a portion of a borrow-pit, at the corners of which the depth of excavation is marked in feet and tenths. Each of the regular sections of earthwork is a truncated rectangular prism whose volume is equal to the average of the four corner heights multiplied by the area of the cross-section, or expressed as a formula,

$$\text{Volume Truncated Rectangular Prism} = A \times \frac{h_1 + h_2 + h_3 + h_4}{4}$$

where A is the area of the cross-section and h_1, h_2, h_3, and h_4 are the corner heights.

For a truncated triangular prism such as *abc*, using the same notation,

$$\text{Volume Truncated Triangular Prism} = A \times \frac{h_1 + h_2 + h_3}{3}.$$

In computing a trapezoidal prism, such as *fdhg*, the trapezoid is subdivided into a rectangle *fehg* and a triangle *fde*; or for *jhds*, into two triangles by diagonal lines, as *jhs* and *hds* and their volumes may be computed by the above formula.

When there are several prisms with the same cross-section, as shown in Fig. 173, these rectangular prisms can be computed as one solid by assembling them as follows: — multiply each corner

* For a complete discussion of the computation of Borrow-Pits see Railroad Curves and Earthwork by Professor C. F. Allen, published by McGraw-Hill Book Company, New York.

height by the number of rectangular prisms in which it occurs and then add these results and divide by 4. This is then multiplied by the area of the cross-section of one prism. For example, in Fig. 173, the quantity bounded by *amnrsja* can be found by



FIG. 173. PLAN OF PORTION OF A BORROW-PIT.

one computation because it is composed of a series of prisms having the same cross-section. In the summation of the heights, those at *a*, *m*, *n*, *r*, and *s* are taken but once, those at such points as *c*, *g*, *h*, etc. are multiplied by 2, at *j* the height is multiplied by 3, and at such points as *k* it is multiplied by 4.

Where the excavation is completed to a certain level, as in a cellar, it is a special case of above. The area of the cellar can be

divided into rectangles, their corner heights taken, and from these the volume can be computed.

409. VOLUME OF PRISMOID. — The data obtained from field notes are usually in the form of cross-sections which are taken at right angles to some general line of the construction, thereby dividing the earthwork into prismoidal solids with their bases parallel and their sides either plane or warped surfaces.

410. End Area Formula. — The simplest method of computing the volume of a prismoidal solid is to average the areas of the two bases and multiply by the distance between them, i.e.,

$$V = \frac{A_1 + A_2}{2} \times l \qquad (\textit{End Area Formula})$$

in which A_1 and A_2 are the areas of the two end bases and l is the distance between them. This method is used to a very great extent throughout the country, although it does not give sufficiently accurate results for certain classes of work.

411. Prismoidal Formula. — The correct volume of a prismoid is expressed by the *Prismoidal Formula:* *

$$V = \frac{l}{6}(A_1 + 4A_m + A_2)$$

in which l is the distance between the two bases, A_1 and A_2; and A_m is the "*middle area*," i.e., the area half-way between the two bases, which, when their dimensions are given, is obtained by averaging the corresponding dimensions of the two end areas, A_1 and A_2; it should **not** be taken as the mean of A_1 and A_2.

412. The end areas can easily be computed from the field notes by dividing them into triangles as in Fig. 174.



FIG. 174.

* For demonstration see "A Course in Mathematics," by Woods and Bailey, Vol. II, Art. 39, p. 74.

Notes of section: $\frac{29.0}{+6\,0}$ $+\ 4.0$ $\frac{21.5}{+1.0}$

$$\text{Area} = \frac{4 \times (21.5 + 29)}{2} + \frac{20 \times (1 + 6)}{2}$$
$$= 2 \times 50.5 + 10 \times 7 = 171.$$

It is also the custom with some surveyors to plot each section carefully to scale and to obtain its area by use of the planimeter (Art. 405, p. 387). This is probably the most practical method when the sections are very irregular since the field work does not warrant the use of very accurate methods.

There are several other methods employed in computing earthwork but the above are by far the most common.

Several sets of Earthwork Tables and Diagrams have been published which reduce the work of computation very materially.

413. ESTIMATES FOR GRADING.— Estimates for grading may be conveniently made by means of a topographic map. On this map will appear the contours of the original surface. The contours representing the finished surface are also sketched upon the map, and the smaller the interval between the contours the more accurate will be the result. In Fig. 175 the full lines represent the contours of the original surface which is to be altered so that when the necessary cutting and filling has been done the new surface will have the appearance indicated by the dash contours. At contour 20 and at contour 25 no grading is to be done. On the plan, first sketch the lines *ABCDEF* and *AGHIJB* which are lines of "no cut" and "no fill," i.e., lines which enclose areas that are either to be excavated or filled. The amount of excavation and embankment must be computed separately. In sketching such lines the lines *AB*, *ED*, and *HI*, as will be seen, follow the intersection of the original contours with the new ones, since at these points there is no cut or fill. There are no direct data on the plan which define where the earthwork ends at *C* but the assumption is here made that the fill will run out to meet the original surface at about the next contour at *C*. In this example the fill must run out somewhere between the 24-ft. contour and the 25-ft. contour, for if it ran beyond the 25-ft.

contour there would be another new 25-ft. contour shown on the plan. Therefore the line *BCD* has been sketched to represent the limits of the fill in that vicinity; similarly *EFA*, *AGH*, and *IJB* have been sketched.

There are three general methods of computing the earthwork from the data given on the plan; (1) by computing directly the amount of cut or fill between successive contours, (2) by



FIG. 175.

assuming a horizontal plane below the lowest part of the earthwork and computing the volume of the earth between this plane and the original surface, then computing the volume between the same plane and the finished surface; the difference between these two volumes will be the amount of earthwork, or (3) by drawing on the plan a line of no cut or fill, a line representing,

say, 5 ft. cut or fill, a line representing 10 ft. cut or fill and so on. Then compute the volume between these successive 5-ft. layers.

414. (1) Referring to Fig. 175 and applying the first method, the volume of the solid *AMPE* is that of a solid having two parallel end planes *AKEL* (a plane at elevation 21) being the lower, and *MNPO* (a plane at elevation 22) being the upper plane. The altitude between these two end planes will be the difference in elevation between 21 and 22, or will be 1 ft.

The areas of the horizontal planes *AKEL*, *MNPO*, *QRST*, and *BUDV* may be obtained by planimeter (Art. 405, p. 387) or otherwise, and the volume of the solid *AKEL-MNPO* may be obtained by the End Area Method (Art. 375, p. 344), its altitude being 1 ft. If it is desired to obtain the volume by the use of the Prismoidal Formula the volume of the solid *AKEL-QRST* may be found by using *AKEL* as one base, *QRST* as the other, and *MNOP* as the middle area, the altitude, or length, of the solid being the difference between 21 and 23, or 2 ft. While neither of these methods is mathematically exact, they are the ones usually employed for this kind of a problem. The solid *AKEL-F* may be considered to be a pyramid with a base *AKEL* and an altitude of 1 ft.

EXAMPLE.

In Fig. 175 the amount of fill on the area *ABCDEF* is computed below.

Area *AELK* = 900 sq. ft. $900 \times \frac{1}{3} = 300$ cu. ft. (Pyramid)

" *MNPO* = 1000 $\frac{900 + 1000}{2} \times 1 = 950.$

" *QRST* = 1020 $\frac{1000 + 1020}{2} \times 1 = 1010.$

" *BUVD* = 680 $\frac{1020 + 680}{2} \times 1 = 850.$

$680 \times \frac{1}{3} = 227$ (Pyramid)

3)3337 cu. ft.

9)1112

124 cu. yds. Total Fill.

415. (2) Referring again to Fig. 175 and applying the second method, the area of *ABCDEF* is found (by planimeter); this is the area of a plane at, say, elevation 20, since none of the fill

extends below contour 20. Then the area of *ABCDEL* is found, which is the area of the plane cutting the original ground at elevation 21. Similarly the areas of *MBCDPO*, *QBCDST*, and *BCDV* are found. The volume of the solids between these planes may be computed by the End Area Method or by use of the Prismoidal Formula, in which case every other contour plane is used as a middle area as explained in the preceding paragraph. The volume of solid whose base is *BCDV* is a pyramid whose altitude is the vertical distance between the 24-ft. contour and point *C*, which in this case is 1 ft.

By the same general method the areas of *ABCDEK*, *MBCDPN*, etc., which refer to the new surface of the ground, may be obtained, and the volume of the solids between successive contour planes computed. The difference between this quantity and the quantity between a plane at elevation 20 and the original surface will give the amount of fill.

While in this particular problem the first method is the shorter, still there are cases where the second method will be somewhat simpler. It is particularly useful when the actual amount of cut or fill is not desired but when it is required to know if the proposed alterations will require more or less earth than can be easily obtained on the premises and, if so, about how much the excess will be. In this case the portions of cut and fill will not have to be computed separately. A line is drawn around the limits of the entire area where the grading is to be done, the volume between an assumed plane and the original surface is found, and then the volume between the same plane and the proposed surface. The difference between the two values will give the amount of excess of earthwork.

416. (3) Fig. 176 illustrates a third method of computing earthwork from the data given on a topographic map. The original contours are shown in full lines and the contours of the proposed surface in dash lines. Through the intersection of the new contours with the original ones is drawn the line of "no cut" (zero line), the line where the cut is just 5 ft. (marked 5), the line of 10 ft. cut (marked 10), etc. These dotted curves enclose areas which are the horizontal projections of irregular surfaces which are parallel to the final surface and at 5 ft., 10 ft.,



FIG. 176.

15 ft., etc., above the final surface. The solids included between these 5 ft. irregular surfaces are layers of earth each 5 ft. thick, and their volumes may be computed by either the End Area Method or by the Prismoidal Formula as explained in the preceding methods. The areas of these horizontal projections are obtained from the map and the vertical dimensions of the solids are the contour intervals.

417. ROUGH ESTIMATES. — Rough estimates of the quantity of earthwork are often required for preliminary estimates of the cost of construction or for monthly estimates of the amount of work done. For preliminary estimates of road construction, very

frequently the notes of alignment and the profile of the center line are the only information at hand. From this profile the center cuts or fills can be obtained, and the cross-sections can be assumed to be level sections (Art. 258, p. 243) and computed by the End Area Method. The slight errors resulting will be corrected in the final estimate.

In obtaining the required data from which to make an approximate estimate of the quantity of earthwork, the engineer has an opportunity to exercise his judgment to an unusual degree. Rough estimates do not, as a rule, call for a large amount of field-work. It is important that as few measurements as possible should be taken and that these should also be at the proper places to give complete data and to allow simple computations. Too often engineers, as soon as they arrive on the work and before making a study of their problems, begin to take measurements, consequently they return to the office after hours of hard work with a mass of figures from which it will take several more hours to compute the quantities. Whereas, a few moments' thought given to the choosing of the proper measurements to be taken in the field would give data which could be computed in a few moments by use of the slide rule, affording results sufficiently accurate for rough estimates.

PROBLEMS.

1. A series of perpendicular offsets are taken from a straight line to a curved boundary line. The offsets are 15 ft. apart and were taken in the following order: 6.8, 7.2, 4.6, 5.7, 7.1, 6.3, and 6.8.

(a) Find the area between the straight and curved lines by the Trapezoidal Rule.

(b) Find the same area by Simpson's One-Third Rule.

2. It is desired to substitute for a curved boundary line a straight line which shall part off the same areas as the curved line. A trial straight line AB has been run; its bearing is S 10° 15′ W, its length is 418.5 ft., and point B is on a boundary line CD which has a bearing S 80° W. The sum of the areas between the trial line and the crooked boundary on the easterly side is 2657. ft.; on the westerly side it is 7891. ft. It is required to determine the distance BX along CD such that AX shall be the straight boundary line desired. Also find the length of the line AX.

3. In the quadrilateral $ACBD$ the distances and angles which were taken in the field are as follows:

$A\ B = 50.63$ $\qquad$ $A\ B\ C = 105°\ 39'\ 00''$
$B\ C = 163.78$ $\qquad$ $B\ A\ D = 89°\ 37'\ 30''$
$C\ D = 93.80$
$D\ A = 160.24$
$D\ B = 167.73$

Check the fieldwork by computations, and figure the area of the quadrilateral by using right triangles entirely.

4. Two street lines intersect at an angle (deflection angle) of 48° 17′ 30″. The corner lot is rounded off by a circular curve of 40-ft. radius.

(a) Find the length of this curve to the nearest $\frac{1}{100}$ ft.

(b) Find the area of the land included between the curve and the two tangents to the curve (the two street lines produced).

5. Find the quantity in cubic yards, in the borrow-pit shown in Fig. 173; the squares are 25 ft. on a side, and the line $a\ s\ t$ is straight.

6. At station 6 a rectangular trench was measured and found to be 3 ft. wide and 4 ft. deep. At station 6+70 it was found to be 3.2 ft. wide and 8.6 ft. deep.

(a) Find by use of the Prismoidal Formula the quantity of earthwork between stations 6 and 6+70. Result in cubic yards.

(b) Find the volume of the same by End Area Method.

7. The following is a set of notes of the earthwork of a road embankment.

12	27.0 / + 8.0		+ 4.2		23.4 / +5.6
11 + 60	30.0 / +10.0	15.0 / +4.5	+ 4.0	15.0 / +7.5	24.0 / +6.0
Sta. 11	21.0 / +4.0		+ 6.0		25.8 / +7.2

The base of the road is 30 ft. and the slopes are 1½ to 1.
Find by the End Area Method the quantity of earthwork from Sta. 11 to 12. Result in cubic yards.

CHAPTER XIV.

AREA BY DOUBLE MERIDIAN DISTANCES.—COÖRDINATES.

418. COMPUTATION OF AREA. — The computation of the area of any piece of property which has been surveyed as a traverse will in general consist of (1) the computation of the area enclosed by the traverse and (2), where the traverse does not follow the property line, the computation of fractional areas to be added to or subtracted from the area of the traverse as the case may be.

419. COMPUTATION OF AREA BY DOUBLE MERIDIAN DISTANCE METHOD. — In the field notes the length and the bearing of each line of the traverse are recorded. To obtain the area enclosed the points of the survey are referred to a system of rectangular coördinates. In Fig. 177 the coördinate axes chosen are the magnetic meridian through the most westerly point F, and a line through F at right angles to the meridian. In compass surveys it is convenient to use the magnetic meridian for one of the axes; in transit surveys the true meridian is often used when its direction is known, but any arbitrary line may be used as an axis and some convenience results from choosing one of the lines of the survey as one of the axes.

In computing the area, first find the length of the projection of each line on each of the coördinate axes, or in other words, find the *northing* or *southing* and the *easting* or *westing* of each line, or *course*, of the traverse. The projection of any line on the meridian is called its *difference of latitude* or simply its *latitude*. The projection of a line on the other axis is called its *difference of departure*, or simply its *departure*.* In Fig. 177 the latitude of FA is Fq; the departure of FA is qA. The latitude and departure of each course are computed by solving the right triangle formed by drawing lines through the extremities of this course

* Some authors use the terms *latitude difference* and *longitude difference*.



FIG. 177.

and parallel to the coördinate axes. It is evident from the figure that

$$\text{Latitude} = \text{Distance} \times \cos \text{Bearing}.$$

$$\text{and} \quad \text{Departure} = \text{Distance} \times \sin \text{Bearing}.$$

Latitudes are called *North* or *South* and departures *East* or *West*, depending upon the direction of the course as shown by its letters, e.g., if the bearing is N 30° E this course has a North latitude and an East departure. North latitudes and East departures are considered as *positive* (+), South latitudes and West departures

as *negative* (—). In the figure the courses are assumed to run from F to A, from A to B, etc.

420. After all of the latitudes and departures have been computed (supposing for the present that the traverse is a closed



FIG. 177.

figure) proceed to find the areas of all the trapezoids or triangles, such as *DErs*, *EFr*, etc., formed by (1) the courses, (2) their projections on the meridian, and (3) the perpendiculars

from the extremities of the courses to the meridian. It is evident in the figure shown that the area of the field is equal to

$$(AB\,wq + BCtw + CDst) - (DErs + EFr + FAq),$$

that is, in this figure the sum of all the areas determined by lines running northward minus the sum of all the areas determined by lines running southward. These are known as *north areas* and *south areas*.* In computing the areas of these trapezoids it is convenient as well as customary to find the *double areas* and divide the final result by 2 instead of dividing by 2 in figuring each trapezoid. The area of any trapezoid equals the average distance of the extremities of the course from the meridian, multiplied by the length of the projection of the course on the meridian. This average distance of the ends of the line from the meridian is known as the *meridian distance* of the course, i.e., the meridian distance of the middle point of the course. In computing the double areas, twice this distance, or the *double meridian distance* (D.M.D.), is used, which is equal to the sum of the distances of the ends of the course from the meridian. In arranging the data for computing the double meridian distances, the courses must be tabulated in consecutive order around the traverse, whether they were so taken in the field or not. The D.M.D. of the course FA is qA which is the departure of the course FA. The D.M.D. of AB is $qA + wB = qA + qA + zB$, i.e., the D.M.D. of course FA + the dep. of FA + the dep. of AB. The D.M.D. of $BC = tC + wB = tv + vC + qA + zB = qA + wB + zB + vC$ = D.M.D. of AB + dep. of AB + dep. of BC.

Hence the D.M.D. of all of the courses may be computed by the following rules: —

(1) The D.M.D. of the first course (starting from the primary meridian†) equals the departure of the course itself.

---

* If the traverse had been run around the field in the opposite direction these north areas would become south areas. The result would be the same, however, in either case since it is the algebraic sum of the areas which is obtained.

† Any meridian could have been chosen as the primary meridian, but negative signs are avoided if the most westerly point is chosen as the starting point.

(2) The D.M.D. of any other course equals the D.M.D. of the preceding course plus the departure of the preceding course plus the departure of the course itself.

(3) The D.M.D. of the last course should be numerically equal to its departure, but with opposite sign.

The double areas of all the trapezoids may now be found by simply multiplying the D.M.D. of each course by the latitude of the same course, North latitudes being regarded as *plus* and South latitudes as *minus*. The sum of all the north double areas minus the sum of all the south double areas equals twice the area of the field. Be careful to **divide by 2** after completing the other details of the computation.

421. COMPUTATION FOR AREA OF COMPASS SURVEY BY D.M.D. METHOD. — The details of the above are illustrated in Fig. 178, which is the computation of the area of the traverse given in the compass notes in Fig. 50, p. 100. It will be seen from a study of the notes that there was local attraction of ½° at station *B*, and that in the following computations the corrected bearings are used (Art. 41, p. 30).

In Fig. 178 the bearings, distances, latitudes, departures, and D.M.D.'s, which are recorded on a line with station *F* are those corresponding to the course *FA;* those recorded on a line with station *A* refer to the course *AB;* etc. After the bearings and distances are entered in the table the places which are to be blank in the remaining columns are cancelled as shown; this is a check against putting the results of the computations in the wrong spaces. In computing the latitudes and departures the *log distance* is first entered; the *log sin bearing* is written below this and the *log cos bearing* is recorded above. To obtain the *log latitude* add the upper two logarithms; to obtain the *log departure* add the lower two logarithms. When the latitude and departure of a course have been obtained see if the results appear to be consistent with the given bearing and distance; when the bearing of a course, for example, is less than 45° its latitude is greater than its departure and *vice versa*.

Area of Wood Lot of John Smith Bk. 14-P. 27. Harvey Oct. 12, 1905.

Sta.	Bearing	Dist. (chains)	Latitude N+	Latitude S−	Departure E+	Departure W−	Balanced Lat.	Balanced Dep.	D.M.D.	Double Area +	Double Area −
F	S 32 1/4 E	11.18	—	9.45	5.97	—	-9.44	+5.97	5.97	—	56.4
A	East	17.79	—	—	17.79	—	+0.01	+17.78	29.72	0.3	—
B	N 58 1/4 E	13.58	7.15	—	11.55	—	+7.16	+11.54	59.04	422.7	—
C	N 1 1/2 E	32.42	32.41	—	0.85	—	+32.43	+0.83	71.41	2315.8	—
D	S 85 3/4 W	23.80	—	1.76	—	23.73	-1.75	-23.74	48.50	—	84.9
E	S 23 1/2 W	31.00	—	28.43	—	12.36	-28.41	-12.38	12.38	—	351.7
		129.77	39.56	39.64	36.16	36.09				2738.8	493.0
				39.56	36.09					493.0	

Error in Lat. .08 .07 Error in Dep. 2 | 2245.8

Closing Linear Error = $\sqrt{8^2+7^2}$ = 10 Links

"Error of Closure" = $\frac{0.1}{129}$ = 1 in 1300.

1123. sq. ch.
112.3 acres

	F	A	B	C	D	E
Lat.	9.45	0	7.15	32.41	1.76	28.43
Log Lat.	0.9756		0.8541	1.5107	0.2465	1.4538
Log Cos Bear.	9.9272		9.7212	9.9999	8.8689	9.9624
Log Dist.	1.0484		1.1329	1.5108	1.3766	1.4914
Log Sin Bear.	9.7272		9.9296	8.4179	9.9988	9.6007
Log Dep.	0.7756		1.0625	9.9287	1.3754	1.0921
Dep.	5.97	17.79	11.55	0.85	23.73	12.36

D.M.D.s

5.97 F
5.97
17.78
29.72 A
17.78
11.54
59.04 B
11.54
.83
71.41 C
+ .83
72.24
−23.74
48.50 D
−23.74
24.76
−12.38
12.38 E Check

Areas

F
5.97
9.44
2388
2388
53.73
56.4

A
29.72
.01
.3

B
59.04
7.16
354.24
5904
41328
422.7

C
32.43
71.41
32.43
12972
3243
22701
2315.8

D
48.5
1.75
2425
3395
485
84.9

E
28.41
12.38
22728
8523
5682
2841
351.7

FIG. 178. AREA OF COMPASS AND CHAIN SURVEY BY DOUBLE MERIDIAN DISTANCE METHOD.

422. Balancing a Chain and Compass Traverse. — Before the D.M.D. method can be properly applied the errors of measurement of the traverse should be so distributed that the figure becomes a closed polygon. If the field is a closed polygon the sum of the north latitudes will equal the sum of the south latitudes, and the sum of the east departures will equal the sum of the west departures. As soon as the latitudes and departures are computed this test is applied. If the sums differ, the error is distributed in such a way as to make the sums exactly equal, and at the same time to give to each latitude and departure its most probable value. In the case of a compass survey the errors are fully as likely to be in the bearings, which have been read to the nearest quarter of a degree, as in the distances; hence if nothing definite is known in regard to the errors they are assumed to be proportional to the lengths of the lines and the survey is balanced by the following rule which alters not only the lengths of the lines but also their directions.

423. *The correction to be applied to the* $\left\{ \begin{matrix} latitude \\ departure \end{matrix} \right\}$ *of any course is to the total error in* $\left\{ \begin{matrix} latitude \\ departure \end{matrix} \right\}$ *as the length of the course is to the perimeter of the field.*

This rule is based upon purely mathematical considerations and should be applied **only** when nothing is known as to where the errors probably occurred. Usually the surveyor knows where the error is probably greatest and consequently in balancing the survey he will place the largest corrections where, in his judgment, they belong. In measuring with the chain, the recorded distances tend always to be too **long,** because the sag, poor alignment, and poor plumbing, all serve to shorten the chain; consequently the probability is that the recorded measurements are too long, therefore in balancing it is more logical to subtract from the latitudes and departures in the columns whose sums are greater rather than to add anything to the latitudes and departures in the smaller columns. The corrections should of course be applied in such a way as to decrease the difference

between the two columns. In the example (Fig. 178) the total error in latitude is 0.08 and the total error in departure is 0.07. The perimeter of the traverse is 129.77. Hence the correction per chain-length is 0.062 links for latitudes, and 0.054 for departures. The corrected values of the latitudes and departures are given in the columns headed *balanced latitudes* and *balanced departures*.

424. From the balanced departures we then compute the D.M.D. of each course as shown in the next column. Observe that the last D.M.D. (point F), as computed from the preceding one, is exactly equal to the departure of the last course. This checks the computation of the D.M.D.'s. The D.M.D.'s are now multiplied by their corresponding latitudes and the products placed in the *double area* columns, those having N latitudes being placed in the column of north (+) double areas and those having S latitudes in the column of south (−) double areas. The sums of these columns differ by 2245.8. One-half of this, or, 1123. is the area of the field in square chains, which equals 112.3 acres.

By proceeding around the field in the reverse direction the letters of all of the bearings would be changed, in which case the column of south double areas would be the larger.

425. Double Parallel Distance. — There is no particular reason for using the trapezoids formed by projecting the courses on to the meridian rather than those formed by projecting them on to the other axis. In the latter case the *Double Parallel Distance* (*D.P.D.*) should be computed, and the result multiplied by the departure for each course.

In the D.M.D. method the computations have been checked at every step with the exception of the multiplication of the D.M.D.'s by the latitudes. A check on this part of the work can be obtained by figuring the area by use of the D.P.D.'s. This furnishes an example of a very desirable method of checking, as a different set of figures is used in computing the double areas, and the opportunity for repeating the same error is thus avoided. Fig. 179 shows the computation by the D.P.D. method of the area of the same survey as is calculated by the D.M.D. method in Fig. 178.

Sta.	Bearing	Dist. (chains)	Balanced Lat	Balanced Dep	D.P.D.	Double Areas +	Double Areas —
A	East	17.79	+0.01	+17.78	+0.01	0.2	
B	N58¼E	13.58	+7.16	+11.54	+7.18	82.9	
C	N1½E	32.42	+32.43	+0.83	+46.77	38.8	
D	S85¾W	23.80	-1.75	-23.74	+77.45		1838.7
E	S23½W	31.00	-28.41	-12.38	+47.29		585.5
F	S32¼E	11.18	-9.44	+5.97	+9.44	56.4	
						178.3	2424.2

178.3
2 | 2245.9
1123. sq. ch.
112.3 Acres

DPD's
0.01
0.01
7.16
7.18 B
7.16
32.43
46.77 C
32.43
79.20
1.75
77.45 D
-30.16
47.29
-37.85
9.44 F Check

Areas

A
17.78
.01
.2

B
11.54
7.18
92.32
11.54
8078
82.9

C
46.77
.83
14031
374 16
38.8

D
77.45
23.74
30980
542 15
232 35
154 90
1838.7

E
47.29
12.38
378 32
14187
9458
4729
585.5

F
5.97
9.44
2388
2388
5373
56.4

FIG. 179. AREA OF COMPASS SURVEY BY DOUBLE PARALLEL DISTANCES.

426. Error of Closure. — An indication of the accuracy of the survey is found in the *error of closure*. If a complete traverse of the field has been made the final point, as computed, should coincide with the first. The amount by which they fail to coincide is the total error of the survey and may be found by the formula

$$E = \sqrt{l^2 + d^2}$$

where l is the error in latitude and d is the error in departure. If this distance E is divided by the perimeter of the field the resulting fraction is called the *error of closure*, which in this survey is approximately $\frac{1}{1800}$ (see Art. 132, p. 99).

427. COMPUTATION OF AREA OF A TRANSIT AND TAPE SURVEY. — The field notes show the lengths of the sides of the traverse, all of the angles and perhaps the magnetic bear-

ings of some or all of the courses. If an observation has been made for determining the direction of the meridian, this affords the means of computing the true bearings of all of the traverse lines.

428. The first step in reducing the notes (provided it has not already been done in the field) is to see if the difference between the sum of the right and left deflection angles equals 360°. If interior angles have been measured, their sum should equal the number of sides of the field times two right angles, minus four right angles. If there is a small error in the sum of the angles this is usually adjusted by placing the error in the angles where it probably occurred. If nothing is known as to where it probably occurred the corrections should be made in the angles adjacent to the **short** lines, as any error in sighting or setting up the transit causes a greater angular error in a short line than in a long one. (Art. 143, p. 108.)

The transit survey is referred to a system of rectangular coördinates, as in case of the compass survey. If the direction of the true meridian is known (either from a special observation or by connection with some other survey referred to the meridian), it is advisable to use this meridian as one of the coördinate axes. If the direction of the true meridian is not known the magnetic meridian may be used. This of course is convenient in some respects because the bearings taken in the field already refer to this meridian. If not even the magnetic meridian is known it will then be advisable to choose some line of the survey (preferably a long one) as the axis, for using one of the traverse lines as an axis saves computing the latitude and departure of one course.

Whatever line is chosen as an axis, the bearings used for computing the latitudes and departures are to be obtained from the **measured angles** (after correction), and **not** from the observed bearings. For instance, if some line is selected and its magnetic bearing used, then the bearings of all of the other lines should be computed from this one by means of the (corrected) transit angles. In this way the bearings are relatively as accurate as the transit angles, even though the whole survey may be referred to an erroneous meridian due to the error of the magnetic

Area J. H. Bradley Estate – Bk 42, p 37. Fuller June 7, 1906. Wilcox - Checker

Sta	Bearing	Dist. (feet)	Latitude N+	Latitude S−	Departure E+	Departure W−	Balanced Lat.	Balanced Dep.	DMD	Double Area +	Double Area −
H	S 38-07-15 E	103.75	—	81.62	64.05	—	-81.62	+64.05	64.05	—	5228
J	N 86-52-30 E	96.75	5.27	—	96.61	—	+ 5.27	+ 96.61	224.71	1184	—
K	S 39-18-30 E	420.77	—	325.57	266.56	—	-325.55	+266.55	587.87	—	191381
A	N 62-31-30 E	208.64	96.26	—	185.11	—	+ 96.26	+185.11	1039.53	100066	—
B	N 25-56-30 W	436.79	392.78	—	—	191.08	+392.77	-191.06	1033.58	405959	—
C	S 87-01-15 W	56.48	—	2.94	—	56.40	- 2.94	- 56.40	786.12	—	2311
D	S 53-22-00 W	98.80	—	58.95	—	79.28	-58.95	- 79.28	650.44	—	38343
E	N 36-38-00 W	68.62	55.07	—	—	40.94	+55.07	- 40.94	530.22	29199	—
F	N 59-29-00 W	95.10	48.29	—	—	81.93	+48.29	- 81.93	407.35	19671	—
G	S 51-40-45 W	207.41	—	128.61	—	162.72	-128.60	-162.71	162.71	—	20925
		1793.11	597.67	597.69	612.33	612.35				556079. 258188.	258188

Error in Lat. 0.02 Error in Dep. 0.02

"Error of Closure" = $\frac{\sqrt{2^2+2^2}}{179311} = \frac{1}{63,500}$

2) 297891

148946 sq. ft. Area

Deflection Angles

	Right	Left
A		78-10
B		88-28
C		67-02 (67-02-15)
D		33-39-15
E	90-00	
F		22-51
G		68-50-15
H		89-48
J		55-00-15
K	53-49	
	143-49	500-228-45
		143-49
		359-59-45

Error in Angles 0°-00'-15"
Add 0'-15" to angle C

Bearings

E N 36-38 W
22-51
F N 59-29 W
68-50-15
128-19-15
180-
G S 51-40-45 W
89-48
H S 38-07-15 E
55-00-15
93-07-30
180
J N 86-52-30 E
53-49
140-41-30
180
K S 39-18-30 E
78-10
117-28-30
180
A N 62-31-30 E
88-28
B N 25-56-30 W
67-02-15
92-58-45
180
C S 87-01-15 W
33-39-15
D S 53-22 W
90
E N 36-38 W

D.M.D

H 64.05
64.05
96.61
224.71
96.61
266.55
K 587.87
266.55
185.11
A 1039.53
185.11
1224.64
-191.06
B 1033.58
-247.46
C 786.12
-135.68
D 650.44
-120.12
E 530.22
-122.87
F 407.35
-244.64
G 162.71

FIG. 180. AREA OF A TRANSIT AND TAPE SURVEY BY DOUBLE MERIDIAN DISTANCE METHOD.

(The remainder of the computations is in Fig. 181.)

Latitudes and Departures

	H	J	K	A	B
Lat.	81.62	5.27	325.57	96.26	392.78
Log Lat.	1.911803	0.72216	2.512645	1.983439	2.594149
Log Cos. Bear.	9.895815	8.73651	9.888600	9.664041	9.953876
Log Dist.	2.015988	1.98565	2.624045	2.319398	2.640273
Log Sin. Bear	9.790512	9.99935	9.801742	9.948027	9.640934
Log Dep.	1.806500	1.98500	2.425787	2.267425	2.281207
Dep	64.05	96.61	266.56	185.11	191.08

	C	D	E	F	G
Lat.	2.94	58.95	55.07	48.29	128.61
Log Lat.	0.46767	1.77051	1.74088	1.68386	2.109267
Log Cos. Bear	8.71578	9.77575	9.90443	9.70568	9.792437
Log Dist.	1.75189	1.99476	1.83645	1.97818	2.316830
Log Sin Bear	9.99941	9.90443	9.77575	9.93525	9.894621
Log Dep.	1.75130	1.89919	1.61220	1.91343	2.211451
Dep	56.40	79.28	40.94	81.93	162.72

Double Areas

	H	J	K	A	B
Log DMD	1.80650	2.35162	2.769281	3.016837	3.014344
Log Lat	1.91180	0.72181	2.512618	1.983446	2.594138
Log Area	3.71830	3.07343	5.281899	5.000283	5.608482
Area	5228	1184	191381	100066	405959

	C	D	E	F	G
Log DMD	2.89549	2.813207	2.724456	2.609968	2.211414
Log Lat.	0.46835	1.770484	1.740915	1.683857	2.109246
Log Area	3.36384	4.583691	4.465371	4.293825	4.320660
Area	2311	38343	29199	19671	20925

FIG. 181.

(These computations go with Fig. 180.)

bearing of the first line. In calculating these bearings the work should be checked by computing the bearing of each line from that preceding, the bearing of the last line being followed by the calculation of a new bearing of the first line of the traverse which must agree with the magnetic bearing assumed for it, provided the deflection angles have been adjusted so that their algebraic sum is 360°. The observed magnetic bearings of the different courses will serve as a check against large mistakes in this calculation.

429. When all of the bearings have been figured the latitudes and departures are to be computed. In good transit surveys five places in the trigonometric functions will usually be necessary. If the angles are measured, by repetition, to a small fraction of a minute, seven-place logarithmic tables may profitably be em-

ployed, as much interpolation is avoided by their use, but the logarithms need not be taken out to more than five or six places. Seven places, of course, are more than are necessary so far as precision is concerned (Art. 386, p. 372).

The computation of the latitudes and departures may be conveniently arranged as shown in Fig. 161 which is the computation of the survey in Fig. 52, p. 103. After the latitudes and departures have been calculated they are tabulated.*

430. Balancing a Transit and Tape Traverse. — In adjusting (balancing) a transit traverse a different rule is used from the one given in Art. 423. In the case of a transit survey the error is chiefly in the measurement of distances, as it is much easier to secure accurate results in the angular work than in the tape measurements. The following rule is commonly applied:—

The correction to be applied to the $\left\{\begin{matrix}\textit{latitude}\\ \textit{departure}\end{matrix}\right\}$ *of any course is to the total error in* $\left\{\begin{matrix}\textit{latitude}\\ \textit{departure}\end{matrix}\right\}$ *as the* $\left\{\begin{matrix}\textit{latitude}\\ \textit{departure}\end{matrix}\right\}$ *of that course is to the sum of all of the* $\left\{\begin{matrix}\textit{latitudes}\\ \textit{departures}\end{matrix}\right\}$ *(without regard to algebraic sign).*

As in the case of a compass survey, the surveyor's knowledge of the circumstances should always take precedence over the rule, and it is probably more nearly correct to **shorten** the latitudes or departures in the larger columns than to **lengthen** them in the smaller columns. This is because distances are usually recorded longer than they actually are; the only cases where the distance is probably too short is when an excessive pull has been given to the tape or a mistake made in measurement. It will be observed in the original notes (Fig. 52, p. 103) that the distances BC, GH, and KA were all questioned, i.e., they were measured under such conditions that it is probable that there may be one or two hundredths error in them. In balancing the latitudes and departures then, this information is used. In Fig. 180 it will be seen that in balancing the survey the latitudes and departures

* Some prefer to obtain the latitudes and departures from "Traverse Tables," such as Gurden's Tables, in which the bearings are given for every minute and distances from 1 to 100.

of these questioned measurements have been changed in such a way as to reduce the length of BC, GH, and KA each one hundredth of a foot.

In balancing the angles, in which there was an error of 15 seconds, it will be noticed that the correction for this error, being small, was put into one angle, that at C, one of whose sides is the shortest line in the traverse. The area is computed as explained in Art. 420, p. 402.

431. Fractional Areas. — Fig. 182 is the computation of the



FIG. 182. COMPUTATION OF TRANSIT AND TAPE SURVEY, INCLUDING FRACTIONAL AREA.

survey shown in Fig. 53, p. 104. The traverse was run with a transit and tape, the angles being measured to the nearest minute

and the sides to tenths of a foot. Nothing appears in the field notes to indicate that any of the lines were difficult to measure, so it is assumed that any errors in measurement are as likely to occur in one line as another. Therefore, in balancing the latitudes and departures of this survey, the rule given in Art. 395 is applied. In balancing the angles, in which there was an error of 1 minute, the entire error was placed in the angle at D where the side DE is short in comparison with the other sides.

It will be noticed that the distances which appear on the sketches in the computation are slightly different from those which appear in the field notes (Fig. 53); this is due to the fact that the distances have been corrected for erroneous length of tape before undertaking to calculate the area. The intermediate steps in the computation of this traverse do not appear in Fig. 182, but they are the same as in the last traverse. The D.M.D.'s were computed from F, the most westerly point. The computation of the fractional areas is also given.

432. SUPPLYING MISSING DATA. — If any two of the bearings or distances are omitted in the traverse of a field the missing data can be supplied and the area obtained by computations based on the measurements taken. As has been shown in Art. 422, p. 406, the algebraic sum of all the latitudes in a closed survey must equal zero, and the algebraic sum of all the departures must equal zero; or, to put it in the form of an equation,

$$Z_1 \cos A + Z_2 \cos B + Z_3 \cos C + \text{etc.} = 0$$
$$Z_1 \sin A + Z_2 \sin B + Z_3 \sin C + \text{etc.} = 0$$

where Z_1, Z_2, Z_3, etc., are the lengths of the corresponding courses. Therefore from these two equations any two unknown values in them can be computed.

The missing data could be any of the following combinations: —

(1) The bearing and length of a line.
(2) The length of a line and the bearing of another line.
(3) The lengths of two lines.
(4) The bearings of two lines.

433. Case (1) where the bearing and length of a line are missing is by far the most common. Its solution is also more direct than that of the other cases.

If the latitudes and departures of all of the measured sides are calculated, the sum of N and S latitudes will be found to differ, and the amount by which they differ is the latitude of the omitted side **plus** or **minus** the errors of latitudes. Similarly the amount by which the E and W departures differ is the departure of the course omitted **plus** or **minus** the errors of departures. From the latitude and departure of a course its length and bearing may be readily found.

A practical application of this case is found in the problems of subdividing a field by a line running from one known point to another, the direction and length of the dividing line not having been measured. The area of the portion cut off by this line can readily be computed by the above method. In case the angles were taken with the transit, the bearing of one line would be assumed to be correct and all other bearings computed to correspond.

It is evident from the above that in supplying missing data the observed measurements must be assumed to be correct, as there is no way of proving this from the computations. For this reason it is never advisable, when it can possibly be avoided, to supply missing data derived from computations on which a field check has not been obtained.

434. The solutions of the other three cases of missing data are not so simple, as they involve the use of simultaneous equations; they will not be discussed here.

435. Besides the four cases mentioned above there are some special cases which are capable of solution. In Fig. 183 the lines and angles measured are shown by full lines. The bearing of AB is given. Here one side and two angles are missing. The solution is as follows. In the triangle EAB find EB, EBA, and AEB. In the triangle EDC find EC, DCE, and DEC. Then in the triangle EBC, in which EC,



FIG. 183.

EB, and *EBC* are known, find *ECB*, *CEB*, and *BC*. All the angles and sides are then known. Other special cases may be solved in a similar manner.

436. DETECTING MISTAKES. — Mistakes in fieldwork may often be detected by means of the calculations. One of the easiest mistakes to make in surveying is to omit a whole tape-length in counting. If such a mistake were made and the latitudes and departures were computed, the linear error of closure of the survey would prove to be about a tape-length. In order to find in which line this mistake probably occurred compute the bearing of this linear error of closure and examine the traverse to find a line having a bearing the same or nearly the same. The error in departure divided by the error in latitude equals the **tangent of the bearing of the line** which represents the error of closure of the traverse. The errors of the survey, of course, will prevent these bearings from agreeing exactly. If two mistakes have been made it may be difficult and sometimes impossible to determine where they occurred. When an error of this sort is indicated by the computation the line should be remeasured. It is bad practice to change an observed measurement because it is found by calculation to disagree with other measured distances.

It may, and frequently does, happen that there is more than one line in the traverse which has about the same bearing. In such a case it is impossible to tell in which of these lines the mistake occurred. But if a cut-off line is measured as was suggested in Art. 145, p. 110, and one portion of the survey balances, the other part will contain the mistake. By proceeding in this way the number of lines in which the mistake could occur is reduced so that its location can be determined and checked by field measurement.

437. THE SUBDIVISION OF LAND. — There are a great many different problems which may arise in the subdivision of land and which may be solved simply by the application of the principles of trigonometry. A few of these problems are so common and so frequently involved in the working out of more complicated cases that their solution will be given.

438. To Cut Off from a Traverse a Given Area by a Straight Line starting from a Known Point on the Traverse. — In Fig. 184, $ABCDE$ represents the traverse which has been plotted and whose area has been computed. It is desired to cut off a certain area by a line running from F which is at a known distance from A or E. The line FG' is drawn on the plan so as to make the area $FG'DE$ approximately equal to the desired area. The line DG' is scaled off and the scaled distance used as a trial length. Then the side FG' and its bearing can be found by the method explained in Art. 433, p. 415, and the area $FEDG'$ computed in the usual manner. The difference between the required area and the area of $FEDG'$ is the amount to be added to or subtracted from $FEDG'$. If this correction area is a minus area then the triangle $FG'G$ will represent it. In this triangle the base FG' and its area being known the altitude hG and the distances GG' and FG can be readily computed. In the traverse $FGDE$, which is the required area, the length of the missing side FG and its bearing can be supplied.



FIG. 184.

Instead of using the trial line FG' the line FD might have been first assumed and the correction triangle would then be FDG. This method has the advantage of containing one less side in the first trial area, but the correction triangle is large, whereas in the method explained above the correction triangle is small which may be of advantage in that part of the computation.

439. To Cut Off from a Traverse a Given Area by a Line running in a Given Direction. — In Fig. 184, $ABCDE$ represents a closed traverse from which is to be cut off a given area by a line running at a given angle (BJK) with AB. On the plot of the

traverse draw the line $J'K'$ in the given direction cutting off $J'BCK'$ which is, as nearly as can be judged, the required area. Scale the distance BJ' and use this trial distance in the computations. Then compute the distance $J'K'$ and the area of $J'BCK'$ by the method suggested in Art. 435, i.e., by dividing $J'BCK'$ into two oblique triangles. The difference between this area and the required area is then found, which is a correction trapezoid to be added to or subtracted from $J'BCK'$. In this case it will be assumed that it is to be added to $J'BCK'$.



FIG. 184.

In this correction trapezoid the area and one base $J'K'$ are known; also the base angles, J' and K'. From these data an approximate value for the altitude of the trapezoid can be obtained and the length of the other base $K''J''$ of the trapezoid computed from this altitude and the length of $J'K'$. Then the area of this trapezoid $J'K'K''J''$ can be accurately determined; the difference between this and the required correction will be small and the dimensions of the second correction trapezoid $J''K''K'J'$ can probably be readily computed from its area and the length of $J''K''$ which are known. By successive trials, probably not more than two, the correct line JK can be found. If lines AB and CD are approximately parallel the trapezoid is nearly a parallelogram and its correct altitude can then be quickly determined.

440. To Find the Area Cut Off from a Traverse by a Line running in a Given Direction from a Given Point in the Traverse. —This problem may be readily solved by drawing a line from the given point in the traverse to the corner which lies nearest the other extremity of the cut-off line. The area of the traverse thus formed is then computed, and this area corrected by means of a correction triangle.

In Fig. 185, *ABCDEFG* represents a plot of a field. It is desired to run the line from *E* in a given direction *EH* and to compute the area *HEFGAB* cut off by this line. The latitude and departure of points *B* and *E* being known the bearing and length of *BE* and the area of *ABEFG* can be computed. Then the area and the remaining sides of the triangle *BEH* can be obtained from *BE* and the angles at *B* and *E*.



FIG. 185.

It is obvious that the solution of such problems as these is greatly facilitated by plotting the traverse before attempting the computations.

CALCULATIONS RELATING TO TRAVERSES WHICH DO NOT CLOSE.



FIG. 186.

441. TO CALCULATE THE TOTAL DISTANCE BETWEEN END POINTS. — Fig. 186 represents the traverse *ABCDEF* in which the distance *AF* and the angle *BAF* are desired. *AB* can be assumed as one of a pair of rectangular coördinate axes and the coördinates of point *F* (*AH* and *HF*) computed by the method explained in Art. 445, p. 421. *AF* and the angle *BAF* can then be easily found. This method is of service in checking traverse plots of this type.

442. CUT-OFF LINES. — The calculation of cut-off lines, like the line *CF* in Fig. 186, is the same problem as was explained in Art. 433, p. 415. The angles *DCF* and *EFC* have been measured in the field and the traverse *CDEF* is thus complete except that the length of the line *CF* is unknown. The length of *CF* and the angle it makes with *AB* can be readily computed since the coördinates of *C* and *F* can be found.

443. COMPUTATION OF AZIMUTHS WHEN CHECKING ANGLES TO A DISTANT OBJECT. — In this kind of problem the coördinates of all the points along the traverse can be computed with reference to some coördinate axes. At A and B (Fig. 187) angles have been taken to S, and from these angles the coördinates of point S, referred to AB and a line perpendicular to AB as axes, can be computed (Art. 445, p. 421). Coordinates of S referred to the same axes should have the same value when figured from BC as a base as when calculated from the base CD and so on. If, however, when computed by means of angles at D and E, the point falls at S', and angles E and F give its location also at S' there is evidence of a mistake in the traverse at D. If the two locations of S and S' are such that a line between them is parallel to either CD or DE, the mistake was probably made in the measurement of the line parallel to SS' and the distance SS' should be approximately equal to the amount of the mistake in measurement. If, however, SS' is not parallel to either CD or DE the mistake probably lies in the angle at D.



FIG. 187.

444. CALCULATION OF TRIANGULATION. — In a triangulation system the base-line is the only line whose length is known at the start. The sides of any triangle are found from the law of sines, i.e.,

$$\frac{\sin A}{\sin B} = \frac{a}{b} \qquad \frac{a \sin B}{\sin A} = b$$

$$\frac{\sin A}{\sin C} = \frac{a}{c} \qquad \frac{a \sin C}{\sin A} = c$$

Assuming a to be the base and the angles A, B, and C to have been measured the calculations are arranged as follows:

(1) $\log a$ (1400.74) $= 3.1463575$
(2) Colog Sin A ($57° 42' 16''$) $= 0.0729874$
(3) $\log$ Sin B ($61° 17' 53''$) $= 9.9430639$
(4) $\log$ Sin C ($60° 59' 51''$) $= 9.9418088$

Sum of (1) (2) (3) $\log b = 3.1624088$
Sum of (1) (2) (4) $\log c = 3.1611537$

445. COÖRDINATES. — In many cities the coördinate system of surveying is used (see Chapter X). In this system the position of each corner of the different lots is fixed by rectangular coördinates measured from two lines at right angles to each other.

Often the origin of coördinates O (Fig. 188) is so chosen that the whole city is in the first quadrant YOX. Distances measured parallel to XX' are usually called abscissas and those parallel to YY' ordinates.



FIG. 188.

The advantage of this system of surveying lies in the fact that since all surveys refer to the same reference lines, they are therefore tied to each other; and also in the fact that a lot can be relocated from the coördinates of its corners even if all of the corner bounds have been destroyed.

Generally the coördinate lines run N and S, and E and W, but when city streets have been laid out at right angles to each other and not on N and S, and E and W lines, it may be more convenient to have the system of coördinates parallel to the street lines.

The coördinates of any unknown point are usually computed from the coördinates of some other point to which the unknown

point is tied by an angle and distance. The difference in coördinates between the known and unknown points will be obtained as follows: —

Difference in X = distance × sin azimuth angle.
Difference in Y = distance × cos azimuth angle.

Sometimes the unknown point is located by angles from two other known points, in which case the distance and azimuth between the two points whose coördinates are known can be computed and then the distance and direction from one of the known points to the unknown point. The problem is then in the form described in the previous paragraph.



FIG. 189.

446. TO DETERMINE THE AREA OF A FIELD BY RECTANGULAR COÖRDINATES. — The area of the field 1, 2, 3, 4 (Fig. 189) is equal to the trapezoids

$$(a, 1, 2, b) + (b, 2, 3, c) - (a, 1, 4, d) - (d, 4, 3, c).$$

Expressed as an equation in terms of the coördinates the area is

$$1, 2, 3, 4 = (y_1 - y_2)\frac{x_1 + x_2}{2} + (y_2 - y_3)\frac{x_2 + x_3}{2} - (y_4 - y_3)\frac{x_4 + x_3}{2} - (y_1 - y_4)\frac{x_1 + x_4}{2} \quad (1)$$

$$= \tfrac{1}{2}\{(y_1 (x_2 - x_4) + y_2 (x_3 - x_1) + y_3 (x_4 - x_2) + y_4 (x_1 - x_3)\} \quad (2)$$

From this equation is derived the following rule for obtaining the area of a closed field from the coördinates of its corners: —

(1) Number the corners consecutively around the field.

(2) Multiply each $\left\{\begin{matrix}\text{abscissa}\\ \text{ordinate}\end{matrix}\right\}$ by the difference between the following and the preceding $\left\{\begin{matrix}\text{ordinates}\\ \text{abscissas}\end{matrix}\right\}$, always subtracting the following from the preceding (or always subtracting the preceding from the following), and take half the sum of the products.

447. Fig. 190 illustrates the computation of an area from

Corner	North (Y) (Feet)	East (X) (Feet)	Diff. Adj. X's	+ Areas	— Areas
1	3304.29	2601.71	+ 372.92	113,476	
2	3462.91	2486.21	+ 90.55	41,917	
3	3591.20	2511.16	− 333.79		197,337
4	3651.81	2820.00	− 347.97		226,810
5	3470.19	2859.12	+ 218.29	102,642	
				258,035	424,147
					258,035
					2 | 166,112
					83,056 Sq. Ft.

FIG. 190. AREA OF LOT FROM COÖRDINATES OF ITS CORNERS.

the coördinates. Each Y has been diminished by 3000 ft. before multiplying by the difference in X's.

448. Equation (1) may be developed into the following form:

$$1, 2, 3, 4 = \tfrac{1}{2}(x_2y_1 - x_1y_2 + x_3y_2 - x_2y_3 + x_4y_3 - x_3y_4 + x_1y_4 - x_4y_1) \quad (3)$$

When this formula is to be used the coördinates may be arranged in the following simple manner:

$$1, 2, 3, 4 = \tfrac{1}{2}\left(\frac{x_1}{y_1}\diagdown\frac{x_2}{y_2}\diagdown\frac{x_3}{y_3}\diagdown\frac{x_4}{y_4}\diagdown\cdots\diagdown\frac{x_1}{y_1}\right) \quad (4)$$

From equation (3) it will be seen that the area is equal to the sum of the products of the coördinates joined by **full** lines in (4) **minus** the sum of the products of the coördinates joined by **broken** lines. This formula involves the multiplications of larger numbers than in (2), but does not require any intermediate subtractions.

PROBLEMS.

1. The latitude of a line of a traverse is + 106.42 ft.; its departure is −273.62. What is its bearing?

2. From the following notes of a compass survey, compute by the double meridian distance method the area in acres.

Station.	Bearing.	Distance (Chains).
A	N 46°½ W	20.76
B	N 51°¾ E	13.80
C	East	21.35
D	S 56° E	27.60
E	S 33°¼ W	18.80
F	N 74°½ W	30.98

3. In the following notes of a compass survey the length and bearing of one of the courses were omitted. Substitute the correct values and compute the area (in acres) by the double meridian distance method.

Station.	Bearing.	Distance (Chains).
1	S 40° W	17.50
2	N 45° W	22.25
3	N 36°¼ E	31.25
4	North	13.50
5	(omitted)	(omitted)
6	S 8°½ W	34.25
7	West	32.50

4. From the notes given in Fig. 52, p. 103, and Fig. 180, p. 410, compute by the double meridian distance method the area of the traverse *ABCDEK*.

5. In the following traverse there are two mistakes. Find where they occur and determine their amounts.

Station.	Observed Bearing.	Deflection Angle.	Distance (Feet).	Calculated Bearings.	Remarks.
A	N 34° E	164° 14′ R	240.2	N 34° 00′ E	
B	S 73°½ E	62° 16′ R	163.7		
C	S 10°¼ W	84° 22′ R	207.6		$CE = 188.1$
D	N 26° ½ W	142° 49′ R	273.1		$BCE = 34° 14'$
E	S 52° W	103° 41′ L	147.4		$DEC = 81° 25'$

6. The following is a set of notes of an irregular boundary of a lot of land. It is desired to straighten this crooked boundary line by substituting a straight line running from *B* to the line *EF*. Find the bearing of the new boundary line and its length; also the distance along *EF* from point *E* to the point where the new line cuts *EF*.

Station.	Bearing.	Distance (Feet).
A	S 89° 14′ E	373.62
B	N 13° 10′ E	100.27
C	N 0° 17′ W	91.26
D	N 27° 39′ E	112.48
E	N 72° 12′ W	346.07
F	S 5° 07′ W	272.42
	etc.	etc.

7. (*a*) In the lot of land, *ABCD*, the lines *AB* and *DC* both have a bearing of N 23° E; the bearing of *AD* is due East; *AD* is 600 ft., *AB* is 272.7 ft., and *DC* is 484.6 ft. Find the length of a line *EF* parallel to *AB* which will cut off an area *ABFE* equal to half an acre. Also find the length of the lines *AE*, and *BF*. (*b*) What is the area of *EFCD*?

8. Given the notes of a traverse, which does not close, as follows: —

Station.	Deflection Angle.	
0		Find the length
6 + 40	6° 17′ L	of a straight line
9 + 20	18° 43′ L	from 0 to 20+ 64
14 + 55	12° 47′ R	and the angle it
17 + 18	45° 24′ L	makes with the
20 + 64	68° 06′ R	line from 0 to 6
		+ 40.

9. Compute the area of the following traverse by coördinates.

Station.	Deflection Angle.	Bearing.	Distance (Feet).
A	78° 10′ 00″ L		208.64
B	88° 28′ 00″ L		436.79
C	67° 02′ 15″ L		56.48
D	33° 39′ 15″ L		98.80
E	90° 00′ 00″ R		68.62
F	22° 51′ 00″ L		95.10
G	68° 50′ 15″ L	N 36° 14′ 00″ W	207.41
H	89° 48′ 00″ L		103.75
I	55° 00′ 15″ L		90.75
J	53° 49′ 00″ R		420.77

10. The line Ax has a bearing S 51° 10′ E, and line Ex has a bearing N 21°04′ E. A and E are connected by the following traverse: AB, S 60° 51′ W, 102.69 ft.; BC, S 0° 59′ E, 298.65 ft.; CD, S 89° 01′ E, 101.20 ft.; DE, N 80° 52′ E, 148.28 ft. Compute the distances Ax and Ex.

11. On a street line ACE whose bearing is S 89° 10′ E, the distance AC is 50.00 ft. and CE is 101.50 ft. The side line AG of a house lot has a bearing of S 2° 05′ W. Point B is on this side line and is 31.25 ft. from A. The opposite side of the lot, CH has a bearing S 1° 20′ W, and the side line of the next lot, EI has a bearing S 1° 10′ E. From B a line having a bearing N 89° 16′ E cuts these side lines, at points B, D and F. Compute distances CD, BD, EF, and DF.

12. A traverse run from A to D has the following bearings and distances: AB, S 26° 19′ E, 91.2 ft.; BC, S 89° 58′ E, 216.00 ft.; CD, N 1° 19′ E, 371.25 ft. Point E is 191.00 ft. from A and 212.10 ft. from D. Compute the bearings of AE and DE, and the angles EAD, EDA and AED.

13. A corner city lot $ABCDE$ has the following interior angles. $A = 7° 15′$, $B = 94° 50′$, $C = 91° 22′$, $D = 120° 27′$, $E = 226° 06′$. The measured sides are $AB = 583.58$, $BC = 102.88$, $CD = 153.01$, $DE = 86.85$, $EA = 391.42$. Bearing of AB is N 66° 50′ E. At the corner B the lot is rounded by a circular curve of 20.00 ft. radius; point B is at the vertex of this curve. Compute the area of the lot.

PART IV.

PLOTTING.

PART IV.

PLOTTING.

CHAPTER XV.

DRAFTING INSTRUMENTS AND MATERIALS.

It is assumed in this section that the student is familiar with the ordinary drawing instruments such as the T-square, triangles, dividers, compasses, and scales, as well as with their use.

ENGINEERING DRAFTING INSTRUMENTS.

449. There are several drafting instruments which are used by engineers and surveyors but which are not so generally employed in other kinds of drafting work. The most common of these are briefly described in the following articles.

450. STRAIGHT-EDGE. — Engineering drawings are made with greater accuracy than much of the drafting work of other professions. In fact many engineering drawings are limited in precision only by the eyesight of the draftsman. It is evident, then, that to use a T-square which is run up and down the more or less uneven edge of a drawing board will not produce drawings of sufficient accuracy. For this reason in many classes of engineering work the edge of the drawing board is not relied upon. Furthermore, in most plots of surveying work the lines are not parallel or perpendicular to each other except by chance, but run at any angle which the notes require; and there is therefore not so much call for the use of a T-square as there is in architectural, machine, or structural drawings. All drawings are usually laid out starting from some straight line drawn on the paper by means of a straight-edge, which is simply a flat piece of steel or wood like the blade of a T-square. Steel straight-edges are more accurate and are more commonly used by engineering draftsmen than the wooden ones, the edges of which are likely to nick or warp and become untrue. They can be ob-

tained of almost any length and of any desired weight, the common length being about 3 feet.

451. ENGINEER'S SCALE. — Practically all engineering plans are made on a scale of 10, 20, 30, etc. feet to an inch. In the engineer's scale, therefore, the inch is divided into 10, 20, 30, etc. parts, instead of into eighths and sixteenths as in the architect's scale. Engineer's scales are made 3, 6, 12, 18, and 24 inches long. One form is the flat wooden rule with both edges beveled and a scale marked on each bevel. Some flat rules are beveled on both faces and on both edges of each face, thereby giving four scales on one rule. Still another very common form is the triangular scale, made of wood or metal, and having six different scales, one on each edge of the three faces. In such rules the scales are usually 20, 30, 40, 50, 60, and 80 ft. or 10, 20, 30, 40, 50, and 60 ft. to an inch. Scales are, however, often made having the inch divided into 100 parts, but in plotting a map which is on a scale of 100 ft. to an inch the work is probably more easily done by using a scale of 10, 20, or 50 divisions to an inch and estimating the fractional part of a division than by trying to plot with a 100-ft. scale which is so finely graduated as to be very hard to read without the aid of a magnifying glass. A 20-ft. or 50-ft. scale is more satisfactory for precision than a 10-ft. scale when it is desired to plot on a scale of 100 ft. to the inch. A plan on a 200-ft. scale is always plotted by using a 20-ft. scale, a 300-ft. plan by using a 30-ft. scale, etc.

A map covering considerable area, like the map of a state, for example, must be plotted to a very small scale, and this is usually given in the form of a ratio such as 1 to 500, 1 to 2500, etc., meaning that one unit on the map is $\frac{1}{500}$, $\frac{1}{2500}$, etc. of the corresponding distance on the ground; this is sometimes called the *natural* scale. For plotting such maps specially constructed scales with decimal subdivisions are used.

452. PROTRACTOR. — A *protractor* is a graduated arc made of metal, paper, celluloid, or horn, and is used in plotting angles. There are many varieties of protractor, most of them being either circular or semicircular.

453. Semicircular Protractor. — Probably the most common is the semicircular protractor which is usually divided into de-

grees, half-degrees, and sometimes into quarter-degrees. Fig. 191 represents a semicircular protractor divided into degrees.



FIG. 191. SEMICIRCULAR PROTRACTOR.

In plotting an angle with this protractor the bottom line of the instrument is made to coincide with the line from which the angle is to be laid off, and the center of the protractor, point *C*, is made to coincide with the point on the line. On the outside of the arc a mark is made on the drawing at the desired reading. The protractor is then removed from the drawing and the line drawn on the plan.



FIG. 192. SEMICIRCULAR PROTRACTOR.

Instead of having the 0° and 180° of the protractor on its lower edge some instruments are made as shown in Fig. 192.

This form is claimed by some draftsmen to be more convenient, because in handling the protractor by placing the fingers on the base neither the graduations nor the line on the plan are covered by the hand.

454. Full-Circle Protractor. — The full-circle protractor is of use particularly in stadia work or in plotting any notes where azimuth angles of over 180° have been taken. For such work as stadia plotting an ordinary paper protractor 8 to 12 inches in diameter is sufficiently accurate, and, in fact, paper protractors of this size will yield more accurate results than the smaller metal ones.

455. Some of the metal protractors are provided with an arm and vernier attachment. These, while giving more precise results, require more time for manipulation, and a plain metal protractor with a diameter of, say, 8 inches will give sufficiently close results for all ordinary work. As a matter of fact a protractor with a vernier reading to minutes can be set much closer than the line can be drawn, and it is therefore a waste of time to attempt to lay off the angles on a drawing with any such accuracy. There is, however, a protractor of this type with a vernier reading to about 5 minutes which may be of use in precise plotting.

456. Three-Armed Protractor. — The three-armed protractor is used for plotting two angles which have been taken with an instrument (usually a sextant) between three known points, for the purpose of locating the position of the observer (the vertex of the two angles). The protractor has three arms, the beveled edges of which are radial lines. The middle arm is fixed at the 0° mark and the other two arms, which are movable, can be laid off at any desired angle from the fixed arm by means of the graduations on the circle, which number each way from the fixed arm. The two movable arms having been set at the desired angles and clamped, the protractor is laid on the plan and shifted about until each of the three known points, (which have already been plotted on the plan), lies on a beveled edge of one of the three arms of the protractor. When the protractor is in this position its center locates the point desired which is then marked by a needle point Only one location of this center point can be obtained except in the case where the three known

points lie in the circumference of a circle which passes through the center.

457. There are several other types of protractor made, but the principle and use of all of them are much the same as those of the simple types which have been explained. It is well in purchasing a protractor to test it to see that the center point lies on a straight line between the 0° and 180° marks, that the edge of the protractor is the arc of a true circle, and that the graduations are uniform.

458. PANTOGRAPH. — This instrument is composed of several flat pieces of metal or wood joined in such a way as to form a parallelogram. One of the three points *A*, *B*, and *C*, (Fig. 193) is fixed and the other two movable. The remaining bear-



FIG. 193. THE PANTOGRAPH.

ing points are not essential except to support and steady the instrument. The two movable points are so attached to the instrument that they will trace out exactly similar figures. The instrument is used for copying a plan either to the same or to a different scale. There are several different forms of pantograph varying considerably in appearance, but they are all based on the same principle. The essential condition in their design is that all three points *A*, *B*, and *C*, must lie in a straight line and each point must be on one of three different sides (or sides produced) of a jointed parallelogram. Any one of the three points can be the fixed point. It is evident then that by changing the relative positions of these points, by moving them up or down the arms of the parallelogram, but always keeping the points on a

straight line, the scale of the copy can be made to bear any desired relation to the scale of the original drawing. These instruments are usually provided with scales marked on the arms indicating the proper settings for various reductions or enlargements. With a pantograph very accurate results cannot as a rule be obtained because there is lost motion in the several joints of the instrument. Some of the expensive metal pantographs, however, will give fairly good results.

459. PARALLEL RULER. — This is a beveled rule made of metal and mounted on two rollers of exactly the same diameter. It is used for drawing parallel lines. This instrument can be made to do accurate work, but it must be handled with a great deal of care to prevent the rollers from slipping. It is especially useful in drafting diagrams of graphical statics in connection with structural design, in drawing the parallel sides of buildings, section lining, blocking out for titles, and in drafting large titles which require mechanical lettering.

460. BEAM COMPASS. — This is an instrument used for drawing the arcs of circles whose radii are longer than can be set out with the ordinary compass drafting instrument. It is composed of a strip of wood or metal with two metal attachments which can be fastened to it. One of these attachments carries a needle point and the other, which is usually provided with a slow-motion screw for exact settings, carries a pencil or a pen. This instrument is particularly useful in laying out large rectangles such as are called for when surveys are plotted by coördinates (Art. 484, p. 449).

461. CONTOUR PEN. — This pen is constructed very much like an ordinary right-line ruling pen except that it has a metal shaft, running through the entire length of the holder, to which the pen is attached. The shaft revolves inside of the holder, and the pen is so shaped that it drags behind taking a position in the direction in which it is being moved. It is used for drawing irregular curved lines such as contours or shore lines. Not a little practice is required before one can use a pen of this type accurately. When skill in its use is once acquired, however, a plan can be easily made on which the contours all have a uniform weight of line giving a very satisfactory appearance. The

purpose of a contour line is to show the facts as to the surface, and this pen should not be used unless it is found by trial that it does the work in hand properly. Accuracy is more important than appearance.

462. PROPORTIONAL DIVIDERS. — Proportional dividers are substantially an ordinary pair of dividers with both legs prolonged through the pivot-point thereby forming another pair of legs above the pivot. The pivot is movable so that it can be pushed up and down in a slot in the legs and clamped in any desired position, thereby altering the relative lengths of the two pairs of legs. The sliding is accomplished in some dividers by a rack-and-pinion motion. When the pivot is in the middle position the legs are equal, and the space between the two points of one pair of legs is equal to the space between the other pair. There are marks on the legs showing the proper settings for the pivot so that the space between one pair of points will bear any desired ratio to the space between the other pair. The marks on the legs should not be accepted as correct, but should be tested by actual trial. One end of the proportional dividers is used to space off the distances from the original map and the other end used to plot that distance on the new map. Thus by means of this instrument a drawing can be enlarged or reduced to a definite scale without the use of the engineer's scale.

A drawing which is to be made two-thirds the size of the original can be readily reduced by scaling the distances from the original with a 20-ft. scale and plotting them on the new drawing by use of a 30-ft. scale. But when the reduction is some odd ratio which cannot be readily accomplished by means of the engineer's scale proportional dividers are very useful.

463. RAILROAD CURVES, FRENCH CURVES, FLEXIBLE CURVE, AND SPLINE. — For drawing arcs of curves of long radii, such as occur on railroad plans and on plans of curved streets, in city work, curves made of wood, hard rubber, celluloid, or metal are used; these come in sets of about one hundred, with radii varying from about 2 inches to 300 inches. The metal curves are the most common and are made with the inside and outside edges of the same radii both edges being beveled. When a pencil line is drawn the beveled edges may be used against the

paper, and when ink lines are drawn the curve can be turned over so that the beveled edges are up, thus preventing the ink from running in under the curve on the paper. Some curves for railroad work are made with a short straight edge tangent to the curve at one end and with the point where the curve begins marked by a line across it.

464. Irregular curves, called *French Curves*, are of a variety of shapes. They are made of wood, hard rubber, and celluloid, and are used to guide the pencil or pen in tracing out irregular curved lines on the map.

465. A *Flexible Curve* consists of a strip of rubber fastened to a flexible metal back. This curve can be twisted to conform to any irregular curved line on the map and can then be used as a guide against which the pencil or pen is held in tracing out the curve.

466. A *Spline* is a long thin flexible piece of wood, hard rubber, celluloid, or metal which can be bent so as to conform to a curve. It is usually held in position by specially designed weights with light metal arms which fit into a thin groove in the top edge of the spline. This instrument is used by naval architects for drawing long flat irregular curves such as occur in ship designs. In engineering drafting it is used in drawing the lines of arches, which frequently are not circular.

DRAWING PAPERS.

467. The drawing papers used by surveyors may be divided into four general classes; (1) those used for plotting plans, (2) tracing paper or tracing cloth which is used for copying drawings, (3) cross-section and profile papers, and (4) process papers.

468. DRAWING PAPER FOR PLANS.* — There are numerous grades of drawing paper ranging from very cheap "detail" to heavy paper mounted on cloth, called "mounted paper." For rough plots which are to be copied later or which are for temporary use only, a manilla detail paper is frequently used; but where the drawing is to be of a more permanent character a heavy white or manilla paper is used. Still more permanent

* See Appendix B for description of how to mount drawing paper on cloth.

plans, such as the plan of a survey of a city, should be plotted on heavy mounted paper. There is generally a right and a wrong side to all papers, which can be distinguished by the "water-mark"; this will read direct when the right side of the paper is toward the observer. A paper to be satisfactory for use should have a surface not too porous to take ink nicely, and of a fiber such that after scratching with a knife or rubbing with an ink eraser, the surface will still take ink effectively. No paper, however, after scratching can be expected to take bottle red ink, which permeates the fiber with extraordinary ease.

469. TRACING PAPER AND TRACING CLOTH. — In making copies of drawings, a thin transparent paper called *tracing paper* is often used. It is not tough enough to withstand rough handling and is used only for drawings of a temporary character. There are, however, certain kinds of transparent bond paper in use which will withstand considerable hard usage.

470. For more permanent drawings a *tracing cloth* is used, made of a very uniform quality of linen coated with a preparation to render it transparent. Most tracing cloth as it comes from the manufacturer will not readily take the ink, and it is necessary to rub powdered chalk or talc powder over the entire surface of the cloth before inking the drawing. After the surface chalk is brushed off, the tracing cloth is ready for use. Tracing linen generally has one side glazed and the other dull. Pencil lines can be drawn on the rough side, but the smooth side will not take even a very soft pencil; either side may be used for ink drawings. Some draftsmen prefer to use the glazed side but the dull side is more commonly used. A tracing inked on the glazed side may be tinted on the dull side either by crayons or by a wash; the latter will cockle the cloth unless it is put on quite "dry." It is easier to erase from the glazed than from the dull side, but the dull side will stand more erasing,* and gives more uniform lines.

---

* Erasure of ink lines from a tracing, as well as from any drawing paper, is a delicate undertaking. Success will result if the following suggestions are carefully observed: — with a smooth sharp knife pick off the ink from the paper; this can be done almost without touching the paper. When practically all of the ink is off, rub the line with a pencil eraser. This will take off the rest of the line except

In making a tracing of another tracing it will be found that the lines can be more readily seen if a white paper is put under the lower tracing. It frequently happens that it is necessary to make a tracing of a blue-print. The white lines of the blue-print are not easily seen through the tracing linen. An arrangement which will assist greatly in such work is to have a piece of plate glass set into the top at one end of a drawing table in such a way that it forms part of the top of the table. The blue-print is placed over this glass and the light shining through from the under side of this glass and through the blue-print will make the white lines easily visible for copying.

It is common practice, after a survey is made and before or during the computation of it, to plot the field notes accurately on detail paper and later to copy the plot on tracing cloth, which is the final drawing of the survey.

From these tracing drawings any number of process prints can be made (Art. 473), the tracing taking the place of the negative used in photographic printing.

471. CROSS-SECTION, AND PROFILE PAPERS. — Paper divided into square inches which, in turn, are divided into small subdivisions is used to plot cross-sections of earthwork and the like. The inch squares are usually divided into $\frac{1}{8}''$, $\frac{1}{16}''$, $\frac{1}{10}''$, or $\frac{1}{20}''$. Cross-section paper can also be obtained divided according to the metric system, or with logarithmic divisions. Cross-section paper usually comes in sheets.

472. *Profile Paper* which, as the name implies, is used for plotting profiles comes in rolls of 10 yds. or more. The vertical divisions are usually much smaller than the horizontal divisions, which makes it easier to plot the elevations accurately. The horizontal distances to be plotted occur mostly at full sta-

---

perhaps a few specks of ink which can readily be removed by a sharp knife. This method of erasing takes more time than the ordinary method of rubbing with an ink eraser until the line has disappeared, but it leaves the paper in much better condition to take another line. It is impossible to obtain good results by this method unless the knife has an edge which is both smooth and sharp. Where the surface of the tracing cloth has been damaged the application of a thin coating of collodion on the damaged portion will produce a surface which will take the ink.

tion points, which are represented on the profile by the vertical rulings on the paper.

Both the cross-section and the profile papers come in colors, (usually red, green, blue, orange, or burnt sienna) so that a black or a red ink line (the two most commonly used) will show up distinctly on the paper. These papers can be obtained also of very thin transparent material or in tracing cloth form, suitable for use in making process prints. Profile papers usually come in long rolls 20 inches wide.

473. PROCESS PAPERS. — Blue-Prints. — The most common process paper used in drafting offices is blue-print paper. It is a white paper coated on one side with a solution which is sensitive to light. After the solution is applied, the paper is dried and then rolled and sealed up for the market in light-proof rolls of 10 yds. or more. Fresh blue-print paper has a greenish-yellow color. The process of coating the paper and the general handling of the blue-print business is so well advanced and the price of the prepared paper is so low that surveyors now-a-days seldom coat their own paper. The process is a very simple one, however, and in emergencies, when commercial blue-print paper cannot be obtained, it may be very useful to know how to prepare it. A good formula for the solution is given below.

Make the following two solutions separately (in the light if desirable) and mix, **in subdued light or in a dark room,** equal parts of each of them.

Solution (1)

Citrate of Iron and Ammonia,	1 part (by weight)
Water,	5 parts (" ")

Solution (2)

Red Prussiate of Potash (re-crystalized),	1 part (by weight)
Water,	5 parts (" ")

The mixed solution is applied to the paper by means of a camel's hair brush or a sponge; this is done in a dark room or in subdued light. The paper is coated by passing the sponge lightly over the surface three or four times, first lengthwise of the paper and then crosswise, giving the paper as dry a coating

as possible consistent with having an even coating; it is then hung up to dry. The above coating will require about 5 minutes exposure in bright sunlight; for quick printing paper, use a larger proportion of citrate of iron and ammonia.

The blue-print of a plan is generally made in a printing frame, which is merely a rectangular frame holding a piece of heavy glass, with a back to the frame which can be lifted from the glass. This back is padded so as to fit tight against the glass when the back is clamped into position. The process of taking a print is, briefly, to expose the tracing, with the blue-print paper under it, to the sunlight a proper length of time and then remove the blue-print paper and wash it in water.

474. In detail, the process is as follows. First, turn the printing-frame over so that the glass is on the bottom, and remove the back of the frame. Then, after the tracing cloth has been rolled, if necessary, so that it will lie flat, place it **with its face against the glass.** Place the blue-print paper, which has been cut to the proper size, on top of the tracing with the **sensitized side of the paper next to the tracing.** The back of the frame is then clamped into position and the frame turned over so that the glass is up. It should then be examined to see that the tracing has been put into the frame with its ink lines against the glass, that the blue-print paper is under the entire tracing, and that there are no wrinkles in the tracing. All of the process to this stage should be done in subdued light, usually in a room with the shades drawn to keep out most of the sunlight.

The frame is then moved out into the direct sunlight, placed as nearly as may be at right angles to the rays of sunlight, and left there a proper length of time, which will depend upon the sensitiveness of the coating of the paper and the intensity of the light. Some blue-print papers will print in 20 seconds, others require 5 or 6 minutes in direct sunlight. In purchasing, then, it is necessary to ascertain from the dealer the "speed" of the paper and govern the exposure accordingly. Blue-prints can be made in cloudy weather as well as when the sun is visible, the only difference being that it requires a much longer time for the exposure. In all cases where the time of exposure is doubtful the following simple test may be applied. Instead of taking a

print of the entire tracing the first time, use only a small piece of the blue-print paper and put it in the frame as explained above and expose it a given time. Take it out and wash it, and from this test judge the length of exposure necessary to give the print of the entire drawing. An under-exposed print, after it has been washed, will be light blue in color with white lines; an over-exposed print will be dark blue with bluish-white lines. The result desired is **a dark or medium blue background with white lines.** It should be borne in mind, in judging the results, that all prints become a little darker when they are dry.

In washing the print it should be entirely immersed in clear water at first; care should be taken that no part of the print is left dry. It should be washed by moving it back and forth in the water or by pouring water over it until the greenish solution is entirely washed off its face. The print should be left in the water for 10 to 20 minutes, then it is hung up to dry. It will dry more quickly if hung so that one corner is lower than the others. It should not be hung where the sun will shine on it as the sunlight will fade it.

In taking prints great care must be exercised **not to get the tracing wet.** When the prints are being washed **the tracing should always be put in a safe place where the water will not spatter on it** and it should never be handled with moist hands. It is practically impossible to eradicate the effect of a drop of water or even the marks made by damp fingers on tracing cloth; it is sure to show in every subsequent print which is taken from the tracing.

475. *Blue-print cloth* is prepared in the same manner as the blue-print paper. Its advantage over the paper lies solely in the fact that it does not shrink as badly and is much more durable. Prints which are to be used on construction work where they are sure to get rough usage are sometimes made on cloth.

476. Vandyke Solar Paper. — There has always been a call for a sensitive paper which will give positive prints, — a black, a brown, or a blue line on a white background. Such effect was secured by the old so-called "black print process," but its operation was not altogether simple and good results were not reason-

ably sure. The Vandyke paper has apparently solved this difficulty, and in addition affords other advantages which the old "black process" paper did not possess.

Vandyke paper is a sensitized paper which is printed in the same way as a blue-print, except that the tracing is put into the frame so that the ink lines will be against the Vandyke paper. The exposure is about 5 minutes in direct sunlight or, more definitely, until the portion of the Vandyke paper which protrudes beyond the tracing is a rich dark tan color. Fresh Vandyke paper is light yellow in color. The print is washed for about 5 minutes in clear water (where it grows lighter in color) and then it is put into a solution consisting of about one-half ounce of fixing salt (hyposulphite of soda) to one quart of water, where it turns dark brown. It is left in the fixing bath about 5 minutes, after which the print is again washed in water for 20 to 30 minutes and then hung up to dry. The fixing solution may be applied with a sponge or brush if only a few Vandykes are being made, but it is better to immerse them in a tank containing the solution.

After the Vandyke print is washed the body is dark brown in color while the lines are white. This is not the final print to be sent out; it is simply the *negative*.

This Vandyke print is then put into the printing-frame in place of the tracing, the face of the Vandyke being next to the sensitive side of the process paper, and from it as many prints as are desired are made on blue-print paper or on any kind of sensitized paper desired. These blue-prints made from Vandykes have a white background while the lines of the drawing appear in deep blue lines, for in this case the rays of the sun act only through the white parts of the Vandyke (the lines), whereas in making an ordinary blue-print from a tracing the sun's rays act on the paper through all parts of the tracing cloth except where the lines appear. Where brown lines on a white background are desired, the print is made by using a sensitized sheet of Vandyke paper, in place of the blue-print paper.

One of the advantages of this process is that, as soon as a Vandyke has been made from the tracing, the tracing can be filed away and kept in excellent condition, the Vandyke being used in making all prints.

Another advantage in the use of the blue-prints which have been made by this process is that any additions made in pencil or ink show clearly on the white background of the print which is not true of the ordinary blue-print, on which corrections must be made with a bleaching fluid or water-color.

477. Electrical Printing Frames. — The uncertainty of the sunlight for making prints has brought forward a printing frame in which an artificial light is used.

One form of electrical printing frame is an apparatus consisting of a hollow glass cylinder, formed of two sections of glass, and resting on a circular base which is rotated by clock work. An electric light is suspended in the center line of the cylinder where it travels up and down by means of a clock work attachment.

The tracing and paper are wrapped around the outer surface of the glass where they are tightly held against the glass by a canvas which is wound around the cylinder by means of a vertical roller operated by a handwheel. The cylinder can be rotated at any desired speed and the light which travels up and down the axis of the cylinder can be moved through any desired distance or at any desired speed. These motions are all made automatically when the apparatus is once adjusted.

In another type of electrical machine several horizontal rollers are provided, with the light so arranged that as the tracing and blue-print paper passes from one roller to another the exposure is made. The speed of the machine is controllable and the length of the tracing that can be printed is limited only by the length of the roll of blue-print paper. With this machine, then, long plans or profiles can be printed without the necessity of frequent splicing which is required with other types of printing frame; furthermore the color of the print is also uniform throughout. The machine is driven by an electric motor. There are several machines of this general type on the market; some of them are provided with an apparatus for washing the prints as fast as they come from the machine.

478. Inks and Water-Colors. — Bottled ink, which is prepared in various colors, is used extensively on engineering drawings. The so-called "waterproof" inks differ from other

inks in that a water-color wash can be put over the lines without causing them to "run." Bottled inks are satisfactory for most drawings, but when very sharp and fine hair-lines are required it is well to use the stick india ink. This is made by grinding the ink together with a little water in a saucer made for this purpose, until the ink is thick and black enough to be used. If the ink becomes dry it can be restored to as good condition as when first ground by adding water, a drop or two at a time, and rubbing it with a piece of cork or a pestle; if the water is added too rapidly the ink will flake.

While the bottled black inks are fairly well prepared, the red inks are very unsatisfactory. They will sometimes run on paper where only very slight erasures have been made; in fact, on some of the cheaper papers red ink will always run. For tracing purposes red ink is wholly unsatisfactory, as it is impossible to obtain a good reproduction of a red ink line by any of the process prints. Where red lines are needed the use of *scarlet vermilion water-color* will be found to give not only a brilliant red line on the tracing, but also "body" enough in the color so that the lines will print fully as well as the black ink lines. Scarlet vermilion water-color will give much better lines on any paper than the bottled red inks. Only enough water should be used to make the water-color flow well in the pen. Other water-colors are used in the place of the bottled colored inks, such as *Prussian blue* instead of bottled blue ink, or *burnt sienna* instead of brown ink, and these give much better results.

It is frequently necessary on blue-prints to represent additions in white, red, or yellow. A white line can easily be put on by using *Chinese white* water-color; but sometimes a bleaching fluid is used which bleaches out the blue leaving the white paper visible. The best color for a red line on blue-prints is scarlet vermilion water-color; and for a yellow line none of the ordinary yellow water-colors gives as brilliant lines as Schoenfeld & Co.'s *light chrome yellow*.

For tinting drawings water-colors and dilute inks are used. Effective tinting may be done on tracings by using colored pencils on the rough side of the linen.

CHAPTER XVI.

METHODS OF PLOTTING.*

479. LAYING OUT A PLAN. — Laying out a plan requires careful work. If a good-looking plan is to be obtained this part of the work must be done with not a little judgment. Besides the plan of the survey or property the drawing must have a title, and sometimes notes and a needle to show the direction of the meridian. These must all be arranged so that the entire drawing when completed will have a symmetrical appearance. Often the plot is of such awkward shape that it is very difficult to lay out the drawing so that it will look well, and the draftsman's artistic instincts are taxed to the utmost to produce a satisfactory result.

480. Scale. — In many cases the scale of the plan as well as the general arrangement of its parts must be chosen by the engineer. Surveys of considerable extent which do not contain a great many details, such, for example, as the preliminary survey for a railroad, may be drawn to a scale of 400 ft. to an inch. A plan of a large piece of woodland or a topographical map of a section of a town may be represented on a scale of from 100 ft. to 400 ft. to an inch. A plan of a city lot for a deed is represented on a 20-ft. to 80-ft. scale; and city streets, such as sewer plans and the like, are frequently drawn to a scale of 20 ft. to 40 ft. to an inch. Sometimes on plans of construction work drawings of different scale are made on the same sheet. The drawing for a conduit, for example, may be represented by a general plan on a scale of 80 ft. to an inch, while on the same sheet the conduit may be shown in section on a scale of 4 ft. to an inch.

The field maps of the U. S. Coast and Geodetic Survey are usually plotted on a scale of $\frac{1}{10000}$, but some special maps are made on scales as large as $\frac{1}{2000}$. The field maps of the U. S. Geological Survey are mostly plotted to a scale of $\frac{1}{30000}$ and reduced on the lithograph sheets to $\frac{1}{62500}$ or $\frac{1}{125000}$.

* For a brief description of different projections for maps of large areas, such as states or counties, see Volume II, Chapter X.

These remarks in regard to scales are not to be considered in any sense as hard and fast rules to govern all conditions. They are suggested simply to give some idea of the existing practice in this matter.

METHODS OF PLOTTING TRAVERSES.

481. PLOTTING BY PROTRACTOR AND SCALE. — The most common method of plotting angles is by use of the protractor (Art. 452, p. 430), and of plotting distances, by use of the engineer's scale. Every traverse consists of a series of straight lines and angles, which can be plotted by a protractor in the following manner. First, the survey to be mapped should be sketched out roughly to scale, in order to ascertain its extent and shape so as to decide the size of paper necessary for any given scale of drawing and to determine its general position on the sheet, which will fix the direction of the first line of the traverse, to be used as a starting line for the entire drawing. This having been done, the first line is drawn in the proper place on the paper, its length is scaled off by using the proper scale, and its two extremities accurately marked by pencil dots or by means of a needle point, and surrounded by a light penciled circle. The line should be drawn so that it will extend beyond the next angle point a distance greater than the radius of the protractor, this extension of line being of use in the manipulation of the protractor.

The protractor is placed so that its center is exactly on the second angle point and so that **both** the 0° and 180° marks of the protractor exactly coincide with the line. The traverse angle taken from the field notes is plotted, the protractor removed, the line drawn, and the length of the second course carefully scaled. Then the protractor is placed along this new line and opposite the third point, the angle at that point is laid off, the next line drawn, and the distance scaled. By this process the entire traverse is plotted.

482. Checks. — On all plotting work, just as on all field-work and computations, frequent checks should be applied to insure accuracy.

If the traverse is a closed traverse the plot, of course, should close on the paper.* If it does not and the error of closure is in a direction parallel to any one of the lines, there is probably a mistake in plotting the length of that line. If there is no indication of this sort the mistake may be either in scaling, in laying off the angles, or in both. In such a case the entire plot should be checked unless there is some reason to think that a certain line may have been laid off at the wrong angle, in which event that questionable angle should be replotted. The bearings of all the lines of the traverse can be computed with reference to the magnetic or to any assumed meridian; any line can be produced to meet the meridian line, and this angle measured and checked. Similarly, the bearing of the last line of a traverse which does not close can be computed and the angle the last line makes with the meridian measured. If it checks the computed angle it is evident that no error has been made in the angles unless mistakes were made that exactly balance each other, which is not probable. In this way, by "cutting into" the drawing here and there, the angular error, if there is one, can be quickly "run down," without laying out all of the angles again and so possibly repeating the mistake that was originally made. The angles measured in applying this check have different values from the ones first laid out, and the chance of repeating the original mistake is thereby eliminated. If no error is found to exist in the angles, the distances should next be checked. This can be done in two ways, and in some drawings both of these checks should be applied.

First, scale each line separately setting down the results independently upon a sheet of paper. After these are all recorded (and not before), compare the lengths with the lengths of lines as taken from the field notes. No error should be allowed to pass if it is large enough to be readily plotted by the use of the scale.

* Instead of plotting every line of the traverse from its preceding line and returning, in the case of a closed traverse, to the other end of the starting line, it may be well to plot half the traverse from one end of the starting line and the other half from the other end; the check will then come at a point about half-way around the traverse. The advantage of this method lies in the fact that accumulative errors are to some extent avoided since they are carried through only half as many courses.

Second, take a long straight piece of paper, lay this on the drawing, and mark off the length of the first line on the edge of the paper; then mark off the length of the second line starting from the mark which denotes the end of the first line, and proceed in a similar way to the end of the traverse. Apply the scale to the strip of paper and read the station of each mark; record each of these independently and afterwards compare them with the field notes. The entire length of line should check within a reasonable amount depending upon the scale; the allowable error can easily be determined by the principle explained in Art. 23, p. 14.

By checking angles and distances by the above methods errors of any consequence can be avoided; in any case **a draftsman should not allow a drawing to leave his hands which has not been properly checked and known to be correct.**

When the traverse is not closed, such checks as have been described above must **always** be applied; otherwise there is no assurance whatever that the plan is correct. It is especially necessary to check the bearings of lines frequently, so that the accumulation of small errors may not become appreciable.

483. Protractor and T-Square. — While the ordinary T-square is not much used in plotting engineering plans, there are some occasions where it is convenient to use it. Where a traverse has been run by bearings or by deflection angles the T-square with a shifting head can be conveniently used in connection with a protractor for plotting the angles by bearings.

The paper is fastened to a drawing board having a metal edge, which insures one straight edge to the board. A meridian line is drawn on the paper, and the shifting head of the T-square is fastened so that the blade coincides with the meridian line. Then as the T-square is slid up and down the edge of the drawing board its blade always takes a direction parallel to the meridian. By means of the protractor shown in Fig. 192 the bearing of each line can be readily laid off or checked as illustrated by Fig. 194 and the distances laid off with the scale. In order to secure a satisfactory check, the deflection angles should be laid off directly from the previous line, and the bearings checked by means of the T-square and protractor.

It is evident that the bearings of the lines may be computed just as well from any assumed meridian as from the magnetic or true meridian; and that the drawing can be fastened to the board



FIG. 194. LAYING OFF BEARINGS BY USE OF T-SQUARE AND PROTRACTOR.

in such a way that the T-square can be conveniently used. This method is especially applicable to compass surveys as it obviates the necessity of drawing a new meridian line through each angle point.

This method can be easily applied also as a means of checking any of the angles of a traverse which have been plotted by any of the ordinary methods.

484. PLOTTING BY RECTANGULAR COÖRDINATES. — In plotting by this system all points in the traverse are referred to a pair of coördinate axes. For convenience these axes are often the same as those used in calculating the area enclosed by the traverse. The advantages of this method are, (1) that all measurements are made by means of the scale only and (2) that the plotting may be readily checked.

To plot a survey of a field by rectangular coördinates, first calculate the *total latitude* and the *total departure*, that is, the ordinate and the abscissa, of each point in the survey. If the meridian through the most westerly point and the perpendicular through the most southerly point are chosen as the axes negative

signs in the coördinates will be avoided. The coördinates of the transit points are computed by beginning with the most westerly point, whose total departure is zero, and adding successively the departure of each of the courses around the traverse. *East* departures are called *positive* and *West* departures *negative*. The total departure of the starting point as computed from that of the preceding point will be zero if no mistake is made in the computations. The total latitudes may be computed in a similar manner beginning, preferably, with the most southerly point as zero.

485. For plotting the points on the plan, a convenient method of procedure is to construct a rectangle whose height equals the difference in latitude of the most northerly and the most southerly points and whose width equals the difference in departure of the most westerly and the most easterly points. If the most westerly and the most southerly points are taken as zero then the greatest ordinate and the greatest abscissa give the dimensions of the rectangle. The right angles should be laid off either by the use of a reliable straight-edge and a triangle or by the beam compass.

486. The better method, however, is to construct the perpendiculars by means of a straight-edge and a triangle. It is



FIG. 195. ERECTING A PERPENDICULAR WITH A STRAIGHT-EDGE AND AN INACCURATE TRIANGLE.

not at all necessary, although it is always desirable, that the triangle shall be accurate. It should be used in the following manner. It is first placed against the straight-edge, as shown by the full lines in Fig. 195, and a point A, marked on the paper. Point C is also marked opposite a certain definite part of the triangle. Then the triangle is reversed to the dotted position and brought so that its edge coincides with point A, and then point B is marked opposite point C, as nearly as can be judged. A point D is plotted midway between B and C and the line AD is then drawn which is perpendicular to the straight-edge. If the triangle is accurate point B will fall on point C, so that this is a method of testing the accuracy of the right angle of any triangle. If it is found to be inaccurate it should be sent to an instrument maker and be "trued up." A few cents spent in keeping drafting instruments in shape will save hours of time trying to locate small errors, which are often due to the inaccuracy of the instruments used.

If the compass is used the right angle may be laid off by geometric construction. On account of the difficulty of judging the points of intersection of the arcs, very careful work is required to obtain good results with the compass.

Since the accuracy of all of the subsequent work of a coördinate plot depends upon the accuracy with which the rectangle is constructed, great care should be taken to check this part of the work. The opposite sides of the rectangle should be equal and the two diagonals should be equal, and these conditions should be tested by scaling or with a beam compass before continuing with the plot.

487. After the rectangle has been constructed, all points in the survey can be plotted by use of the scale and straight-edge. To plot any point, lay off its total latitude on both the easterly and the westerly of the two meridian lines of the rectangle, beginning at the southerly line of the rectangle. Draw a line through both of these points by means of a straight-edge.*

* Accurate work, of course, cannot be obtained with a straight-edge that is not true. A straight-edge can easily be tested by drawing a fine pencil line on the paper along one edge of the straight-edge; then turn the straight-edge over on its other side, fit the same edge to the two ends of the pencil line, and see if the edge coincides with the line.

Then lay off along this line the total departure, beginning at the westerly side of the rectangle, thus obtaining the desired position of the point.

The computations of the total latitudes and departures and the method of plotting a traverse by the coördinate method are shown in Fig. 196. This is the survey which is shown in the



FIG. 196. COMPUTATIONS AND PLOTTING BY RECTANGULAR COÖRDINATES.

calculations in Fig. 180, p. 410, and in the form of notes in Fig. 52, p. 103.

488. Plotting by rectangular coördinates is the most accurate of all the methods usually employed. It is not very often applied, however, to traverses which do not close, as there is seldom any other use for the coördinates of such a traverse, and the

labor of computing them for this purpose alone is hardly warranted. For such traverses, therefore, either the protractor and scale, the Tangent Method, or the Chord Method (which are explained in the following articles) may be employed. But for plans of a closed traverse, where the latitudes and departures have been computed in connection with calculating its area, this coördinate system of plotting is frequently used.

489. Checks. — When the transit points have been plotted, the scale distance between consecutive points should equal the distance measured in the field. It sometimes happens that some of the transit lines run so nearly parallel to one of the axes that the distances will scale the right amount even though a mistake has been made in laying off one of the coördinates. In such a case any appreciable error can be detected by testing the bearings of the lines by means of a protractor. These two tests, together with the scaled distances of any cut-off lines which may have been measured in the field, (Art. 145, p. 110), form a good check on the accuracy of the plotting. Since all of the points are plotted independently errors cannot accumulate. If it is found that any scaled distance fails to check with the measured distance it is probable that one of the two adjacent lines will also fail to check and that the point common to the two erroneous lines is in the wrong position.

It should be remembered that everything depends upon the accuracy of the rectangle and that nothing should be plotted until it is certain that the right-angles have been accurately laid off.

490. PLOTTING BY TANGENTS. — The traverse should first be plotted approximately on some convenient small scale by use of the protractor and scale, to ascertain its extent and shape. The importance of this little plot is often overlooked, with the result that when the plan is completed it is found to be too close to one edge of the paper or otherwise awkwardly located on the sheet. It takes only a few moments to draw such a sketch, and unless the draftsman is sure of the shape and extent of the plot he should always determine it in some such manner before the plan is started.

The directions of all the lines are referred to some meridian

and the bearings determined with an accuracy consistent with the measured angles. From the auxiliary plot it can be decided where to start the first course of the traverse on the paper and in what direction to draw the meridian, so that the lines of the completed traverse will be well balanced with the edges of the sheet, and so that the needle will be pointing, in a general way, toward the top of the drawing rather than toward the bottom.

The bearing of the first line is plotted as follows (Fig. 197).



FIG. 197. PLOTTING BY TANGENT OFFSETS.

Lay off on the meridian line a length Aa of at least 10 inches and erect a perpendicular at a on the right-hand side of the meridian if the bearing of the first course is east, and on the left-hand side if it is west. Look up in the table of natural functions the tangent of the bearing of the first course and scale off this distance ab on the perpendicular.* Draw Ab which is

* These distances and also the 10-inch base-lines are all laid off by use of the engineer's scale. By using the 10-ft. or 100-ft. scale the tangents can be laid off without any computation, whereas with the other scales the tangent must be multiplied by some number, e.g., by 2 if the 20-ft. scale is used, by 3 if the 30-ft. scale is used, etc., taking care in the pointing off.

If it is deemed unnecessary to use a base as long as 10 inches, one can be laid off at the "10" mark on any engineer's scale and the tangent distances laid off by using the same scale, e.g., if a 20-ft. scale is used the "10" mark will give a base-line 5 inches long.

the direction of the first course. On this line scale off AB, the length of the first course. On this line produced lay off Bg equal to 10 inches and erect a perpendicular, scaling off on the perpendicular the length gd equal to the tangent of the **deflection angle** at B. This determines the direction of BC from the first course. The remaining lines of the traverse are plotted in the same manner, using each time the deflection angle.

491. Checks. — Unless the survey is a closed traverse checks must be occasionally applied. Every third or fourth course should be checked by finding the angle between it and the meridian line. This angle should be found by the same method (tangent offset method) and by using a base of 10 inches as in plotting the angles. In checking the course De, for example, a meridian is drawn through D parallel to Aa, De is scaled off 10 inches, and a perpendicular ef erected. The distance ef is scaled and from the table of tangents the angle fDe is obtained. If the angle that the course makes with the meridian line disagrees with the calculated bearing of that course by any considerable amount, say, 10 minutes of angle or more, the previous courses should be replotted. If the error is less than 10 minutes the course which is being checked should be drawn in the correct direction so that even the slight error discovered may not be carried further along in the plot. Then after the plotting has proceeded for three or four more courses the check is again applied.

The bearings of the lines can be checked by use of the protractor and this will detect errors of any considerable size, but this method will not disclose any small errors ; moreover, if it is desired to have the plot when completed as accurate as could be expected from the precise method employed, it is entirely inconsistent to check by use of a method which is far less accurate than the one used in making the plot. For this reason the checks on the direction of the lines are applied with the same care and by the same method as was used in the original layout of the angles.

Occasionally it is more convenient to plot the complement of an angle rather than the angle itself, as was done in plotting the line EF. In this case the right angle erected at E must be laid

off with great care, preferably by the method explained in Art. 486, p. 450.

It is evident that the direction of each course could have been plotted by drawing a meridian line through the transit points and by laying off the **bearings** by the tangent method. But if such a method were used there would be no single check applied that would check all the previous courses, which is an important feature of the method explained above.

If the traverse is not closed the lengths of the lines of the traverse should **always** be checked by the methods explained in Art. 482, p. 446.

492. PLOTTING BY CHORDS. — This method, which is employed by many draftsmen in plotting traverse lines, is fairly good although probably not so accurate as the Coördinate or as convenient as the Tangent Methods.

Fig. 198 represents the traverse *ABCDEF* which has been



FIG. 198. PLOTTING BY CHORDS.

plotted by chords. It is the same traverse that is shown in Fig. 197.

On the meridian line the distance *Aa* is scaled off equal to 10 inches and the arc *ab* swung from *A* as a center by use of the ordinary pencil compass. Then from a table of chords * the

* Tables of chords can be found in Trautwine's "Civil Engineer's Pocket Book," published by John Wiley & Sons, New York.

length of the chord *ab* is found for the angle *aAb*. The point *b* is sometimes located by setting the dividers at the distance *ab* and with *a* as a center intersecting the arc *ab* at *b*; but the more accurate method is to scale from point *a* the chord distance and mark the point *b* on the arc. Then the line *Ab* is drawn and *AB* scaled off on it. With *B* as a center the arc *gd* is drawn and the chord *gd*, corresponding to the deflection angle at *B*, is scaled off. *Bd* is then drawn and *BC* scaled off on it. In the same way the entire traverse is plotted.

493. Use of the Sine. — It is evident that the chord

$$ab = 2 \times 10 \times \sin \frac{A}{2};$$

hence, if a table of chords is not available, a table of sines (always easily obtainable) can be used. The sine of half the angle can be taken from the tables and multiplied by 20 mentally. Some draftsmen use the table of sines and a radius of 5 inches to avoid the multiplication. This is not recommended because a base of 5 inches is not long enough to insure a very accurate drawing. The necessity of multiplying by 2 can very easily be done away with by laying off the radius with a 20-ft. scale and scaling off the sine of the angle with a 10-ft. scale.

With dividers of the ordinary size it is impossible to lay out an arc with a 10-inch radius. In such a case either beam compasses must be used or the radius employed must be shorter, so short, in fact, that it will frequently be better to resort to the Tangent Method.

494. Checks. — Since this method is usually applied to traverses which do not close it is desirable to check every fourth or fifth course so that a mistake will not be carried too far before it is discovered and thereby cause a waste of time. In Fig. 198 it is desired to check the calculated bearing of *De*. The meridian *Df* is drawn through *D* parallel to *Aa*, the arc *fe* is swung with *D* as a center and with a radius of 10 inches, and the chord *ef* is scaled. From the table of chords (or sines) the angle *fDe* (the bearing) can be found. It should agree reasonably well with the calculated bearing. The degree of precision to be expected when plotting by chords is a little less than

that suggested for the Tangent Method in Art. 455, unless the beam compass is used. The Tangent Method, especially if the right angles are laid off by reversing the triangle, gives more accurate results than the Chord Method, for the use of the ordinary compass in the Chord Method is a fruitful source of error unless it is handled with the utmost care.

METHOD OF PLOTTING DETAILS.

495. BUILDINGS, FENCES, STREAMS, ETC. — The previous articles have dealt with the plotting of the traverse lines only, and these in many cases form merely the skeleton of the final plan. In the field the details of the survey are located from the transit line; and, in a similar manner, the details are located on the plan from the traverse line which has already been plotted.

Buildings, fences, shore-lines, streams, etc. are all plotted by means of the scale for distances and the protractor for the angles. Often a smaller protractor is used for this sort of work than for the traverse lines. This is permissible, for the lines which locate the details are usually short in comparison with the traverse lines and the resulting error is small in any case; furthermore any slight error in the location of a detail will not as a rule affect the rest of the drawing, whereas an error in a transit line will, of course, have an effect on all of the rest of the drawing. The plotting of buildings has been taken up in connection with their location. (See Chapter VI.)

In plotting a set of notes where several angles have been taken at one point, such as in stadia surveying, it is well to plot all of the angles first, marking them by number or by their value, and then to plot the distances with the scale.

496. CONTOURS. — Where contours are located by the cross-section method (Art. 334, p. 314), this cross-section system is laid out in soft penciled lines on the drawing. The elevations which were taken are written at their respective points on the plan and then the contours desired are sketched. The ground is assumed to slope uniformly between adjacent elevations, and, by interpolation between these points, the location of the contours on the plan can be made. When the contours have been

located, the cross-section lines and elevations are erased unless the plan is intended to be used as a working drawing. As a rule all useful data, such as construction lines and dimensions, are left on a working drawing.

When the contours are located by any other means the principle is the same. The points whose elevations have been determined are plotted by scale and protractor, and the contours are interpolated between the elevations and sketched on the plan.

497. CROSS-SECTIONS. — In plotting on cross-section paper, the rulings of the paper are used as the scale, and all the dimensions of the cross-section, which are to be plotted, are laid off by counting the number of squares on the cross-section paper.

In highway, railroad, and dam construction it is often necessary to keep a record of the progress made on the earthwork by plotting the cross-section at each station, and, as the work goes on, to mark on each section in colored ink the progress of the work for each month. In this way monthly estimates can be readily made, and the cross-section sheets will also give a record of the progress of the work, each month being represented by a different colored line or by a different style of line.

Where a series of cross-sections like this are to be plotted the station number and the elevation of the finished grade are recorded just under or over the section. To avoid mistakes in numbering the sections this should be done at the time of plotting the section.

As these cross-section sheets rarely go outside the office they are usually considered in the same class with working drawings, and dimensions, such as the areas of sections or the quantities of earthwork, are usually recorded on them, together with any other data which may be of use in calculating the volumes.

498. PROFILES. — Profiles are almost always plotted on profile paper, although occasionally they are plotted on the same sheet with the plan so that the two can be readily compared.

The profile is intended to show (graphically) relative elevations. In most surveys the differences in elevation are so small in comparison with the horizontal distances that it is necessary to exaggerate the vertical scale of the profile so that the eleva-

tions can be read from the profile with a reasonable degree of accuracy. The horizontal scale of the profile should be the same as the scale of the plan, but the vertical scale should be exaggerated, say, 5 to 20 times the horizontal scale, depending upon how close it is desired to read the elevations from the drawing. If the horizontal scale of the profile is 80 ft. to an inch its vertical scale should probably be 20, 10, or 8 ft. to an inch.

499. In plotting any profile the first step is to lay it out properly on the paper, i.e., to decide, from an examination of the range of the elevations, where to start it on the paper so that it will look well when completed, and so that any additions or studies which may subsequently be drawn on it will come within the limits of the paper. Station 0 of the profile should come on one of the heavy vertical lines, and the heavy horizontal lines should represent some even elevation such as 100, 125, 150, etc.

The profile is plotted by using the rulings of the profile paper as a scale; it is drawn in pencil first and afterward inked in. It will be found, if these profile papers are carefully measured with a scale, that they are not as a rule very accurate. The rulings may be uniform, but owing to the shrinkage of the paper the divisions frequently do not scale as long as they should. In plotting a profile or section on such paper no attempt is made to use a scale; the scale of the paper is assumed to be correct and the intermediate points are plotted by estimation, which can almost always be accurately done since the rulings of the paper are quite close together.

The data for a profile of the ground generally consist of levels taken in the field at such points that the ground may be assumed to run straight between adjacent elevations. For this reason, in drawing the profile, the points where the slope of the ground changes should not be rounded off. On the other hand, however, the ground probably does not come to an actual angle at that point. The profile should be plotted therefore as a series of free-hand straight lines drawn so that the angles are not emphasized. When a profile is made from a contour map, the line should be a smooth, rather than an angular line.

500. Profiles of the surface of the ground are generally made for the purpose of studying some proposed construction

which is represented on the profile by a grade line, consisting usually of a series of straight lines. The points where the gradient changes are plotted and connected by straight ruled lines unless the proposed grade should happen to be a vertical curve (Art. 294, p. 276). Vertical lines are also drawn from the bottom of the profile to the grade line at these points.

501. When the elevations are such that the profile, if continued, will run off the top or bottom of the paper the entire surface line is lowered or raised some even number of feet, such as 20 or 50 ft., and the plotting continued: the number of feet represented between two heavy horizontal rulings of the profile paper should determine the drop or rise of the grade line. This change should be made, when convenient, on one of the heavy vertical rulings of the paper or on one of the vertical lines where the gradient changes.

502. Checks. — After plotting the surface and grade elevations in pencil, read off from the profile the station and elevation of each point as plotted and record both the station and elevation on a piece of paper. Compare these readings with the data given and make the necessary corrections. Time can be saved if one man reads off the station and elevation from the profile while a second man compares the readings with the note-book. A quick method of **plotting** profiles is to have one man read the notes while the other man plots them, but when the profile is being **checked** this method should not be used ; the man, preferably the one who did not do the plotting, should **read from the profile as plotted** and these readings should be compared with the note-book.

PROBLEMS.

1. Plot the surveys given in Fig. 50, p. 100, and in Fig. 53, p. 104, by Protractor and Scale, Rectangular Coördinates, Tangents, or Chords.

2. Plot by use of Scale and Protractor the notes given in Fig. 80, p. 175, and in Fig. 132, p. 302.



FIG. 199. COMPLETED LAND PLAN.

CHAPTER XVII.

FINISHING AND FILING DRAWINGS.*

503. WHAT SHOULD APPEAR ON A DRAWING. — Drawings are made for a great variety of purposes, so that the data which a plan should contain depend entirely upon the use to which it is to be put. There are, however, several important things which should appear on every engineering drawing. In the first place, it should have a complete title which should be a brief description of the drawing. The title should state whether the drawing is a plan, cross-section, profile, etc.; what it represents, — a lot of land, a sewer, a railroad, etc.; the name of the owner; the place; the date; the scale; and the name of the surveyor. Besides the title, some plans, such as land plans, always require the names of owners of abutting property, and a meridian. Notes are frequently added giving such information as is necessary to interpret the plan. All essential dimensions are lettered in their proper places.

Besides these it is well to insert in some inconspicuous place (preferably near the border) the number of the note-book and the page from which the notes were plotted, and also the initials of the draftsman who made the drawing and of the man who checked it.

Fig. 199 represents a land plan which contains all of the essentials; it is a plot of the land shown in the form of notes in Fig. 52, p. 103; its computations are on p. 410; and its working plot is illustrated by Fig. 196, p. 452.

504. TRAVERSE LINES. — The convenient use of a plan sometimes requires the traverse line to be shown on the completed drawing. In such a case it is usually shown as a full colored line, each of the angle points being represented by a very small circle of the same color, the center of which marks the angle point. Sometimes the lines of the traverse are drawn to the angle points

* For methods of finishing topographic and hydrographic maps see Volume II. Chapter XI.

which are marked by very short lines bisecting the angles. Fig. 200 illustrates these two methods of marking transit points.



FIG. 200. METHODS OF MARKING ANGLE POINTS ON TRAVERSE LINES.

Triangulation stations are represented by a small equilateral triangle drawn around the station point. Fig. 131, p. 294, contains several examples of this.

505. PHYSICAL FEATURES. — The boundaries of property and the physical features which are represented on a plan, such as streets, buildings, etc., are usually drawn in black ink. Any additions or proposed changes are frequently drawn in colored ink, usually in red, although water-color is much better for the reasons stated in Art. 478, p. 443.

Shore lines and brooks are represented either in black or in Prussian blue. As a rule the shore line should be one of the heaviest, if not the heaviest line, on the drawing. Water-lining shown in the topographical signs in Fig. 181, adds materially to the prominence and appearance of a shore line.

506. TOPOGRAPHIC CONVENTIONAL SIGNS. — On topographic maps certain physical features are shown by conventional signs which have come to be used so generally that they are practically standard throughout the country. A few of the more common of these symbols are shown in Fig. 201. The one representing "cultivated land" and the horizontal lines of the "salt marsh" and "fresh marsh" symbols are ruled; the rest are executed with an ordinary pen, Gillott's No. 303 being a good one for such work. (See also Volume II, Chapter XI.)

It will be noticed that in the symbol for "grass" the individual lines of a group all radiate from a center below the group and also that they end on a horizontal line at the bottom. The



DECIDUOUS TREES (OAK).



DECIDUOUS TREES (ROUND LEAF).



GRASS.



CULTIVATED LAND.



FRESH MARSH.



SALT MARSH — SAND.



WATERLINING.

LEDGES — EVERGREEN TREES.

FIG. 201. TOPOGRAPHIC CONVENTIONAL SIGNS.

horizontal line, in the case of "grass" or "marsh" symbols, should always be **parallel to the bottom of the map.**

In executing "water-lining" the first line outside the shore line should be a light full line drawn just as close to the shore line as possible, and should follow very carefully every irregularity of the shore line. The next water-line should be drawn parallel to the first but with a little more space between them than was left between the shore line and the first water-line. Then the third water-line should be spaced a little farther out, and so on; five to ten lines are sufficient to represent this symbol properly. As the succession lines are added farther and farther from the shore line, the little irregularities of the shore gradually disappear until the outer water-line shows only a few irregularities opposite the most prominent ones of the shore.

Water-lining, as well as fresh marsh and salt marsh symbols, is often represented in Prussian blue. In fact, on some topographic maps most of the signs are represented by colors, — the trees by green, the grass by a light green tint, water by a light blue tint, cultivated land by yellow ochre, and so on.

Contour lines (shown in several of the cuts in Chapter XI.) are almost always drawn in burnt sienna water-color. Every fifth or tenth contour is usually represented by a line slightly heavier and also a little darker in color. Gillott's No. 303 pen will be found to give good results for this work; but a contour pen, if it can be handled well, will give very uniform lines especially where the contours have no sharp turns. In numbering the contours some prefer to break the lines and place the numbers in the spaces, while others prefer to place the numbers just above or below the contours. Frequently a number is placed on every contour, but for most plans this is entirely unnecessary. If the contours are somewhat regular it is only necessary to number, say, every fifth contour. A good general rule to follow is to number only those lines which are necessary in order that the elevation of any contour may be found without appreciable mental effort. The numbers on the contours should be small plain figures in burnt sienna.

The shape of the surface of the ground is sometimes represented by hachure lines, which are illustrated in Fig. 202. The

contour lines are first sketched in pencil as a guide to the draftsman in drawing the hachure lines, which should be drawn normal to the contours. The short lines are drawn from the summit downward in rows, each row just touching the next preceding row. The steepness of the slope is represented by the weight and length of the lines,—the steeper the slope the heavier and shorter the lines. The individual lines are **equally** spaced, but on the flat slopes where the lines are lighter they have the appearance of being spaced farther apart.



FIG. 202. HACHURE LINES.

507. Such physical features as railroads, highways, buildings,

Building. (On large scale maps.)

Barn or Shed. (On large scale maps.)

Buildings. (On small scale maps.)

Fence.

City or Town Boundary.

Stone wall.

Stone Retaining wall.

Single Track Railroad.

Double Track Railroad.

Roads.

Trail.

Bridge.

△ Triangulation Station.

⊡ Stadia Station.

⊙ Transit Point. Intersection Point (in Triangulation.)

B.M. x1232 Bench Mark.

ROMAN

ABCDEFGHIJKLMNOPQRSTU
VWXYZ &
abcdefghijklmnopqrstuvwxyz

GOTHIC

ABCDEFGHIJKLMNOPQRSTU
VWXYZ &
abcdefghijklmnopqrstuvwxyz

Stump Writing

ABCDEFGHIJKLMNOPQRSTUVWXYZ
abcdefghijklmnopqrstuvwxyz

1234567890 ½ ¾ ⅞ *1234567890 ½ ¾* 1234567890 ½ ¾ ⅞

ABCDEFGHIJKLMNOPQRSTUVWXYZ
abcdefghijklmnopqrstuvwxyz
1234567890 ½ ¾
Reinhardt's Style
A B C D E F G H I J K L M N O P Q
R S T U V W X Y Z &
a b c d e f g h i j k l m n o p q r s t u v w x y z
1234567890 ½ ¼ 5/32 2 3/16 5 1/8 1234567890 1/8 9 3/4 7/8
A B C D E F G H I J K L M N O P Q R S
T U V W X Y Z &
abcdefghijklmnopqrstuvwxyz

FIG. 205. (Drawn by W. L. Vennard and E. D. Sewell.)

and boundaries are usually represented in black ink by the symbols shown in Fig. 203.

508. LETTERING.*— The lettering on a drawing probably has more to do with its appearance than any other feature. To be able to do good lettering at first is a gift which but few men possess. It is an art that can be acquired by the most awkward draftsman, however, if he will study it carefully and devote a little time to systematic practice.

Several different styles of lettering are shown in Figs. 204 and 205. The general style to use in any given case depends on the type of drawing and on the use to which it is to be put. On plans which are to be sent from the office as completed drawings such letters as the Roman or Gothic may be appropriate. Stump writing is a style of lettering which is difficult to execute but whose appearance, when well done, is very artistic. The ornate lettering in vogue a few years ago has been superseded by simpler styles which require much less time to produce. For construction drawings, like a plan of a bridge or a conduit, for example, the Reinhardt letters are used



FIG. 206. LETTERING ON SLOPES.

* For a complete discussion and illustrations of lettering see any of the following publications: "Plain Lettering," by Professor Henry S. Jacoby, published by the Engineering News Publishing Company; "Technic of Mechanical Drafting," by Charles W. Reinhardt, published by the Engineering News Publishing Company.

to a considerable extent. The title of such a plan looks well lettered in either erect or inclined Gothic.

All plans should be lettered so as to read from the bottom. Unless a draftsman exercises considerable care he will find, when the plan is completed, that some of the lettering is upside down. Fig. 206 illustrates the proper lettering of lines of various slopes.

For fine lettering, No. 604 Gillott is a good pen. It may be a little too fine the first day or two but it soon wears down to about the right condition and stays practically in that condition. Gillott's No. 303 is a little finer pen but is adapted to the finest lettering usually required. No. 170 is still finer; it is well adapted to double stroke work, such as Roman letters.

For heavier lines, King's No. 9 Nonpareil pen is good. Ball-point pens are used for single stroke lettering, but one has to be expert to make such letters as *P* and *F* with a ball-point pen without blotting the upper left-hand corner of the letter.

There is a set of patent pens called Paysant pens and numbered according to their fineness; the higher the number the finer the pen. The No. 6 or No. 7 Paysant pen is about right for such lettering as appears in "Notes" on plans; No. 4 and No. 5 are adopted to lettering of titles. It requires a little knack to use a Paysant pen, but it is a knack which is very readily acquired.

It is impossible to obtain satisfactory results in making single stroke letters by the use of one pen only. A different pen is required for different weight of lines. Usually a set of from four to six pens is necessary for this sort of lettering.

509. Titles. — The design of the title of a plan gives the draftsman an opportunity to exercise good taste. It should be so arranged and the size of the letters so chosen that the most important part of the title strikes the eye first. In general, each line of lettering should be centered, and the spacing between the lines should be so arranged that no part will either appear crowded or seem to be floating away from the rest of the title. The general outline of the title should be pleasing to the eye.

Fig. 187 shows a set of titles which are well balanced and complete. Fig. 188 shows the style of lettering appropriate for a profile, a cross-section, or construction details.

Preliminary Survey for a Railroad
from
Crescent Beach to Woodlawn Cemetery.
October, 1892.
Scale 400 feet to 1 inch.

COMMONWEALTH OF MASSACHUSETTS.

METROPOLITAN WATER WORKS.

WACHUSETT DAM

UPPER GATE-CHAMBER.

JULY 9, 1900.

UNITED STATES
COAST AND GEODETIC SURVEY

SKETCH OF GENERAL PROGRESS

JUNE 30 1897

Eastern Sheet

FIG. 207. TITLES OF PLANS.

TRACK ELEVATION.

C. & W. I. R. R.

Cross-Section of Bridge Showing Floor Construction.

Scale $\frac{1}{2}$ in. = 1 ft.

HORIZONTAL SECTIONS

THROUGH UPPER SLUICE-GATE

THROUGH LOWER SLUICE-GATE

THROUGH LOWER VALVE WELL

0 1 2 3 4 5 6 FT.

Preliminary Profile

for a Railroad from

Redford Junction to North Liberty

Sta. 0 to Sta. 498+68.7

May 1906

FIG. 208. TITLES OF PROFILES.

510. Notes. — Most drawings require notes of some sort. These are usually executed with a plain letter like the Reinhardt alphabet. In Fig. 209 are a few samples the general style of which is consistent with modern practice.

Note:-This reinforcement is 8'-0" long, and comes directly under each track. Leave ample room for bridge-seat.

Note:-The datum plane used for contours and soundings on this map is "Boston City Base."
Boston City Base is 0.64 ft. below base known as "Mean Low Water at Navy Yard" which is the datum used by the U.S. Coast Survey, the U.S. Engineer's Office, and the Mass. Harbor and Land Commission.

Soundings and Contours confirmed and extended by data from map (L-476) on file with Massachusetts Harbor and Land Commission.

FIG. 209. SAMPLES OF NOTES.

511. Border Lines. — The border line of a drawing should consist of a heavy single line or double lines closely spaced. It should neither be so heavy nor of such fancy design as to be conspicuous. Plain clear drawings are the practice of to-day, and the border line should be in keeping with the rest of the drawing. For drawings 2 ft. long, the border should be about $\frac{3}{4}''$ from the edge of the sheet: for drawings 4 ft. long, 1″ to $1\text{–}\frac{1}{4}''$ looks well. On some, particularly office drawings, the border is unnecessary and may be undesirable. Fig. 210 gives a few examples of simple practical border lines.



FIG. 210. BORDER LINES.

512. Meridians. — On all land plans it is customary to draw either the true or the magnetic meridian; often both of them are represented. To be in keeping with the rest of the drawing this should be simple in design. Too frequently, however, the draftsman attempts to "lay himself out" on the needle with the result that it is so large and ornate that it is the first thing in the drawing that strikes the eye. The simple meridians shown in Fig. 211 are suggested as suitable for ordinary land plans.

The plan should always be drawn, if possible, so that the

meridian will point, in general, toward the top of the drawing rather than toward the bottom. Sometimes it is drawn with its upper part above and its tail below the drawing. In such a case



FIG. 211. MERIDIANS.

the line of the meridian must never cut any of the lines of the drawings: it should be interrupted far enough from the drawing so that it cannot be mistaken for one of the property lines.

513. Scales. — On account of the shrinkage of drawing paper the scale is sometimes drawn on the plan itself **at the time that the drawing is plotted**. It is well to have it sufficiently long, say, 3 to 10 inches (depending upon the size of the drawing), so that it will be of use in detecting the amount of shrinkage. This, of course, will determine the shrinkage only in the direction of the scale. These scales are usually placed directly under the title or in one of the lower corners. Fig. 212 gives two examples of scales.

In plotting a coördinate survey, the intersections of the north and south with the east and west lines should be marked on the finished drawing, as these are of great assistance in plotting additions. Moreover the distances between these points give a reliable measure of the change in scale of the map due to shrinkage.

514. SHRINKAGE OF DRAWING PAPERS. — All of the papers in use will shrink and swell more or less with variations o

weather conditions. The heavy mounted papers are affected the least, but large drawings even on such paper will be found on examination to change in size perceptibly. The fact that they do not always shrink the same amount in different directions



FIG. 212. SCALES.

makes it difficult to estimate the amount of the change and to allow for it. This effect can be estimated quite closely, however, by testing the drawing by measuring accurately a few lines running in different directions **when it is plotted** and scaling the same lines at any other time and making allowance for the change. Scaled distances on tracing cloth are quite unreliable if it is not kept in a dry place, and blue-prints generally shrink in washing so that scale measurements taken from them usually contain considerable error.

515. MAPS OF LARGE EXTENT. — Some maps, like the location map of a railroad or the map of a city, are so large that they must be made in sections. In such cases two slightly different methods are employed. One method is to plot the several sheets so that the drawing on one will extend to but not include any of the drawing on the adjacent sheet, the limits of the drawings being defined by straight lines. The other method is to have the drawing on each sheet lap over the drawings on the adjacent sheets a little. In this case marks are made on all drawings which make it possible to fit them to the corresponding marks on the adjacent drawings when they are being used jointly.

In attempting to arrange the sheets of adjacent drawings after they have been in use for any considerable time, it is often found that they do not fit well on account of the unequal shrinking and

swelling of the paper. Moreover in plotting lines on separate sheets so that they will fit exactly, there are mechanical difficulties which can only be appreciated by the draftsman who has had experience with them. These objections, together with the fact that a comprehensive view of the whole situation cannot be taken in at one time, have led some engineers to prefer large and unwieldy drawings to a system of separate sheets, but the latter are much more convenient when the plans are to be used in the field.

516. INKING IN A PROFILE. — The surface line is usually shown as a full firm black line and the grade line as a full red line (Art. 478, p. 443). A horizontal base-line is sometimes drawn in red a short distance above the bottom of the paper and vertical red lines are drawn from this line to the grade line at every change of gradient and at both ends of the profile. On these vertical lines are recorded the grade elevations at these points and the "plus" if the place where the gradient changes is not at a full station. On the base-line between these red vertical lines is recorded the gradient of the grade line above. Under the base-line is the stationing, which is marked at every heavy vertical ruling of the profile paper, together with any other notes of alignment which may be desired.

Information such as the names of streets, brooks, etc., is lettered vertically above the profile and at the proper station. A title and the scale are sometimes placed on the face of the profile; sometimes these are put on the back of the profile at one end of it (or both in the case of a long profile), so that the title can be read when it is rolled up.

517. CLEANING DRAWINGS. — Every drawing, during its construction, collects more or less dirt. Often construction lines are drawn which must be erased when the plan is completed. In cleaning a drawing an ordinary soft pencil eraser is used for the pencil lines while a sponge eraser or stale bread crumbs will remove the dirt satisfactorily without affecting the ink lines.

To take off the pencil lines and dirt from tracing cloth, wash the drawing with a cloth saturated with gasolene or benzine. This will remove pencil lines entirely and will clean

the tracing perfectly without any injurious effect on the tracing cloth.

518. FILING DRAWINGS. — While the particular method of filing plans varies considerably in different offices, there are a few general ideas carried out by all drafting offices in regard to the preservation as well as the systematic filing of drawings. There is no doubt that the best method of filing plans is to keep them flat, but this is not practicable with large plans which must usually be filed in rolls. In all systems of plan filing there appears to be a proper use of both flat and rolled plans.

In large offices plans are, as a rule, made in several standard sizes prescribed by the rules of the office, and are filed flat in shallow drawers which are built to fit the different sizes of drawings. In some offices the adherence to standard sizes is very rigid, and considerable time is often spent to bring drawings within the limits of one of these sizes. When these sizes are exceeded the plans are either made in sections of standard size, as explained in Art. 515, or they are made as large plans which are rolled and filed away in pasteboard tubes. Sometimes very large plans are filed flat by hanging them from an overhead frame.

Plans filed flat are marked each with its proper index number in one corner, preferably the lower right-hand corner, so that as the drawer is opened the numbers can be readily examined. In some offices it is required that in returning a drawing it shall be placed in its proper order in the drawer as well as in the proper drawer, while in other offices the plan drawers are made very shallow, so as to contain only about 15 or 20 drawings, and when a plan is returned no attempt is made to put it in any particular place in the drawer, there being, at the most, only a very few drawings to handle to obtain the one desired.

Rolled drawings are marked on the side of the rolls at each end so as to be easily read by one standing in front of the shelf on which the plans are stored. Another style of roll is closed at one end with a white label on the outside of the closed end. When the plan has been put into the tube it is so placed on the

shelf that the label on which the plan number is marked is at the front edge of the shelf where it can be conveniently read. When the plan is in use the empty tube is left on the shelf with its open end outward so that its number is in the back part of the shelf where it cannot be read.

Large plans which are made in sections are often filed in large folios or books in such a way that they can be readily taken out and used separately.

519. INDEXING DRAWINGS. — There are so many systems of indexing plans that no attempt will be made to explain them other than to suggest a few of the essentials of any good system. Every system of numbering the plans should be such that one can tell from its number whether the drawing is a sketch, a working drawing, a finished drawing, a tracing, or a process print. The numbering also should suggest the type of drawing, as a land plan, a construction plan, etc.

For offices where few plans are on file an index book may suffice for recording the plans, but in large drafting offices the card catalogue system is used extensively. By a judicious use of "markers" a card catalogue system can be so devised that it will be necessary to examine only a very few cards to find the one corresponding to any plan. Frequently it is necessary to index a plan by two or three different cards under different general headings.

520. FILING NOTE-BOOKS. — Note-books should always be filed in vaults where they will be protected against fire. Too frequently through lack of forethought note-books containing information which it has cost thousands of dollars to collect are carelessly filed on a shelf in the drafting office. In some offices the rules require that every note-book and valuable plan shall be placed in the vault at the end of the day's work, and this appears to be the proper practice.

Some offices go so far as to require that all notes shall be copied in ink and the original notes kept permanently filed in the vault to guard against their loss. Whether a copy is made or not, the **original** should be preserved as it has a value, in a lawsuit for instance, which any **copy** does not possess. When copies are made of the original notes they are sometimes made

in a loose-leaf book so that if any notes are taken from the office it is not necessary to take more than a very few leaves of the copy; the original notes never go from the office except in rare cases.

521. Indexing Notes. — The notes contained in the field note-books are often indexed either in a book for this purpose or by means of a card catalogue. The method of indexing is similar to that used for plans.

522. Other Records. — Other records, such as borings, soundings, estimates, computations, etc.. are carefully filed and indexed so that it will be easy to refer to them.

TABLES.

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
100	00000	00043	00087	00130	00173	00217	00260	00303	00346	00389
1	0432	0475	0518	9561	0604	0647	0689	0732	0775	0817
2	0860	0903	0945	0988	1030	1072	1115	1157	1199	1242
3	1284	1326	1368	1410	1452	1494	1536	1578	1620	1662
4	1703	1745	1787	1828	1870	1912	1953	1995	2036	2078
5	2119	2160	2202	2243	2284	2325	2366	2407	2449	2490
6	2531	2572	2612	2653	2694	2735	2776	2816	2857	2898
7	2938	2979	3019	3060	3100	3141	3181	3222	3262	3302
8	3342	3383	3423	3463	3503	3543	3583	3623	3663	3703
9	3743	3782	3822	3862	3902	3941	3981	4021	4060	4100
110	04139	04179	04218	04258	04297	04336	04376	04415	04454	04493
1	4532	4571	4610	4650	4689	4727	4766	4805	4844	4883
2	4922	4961	4999	5038	5077	5115	5154	5192	5231	5269
3	5308	5346	5385	5423	5461	5500	5538	5576	5614	5652
4	5690	5729	5767	5805	5843	5881	5918	5956	5994	6032
5	6070	6108	6145	6183	6221	6258	6296	6333	6371	6408
6	6446	6483	6521	6558	6595	6633	6670	6707	6744	6781
7	6819	6856	6893	6930	6967	7004	7041	7078	7115	7151
8	7188	7225	7262	7298	7335	7372	7408	7445	7482	7518
9	7555	7591	7628	7664	7700	7737	7773	7809	7846	7882
120	07918	07954	07990	08027	08063	08099	08135	08171	08207	08243
1	8279	8314	8350	8386	8422	8458	8493	8529	8565	8600
2	8636	8672	8707	8743	8778	8814	8849	8884	8920	8955
3	8991	9026	9061	9096	9132	9167	9202	9237	9272	9307
4	9342	9377	9412	9447	9482	9517	9552	9587	9621	9656
5	9691	9726	9760	9795	9830	9864	9899	9934	9968	10003
6	10037	10072	10106	10140	10175	10209	10243	10278	10312	0346
7	0380	0415	0449	0483	0517	0551	0585	0619	0653	0687
8	0721	0755	0789	0823	0857	0890	0924	0958	0992	1025
9	1059	1093	1126	1160	1193	1227	1261	1294	1327	1361
130	11394	11428	11461	11494	11528	11561	11594	11628	11661	11694
1	1727	1760	1793	1826	1860	1893	1926	1959	1992	2024
2	2057	2090	2123	2156	2189	2222	2254	2287	2320	2352
3	2385	2418	2450	2483	2516	2548	2581	2613	2646	2678
4	2710	2743	2775	2808	2840	2872	2905	2937	2969	3001
5	3033	3066	3098	3130	3162	3194	3226	3258	3290	3322
6	3354	3386	3418	3450	3481	3513	3545	3577	3609	3640
7	3672	3704	3735	3767	3799	3830	3862	3893	3925	3956
8	3988	4019	4051	4082	4114	4145	4176	4208	4239	4270
9	4301	4333	4364	4395	4426	4457	4489	4520	4551	4582
140	14613	14644	14675	14706	14737	14768	14799	14829	14860	14891
1	4922	4953	4983	5014	5045	5076	5106	5137	5168	5198
2	5229	5259	5290	5320	5351	5381	5412	5442	5473	5503
3	5534	5564	5594	5625	5655	5685	5715	5746	5776	5806
4	5836	5866	5897	5927	5957	5987	6017	6047	6077	6107
5	6137	6167	6197	6227	6256	6286	6316	6346	6376	6406
6	6435	6465	6495	6524	6554	6584	6613	6643	6673	6702
7	6732	6761	6791	6820	6850	6879	6909	6938	6967	6997
8	7026	7056	7085	7114	7143	7173	7202	7231	7260	7289
9	7319	7348	7377	7406	7435	7464	7493	7522	7551	7580
150	17609	17638	17667	17696	17725	17754	17782	17811	17840	17869

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
150	17609	17638	17667	17696	17725	17754	17782	17811	17840	17869
1	7898	7926	7955	7984	8013	8041	8070	8099	8127	8156
2	8184	8213	8241	8270	8298	8327	8355	8384	8412	8441
3	8469	8498	8526	8554	8583	8611	8639	8667	8696	8724
4	8752	8780	8808	8837	8865	8893	8921	8949	8977	9005
5	9033	9061	9089	9117	9145	9173	9201	9229	9257	9285
6	9312	9340	9368	9396	9424	9451	9479	9507	9535	9562
7	9590	9618	9645	9673	9700	9728	9756	9783	9811	9838
8	9866	9893	9921	9948	9976	20003	20030	20058	20085	20112
9	20140	20167	20194	20222	20249	0276	0303	0330	0358	0385
160	20412	20439	20466	20493	20520	20548	20575	20602	20629	20656
1	0683	0710	0737	0763	0790	0817	0844	0871	0898	0925
2	0952	0978	1005	1032	1059	1085	1112	1139	1165	1192
3	1219	1245	1272	1299	1325	1352	1378	1405	1431	1458
4	1484	1511	1537	1564	1590	1617	1643	1669	1696	1722
5	1748	1775	1801	1827	1854	1880	1906	1932	1958	1985
6	2011	2037	2063	2089	2115	2141	2167	2194	2220	2246
7	2272	2298	2324	2350	2376	2401	2427	2453	2479	2505
8	2531	2557	2583	2608	2634	2660	2686	2712	2737	2763
9	2789	2814	2840	2866	2891	2917	2943	2968	2994	3019
170	23045	23070	23096	23121	23147	23172	23198	23223	23249	23274
1	3300	3325	3350	3376	3401	3426	3452	3477	3502	3528
2	3553	3578	3603	3629	3654	3679	3704	3729	3754	3779
3	3805	3830	3855	3880	3905	3930	3955	3980	4005	4030
4	4055	4080	4105	4130	4155	4180	4204	4229	4254	4279
5	4304	4329	4353	4378	4403	4428	4452	4477	4502	4527
6	4551	4576	4601	4625	4650	4674	4699	4724	4748	4773
7	4797	4822	4846	4871	4895	4920	4944	4969	4993	5018
8	5042	5066	5091	5115	5139	5164	5188	5212	5237	5261
9	5285	5310	5334	5358	5382	5406	5431	5455	5479	5503
180	25527	25551	25575	25600	25624	25648	25672	25696	25720	25744
1	5768	5792	5816	5840	5864	5888	5912	5935	5959	5983
2	6007	6031	6055	6079	6102	6126	6150	6174	6198	6221
3	6245	6269	6293	6316	6340	6364	6387	6411	6435	6458
4	6482	6505	6529	6553	6576	6600	6623	6647	6670	6694
5	6717	6741	6764	6788	6811	6834	6858	6881	6905	6928
6	6951	6975	6998	7021	7045	7068	7091	7114	7138	7161
7	7184	7207	7231	7254	7277	7300	7323	7346	7370	7393
8	7416	7439	7462	7485	7508	7531	7554	7577	7600	7623
9	7646	7669	7692	7715	7738	7761	7784	7807	7830	7852
190	27875	27898	27921	27944	27967	27989	28012	28035	28058	28081
1	8103	8126	8149	8171	8194	8217	8240	8262	8285	8307
2	8330	8353	8375	8398	8421	8443	8466	8488	8511	8533
3	8556	8578	8601	8623	8646	8668	8691	8713	8735	8758
4	8780	8803	8825	8847	8870	8892	8914	8937	8959	8981
5	9003	9026	9048	9070	9092	9115	9137	9159	9181	9203
6	9226	9248	9270	9292	9314	9336	9358	9380	9403	9425
7	9447	9469	9491	9513	9535	9557	9579	9601	9623	9645
8	9667	9688	9710	9732	9754	9776	9798	9820	9842	9863
9	9885	9907	9929	9951	9973	9994	30016	30038	30060	30081
200	30103	30125	30146	30168	30190	30211	30233	30255	30276	30298

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
200	30103	30125	30146	30168	30190	30211	30233	30255	30276	30298
1	0320	0341	0363	0384	0406	0428	0449	0471	0492	0514
2	0535	0557	0578	0600	0621	0643	0664	0685	0707	0728
3	0750	0771	0792	0814	0835	0856	0878	0899	0920	0942
4	0963	0984	1006	1027	1048	1069	1091	1112	1133	1154
5	1175	1197	1218	1239	1260	1281	1302	1323	1345	1366
6	1387	1408	1429	1450	1471	1492	1513	1534	1555	1576
7	1597	1618	1639	1660	1681	1702	1723	1744	1765	1785
8	1806	1827	1848	1869	1890	1911	1931	1952	1973	1994
9	2015	2035	2056	2077	2098	2118	2139	2160	2181	2201
210	32222	32243	32263	32284	32305	32325	32346	32366	32387	32408
1	2428	2449	2469	2490	2510	2531	2552	2572	2593	2613
2	2634	2654	2675	2695	2715	2736	2756	2777	2797	2818
3	2838	2858	2879	2899	2919	2940	2960	2980	3001	3021
4	3041	3062	3082	3102	3122	3143	3163	3183	3203	3224
5	3244	3264	3284	3304	3325	3345	3365	3385	3405	3425
6	3445	3465	3486	3506	3526	3546	3566	3586	3606	3626
7	3646	3666	3683	3706	3726	3746	3766	3786	3806	3826
8	3846	3866	3885	3905	3925	3945	3965	3985	4005	4025
9	4044	4064	4084	4104	4124	4143	4163	4183	4203	4223
220	34242	34262	34282	34301	34321	34341	34361	34380	34400	34420
1	4439	4459	4479	4498	4518	4537	4557	4577	4596	4616
2	4635	4655	4674	4694	4713	4733	4753	4772	4792	4811
3	4830	4850	4869	4889	4908	4928	4947	4967	4986	5005
4	5025	5044	5064	5083	5102	5122	5141	5160	5180	5199
5	5218	5238	5257	5276	5295	5315	5334	5353	5372	5392
6	5411	5430	5449	5468	5488	5507	5526	5545	5564	5583
7	5603	5622	5641	5660	5679	5698	5717	5736	5755	5774
8	5793	5813	5832	5851	5870	5889	5908	5927	5946	5965
9	5984	6003	6021	6040	6059	6078	6097	6116	6135	6154
230	36173	36192	36211	36229	36248	36267	36286	36305	36324	36342
1	6361	6380	6399	6418	6436	6455	6474	6493	6511	6530
2	6549	6568	6586	6605	6624	6642	6661	6680	6698	6717
3	6736	6754	6773	6791	6810	6829	6847	6866	6884	6903
4	6922	6940	6959	6977	6996	7014	7033	7051	7070	7088
5	7107	7125	7144	7162	7181	7199	7218	7236	7254	7273
6	7291	7310	7328	7346	7365	7383	7401	7420	7438	7457
7	7475	7493	7511	7530	7548	7566	7585	7603	7621	7639
8	7658	7676	7694	7712	7731	7749	7767	7785	7803	7822
9	7840	7858	7876	7894	7912	7931	7949	7967	7985	8003
240	38021	38039	38057	38075	38093	38112	38130	38148	38166	38184
1	8202	8220	8238	8256	8274	8292	8310	8328	8346	8364
2	8382	8399	8417	8435	8453	8471	8489	8507	8525	8543
3	8561	8578	8596	8614	8632	8650	8668	8686	8703	8721
4	8739	8757	8775	8792	8810	8828	8846	8863	8881	8899
5	8917	8934	8952	8970	8987	9005	9023	9041	9058	9076
6	9094	9111	9129	9146	9164	9182	9199	9217	9235	9252
7	9270	9287	9305	9322	9340	9358	9375	9393	9410	9428
8	9445	9463	9480	9498	9515	9533	9550	9568	9585	9602
9	9620	9637	9655	9672	9690	9707	9724	9742	9759	9777
250	39794	39811	39829	39846	39863	39881	39898	39915	39933	39950

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
250	39794	39811	39829	39846	39863	39881	39898	39915	39933	39950
1	9967	9985	40002	40019	40037	40054	40071	40088	40106	40123
2	40140	40157	0175	0192	0209	0226	0243	0261	0278	0295
3	0312	0329	0346	0364	0381	0398	0415	0432	0449	0466
4	0483	0500	0518	0535	0552	0569	0586	0603	0620	0637
5	0654	0671	0688	0705	0722	0739	0756	0773	0790	0807
6	0824	0841	0858	0875	0892	0909	0926	0943	0960	0976
7	0993	1010	1027	1044	1061	1078	1095	1111	1128	1145
8	1162	1179	1196	1212	1229	1246	1263	1280	1296	1313
9	1330	1347	1363	1380	1397	1414	1430	1447	1464	1481
260	41497	41514	41531	41547	41564	41581	41597	41614	41631	41647
1	1664	1681	1697	1714	1731	1747	1764	1780	1797	1814
2	1830	1847	1863	1880	1896	1913	1929	1946	1963	1979
3	1996	2012	2029	2045	2062	2078	2095	2111	2127	2144
4	2160	2177	2193	2210	2226	2243	2259	2275	2292	2308
5	2325	2341	2357	2374	2390	2406	2423	2439	2455	2472
6	2488	2504	2521	2537	2553	2570	2586	2602	2619	2635
7	2651	2667	2684	2700	2716	2732	2749	2765	2781	2797
8	2813	2830	2846	2862	2878	2894	2911	2927	2943	2959
9	2975	2991	3008	3024	3040	3056	3072	3088	3104	3120
270	43136	43152	43169	43185	43201	43217	43233	43249	43265	43281
1	3297	3313	3329	3345	3361	3377	3393	3409	3425	3441
2	3457	3473	3489	3505	3521	3537	3553	3569	3584	3600
3	3616	3632	3648	3664	3680	3696	3712	3727	3743	3759
4	3775	3791	3807	3823	3838	3854	3870	3886	3902	3917
5	3933	3949	3965	3981	3996	4012	4028	4044	4059	4075
6	4091	4107	4122	4138	4154	4170	4185	4201	4217	4232
7	4248	4264	4279	4295	4311	4326	4342	4358	4373	4389
8	4404	4420	4436	4451	4467	4483	4498	4514	4529	4545
9	4560	4576	4592	4607	4623	4638	4654	4669	4685	4700
280	44716	44731	44747	44762	44778	44793	44809	44824	44840	44855
1	4871	4886	4902	4917	4932	4948	4963	4979	4994	5010
2	5025	5040	5056	5071	5086	5102	5117	5133	5148	5163
3	5179	5194	5209	5225	5240	5255	5271	5286	5301	5317
4	5332	5347	5362	5378	5393	5408	5423	5439	5454	5469
5	5484	5500	5515	5530	5545	5561	5576	5591	5606	5621
6	5637	5652	5667	5682	5697	5712	5728	5743	5758	5773
7	5788	5803	5818	5834	5849	5864	5879	5894	5909	5924
8	5939	5954	5969	5984	6000	6015	6030	6045	6060	6075
9	6090	6105	6120	6135	6150	6165	6180	6195	6210	6225
290	46240	46255	46270	46285	46300	46315	46330	46345	46359	46374
1	6389	6404	6419	6434	6449	6464	6479	6494	6509	6523
2	6538	6553	6568	6583	6598	6613	6627	6642	6657	6672
3	6687	6702	6716	6731	6746	6761	6776	6790	6805	6820
4	6835	6850	6864	6879	6894	6909	6923	6938	6953	6967
5	6982	6997	7012	7026	7041	7056	7070	7085	7100	7114
6	7129	7144	7159	7173	7188	7202	7217	7232	7246	7261
7	7276	7290	7305	7319	7334	7349	7363	7378	7392	7407
8	7422	7436	7451	7465	7480	7494	7509	7524	7538	7553
9	7567	7582	7596	7611	7625	7640	7654	7669	7683	7698
300	47712	47727	47741	47756	47770	47784	47799	47813	47828	47842

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
300	47712	47727	47741	47756	47770	47784	47799	47813	47828	47842
1	7857	7871	7885	7900	7914	7929	7943	7958	7972	7986
2	8001	8015	8029	8044	8058	8073	8087	8101	8116	8130
3	8144	8159	8173	8187	8202	8216	8230	8244	8259	8273
4	8287	8302	8316	8330	8344	8359	8373	8387	8401	8416
5	8430	8444	8458	8473	8487	8501	8515	8530	8544	8558
6	8572	8586	8601	8615	8629	8643	8657	8671	8686	8700
7	8714	8728	8742	8756	8770	8785	8799	8813	8827	8841
8	8855	8869	8883	8897	8911	8926	8940	8954	8968	8982
9	8996	9010	9024	9038	9052	9066	9080	9094	9108	9122
310	49136	49150	49164	49178	49192	49206	49220	49234	49248	49262
1	9276	9290	9304	9318	9332	9346	9360	9374	9388	9402
2	9415	9429	9443	9457	9471	9485	9499	9513	9527	9541
3	9554	9568	9582	9596	9610	9624	9638	9651	9665	9679
4	9693	9707	9721	9734	9748	9762	9776	9790	9803	9817
5	9831	9845	9859	9872	9886	9900	9914	9927	9941	9955
6	9969	9982	9996	50010	50024	50037	50051	50065	50079	50092
7	50106	50120	50133	0147	0161	0174	0188	0202	0215	0229
8	0243	0256	0270	0284	0297	0311	0325	0338	0352	0365
9	0379	0393	0406	0420	0433	0447	0461	0474	0488	0501
320	50515	50529	50542	50556	50569	50583	50596	50610	50623	50637
1	0651	0664	0678	0691	0705	0718	0732	0745	0759	0772
2	0786	0799	0813	0826	0840	0853	0866	0880	0893	0907
3	0920	0934	0947	0961	0974	0987	1001	1014	1028	1041
4	1055	1068	1081	1095	1108	1121	1135	1148	1162	1175
5	1188	1202	1215	1228	1242	1255	1268	1282	1295	1308
6	1322	1335	1348	1362	1375	1388	1402	1415	1428	1441
7	1455	1468	1481	1495	1508	1521	1534	1548	1561	1574
8	1587	1601	1614	1627	1640	1654	1667	1680	1693	1706
9	1720	1733	1746	1759	1772	1786	1799	1812	1825	1838
330	51851	51865	51878	51891	51904	51917	51930	51943	51957	51970
1	1983	1996	2009	2022	2035	2048	2061	2075	2088	2101
2	2114	2127	2140	2153	2166	2179	2192	2205	2218	2231
3	2244	2257	2270	2284	2297	2310	2323	2336	2349	2362
4	2375	2388	2401	2414	2427	2440	2453	2466	2479	2492
5	2504	2517	2530	2543	2556	2569	2582	2595	2608	2621
6	2634	2647	2660	2673	2686	2699	2711	2724	2737	2750
7	2763	2776	2789	2802	2815	2827	2840	2853	2866	2879
8	2892	2905	2917	2930	2943	2956	2969	2982	2994	3007
9	3020	3033	3046	3058	3071	3084	3097	3110	3122	3135
340	53148	53161	53173	53186	53199	53212	53224	53237	53250	53263
1	3275	3288	3301	3314	3326	3339	3352	3364	3377	3390
2	3403	3415	3428	3441	3453	3466	3479	3491	3504	3517
3	3529	3542	3555	3567	3580	3593	3605	3618	3631	3643
4	3656	3668	3681	3694	3706	3719	3732	3744	3757	3769
5	3782	3794	3807	3820	3832	3845	3857	3870	3882	3895
6	3908	3920	3933	3945	3958	3970	3983	3995	4008	4020
7	4033	4045	4058	4070	4083	4095	4108	4120	4133	4145
8	4158	4170	4183	4195	4208	4220	4233	4245	4258	4270
9	4283	4295	4307	4320	4332	4345	4357	4370	4382	4394
350	54407	54419	54432	54444	54456	54469	54481	54494	54506	54518

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
350	54407	54419	54432	54444	54456	54469	54481	54494	54506	54518
1	4531	4543	4555	4568	4580	4593	4605	4617	4630	4642
2	4654	4667	4679	4691	4704	4716	4728	4741	4753	4765
3	4777	4790	4802	4814	4827	4839	4851	4864	4876	4888
4	4900	4913	4925	4937	4949	4962	4974	4986	4998	5011
5	5023	5035	5047	5060	5072	5084	5096	5108	5121	5133
6	5145	5157	5169	5182	5194	5206	5218	5230	5242	5255
7	5267	5279	5291	5303	5315	5328	5340	5352	5364	5376
8	5388	5400	5413	5425	5437	5449	5461	5473	5485	5497
9	5509	5522	5534	5546	5558	5570	5582	5594	5606	5618
360	55630	55642	55654	55666	55678	55691	55703	55715	55727	55739
1	5751	5763	5775	5787	5799	5811	5823	5835	5847	5859
2	5871	5883	5895	5907	5919	5931	5943	5955	5967	5979
3	5991	6003	6015	6027	6038	6050	6062	6074	6086	6098
4	6110	6122	6134	6146	6158	6170	6182	6194	6205	6217
5	6229	6241	6253	6265	6277	6289	6301	6312	6324	6336
6	6348	6360	6372	6384	6396	6407	6419	6431	6443	6455
7	6467	6478	6490	6502	6514	6526	6538	6549	6561	6573
8	6585	6597	6608	6620	6632	6644	6656	6667	6679	6691
9	6703	6714	6726	6738	6750	6761	6773	6785	6797	6808
370	56820	56832	56844	56855	56867	56879	56891	56902	56914	56926
1	6937	6949	6961	6972	6984	6996	7008	7019	7031	7043
2	7054	7066	7078	7089	7101	7113	7124	7136	7148	7159
3	7171	7183	7194	7206	7217	7229	7241	7252	7264	7276
4	7287	7299	7310	7322	7334	7345	7357	7368	7380	7392
5	7403	7415	7426	7438	7449	7461	7473	7484	7496	7507
6	7519	7530	7542	7553	7565	7576	7588	7600	7611	7623
7	7634	7646	7657	7669	7680	7692	7703	7715	7726	7738
8	7749	7761	7772	7784	7795	7807	7818	7830	7841	7852
9	7864	7875	7887	7898	7910	7921	7933	7944	7955	7967
380	57978	57990	58001	58013	58024	58035	58047	58058	58070	58081
1	8092	8104	8115	8127	8138	8149	8161	8172	8184	8195
2	8206	8218	8229	8240	8252	8263	8274	8286	8297	8309
3	8320	8331	8343	8354	8365	8377	8388	8399	8410	8422
4	8433	8444	8456	8467	8478	8490	8501	8512	8524	8535
5	8546	8557	8569	8580	8591	8602	8614	8625	8636	8647
6	8659	8670	8681	8692	8704	8715	8726	8737	8749	8760
7	8771	8782	8794	8805	8816	8827	8838	8850	8861	8872
8	8883	8894	8906	8917	8928	8939	8950	8961	8973	8984
9	8995	9006	9017	9028	9040	9051	9062	9073	9084	9095
390	59106	59118	59129	59140	59151	59462	59173	59184	59195	59207
1	9218	9229	9240	9251	9262	9273	9284	9295	9306	9318
2	9329	9340	9351	9362	9373	9384	9395	9406	9417	9428
3	9439	9450	9461	9472	9483	9494	9506	9517	9528	9539
4	9550	9561	9572	9583	9594	9605	9616	9627	9638	9649
5	9660	9671	9682	9693	9704	9715	9726	9737	9748	9759
6	9770	9780	9791	9802	9813	9824	9835	9846	9857	9868
7	9879	9890	9901	9912	9923	9934	9945	9956	9966	9977
8	9988	9999	60010	60021	60032	60043	60054	60065	60076	60086
9	60097	60108	0119	0130	0141	0152	0163	0173	0184	0195
400	60206	60217	60228	60239	60249	60260	60271	60282	60293	60304

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
400	60206	60217	60228	60239	60249	60260	60271	60282	60293	60304
1	0314	0325	0336	0347	0358	0369	0379	0390	0401	0412
2	0423	0433	0444	0455	0466	0477	0487	0498	0509	0520
3	0531	0541	0552	0563	0574	0584	0595	0606	0617	0627
4	0638	0649	0660	0670	0681	0692	0703	0713	0724	0735
5	0746	0756	0767	0778	0788	0799	0810	0821	0831	0842
6	0853	0863	0874	0885	0895	0906	0917	0927	0938	0949
7	0959	0970	0981	0991	1002	1013	1023	1034	1045	1055
8	1066	1077	1087	1098	1109	1119	1130	1140	1151	1162
9	1172	1183	1194	1204	1215	1225	1236	1247	1257	1268
410	61278	61289	61300	61310	61321	61331	61342	61352	61363	61374
1	1384	1395	1405	1416	1426	1437	1448	1458	1469	1479
2	1490	1500	1511	1521	1532	1542	1553	1563	1574	1584
3	1595	1606	1616	1627	1637	1648	1658	1669	1679	1690
4	1700	1711	1721	1731	1742	1752	1763	1773	1784	1794
5	1805	1815	1826	1836	1847	1857	1868	1878	1888	1899
6	1909	1920	1930	1941	1951	1962	1972	1982	1993	2003
7	2014	2024	2034	2045	2055	2066	2076	2086	2097	2107
8	2118	2128	2138	2149	2159	2170	2180	2190	2201	2211
9	2221	2232	2242	2252	2263	2273	2284	2294	2304	2315
420	62325	62335	62346	62356	62366	62377	62387	62397	62408	62418
1	2428	2439	2449	2459	2469	2480	2490	2500	2511	2521
2	2531	2542	2552	2562	2572	2583	2593	2603	2613	2624
3	2634	2644	2655	2665	2675	2685	2696	2706	2716	2726
4	2737	2747	2757	2767	2778	2788	2798	2808	2818	2829
5	2839	2849	2859	2870	2880	2890	2900	2910	2921	2931
6	2941	2951	2961	2972	2982	2992	3002	3012	3022	3033
7	3043	3053	3063	3073	3083	3094	3104	3114	3124	3134
8	3144	3155	3165	3175	3185	3195	3205	3215	3225	3236
9	3246	3256	3266	3276	3286	3296	3306	3317	3327	3337
430	63347	63357	63367	63377	63387	63397	63407	63417	63428	63438
1	3448	3458	3468	3478	3488	3498	3508	3518	3528	3538
2	3548	3558	3568	3579	3589	3599	3609	3619	3629	3639
3	3649	3659	3669	3679	3689	3699	3709	3719	3729	3739
4	3749	3759	3769	3779	3789	3799	3809	3819	3829	3839
5	3849	3859	3869	3879	3889	3899	3909	3919	3929	3939
6	3949	3959	3969	3979	3988	3998	4008	4018	4028	4038
7	4048	4058	4068	4078	4088	4098	4108	4118	4128	4137
8	4147	4157	4167	4177	4187	4197	4207	4217	4227	4237
9	4246	4256	4266	4276	4286	4296	4306	4316	4326	4335
440	64345	64355	64365	64375	64385	64395	64404	64414	64424	64434
1	4444	4454	4464	4473	4483	4493	4503	4513	4523	4532
2	4542	4552	4562	4572	4582	4591	4601	4611	4621	4631
3	4640	4650	4660	4670	4680	4689	4699	4709	4719	4729
4	4738	4748	4758	4768	4777	4787	4797	4807	4816	4826
5	4836	4846	4856	4865	4875	4885	4895	4904	4914	4924
6	4933	4943	4953	4963	4972	4982	4992	5002	5011	5021
7	5031	5040	5050	5060	5070	5079	5089	5099	5108	5118
8	5128	5137	5147	5157	5167	5176	5186	5196	5205	5215
9	5225	5234	5244	5254	5263	5273	5283	5292	5302	5312
450	65321	65331	65341	65350	65360	65369	65379	65389	65398	65408

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
450	65321	65331	65341	65350	65360	65369	65379	65389	65398	65408
1	5418	5427	5437	5447	5456	5466	5475	5485	5495	5504
2	5514	5523	5533	5543	5552	5562	5571	5581	5591	5600
3	5610	5619	5629	5639	5648	5658	5667	5677	5686	5696
4	5706	5715	5725	5734	5744	5753	5763	5772	5782	5792
5	5801	5811	5820	5830	5839	5849	5858	5868	5877	5887
6	5896	5906	5916	5925	5935	5944	5954	5963	5973	5982
7	5992	6001	6011	6020	6030	6039	6049	6058	6068	6077
8	6087	6096	6106	6115	6124	6134	6143	6153	6162	6172
9	6181	6191	6200	6210	6219	6229	6238	6247	6257	6266
460	66276	66285	66295	66304	66314	66323	66332	66342	66351	66361
1	6370	6380	6389	6398	6408	6417	6427	6436	6445	6455
2	6464	6474	6483	6492	6502	6511	6521	6530	6539	6549
3	6558	6567	6577	6586	6596	6605	6614	6624	6633	6642
4	6652	6661	6671	6680	6689	6699	6708	6717	6727	6736
5	6745	6755	6764	6773	6783	6792	6801	6811	6820	6829
6	6839	6848	6857	6867	6876	6885	6894	6904	6913	6922
7	6932	6941	6950	6960	6969	6978	6987	6997	7006	7015
8	7025	7034	7043	7052	7062	7071	7080	7089	7099	7108
9	7117	7127	7136	7145	7154	7164	7173	7182	7191	7201
470	67210	67219	67228	67237	67247	67256	67265	67274	67284	67293
1	7302	7311	7321	7330	7339	7348	7357	7367	7376	7385
2	7394	7403	7413	7422	7431	7440	7449	7459	7468	7477
3	7486	7495	7504	7514	7523	7532	7541	7550	7560	7569
4	7578	7587	7596	7605	7614	7624	7633	7642	7651	7660
5	7669	7679	7688	7697	7706	7715	7724	7733	7742	7752
6	7761	7770	7779	7788	7797	7806	7815	7825	7834	7843
7	7852	7861	7870	7879	7888	7897	7906	7916	7925	7934
8	7943	7952	7961	7970	7979	7988	7997	8006	8015	8024
9	8034	8043	8052	8061	8070	8079	8088	8097	8106	8115
480	68124	68133	68142	68151	68160	68169	68178	68187	68196	68205
1	8215	8224	8233	8242	8251	8260	8269	8278	8287	8296
2	8305	8314	8323	8332	8341	8350	8359	8368	8377	8386
3	8395	8404	8413	8422	8431	8440	8449	8458	8467	8476
4	8485	8494	8502	8511	8520	8529	8538	8547	8556	8565
5	8574	8583	8592	8601	8610	8619	8628	8637	8646	8655
6	8664	8673	8681	8690	8699	8708	8717	8726	8735	8744
7	8753	8762	8771	8780	8789	8797	8806	8815	8824	8833
8	8842	8851	8860	8869	8878	8886	8895	8904	8913	8922
9	8931	8940	8949	8958	8966	8975	8984	8993	9002	9011
490	69020	69028	69037	69046	69055	69064	69073	69082	69090	69099
1	9108	9117	9126	9135	9144	9152	9161	9170	9179	9188
2	9197	9205	9214	9223	9232	9241	9249	9258	9267	9276
3	9285	9294	9302	9311	9320	9329	9338	9346	9355	9364
4	9373	9381	9390	9399	9408	9417	9425	9434	9443	9452
5	9461	9469	9478	9487	9496	9504	9513	9522	9531	9539
6	9548	9557	9566	9574	9583	9592	9601	9609	9618	9627
7	9636	9644	9653	9662	9671	9679	9688	9697	9705	9714
8	9723	9732	9740	9749	9758	9767	9775	9784	9793	9801
9	9810	9819	9827	9836	9845	9854	9862	9871	9880	9888
500	69897	69906	69914	69923	69932	69940	69949	69958	69966	69975

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
500	69897	69906	69914	69923	69932	69940	69949	69958	69966	69975
1	9984	9992	70001	70010	70018	70027	70036	70044	70053	70062
2	70070	70079	0088	0096	0105	0114	0122	0131	0140	0148
3	0157	0165	0174	0183	0191	0200	0209	0217	0226	0234
4	0243	0252	0260	0269	0278	0286	0295	0303	0312	0321
5	0329	0338	0346	0355	0364	0372	0381	0389	0398	0406
6	0415	0424	0432	0441	0449	0458	0467	0475	0484	0492
7	0501	0509	0518	0526	0535	0544	0552	0561	0569	0578
8	0586	0595	0603	0612	0621	0629	0638	0646	0655	0663
9	0672	0680	0689	0697	0706	0714	0723	0731	0740	0749
510	70757	70766	70774	70783	70791	70800	70808	70817	70825	70834
1	0842	0851	0859	0868	0876	0885	0893	0902	0910	0919
2	0927	0935	0944	0952	0961	0969	0978	0986	0995	1003
3	1012	1020	1029	1037	1046	1054	1063	1071	1079	1088
4	1096	1105	1113	1122	1130	1139	1147	1155	1164	1172
5	1181	1189	1198	1206	1214	1223	1231	1240	1248	1257
6	1265	1273	1282	1290	1299	1307	1315	1324	1332	1341
7	1349	1357	1366	1374	1383	1391	1399	1408	1416	1425
8	1433	1441	1450	1458	1466	1475	1483	1492	1500	1508
9	1517	1525	1533	1542	1550	1559	1567	1575	1584	1592
520	71600	71609	71617	71625	71634	71642	71650	71659	71667	71675
1	1684	1692	1700	1709	1717	1725	1734	1742	1750	1759
2	1767	1775	1784	1792	1800	1809	1817	1825	1834	1842
3	1850	1858	1867	1875	1883	1892	1900	1908	1917	1925
4	1933	1941	1950	1958	1966	1975	1983	1991	1999	2008
5	2016	2024	2032	2041	2049	2057	2066	2074	2082	2090
6	2099	2107	2115	2123	2132	2140	2148	2156	2165	2173
7	2181	2189	2198	2206	2214	2222	2230	2239	2247	2255
8	2263	2272	2280	2288	2296	2304	2313	2321	2329	2337
9	2346	2354	2362	2370	2378	2387	2395	2403	2411	2419
530	72428	72436	72444	72452	72460	72469	72477	72485	72493	72501
1	2509	2518	2526	2534	2542	2550	2558	2567	2575	2583
2	2591	2599	2607	2616	2624	2632	2640	2648	2656	2665
3	2673	2681	2689	2697	2705	2713	2722	2730	2738	2746
4	2754	2762	2770	2779	2787	2795	2803	2811	2819	2827
5	2835	2843	2852	2860	2868	2876	2884	2892	2900	2908
6	2916	2925	2933	2941	2949	2957	2965	2973	2981	2989
7	2997	3006	3014	3022	3030	3038	3046	3054	3062	3070
8	3078	3086	3094	3102	3111	3119	3127	3135	3143	3151
9	3159	3167	3175	3183	3191	3199	3207	3215	3223	3231
540	73239	73247	73255	73263	73272	73280	73288	73296	73304	73312
1	3320	3328	3336	3344	3352	3360	3368	3376	3384	3392
2	3400	3408	3416	3424	3432	3440	3448	3456	3464	3472
3	3480	3488	3496	3504	3512	3520	3528	3536	3544	3552
4	3560	3568	3576	3584	3592	3600	3608	3616	3624	3632
5	3640	3648	3656	3664	3672	3679	3687	3695	3703	3711
6	3719	3727	3735	3743	3751	3759	3767	3775	3783	3791
7	3799	3807	3815	3823	3830	3838	3846	3854	3862	3870
8	3878	3886	3894	3902	3910	3918	3926	3933	3941	3949
9	3957	3965	3973	3981	3989	3997	4005	4013	4020	4028
550	74036	74044	74052	74060	74068	74076	74084	74092	74099	74107

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
550	74036	74044	74052	74060	74068	74076	74084	74092	74099	74107
1	4115	4123	4131	4139	4147	4155	4162	4170	4178	4186
2	4194	4202	4210	4218	4225	4233	4241	4249	4257	4265
3	4273	4280	4288	4296	4304	4312	4320	4327	4335	4343
4	4351	4359	4367	4374	4382	4390	4398	4406	4414	4421
5	4429	4437	4445	4453	4461	4468	4476	4484	4492	4500
6	4507	4515	4523	4531	4539	4547	4554	4562	4570	4578
7	4586	4593	4601	4609	4617	4624	4632	4640	4648	4656
8	4663	4671	4679	4687	4695	4702	4710	4718	4726	4733
9	4741	4749	4757	4764	4772	4780	4788	4796	4803	4811
560	74819	74827	74834	74842	74850	74858	74865	74873	74881	74889
1	4896	4904	4912	4920	4927	4935	4943	4950	4958	4966
2	4974	4981	4989	4997	5005	5012	5020	5028	5035	5043
3	5051	5059	5066	5074	5082	5089	5097	5105	5113	5120
4	5128	5136	5143	5151	5159	5166	5174	5182	5189	5197
5	5205	5213	5220	5228	5236	5243	5251	5259	5266	5274
6	5282	5289	5297	5305	5312	5320	5328	5335	5343	5351
7	5358	5366	5374	5381	5389	5397	5404	5412	5420	5427
8	5435	5442	5450	5458	5465	5473	5181	5488	5496	5504
9	5511	5519	5526	5534	5542	5549	5557	5565	5572	5580
570	75587	75595	75603	75610	75618	75626	75633	75641	75648	75656
1	5664	5671	5679	5686	5694	5702	5709	5717	5724	5732
2	5740	5747	5755	5762	5770	5778	5785	5793	5800	5808
3	5815	5823	5831	5838	5846	5853	5861	5868	5876	5884
4	5891	5899	5906	5914	5921	5929	5937	5944	5952	5959
5	5967	5974	5982	5989	5997	6005	6012	6020	6027	6035
6	6042	6050	6057	6065	6072	6080	6087	6095	6103	6110
7	6118	6125	6133	6110	6148	6155	6163	6170	6178	6185
8	6193	6200	6208	6215	6223	6230	6238	6245	6253	6260
9	6268	6275	6283	6290	6298	6305	6313	6320	6328	6335
580	76343	76350	76358	76365	76373	76380	76388	76395	76103	76410
1	6418	6425	6433	6110	6448	6455	6462	6470	6477	6485
2	6492	6500	6507	6515	6522	6530	6537	6545	6552	6559
3	6567	6574	6582	6589	6597	6604	6612	6619	6626	6634
4	6641	6649	6656	6664	6671	6678	6686	6693	6701	6708
5	6716	6723	6730	6738	6745	6753	6760	6768	6775	6782
6	6790	6797	6805	6812	6819	6827	6834	6842	6849	6856
7	6864	6871	6879	6886	6893	6901	6908	6916	6923	6930
8	6938	6945	6953	6960	6967	6975	6982	6989	6997	7004
9	7012	7019	7026	7034	7041	7048	7056	7063	7070	7078
590	77085	77093	77100	77107	77115	77122	77129	77137	77144	77151
1	7159	7166	7173	7181	7188	7195	7203	7210	7217	7225
2	7232	7240	7247	7254	7262	7269	7276	7283	7291	7298
3	7305	7313	7320	7327	7335	7342	7349	7357	7364	7371
4	7379	7386	7393	7401	7408	7115	7422	7430	7437	7444
5	7452	7459	7466	7474	7481	7488	7495	7503	7510	7517
6	7525	7532	7539	7546	7554	7561	7568	7576	7583	7590
7	7597	7605	7612	7619	7627	7634	7641	7648	7656	7663
8	7670	7677	7685	7692	7699	7706	7714	7721	7728	7735
9	7743	7750	7757	7764	7772	7779	7786	7793	7801	7808
600	77815	77822	77830	77837	77844	77851	77859	77866	77873	77880

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
600	77815	77822	77830	77837	77844	77851	77859	77866	77873	77880
1	7887	7895	7902	7909	7916	7924	7931	7938	7945	7952
2	7960	7967	7974	7981	7988	7996	8003	8010	8017	8025
3	8032	8039	8046	8053	8061	8068	8075	8082	8089	8097
4	8104	8111	8118	8125	8132	8140	8147	8154	8161	8168
5	8176	8183	8190	8197	8204	8211	8219	8226	8233	8240
6	8247	8254	8262	8269	8276	8283	8290	8297	8305	8312
7	8319	8326	8333	8340	8347	8355	8362	8369	8376	8383
8	8390	8398	8405	8412	8419	8426	8433	8440	8447	8455
9	8462	8469	8476	8483	8490	8497	8504	8512	8519	8526
610	78533	78540	78547	78554	78561	78569	78576	78583	78590	78597
1	8604	8611	8618	8625	8633	8640	8647	8654	8661	8668
2	8675	8682	8689	8696	8704	8711	8718	8725	8732	8739
3	8746	8753	8760	8767	8774	8781	8789	8796	8803	8810
4	8817	8824	8831	8838	8845	8852	8859	8866	8873	8880
5	8888	8895	8902	8909	8916	8923	8930	8937	8944	8951
6	8958	8965	8972	8979	8986	8993	9000	9007	9014	9021
7	9029	9036	9043	9050	9057	9064	9071	9078	9085	9092
8	9099	9106	9113	9120	9127	9134	9141	9148	9155	9162
9	9169	9176	9183	9190	9197	9204	9211	9218	9225	9232
620	79239	79246	79253	79260	79267	79274	79281	79288	79295	79302
1	9309	9316	9323	9330	9337	9344	9351	9358	9365	9372
2	9379	9386	9393	9400	9407	9414	9421	9428	9435	9442
3	9449	9456	9463	9470	9477	9484	9491	9498	9505	9511
4	9518	9525	9532	9539	9546	9553	9560	9567	9574	9581
5	9588	9595	9602	9609	9616	9623	9630	9637	9644	9650
6	9657	9664	9671	9678	9685	9692	9699	9706	9713	9720
7	9727	9734	9741	9748	9754	9761	9768	9775	9782	9789
8	9796	9803	9810	9817	9824	9831	9837	9844	9851	9858
9	9865	9872	9879	9886	9893	9900	9906	9913	9920	9927
630	79934	79941	79948	79955	79962	79969	79975	79982	79989	79996
1	80003	80010	80017	80024	80030	80037	80044	80051	80058	80065
2	0072	0079	0085	0092	0099	0106	0113	0120	0127	0134
3	0140	0147	0154	0161	0168	0175	0182	0188	0195	0202
4	0209	0216	0223	0229	0236	0243	0250	0257	0264	0271
5	0277	0284	0291	0298	0305	0312	0318	0325	0332	0339
6	0346	0353	0359	0366	0373	0380	0387	0393	0400	0407
7	0414	0421	0428	0434	0441	0448	0455	0462	0468	0475
8	0482	0489	0496	0502	0509	0516	0523	0530	0536	0543
9	0550	0557	0564	0570	0577	0584	0591	0598	0604	0611
640	80618	80625	80632	80638	80645	80652	80659	80665	80672	80679
1	0686	0693	0699	0706	0713	0720	0726	0733	0740	0747
2	0754	0760	0767	0774	0781	0787	0794	0801	0808	0814
3	0821	0828	0835	0841	0848	0855	0862	0868	0875	0882
4	0889	0895	0902	0909	0916	0922	0929	0936	0943	0949
5	0956	0963	0969	0976	0983	0990	0996	1003	1010	1017
6	1023	1030	1037	1043	1050	1057	1064	1070	1077	1084
7	1090	1097	1104	1111	1117	1124	1131	1137	1144	1151
8	1158	1164	1171	1178	1184	1191	1198	1204	1211	1218
9	1224	1231	1238	1245	1251	1258	1265	1271	1278	1285
650	81291	81298	81305	81311	81318	81325	81331	81338	81345	81351

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
650	81291	81298	81305	81311	81318	81325	81331	81338	81345	81351
1	1358	1365	1371	1378	1385	1391	1398	1405	1411	1418
2	1425	1431	1438	1445	1451	1458	1465	1471	1478	1485
3	1491	1498	1505	1511	1518	1525	1531	1538	1544	1551
4	1558	1564	1571	1578	1584	1591	1598	1604	1611	1617
5	1624	1631	1637	1644	1651	1657	1664	1671	1677	1684
6	1690	1697	1704	1710	1717	1723	1730	1737	1743	1750
7	1757	1763	1770	1776	1783	1790	1796	1803	1809	1816
8	1823	1829	1836	1842	1849	1856	1862	1869	1875	1882
9	1889	1895	1902	1908	1915	1921	1928	1935	1941	1948
660	81954	81961	81968	81974	81981	81987	81994	82000	82007	82014
1	2020	2027	2033	2040	2046	2053	2060	2066	2073	2079
2	2086	2092	2099	2105	2112	2119	2125	2132	2138	2145
3	2151	2158	2164	2171	2178	2184	2191	2197	2204	2210
4	2217	2223	2230	2236	2243	2249	2256	2263	2269	2276
5	2282	2289	2295	2302	2308	2315	2321	2328	2334	2341
6	2347	2354	2360	2367	2373	2380	2387	2393	2400	2406
7	2413	2419	2426	2432	2439	2445	2452	2458	2465	2471
8	2478	2484	2491	2497	2504	2510	2517	2523	2530	2536
9	2543	2549	2556	2562	2569	2575	2582	2588	2595	2601
670	82607	82614	82620	82627	82633	82640	82646	82653	82659	82666
1	2672	2679	2685	2692	2698	2705	2711	2718	2724	2730
2	2737	2743	2750	2756	2763	2769	2776	2782	2789	2795
3	2802	2808	2814	2821	2827	2834	2840	2847	2853	2860
4	2866	2872	2879	2885	2892	2898	2905	2911	2918	2924
5	2930	2937	2943	2950	2956	2963	2969	2975	2982	2988
6	2995	3001	3008	3014	3020	3027	3033	3040	3046	3052
7	3059	3065	3072	3078	3085	3091	3097	3104	3110	3117
8	3123	3129	3136	3142	3149	3155	3161	3168	3174	3181
9	3187	3193	3200	3206	3213	3219	3225	3232	3238	3245
680	83251	83257	83264	83270	83276	83283	83289	83296	83302	83308
1	3315	3321	3327	3334	3340	3347	3353	3359	3366	3372
2	3378	3385	3391	3398	3404	3410	3417	3423	3429	3436
3	3442	3448	3455	3461	3467	3474	3480	3487	3493	3499
4	3506	3512	3518	3525	3531	3537	3544	3550	3556	3563
5	3569	3575	3582	3588	3594	3601	3607	3613	3620	3626
6	3632	3639	3645	3651	3658	3664	3670	3677	3683	3689
7	3696	3702	3708	3715	3721	3727	3734	3740	3746	3753
8	3759	3765	3771	3778	3784	3790	3797	3803	3809	3816
9	3822	3828	3835	3841	3847	3853	3860	3866	3872	3879
690	83885	83891	83897	83904	83910	83916	83923	83929	83935	83942
1	3948	3954	3960	3967	3973	3979	3985	3992	3998	4004
2	4011	4017	4023	4029	4036	4042	4048	4055	4061	4067
3	4073	4080	4086	4092	4098	4105	4111	4117	4123	4130
4	4136	4142	4148	4155	4161	4167	4173	4180	4186	4192
5	4198	4205	4211	4217	4223	4230	4236	4242	4248	4255
6	4261	4267	4273	4280	4286	4292	4298	4305	4311	4317
7	4323	4330	4336	4342	4348	4354	4361	4367	4373	4379
8	4386	4392	4398	4404	4410	4417	4423	4429	4435	4442
9	4448	4454	4460	4466	4473	4479	4485	4491	4497	4504
700	84510	84516	84522	84528	84535	84541	84547	84553	84559	84566

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
700	84510	84516	84522	84528	84535	84541	84547	84553	84559	84566
1	4572	4578	4584	4590	4597	4603	4609	4615	4621	4628
2	4634	4640	4646	4652	4658	4665	4671	4677	4683	4689
3	4696	4702	4708	4714	4720	4726	4733	4739	4745	4751
4	4757	4763	4770	4776	4782	4788	4794	4800	4807	4813
5	4819	4825	4831	4837	4844	4850	4856	4862	4868	4874
6	4880	4887	4893	4899	4905	4911	4917	4924	4930	4936
7	4942	4948	4954	4960	4967	4973	4979	4985	4991	4997
8	5003	5009	5016	5022	5028	5034	5040	5046	5052	5058
9	5065	5071	5077	5083	5089	5095	5101	5107	5114	5120
710	85126	85132	85138	85144	85150	85156	85163	85169	85175	85181
1	5187	5193	5199	5205	5211	5217	5224	5230	5236	5242
2	5248	5254	5260	5266	5272	5278	5285	5291	5297	5303
3	5309	5315	5321	5327	5333	5339	5345	5352	5358	5364
4	5370	5376	5382	5388	5394	5400	5406	5412	5418	5425
5	5431	5437	5443	5449	5455	5461	5467	5473	5479	5485
6	5491	5497	5503	5509	5516	5522	5528	5534	5540	5546
7	5552	5558	5564	5570	5576	5582	5588	5594	5600	5606
8	5612	5618	5625	5631	5637	5643	5649	5655	5661	5667
9	5673	5679	5685	5691	5697	5703	5709	5715	5721	5727
720	85733	85739	85745	85751	85757	85763	85769	85775	85781	85788
1	5794	5800	5806	5812	5818	5824	5830	5836	5842	5848
2	5854	5860	5866	5872	5878	5884	5890	5896	5902	5908
3	5914	5920	5926	5932	5938	5944	5950	5956	5962	5968
4	5974	5980	5986	5992	5998	6004	6010	6016	6022	6028
5	6034	6040	6046	6052	6058	6064	6070	6076	6082	6088
6	6094	6100	6106	6112	6118	6124	6130	6136	6141	6147
7	6153	6159	6165	6171	6177	6183	6189	6195	6201	6207
8	6213	6219	6225	6231	6237	6243	6249	6255	6261	6267
9	6273	6279	6285	6291	6297	6303	6308	6314	6320	6326
730	86332	86338	86344	86350	86356	86362	86368	86374	86380	86386
1	6392	6398	6404	6410	6415	6421	6427	6433	6439	6445
2	6451	6457	6463	6469	6475	6481	6487	6493	6499	6504
3	6510	6516	6522	6528	6534	6540	6546	6552	6558	6564
4	6570	6576	6581	6587	6593	6599	6605	6611	6617	6623
5	6629	6635	6641	6646	6652	6658	6664	6670	6676	6682
6	6688	6694	6700	6705	6711	6717	6723	6729	6735	6741
7	6747	6753	6759	6764	6770	6776	6782	6788	6794	6800
8	6806	6812	6817	6823	6829	6835	6841	6847	6853	6859
9	6864	6870	6876	6882	6888	6894	6900	6906	6911	6917
740	86923	86929	86935	86941	86947	86953	86958	86964	86970	86976
1	6982	6988	6994	6999	7005	7011	7017	7023	7029	7035
2	7040	7046	7052	7058	7064	7070	7075	7081	7087	7093
3	7099	7105	7111	7116	7122	7128	7134	7140	7146	7151
4	7157	7163	7169	7175	7181	7186	7192	7198	7204	7210
5	7216	7221	7227	7233	7239	7245	7251	7256	7262	7268
6	7274	7280	7286	7291	7297	7303	7309	7315	7320	7326
7	7332	7338	7344	7349	7355	7361	7367	7373	7379	7384
8	7390	7396	7402	7408	7413	7419	7425	7431	7437	7442
9	7448	7454	7460	7466	7471	7477	7483	7489	7495	7500
750	87506	87512	87518	87523	87529	87535	87541	87547	87552	87558

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
750	87506	87512	87518	87523	87529	87535	87541	87547	87552	87558
1	7564	7570	7576	7581	7587	7593	7599	7604	7610	7616
2	7622	7628	7633	7639	7645	7651	7656	7662	7668	7674
3	7679	7685	7691	7697	7703	7708	7714	7720	7726	7731
4	7737	7743	7749	7754	7760	7766	7772	7777	7783	7789
5	7795	7800	7806	7812	7818	7823	7829	7835	7841	7846
6	7852	7858	7864	7869	7875	7881	7887	7892	7898	7904
7	7910	7915	7921	7927	7933	7938	7944	7950	7955	7961
8	7967	7973	7978	7984	7990	7996	8001	8007	8013	8018
9	8024	8030	8036	8041	8047	8053	8058	8064	8070	8076
760	88081	88087	88093	88098	88104	88110	88116	88121	88127	88133
1	8138	8144	8150	8156	8161	8167	8173	8178	8184	8190
2	8195	8201	8207	8213	8218	8224	8230	8235	8241	8247
3	8252	8258	8264	8270	8275	8281	8287	8292	8298	8304
4	8309	8315	8321	8326	8332	8338	8343	8349	8355	8360
5	8366	8372	8377	8383	8389	8395	8400	8406	8412	8417
6	8423	8429	8434	8440	8446	8451	8457	8463	8468	8474
7	8480	8485	8491	8497	8502	8508	8513	8519	8525	8530
8	8536	8542	8547	8553	8559	8564	8570	8576	8581	8587
9	8593	8598	8604	8610	8615	8621	8627	8632	8638	8643
770	88649	88655	88660	88666	88672	88677	88683	88689	88694	88700
1	8705	8711	8717	8722	8728	8734	8739	8745	8750	8756
2	8762	8767	8773	8779	8784	8790	8795	8801	8807	8812
3	8818	8824	8829	8835	8840	8846	8852	8857	8863	8868
4	8874	8880	8885	8891	8897	8902	8908	8913	8919	8925
5	8930	8936	8941	8947	8953	8958	8964	8969	8975	8981
6	8986	8992	8997	9003	9009	9014	9020	9025	9031	9037
7	9042	9048	9053	9059	9064	9070	9076	9081	9087	9092
8	9098	9104	9109	9115	9120	9126	9131	9137	9143	9148
9	9154	9159	9165	9170	9176	9182	9187	9193	9198	9204
780	89209	89215	89221	89226	89232	89237	89243	89248	89254	89260
1	9265	9271	9276	9282	9287	9293	9298	9304	9310	9315
2	9321	9326	9332	9337	9343	9348	9354	9360	9365	9371
3	9376	9382	9387	9393	9398	9404	9409	9415	9421	9426
4	9432	9437	9443	9448	9454	9459	9465	9470	9476	9481
5	9487	9492	9498	9504	9509	9515	9520	9526	9531	9537
6	9542	9548	9553	9559	9564	9570	9575	9581	9586	9592
7	9597	9603	9609	9614	9620	9625	9631	9636	9642	9647
8	9653	9658	9664	9669	9675	9680	9686	9691	9697	9702
9	9708	9713	9719	9724	9730	9735	9741	9746	9752	9757
790	89763	89768	89774	89779	89785	89790	89796	89801	89807	89812
1	9818	9823	9829	9834	9840	9845	9851	9856	9862	9867
2	9873	9878	9883	9889	9894	9900	9905	9911	9916	9922
3	9927	9933	9938	9944	9949	9955	9960	9966	9971	9977
4	9982	9988	9993	9998	90004	90009	90015	90020	90026	90031
5	90037	90042	90048	90053	0059	0064	0069	0075	0080	0086
6	0091	0097	0102	0108	0113	0119	0124	0129	0135	0140
7	0146	0151	0157	0162	0168	0173	0179	0184	0189	0195
8	0200	0206	0211	0217	0222	0227	0233	0238	0244	0249
9	0255	0260	0266	0271	0276	0282	0287	0293	0298	0304
800	90309	90314	90320	90325	90331	90336	90342	90347	90352	90358

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
800	90309	90314	90320	90325	90331	90336	90342	90347	90352	90358
1	0363	0369	0374	0380	0385	0390	0396	0401	0407	0412
2	0417	0423	0428	0434	0439	0445	0450	0455	0461	0466
3	0472	0477	0482	0488	0493	0499	0504	0509	0515	0520
4	0526	0531	0536	0542	0547	0553	0558	0563	0569	0574
5	0580	0585	0590	0596	0601	0607	0612	0617	0623	0628
6	0634	0639	0644	0650	0655	0660	0666	0671	0677	0682
7	0687	0693	0698	0703	0709	0714	0720	0725	0730	0736
8	0741	0747	0752	0757	0763	0768	0773	0779	0784	0789
9	0795	0800	0806	0811	0816	0822	0827	0832	0838	0843
810	90849	90854	90859	90865	90870	90875	90881	90886	90891	90897
1	0902	0907	0913	0918	0924	0929	0934	0940	0945	0950
2	0956	0961	0966	0972	0977	0982	0988	0993	0998	1004
3	1009	1014	1020	1025	1030	1036	1041	1046	1052	1057
4	1062	1068	1073	1078	1084	1089	1094	1100	1105	1110
5	1116	1121	1126	1132	1137	1142	1148	1153.	1158	1164
6	1169	1174	1180	1185	1190	1196	1201	1206	1212	1217
7	1222	1228	1233	1238	1243	1249	1254	1259	1265	1270
8	1275	1281	1286	1291	1297	1302	1307	1312	1318	1323
9	1328	1334	1339	1344	1350	1355	1360	1365	1371	1376
820	91381	91387	91392	91397	91403	91408	91413	91418	91424	91429
1	1434	1440	1445	1450	1455	1461	1466	1471	1477	1482
2	1487	1492	1498	1503	1508	1514	1519	1524	1529	1535
3	1540	1545	1551	1556	1561	1566	1572	1577	1582	1587
4	1593	1598	1603	1609	1614	1619	1624	1630	1635	1640
5	1645	1651	1656	1661	1666	1672	1677	1682	1687	1693
6	1698	1703	1709	1714	1719	1724	1730	1735	1740	1745
7	1751	1756	1761	1766	1772	1777	1782	1787	1793	1798
8	1803	1808	1814	1819	1824	1829	1834	1840	1845	1850
9	1855	1861	1866	1871	1876	1882	1887	1892	1897	1903
830	91908	91913	91918	91924	91929	91934	91939	91944	91950	91955
1	1960	1965	1971	1976	1981	1986	1991	1997	2002	2007
2	2012	2018	2023	2028	2033	2038	2044	2049	2054	2059
3	2065	2070	2075	2080	2085	2091	2096	2101	2106	2111
4	2117	2122	2127	2132	2137	2143	2148	2153	2158	2163
5	2169	2174	2179	2184	2189	2195	2200	2205	2210	2215
6	2221	2226	2231	2236	2241	2247	2252	2257	2262	2267
7	2273	2278	2283	2288	2293	2298	2304	2309	2314	2319
8	2324	2330	2335	2340	2345	2350	2355	2361	2366	2371
9	2376	2381	2387	2392	2397	2402	2407	2412	2418	2423
840	92428	92433	92438	92443	92449	92454	92459	92464	92469	92474
1	2480	2485	2490	2495	2500	2505	2511	2516	2521	2526
2	2531	2536	2542	2547	2552	2557	2562	2567	2572	2578
3	2583	2588	2593	2598	2603	2609	2614	2619	2624	2629
4	2634	2639	2645	2650	2655	2660	2665	2670	2675	2681
5	2686	2691	2696	2701	2706	2711	2716	2722	2727	2732
6	2737	2742	2747	2752	2758	2763	2768	2773	2778	2783
7	2788	2793	2799	2804	2809	2814	2819	2824	2829	2834
8	2840	2845	2850	2855	2860	2865	2870	2875	2881	2886
9	2891	2896	2901	2906	2911	2916	2921	2927	2932	2937
850	92942	92947	92952	92957	92962	92967	92973	92978	92983	92988

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
850	92942	92947	92952	92957	92962	92967	92973	92978	92983	92988
1	2993	2998	3003	3008	3013	3018	3024	3029	3034	3039
2	3044	3049	3054	3059	3064	3069	3075	3080	3085	3090
3	3095	3100	3105	3110	3115	3120	3125	3131	3136	3141
4	3146	3151	3156	3161	3166	3171	3176	3181	3186	3192
5	3197	3202	3207	3212	3217	3222	3227	3232	3237	3242
6	3247	3252	3258	3263	3268	3273	3278	3283	3288	3293
7	3298	3303	3308	3313	3318	3323	3328	3334	3339	3344
8	3349	3354	3359	3364	3369	3374	3379	3384	3389	3394
9	3399	3404	3409	3414	3420	3425	3430	3435	3440	3445
860	93450	93455	93460	93465	93470	93475	93480	93485	93490	93495
1	3500	3505	3510	3515	3520	3526	3531	3536	3541	3546
2	3551	3556	3561	3566	3571	3576	3581	3586	3591	3596
3	3601	3606	3611	3616	3621	3626	3631	3636	3641	3646
4	3651	3656	3661	3666	3671	3676	3682	3687	3692	3697
5	3702	3707	3712	3717	3722	3727	3732	3737	3742	3747
6	3752	3757	3762	3767	3772	3777	3782	3787	3792	3797
7	3802	3807	3812	3817	3822	3827	3832	3837	3842	3847
8	3852	3857	3862	3867	3872	3877	3882	3887	3892	3897
9	3902	3907	3912	3917	3922	3927	3932	3937	3942	3947
870	93952	93957	93962	93967	93972	93977	93982	93987	93992	93997
1	4002	4007	4012	4017	4022	4027	4032	4037	4042	4047
2	4052	4057	4062	4067	4072	4077	4082	4086	4091	4096
3	4101	4106	4111	4116	4121	4126	4131	4136	4141	4146
4	4151	4156	4161	4166	4171	4176	4181	4186	4191	4196
5	4201	4206	4211	4216	4221	4226	4231	4236	4240	4245
6	4250	4255	4260	4265	4270	4275	4280	4285	4290	4295
7	4300	4305	4310	4315	4320	4325	4330	4335	4340	4345
8	4349	4354	4359	4364	4369	4374	4379	4384	4389	4394
9	4399	4404	4409	4414	4419	4424	4429	4433	4438	4443
880	94448	94453	94458	94463	94468	94473	94478	94483	94488	94493
1	4498	4503	4507	4512	4517	4522	4527	4532	4537	4542
2	4547	4552	4557	4562	4567	4571	4576	4581	4586	4591
3	4596	4601	4606	4611	4616	4621	4626	4630	4635	4640
4	4645	4650	4655	4660	4665	4670	4675	4680	4685	4689
5	4694	4699	4704	4709	4711	4719	4724	4729	4734	4738
6	4743	4748	4753	4758	4763	4768	4773	4778	4783	4787
7	4792	4797	4802	4807	4812	4817	4822	4827	4832	4836
8	4841	4846	4851	4856	4861	4866	4871	4876	4880	4885
9	4890	4895	4900	4905	4910	4915	4919	4924	4929	4934
890	94939	94944	94949	94954	94959	94963	94968	94973	94978	94983
1	4988	4993	4998	5002	5007	5012	5017	5022	5027	5032
2	5036	5041	5046	5051	5056	5061	5066	5071	5075	5080
3	5085	5090	5095	5100	5105	5109	5114	5119	5124	5129
4	5134	5139	5143	5148	5153	5158	5163	5168	5173	5177
5	5182	5187	5192	5197	5202	5207	5211	5216	5221	5226
6	5231	5236	5240	5245	5250	5255	5260	5265	5270	5274
7	5279	5284	5289	5294	5299	5303	5308	5313	5318	5323
8	5328	5332	5337	5342	5347	5352	5357	5361	5366	5371
9	5376	5381	5386	5390	5395	5400	5405	5410	5415	5419
900	95424	95429	95434	95439	95444	95448	95453	95458	95463	95468

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
900	95424	95429	95434	95439	95444	95448	95453	95458	95463	95468
1	5472	5477	5482	5487	5492	5497	5501	5506	5511	5516
2	5521	5525	5530	5535	5540	5545	5550	5554	5559	5564
3	5569	5574	5578	5583	5588	5593	5598	5602	5607	5612
4	5617	5622	5626	5631	5636	5641	5646	5650	5655	5660
5	5665	5670	5674	5679	5684	5689	5694	5698	5703	5708
6	5713	5718	5722	5727	5732	5737	5742	5746	5751	5756
7	5761	5766	5770	5775	5780	5785	5789	5794	5799	5804
8	5809	5813	5818	5823	5828	5832	5837	5842	5847	5852
9	5856	5861	5866	5871	5875	5880	5885	5890	5895	5899
910	95904	95909	95914	95918	95923	95928	95933	95938	95942	95947
1	5952	5957	5961	5966	5971	5976	5980	5985	5990	5995
2	5999	6004	6009	6014	6019	6023	6028	6033	6038	6042
3	6047	6052	6057	6061	6066	6071	6076	6080	6085	6090
4	6095	6099	6104	6109	6114	6118	6123	6128	6133	6137
5	6142	6147	6152	6156	6161	6166	6171	6175	6180	6185
6	6190	6194	6199	6204	6209	6213	6218	6223	6227	6232
7	6237	6242	6246	6251	6256	6261	6265	6270	6275	6280
8	6284	6289	6294	6298	6303	6308	6313	6317	6322	6327
9	6332	6336	6341	6346	6350	6355	6360	6365	6369	6374
920	96379	96384	96388	96393	96398	96402	96407	96412	96417	96421
1	6426	6431	6435	6440	6445	6450	6454	6459	6464	6468
2	6473	6478	6483	6487	6492	6497	6501	6506	6511	6515
3	6520	6525	6530	6534	6539	6544	6548	6553	6558	6562
4	6567	6572	6577	6581	6586	6591	6595	6600	6605	6609
5	6614	6619	6624	6628	6633	6638	6642	6647	6652	6656
6	6661	6666	6670	6675	6680	6685	6689	6694	6699	6703
7	6708	6713	6717	6722	6727	6731	6736	6741	6745	6750
8	6755	6759	6764	6769	6774	6778	6783	6788	6792	6797
9	6802	6806	6811	6816	6820	6825	6830	6834	6839	6844
930	96848	96853	96858	96862	96867	96872	96876	96881	96886	96890
1	6895	6900	6904	6909	6914	6918	6923	6928	6932	6937
2	6942	6946	6951	6956	6960	6965	6970	6974	6979	6984
3	6988	6993	6997	7002	7007	7011	7016	7021	7025	7030
4	7035	7039	7044	7049	7053	7058	7063	7067	7072	7077
5	7081	7086	7090	7095	7100	7104	7109	7114	7118	7123
6	7128	7132	7137	7142	7146	7151	7155	7160	7165	7169
7	7174	7179	7183	7188	7192	7197	7202	7206	7211	7216
8	7220	7225	7230	7234	7239	7243	7248	7253	7257	7262
9	7267	7271	7276	7280	7285	7290	7294	7299	7304	7308
940	97313	97317	97322	97327	97331	97336	97340	97345	97350	97354
1	7359	7364	7368	7373	7377	7382	7387	7391	7396	7400
2	7405	7410	7414	7419	7424	7428	7433	7437	7442	7447
3	7451	7456	7460	7465	7470	7474	7479	7483	7488	7493
4	7497	7502	7506	7511	7516	7520	7525	7529	7534	7539
5	7543	7548	7552	7557	7562	7566	7571	7575	7580	7585
6	7589	7594	7598	7603	7607	7612	7617	7621	7626	7630
7	7635	7640	7644	7649	7653	7658	7663	7667	7672	7676
8	7681	7685	7690	7695	7699	7704	7708	7713	7717	7722
9	7727	7731	7736	7740	7745	7749	7754	7759	7763	7768
950	97772	97777	97782	97786	97791	97795	97800	97804	97809	97813

TABLE I.—LOGARITHMS OF NUMBERS.

N	0	1	2	3	4	5	6	7	8	9
950	97772	97777	97782	97786	97791	97795	97800	97804	97809	97813
1	7818	7823	7827	7832	7836	7841	7845	7850	7855	7859
2	7864	7868	7873	7877	7882	7886	7891	7896	7900	7905
3	7909	7914	7918	7923	7928	7932	7937	7941	7946	7950
4	7955	7959	7964	7968	7973	7978	7982	7987	7991	7996
5	8000	8005	8009	8014	8019	8023	8028	8032	8037	8041
6	8046	8050	8055	8059	8064	8068	8073	8078	8082	8087
7	8091	8096	8100	8105	8109	8114	8118	8123	8127	8132
8	8137	8141	8146	8150	8155	8159	8164	8168	8173	8177
9	8182	8186	8191	8195	8200	8204	8209	8214	8218	8223
960	98227	98232	98236	98241	98245	98250	98254	98259	98263	98268
1	8272	8277	8281	8286	8290	8295	8299	8304	8308	8313
2	8318	8322	8327	8331	8336	8340	8345	8349	8354	8358
3	8363	8367	8372	8376	8381	8385	8390	8394	8399	8403
4	8408	8412	8417	8421	8426	8430	8435	8439	8444	8448
5	8453	8457	8462	8466	8471	8475	8480	8484	8489	8493
6	8498	8502	8507	8511	8516	8520	8525	8529	8534	8538
7	8543	8547	8552	8556	8561	8565	8570	8574	8579	8583
8	8588	8592	8597	8601	8605	8610	8614	8619	8623	8628
9	8632	8637	8641	8646	8650	8655	8659	8664	8668	8673
970	98677	98682	98686	98691	98695	98700	98704	98709	98713	98717
1	8722	8726	8731	8735	8740	8744	8749	8753	8758	8762
2	8767	8771	8776	8780	8784	8789	8793	8798	8802	8807
3	8811	8816	8820	8825	8829	8834	8838	8843	8847	8851
4	8856	8860	8865	8869	8874	8878	8883	8887	8892	8896
5	8900	8905	8909	8914	8918	8923	8927	8932	8936	8941
6	8945	8949	8954	8958	8963	8967	8972	8976	8981	8985
7	8989	8994	8998	9003	9007	9012	9016	9021	9025	9029
8	9034	9038	9043	9047	9052	9056	9061	9065	9069	9074
9	9078	9083	9087	9092	9096	9100	9105	9109	9114	9118
980	99123	99127	99131	99136	99140	99145	99149	99154	99158	99162
1	9167	9171	9176	9180	9185	9189	9193	9198	9202	9207
2	9211	9216	9220	9224	9229	9233	9238	9242	9247	9251
3	9255	9260	9264	9269	9273	9277	9282	9286	9291	9295
4	9300	9304	9308	9313	9317	9322	9326	9330	9335	9339
5	9344	9348	9352	9357	9361	9366	9370	9374	9379	9383
6	9388	9392	9396	9401	9405	9410	9414	9419	9423	9427
7	9432	9436	9441	9445	9449	9454	9458	9463	9467	9471
8	9476	9480	9484	9489	9493	9498	9502	9506	9511	9515
9	9520	9524	9528	9533	9537	9542	9546	9550	9555	9559
990	99564	99568	99572	99577	99581	99585	99590	99594	99599	99603
1	9607	9612	9616	9621	9625	9629	9634	9638	9642	9647
2	9651	9656	9660	9664	9669	9673	9677	9682	9686	9691
3	9695	9699	9704	9708	9712	9717	9721	9726	9730	9734
4	9739	9743	9747	9752	9756	9760	9765	9769	9774	9778
5	9782	9787	9791	9795	9800	9804	9808	9813	9817	9822
6	9826	9830	9835	9839	9843	9848	9852	9856	9861	9865
7	9870	9874	9878	9883	9887	9891	9896	9900	9904	9909
8	9913	9917	9922	9926	9930	9935	9939	9944	9948	9952
9	9957	9961	9965	9970	9974	9978	9983	9987	9991	9996
1000	00000	00004	00009	00013	00017	00022	00026	00030	00035	00039

Logarithmic Sines and Tangents of Small Angles. — To obtain the log sin or log tan of an angle less than 1° from the 5-place tables add the log of the number of minutes and decimals to the log sin of one minute (6.463726).

EXAMPLE:— Required the log sin 0° 24′ 21″ (= log sin 24.35):

$$\begin{aligned} \log \sin 1' &= 6.46373 \\ \log 24.35 &= \underline{1.38650} \\ \log \sin 0^\circ\ 24'\ 21'' &= 7.85023 \end{aligned}$$

This method is approximate but the error is only 2 units in the 5th place for an angle of 1° and is less for smaller angles. If the log had been obtained by direct interpolation in the 5-place table the error for sin 0° 24′ 21″ would be 10 in the fifth place.

To obtain the angle corresponding to a log sin, subtract 6.463726 from the given log sin; the result is the log of the number of minutes in the angle. For example, the angle corresponding to the log sin 7.64076 is 0° 15′ 02″. If the log tan of an angle were given the procedure would be exactly the same.

If greater accuracy is required than can be obtained by the above method, or for angles up to 5°, the log sin may be found from the relation

$$n' : n = \sin n' : \sin n$$

where n is the nearest angle whose sine is given in the table and n' is the desired angle. The log sin is then given by

$$\log \sin n' = \log \sin n + \log n' - \log n.$$

For the log sin 0° 24′ 21″ this latter method gives 7.85022 which is correct to five decimal places. For angles above 5° direct interpolation in the tables is sufficiently accurate.

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	0°		1°		2°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	−∞	10.00000	8.24186	9.99993	8.54282	9 99974	60
1	6.46373	00000	24903	99993	54642	99973	59
2	76476	00000	25609	99993	54999	99973	58
3	94085	00000	26304	99993	55354	99972	57
4	7.06579	00000	26988	99992	55705	99972	56
5	16270	00000	27661	99992	56054	99971	55
6	24188	00000	28324	99992	56400	99971	54
7	30882	00000	28977	99992	56743	99970	53
8	36682	00000	29621	99992	57084	99970	52
9	41797	00000	30255	99991	57421	99969	51
10	7.46373	10.00000	8.30879	9.99991	8.57757	9.99969	50
11	50512	00000	31495	99991	58089	99968	49
12	54291	00000	32103	99990	58419	99968	48
13	57767	00000	32702	99990	58747	99967	47
14	60985	00000	33292	99990	59072	99967	46
15	63982	00000	33875	99990	59395	99967	45
16	66784	00000	34450	99989	59715	99966	44
17	69417	9.99999	35018	99989	60033	99966	43
18	71900	99999	35578	99989	60349	99965	42
19	74248	99999	36131	99989	60662	99964	41
20	7.76475	9.99999	8.36678	9.99988	8.60973	9.99964	40
21	78594	99999	37217	99988	61282	99963	39
22	80615	99999	37750	99988	61589	99963	38
23	82545	99999	38276	99987	61894	99962	37
24	84393	99999	38796	99987	62196	99962	36
25	86166	99999	39310	99987	62197	99961	35
26	87870	99999	39818	99986	62795	99961	34
27	89509	99999	40320	99986	63091	99960	33
28	91088	99999	40816	99986	63385	99960	32
29	92612	99998	41307	99985	63678	99959	31
30	7.94084	9.99998	8 41792	9.99985	8.63968	9.99959	30
31	95508	99998	42272	99985	64256	99958	29
32	96887	99998	42746	99984	64543	99958	28
33	98223	99998	43216	99984	64827	99957	27
34	99520	99998	43680	99984	65110	99956	26
35	8.00779	99998	44139	99983	65391	99956	25
36	02002	99998	44594	99983	65670	99955	24
37	03192	99997	45044	99983	65947	99955	23
38	04350	99997	45489	99982	66223	99954	22
39	05478	99997	45930	99982	66497	99954	21
40	8.06578	9.99997	8.46366	9.99982	8.66769	9.99953	20
41	07650	99997	46799	99981	67039	99952	19
42	08696	99997	47226	99981	67308	99952	18
43	09718	99997	47650	99981	67575	99951	17
44	10717	99996	48069	99980	67841	99951	16
45	11693	99996	48485	99980	68104	99950	15
46	12647	99996	48896	99979	68367	99949	14
47	13581	99996	49304	99979	68627	99949	13
48	14495	99996	49708	99979	68886	99948	12
49	15391	99996	50108	99978	69144	99948	11
50	8.16268	9.99995	8.50504	9.99978	8.69400	9.99947	10
51	17128	99995	50897	99977	69654	99946	9
52	17971	99995	51287	99977	69907	99946	8
53	18798	99995	51673	99977	70159	99945	7
54	19610	99995	52055	99976	70109	99944	6
55	20407	99994	52434	99976	70658	99944	5
56	21189	99994	52810	99975	70905	99943	4
57	21958	99994	53183	99975	71151	99942	3
58	22713	99994	53552	99974	71395	99942	2
59	23456	99994	53919	99974	71638	99941	1
60	24186	99993	54282	99974	71880	99940	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	89°		88°		87°		

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	3° Sine	3° Cosine	4° Sine	4° Cosine	5° Sine	5° Cosine	′
	8.71880	9.99940	8.84358	9.99894	8.94030	9.99834	60
0	72120	99940	84589	99893	94174	99833	59
1	72359	99939	84718	99892	94317	99832	58
2	72597	99938	84897	99891	94461	99831	57
3	72834	99938	85075	99891	94603	99830	56
4	73069	99937	85252	99890	94746	99828	55
5	73303	99936	85429	99889	94887	99827	54
6	73535	99936	85605	99888	95029	99826	53
7	73767	99935	85780	99887	95170	99825	52
8	73997	99934	85955	99886	95310	99824	51
9							50
10	8.74226	9.99934	8.86128	9.99885	8.95450	9.99823	49
11	74454	99933	86301	99884	95589	99822	48
12	74680	99932	86474	99883	95728	99821	47
13	74906	99932	86645	99882	95867	99820	46
14	75130	99931	86816	99881	96005	99819	45
15	75353	99930	86987	99880	96143	99817	44
16	75575	99929	87156	99879	96280	99816	43
17	75795	99929	87325	99879	96417	99815	42
18	76015	99928	87494	99878	96553	99814	41
19	76234	99927	87661	99877	96689	99813	
20	8.76451	9.99926	8.87829	9.99876	8.96825	9.99812	40
21	76667	99926	87995	99875	96960	99810	39
22	76883	99925	88161	99874	97095	99809	38
23	77097	99924	88326	99873	97229	99808	37
24	77310	99923	88490	99872	97363	99807	36
25	77522	99923	88654	99871	97496	99806	35
26	77733	99922	88817	99870	97629	99804	34
27	77943	99921	88980	99869	97762	99803	33
28	78152	99920	89142	99868	97894	99802	32
29	78360	99920	89304	99867	98026	99801	31
30	8.78568	9.99919	8.89464	9.99866	8.98157	9.99800	30
31	78774	99918	89625	99865	98288	99798	29
32	78979	99917	89784	99864	98419	99797	28
33	79183	99917	89943	99863	98549	99796	27
34	79386	99916	90102	99862	98679	99795	26
35	79588	99915	90260	99861	98808	99793	25
36	79789	99914	90417	99860	98937	99792	24
37	79990	99913	90574	99859	99066	99791	23
38	80189	99913	90730	99858	99194	99790	22
39	80388	99912	90885	99857	99322	99788	21
40	8.80585	9.99911	8.91040	9.99856	8.99450	9.99787	20
41	80782	99910	91195	99855	99577	99786	19
42	80978	99909	91349	99854	99704	99785	18
43	81173	99909	91502	99853	99830	99783	17
44	81367	99908	91655	99852	99956	99782	16
45	81560	99907	91807	99851	9.00082	99781	15
46	81752	99906	91959	99850	00207	99780	14
47	81944	99905	92110	99848	00332	99778	13
48	82134	99904	92261	99847	00456	99777	12
49	82324	99904	92411	99846	00581	99776	11
50	8.82513	9.99903	8.92561	9.99845	9.00704	9.99775	10
51	82701	99902	92710	99844	00828	99773	9
52	82888	99901	92859	99843	00951	99772	8
53	83075	99900	93007	99842	01074	99771	7
54	83261	99899	93154	99841	01196	99769	6
55	83446	99898	93301	99840	01318	99768	5
56	83630	99898	93448	99839	01440	99767	4
57	83813	99897	93594	99838	01561	99765	3
58	83996	99896	93740	99837	01682	99764	2
59	84177	99895	93885	99836	01803	99763	1
60	84358	99894	94030	99834	01923	99761	0
′	86° Cosine	86° Sine	85° Cosine	85° Sine	84° Cosine	84° Sine	′

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	6°		7°		8°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	9.01923	9.99761	9.08589	9.99675	9.14856	9.99575	60
1	02013	99760	08692	99674	14945	99574	59
2	02163	99759	08795	99672	14585	99572	58
3	02253	99757	08897	99670	14624	99570	57
4	02402	99756	08999	99669	14714	99568	56
5	02520	99755	09101	99667	14803	99566	55
6	02639	99753	09202	99666	14891	99565	54
7	02757	99752	09304	99664	14980	99563	53
8	02874	99751	09405	99663	15069	99561	52
9	02992	99749	09506	99661	15157	99559	51
10	9.03109	9.99748	9.09606	9.99659	9.15245	9.99557	50
11	03226	99747	09707	99658	15333	99556	49
12	03342	99745	09807	99656	15421	99554	48
13	03458	99744	09907	99655	15508	99552	47
14	03574	99742	10006	99653	15596	99550	46
15	03690	99741	10106	99651	15683	99548	45
16	03805	99740	10205	99650	15770	99546	44
17	03920	99738	10304	99648	15857	99545	43
18	04034	99737	10402	99647	15944	99543	42
19	04149	99736	10501	99645	16030	99541	41
20	9.04262	9.99734	9.10599	9.99643	9.16116	9.99539	40
21	04376	99733	10697	99642	16203	99537	39
22	04490	99731	10795	99640	16289	99535	38
23	04603	99730	10893	99638	16374	99533	37
24	04715	99728	10990	99637	16460	99532	36
25	04828	99727	11087	99635	16545	99530	35
26	04940	99726	11184	99633	16631	99528	34
27	05052	99724	11281	99632	16716	99526	33
28	05164	99723	11377	99630	16801	99524	32
29	05275	99721	11474	99629	16886	99522	31
30	9.05385	9.99720	9.11570	9.99627	9.16970	9.99520	30
31	05497	99718	11666	99625	17055	99518	29
32	05607	99717	11761	99624	17139	99517	28
33	05717	99716	11857	99622	17223	99515	27
34	05827	99714	11952	99620	17307	99513	26
35	05937	99713	12047	99618	17391	99511	25
36	06046	99711	12142	99617	17474	99509	24
37	06155	99710	12236	99615	17558	99507	23
38	06264	99708	12331	99613	17641	99505	22
39	06372	99707	12425	99612	17724	99503	21
40	9.06481	9.99705	9.12519	9.99610	9.17807	9.99501	20
41	06589	99704	12612	99608	17890	99499	19
42	06696	99702	12706	99607	17973	99497	18
43	06804	99701	12799	99605	18055	99495	17
44	06911	99699	12892	99603	18137	99494	16
45	07018	99698	12985	99601	18220	99492	15
46	07124	99696	13078	99600	18302	99490	14
47	07231	99695	13171	99598	18383	99488	13
48	07337	99693	13263	99596	18465	99486	12
49	07442	99692	13355	99595	18547	99484	11
50	9.07548	9.99690	9.13447	9.99593	9.18628	9.99482	10
51	07653	99689	13539	99591	18709	99480	9
52	07758	99687	13630	99589	18790	99478	8
53	07863	99686	13722	99588	18871	99476	7
54	07968	99684	13813	99586	18952	99474	6
55	08072	99683	13904	99584	19033	99472	5
56	08176	99681	13994	99582	19113	99470	4
57	08280	99680	14085	99581	19193	99468	3
58	08383	99678	14175	99579	19273	99466	2
59	08486	99677	14266	99577	19353	99464	1
60	08589	99675	14356	99575	19433	99462	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	83°		82°		81°		

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	9°		10°		11°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	9.19433	9.99462	9.23967	9.99335	9.28060	9.99195	60
1	19513	99460	24039	99333	28125	99192	59
2	19592	99458	24110	99331	28190	99190	58
3	19672	99456	24181	99328	28254	99187	57
4	19751	99454	24253	99326	28319	99185	56
5	19830	99452	24324	99324	28384	99182	55
6	19909	99450	24395	99322	28448	99180	54
7	19988	99448	24466	99319	28512	99177	53
8	20067	99446	24536	99317	28577	99175	52
9	20145	99444	24607	99315	28641	99172	51
10	9.20223	9.99442	9.24677	9.99313	9.28705	9.99170	50
11	20302	99440	24748	99310	28769	99167	49
12	20380	99438	24818	99308	28833	99165	48
13	20458	99436	24888	99306	28896	99162	47
14	20535	99434	24958	99304	28960	99160	46
15	20613	99432	25028	99301	29024	99157	45
16	20691	99429	25098	99299	29087	99155	44
17	20768	99427	25168	99297	29150	99152	43
18	20845	99425	25237	99294	29214	99150	42
19	20922	99423	25307	99292	29277	99147	41
20	9.20999	9.99421	9.25376	9.99290	9.29340	9.99145	40
21	21076	99419	25445	99288	29403	99142	39
22	21153	99417	25514	99285	29466	99140	38
23	21229	99415	25583	99283	29529	99137	37
24	21306	99413	25652	99281	29591	99135	36
25	21382	99411	25721	99278	29654	99132	35
26	21458	99409	25790	99276	29716	99130	34
27	21534	99407	25858	99274	29779	99127	33
28	21610	99404	25927	99271	29841	99124	32
29	21685	99402	25995	99269	29903	99122	31
30	9.21761	9.99400	9.26063	9.99267	9.29966	9.99119	30
31	21836	99398	26131	99264	30028	99117	29
32	21912	99396	26199	99262	30090	99114	28
33	21987	99394	26267	99260	30151	99112	27
34	22062	99392	26335	99257	30213	99109	26
35	22137	99390	26403	99255	30275	99106	25
36	22211	99388	26470	99252	30336	99104	24
37	22286	99385	26538	99250	30398	99001	23
38	22361	99383	26605	99248	30459	99099	22
39	22435	99381	26672	99245	30521	99096	21
40	9.22509	9.99379	9.26739	9.99243	9.30582	9.99093	20
41	22583	99377	26806	99241	30643	99091	19
42	22657	99375	26873	99238	30704	99088	18
43	22731	99372	26940	99236	30765	99086	17
44	22805	99370	27007	99233	30826	99083	16
45	22878	99368	27073	99231	30887	99080	15
46	22952	99366	27140	99229	30947	99078	14
47	23025	99364	27206	99226	31008	99075	13
48	23098	99362	27273	99224	31068	99072	12
49	23171	99359	27339	99221	31129	99070	11
50	9.23244	9.99357	9.27405	9.99219	9.31189	9.99067	10
51	23317	99355	27471	99217	31250	99064	9
52	23390	99353	27537	99214	31310	99062	8
53	23462	99351	27602	99212	31370	99059	7
54	23535	99348	27668	99209	31430	99056	6
55	23607	99346	27734	99207	31490	99054	5
56	23679	99344	27799	99204	31549	99051	4
57	23752	99342	27864	99202	31609	99048	3
58	23823	99340	27930	99200	31669	99046	2
59	23895	99337	27995	99197	31728	99043	1
60	23967	99335	28060	99195	31788	99040	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	80°		79°		78°		

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	12°		13°		14°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	9.31788	9.99040	9.35209	9.98872	9.38368	9.98690	60
1	31847	99038	35263	98869	38418	98687	59
2	31907	99035	35318	98867	38469	98684	58
3	31966	99032	35372	98864	38519	98681	57
4	32025	99030	35427	98861	38570	98678	56
5	32084	99027	35481	98858	38620	98675	55
6	32143	99024	35536	98855	38670	98671	54
7	32202	99022	35590	98852	38721	98668	53
8	32261	99019	35644	98849	38771	98665	52
9	32319	99016	35698	98846	38821	98662	51
10	9.32378	9.99013	9.35752	9.98843	9.38871	9.98659	50
11	32437	99011	35806	98840	38921	98656	49
12	32495	99008	35860	98837	38971	98652	48
13	32553	99005	35914	98834	39021	98649	47
14	32612	99002	35968	98831	39071	98646	46
15	32670	99000	36022	98828	39121	98643	45
16	32728	98997	36075	98825	39170	98640	44
17	32786	98994	36129	98822	39220	98636	43
18	32844	98991	36182	98819	39270	98633	42
19	32902	98989	36236	98816	39319	98630	41
20	9.32960	9.98986	9.36289	9.98813	9.39369	9.98627	40
21	33018	98983	36342	98810	39118	98623	39
22	33075	98980	36395	98807	39467	98620	38
23	33133	98978	36449	98804	39517	98617	37
24	33190	98975	36502	98801	39566	98614	36
25	33248	98972	36555	98798	39615	98610	35
26	33305	98969	36608	98795	39664	98607	34
27	33362	98967	36660	98792	39713	98604	33
28	33420	98964	36713	98789	39762	98601	32
29	33477	98961	36766	98786	39811	98597	31
30	9.33534	9.98958	9.36819	9.98783	9.39860	9.98594	30
31	33591	98955	36871	98780	39909	98591	29
32	33647	98953	36924	98777	39958	98588	28
33	33704	98950	36976	98774	40006	98584	27
34	33761	98947	37028	98771	40055	98581	26
35	33818	98944	37081	98768	40103	98578	25
36	33874	98941	37133	98765	40152	98574	24
37	33931	98938	37185	98762	40200	98571	23
38	33987	98936	37237	98759	40249	98568	22
39	34043	98933	37289	98756	40297	98565	21
40	9.34100	9.98930	9.37341	9.98753	9.40346	9.98561	20
41	34156	98927	37393	98750	40394	98558	19
42	34212	98924	37445	98746	40442	98555	18
43	34268	98921	37497	98743	40490	98551	17
44	34324	98919	37549	98740	40538	98548	16
45	34380	98916	37600	98737	40586	98545	15
46	34436	98913	37652	98734	40634	98541	14
47	34491	98910	37703	98731	40682	98538	13
48	34547	98907	37755	98728	40730	98535	12
49	34602	98904	37806	98725	40778	98531	11
50	9.34658	9.98901	9.37858	9.98722	9.40825	9.98528	10
51	34713	98898	37909	98719	40873	98525	9
52	34769	98896	37960	98715	40921	98521	8
53	34824	98893	38011	98712	40968	98518	7
54	34879	98890	38062	98709	41016	98515	6
55	34934	98887	38113	98706	41063	98511	5
56	34989	98884	38164	98703	41111	98508	4
57	35044	98881	38215	98700	41158	98505	3
58	35099	98878	38266	98697	41205	98501	2
59	35154	98875	38317	98694	41252	98498	1
60	35209	98872	38368	98690	41300	98491	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	77°		76°		75°		

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	15°		16°		17°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	9.41300	9.98494	9.44034	9.98284	9.46594	9.98060	60
1	41347	98491	44078	98281	46635	98056	59
2	41394	98488	44122	98277	46676	98052	58
3	41441	98484	44166	98273	46717	98048	57
4	41488	98481	44210	98270	46758	98044	56
5	41535	98477	44253	98266	46800	98040	55
6	41582	98474	44297	98262	46841	98036	54
7	41628	98471	44341	98259	46882	98032	53
8	41675	98467	44385	98255	46923	98029	52
9	41722	98464	44428	98251	46964	98025	51
10	9.41768	9.98460	9.44472	9.98248	9.47005	9.98021	50
11	41815	98457	44516	98244	47045	98017	49
12	41861	98453	44559	98240	47086	98013	48
13	41908	98450	44602	98237	47127	98009	47
14	41954	98447	44646	98233	47168	98005	46
15	42001	98443	44689	98229	47209	98001	45
16	42047	98440	44733	98226	47249	97997	44
17	42093	98436	44776	98222	47290	97993	43
18	42140	98433	44819	98218	47330	97989	42
19	42186	98429	44862	98215	47371	97986	41
20	9.42232	9.98426	9.44905	9.98211	9.47411	9.97982	40
21	42278	98422	44948	98207	47452	97978	39
22	42324	98419	44992	98204	47492	97974	38
23	42370	98415	45035	98200	47533	97970	37
24	42416	98412	45077	98196	47573	97966	36
25	42461	98409	45120	98192	47613	97962	35
26	42507	98405	45163	98189	47654	97958	34
27	42553	98402	45206	98185	47694	97954	33
28	42599	98398	45249	98181	47734	97950	32
29	42644	98395	45292	98177	47774	97946	31
30	9.42690	9.98391	9.45334	9.98174	9.47814	9.97942	30
31	42735	98388	45377	98170	47854	97938	29
32	42781	98384	45419	98166	47894	97934	28
33	42826	98381	45462	98162	47934	97930	27
34	42872	98377	45504	98159	47974	97926	26
35	42917	98373	45547	98155	48014	97922	25
36	42962	98370	45589	98151	48054	97918	24
37	43008	98366	45632	98147	48094	97914	23
38	43053	98363	45674	98144	48133	97910	22
39	43098	98359	45716	98140	48173	97906	21
40	9.43143	9.98356	9.45758	9.98136	9.48213	9.97902	20
41	43188	98352	45801	98132	48252	97898	19
42	43233	98349	45843	98129	48292	97894	18
43	43278	98345	45885	98125	48332	97890	17
44	43323	98342	45927	98121	48371	97886	16
45	43367	98338	45969	98117	48411	97882	15
46	43412	98334	46011	98113	48450	97878	14
47	43457	98331	46053	98110	48490	97874	13
48	43502	98327	46095	98106	48529	97870	12
49	43546	98324	46136	98102	48568	97866	11
50	9.43591	9.98320	9.46178	9.98098	9.48607	9.97861	10
51	43635	98317	46220	98094	48647	97857	9
52	43680	98313	46262	98090	48686	97853	8
53	43724	98309	46303	98087	48725	97849	7
54	43769	98306	46345	98083	48764	97845	6
55	43813	98302	46386	98079	48803	97841	5
56	43857	98299	46428	98075	48842	97837	4
57	43901	98295	46469	98071	48881	97833	3
58	43946	98291	46511	98067	48920	97829	2
59	43990	98288	46552	98063	48959	97825	1
60	44034	98284	46594	98060	48998	97821	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	74°		73°		72°		

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	18°		19°		20°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	9.48998	9.97821	9.51264	9.97567	9.53405	9.97299	60
1	49037	97817	51301	97563	53440	97294	59
2	49076	97812	51338	97558	53475	97289	58
3	49115	97808	51374	97554	53509	97285	57
4	49153	97804	51411	97550	53544	97280	56
5	49192	97800	51447	97545	53578	97276	55
6	49231	97796	51484	97541	53613	97271	54
7	49269	97792	51520	97536	53647	97266	53
8	49308	97788	51557	97532	53682	97262	52
9	49347	97784	51593	97528	53716	97257	51
10	9.49385	9.97779	9.51629	9.97523	9.53751	9.97252	50
11	49424	97775	51666	97519	53785	97248	49
12	49462	97771	51702	97515	53819	97243	48
13	49500	97767	51738	97510	53854	97238	47
14	49539	97763	51774	97506	53888	97234	46
15	49577	97759	51811	97501	53922	97229	45
16	49615	97754	51847	97497	53957	97224	44
17	49654	97750	51883	97492	53991	97220	43
18	49692	97746	51919	97488	54025	97215	42
19	49730	97742	51955	97484	54059	97210	41
20	9.49768	9.97738	9.51991	9.97479	9.54093	9.97206	40
21	49806	97734	52027	97475	54127	97201	39
22	49844	97729	52063	97470	54161	97196	38
23	49882	97725	52099	97466	54195	97192	37
24	49920	97721	52135	97461	54229	97187	36
25	49958	97717	52171	97457	54263	97182	35
26	49996	97713	52207	97453	54297	97178	34
27	50034	97708	52242	97448	54331	97173	33
28	50072	97704	52278	97444	54365	97168	32
29	50110	97700	52314	97439	54399	97163	31
30	9.50148	9.97696	9.52350	9.97435	9.54433	9.97159	30
31	50185	97691	52385	97430	54466	97154	29
32	50223	97687	52421	97426	54500	97149	28
33	50261	97683	52456	97421	54534	97145	27
34	50298	97679	52492	97417	54567	97140	26
35	50336	97674	52527	97412	54601	97135	25
36	50374	97670	52563	97408	54635	97130	24
37	50411	97666	52598	97403	54668	97126	23
38	50449	97662	52634	97399	54702	97121	22
39	50486	97657	52669	97394	54735	97116	21
40	9.50523	9.97653	9.52705	9.97390	9.54769	9.97111	20
41	50561	97649	52740	97385	54802	97107	19
42	50598	97645	52775	97381	54836	97102	18
43	50635	97640	52811	97376	54869	97097	17
44	50673	97636	52846	97372	54903	97092	16
45	50710	97632	52881	97367	54936	97087	15
46	50747	97628	52916	97363	54969	97083	14
47	50784	97623	52951	97358	55003	97078	13
48	50821	97619	52986	97353	55036	97073	12
49	50858	97615	53021	97349	55069	97068	11
50	9.50896	9.97610	9.53056	9.97344	9.55102	9.97063	10
51	50933	97606	53092	97340	55136	97059	9
52	50970	97602	53126	97335	55169	97054	8
53	51007	97597	53161	97331	55202	97049	7
54	51043	97593	53196	97326	55235	97044	6
55	51080	97589	53231	97322	55268	97039	5
56	51117	97584	53266	97317	55301	97035	4
57	51154	97580	53301	97312	55334	97030	3
58	51191	97576	53336	97308	55367	97025	2
59	51227	97571	53370	97303	55400	97020	1
60	51264	97567	53405	97299	55433	97015	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	71°		70°		69°		

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	21°		22°		23°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	9.55433	9.97015	9.57858	9.96717	9.59188	9.96403	60
1	55466	97010	57889	96711	59218	96397	59
2	55499	97005	57920	96706	59247	96392	58
3	55532	97001	57951	96701	59277	96387	57
4	55564	96996	57982	96696	59307	96381	56
5	55597	96991	58014	96691	59336	96376	55
6	55630	96986	58045	96686	59366	96370	54
7	55663	96981	58076	96681	59396	96365	53
8	55695	96976	58107	96676	59425	96360	52
9	55728	96971	58138	96670	59455	96354	51
10	9.55761	9.96966	9.58169	9.96665	9.59484	9.96349	50
11	55793	96962	58200	96660	59514	96343	49
12	55826	96957	58231	96655	59543	96338	48
13	55858	96952	58262	96650	59573	96333	47
14	55891	96947	58293	96645	59602	96327	46
15	55923	96942	58324	96640	59632	96322	45
16	55956	96937	58355	96634	59661	96316	44
17	55988	96932	58385	96629	59690	96311	43
18	56021	96927	58416	96624	59720	96305	42
19	56053	96922	58447	96619	59749	96300	41
20	9.56085	9.96917	9.58478	9.96614	9.59778	9.96294	40
21	56118	96912	58508	96608	59808	96289	39
22	56150	96907	58039	96603	59837	96284	38
23	56182	96903	58070	96598	59866	96278	37
24	56215	96898	58101	96593	59895	96273	36
25	56247	96893	58131	96588	59924	96267	35
26	56279	96888	58162	96582	59954	96262	34
27	56311	96883	58192	96577	59983	96256	33
28	56343	96878	58223	96572	60012	96251	32
29	56375	96873	58253	96567	60041	96245	31
30	9.56108	9.96868	9.58284	9.96562	9.60070	9.96240	30
31	56440	96863	58314	96556	60099	96234	29
32	56472	96858	58345	96551	60128	96229	28
33	56504	96853	58375	96546	60157	96223	27
34	56536	96848	58406	96541	60186	96218	26
35	56568	96843	58436	96535	60215	96212	25
36	56599	96838	58467	96530	60244	96207	24
37	56631	96833	58497	96525	60273	96201	23
38	56663	96828	58527	96520	60302	96196	22
39	56695	96823	58557	96514	60331	96190	21
40	9.56727	9.96818	9.58588	9.96509	9.60359	9.96185	20
41	56759	96813	58618	96504	60388	96179	19
42	56790	96808	58648	96498	60417	96174	18
43	56822	96803	58678	96493	60446	96168	17
44	56854	96798	58709	96488	60474	96162	16
45	56886	96793	58739	96483	60503	96157	15
46	56917	96788	58769	96477	60532	96151	14
47	56949	96783	58799	96472	60561	96146	13
48	56980	96778	58829	96467	60589	96140	12
49	57012	96772	58859	96461	60618	96135	11
50	9.57044	9.96767	9.58889	9.96456	9.60646	9.96129	10
51	57075	96762	58919	96451	60675	96123	9
52	57107	96757	58949	96445	60704	96118	8
53	57138	96752	58979	96440	60732	96112	7
54	57169	96747	59009	96435	60761	96107	6
55	57201	96742	59039	96429	60789	96101	5
56	57232	96737	59069	96424	60818	96095	4
57	57264	96732	59098	96419	60846	96090	3
58	57295	96727	59128	96413	60875	96084	2
59	57326	96722	59158	96408	60903	96079	1
60	57358	96717	59188	96403	60931	96073	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	68°		67°		66°		

TALBE II.—LOGARITHMIC SINES AND COSINES.

′	24°		25°		26°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	9.60931	9.96073	9.62595	9.95728	9.64184	9.95366	60
1	60960	96067	62622	95722	64210	95360	59
2	60988	96062	62649	95716	64236	95354	58
3	61016	96056	62676	95710	64262	95348	57
4	61045	96050	62703	95704	64288	95341	56
5	61073	96045	62730	95698	64313	95335	55
6	61101	96039	62757	95692	64339	95329	54
7	61129	96034	62784	95686	64365	95323	53
8	61158	96028	62811	95680	64391	95317	52
9	61186	96022	62838	95674	64417	95310	51
10	9.61214	9.96017	9.62865	9.95668	9.64442	9.95304	50
11	61242	96011	62892	95663	64468	95298	49
12	61270	96005	62918	95657	64494	95292	48
13	61298	96000	62945	95651	64519	95286	47
14	61326	95994	62972	95645	64545	95279	46
15	61354	95988	62999	95639	64571	95273	45
16	61382	95982	63026	95633	64596	95267	44
17	61411	95977	63052	95627	64622	95261	43
18	61438	95971	63079	95621	64647	95254	42
19	61466	95965	63106	95615	64673	95248	41
20	9.61494	9.95960	9.63133	9.95609	9.64698	9.95242	40
21	61522	95954	63159	95603	64724	95236	39
22	61550	95948	63186	95597	64749	95229	38
23	61578	95942	63213	95591	64775	95223	37
24	61606	95937	63239	95585	64800	95217	36
25	61631	95931	63266	95579	64826	95211	35
26	61662	95925	63292	95573	64851	95204	34
27	61689	95920	63319	95567	64877	95198	33
28	61717	95914	63345	95561	64902	95192	32
29	61745	95908	63372	95555	64927	95185	31
30	9.61773	9.95902	9.63398	9.95549	9.64953	9.95179	30
31	61800	95897	63425	95543	64978	95173	29
32	61828	95891	63451	95537	65003	95167	28
33	61856	95885	63478	95531	65029	95160	27
34	61883	95879	63504	95525	65054	95154	26
35	61911	95873	63531	95519	65079	95148	25
36	61939	95868	63557	95513	65104	95141	24
37	61966	95862	63583	95507	65130	95135	23
38	61994	95856	63610	95500	65155	95129	22
39	62021	95850	63636	95494	65180	95122	21
40	9.62049	9.95844	9.63662	9.95488	9.65205	9.95116	20
41	62076	95839	63689	95482	65230	95110	19
42	62104	95833	63715	95476	65255	95103	18
43	62131	95827	63741	95470	65281	95097	17
44	62159	95821	63767	95464	65306	95090	16
45	62186	95815	63794	95458	65331	95084	15
46	62214	95810	63820	95452	65356	95078	14
47	62241	95804	63846	95446	65381	95071	13
48	62268	95798	63 72	95440	65406	95065	12
49	62296	95792	63898	95434	65431	95059	11
50	9.62323	9.95786	9.63924	9.95427	9.65456	9.95052	10
51	62350	95780	63950	95421	65481	95046	9
52	62377	95775	63976	95415	65506	95039	8
53	62105	95769	64002	95409	65531	95033	7
54	62432	95763	64028	95403	65556	95027	6
55	62459	95757	64054	95397	65580	95020	5
56	62486	95751	64080	95391	65605	95014	4
57	62513	95745	64106	95384	65630	95007	3
58	62541	95739	64132	95378	65655	95001	2
59	62568	95733	64158	95372	65680	94995	1
60	62595	95728	64184	95366	65705	949 8	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	65°		64°		63°		

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	27°		28°		29°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	9.65705	9.94988	9.67161	9.94593	9.68557	9.94182	60
1	65729	94982	67185	94587	68580	94175	59
2	65754	94975	67208	94580	68603	94168	58
3	65779	94969	67232	94573	68625	94161	57
4	65804	94962	67256	94567	68648	94154	56
5	65828	94956	67280	94560	68671	94147	55
6	65853	94949	67303	94553	68694	94140	54
7	65878	94943	67327	94546	68716	94133	53
8	65902	94936	67350	94540	68739	94126	52
9	65927	94930	67374	94533	68762	94119	51
10	9.65952	9.94923	9.67398	9.94526	9.68784	9.94112	50
11	65976	94917	67421	94519	68807	94105	49
12	66001	94911	67445	94513	68829	94098	48
13	66025	94904	67468	94506	68852	94090	47
14	66050	94898	67492	94499	68875	94083	46
15	66075	94891	67515	94492	68897	94076	45
16	66099	94885	67539	94485	68920	94069	44
17	66124	94878	67562	94479	68942	94062	43
18	66148	94871	67586	94472	68965	94055	42
19	66173	94865	67609	94465	68987	94048	41
20	9.66197	9.94858	9.67633	9.94458	9.69010	9.94041	40
21	66221	94852	67656	94451	69032	94034	39
22	66246	94845	67680	94445	69055	94027	38
23	66270	94839	67703	94438	69077	94020	37
24	66295	94832	67726	94431	69100	94012	36
25	66319	94826	67750	94424	69122	94005	35
26	66343	94819	67773	94417	69144	93998	34
27	66368	94813	67796	94410	69167	93991	33
28	66392	94806	67820	94404	69189	93984	32
29	66416	94799	67843	94397	69212	93977	31
30	9.66441	9.94793	9.67866	9.94390	9.69234	9.93970	30
31	66465	94786	67890	94383	69256	93963	29
32	66489	94780	67913	94376	69279	93955	28
33	66513	94773	67936	94369	69301	93948	27
34	66537	94767	67959	94362	69323	93941	26
35	66562	94760	67982	94355	69345	93934	25
36	66586	94753	68006	94349	69368	93927	24
37	66610	94747	68029	94342	69390	93920	23
38	66634	94740	68052	94335	69412	93912	22
39	66658	94734	68075	94328	69434	93905	21
40	9.66682	9.94727	9.68098	9.94321	9.69456	9.93898	20
41	66706	94720	68121	94314	69479	93891	19
42	66731	94714	68144	94307	69501	93884	18
43	66755	94707	68167	94300	69523	93876	17
44	66779	94700	68190	94293	69545	93869	16
45	66803	94694	68213	94286	69567	93862	15
46	66827	94687	68237	94279	69589	93855	14
47	66851	94680	68260	94273	69611	93847	13
48	66875	94674	68283	94266	69633	93840	12
49	66899	94667	68305	94259	69655	93833	11
50	9.66922	9.94660	9.68328	9.94252	9.69677	9.93826	10
51	66946	94654	68351	94245	69699	93819	9
52	66970	94647	68374	94238	69721	93811	8
53	66994	94640	68397	94231	69743	93804	7
54	67018	94634	68420	94224	69765	93797	6
55	67042	94627	68443	94217	69787	93789	5
56	67066	94620	68466	94210	69809	93782	4
57	67090	94614	68489	94203	69831	93775	3
58	67113	94607	68512	94196	69853	93768	2
59	67137	94600	68534	94189	69875	93760	1
60	67161	94593	68557	94182	69897	93753	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	62°		61°		60°		

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	30°		31°		32°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	9.69897	9.93753	9.71184	9.93307	9.72421	9.92842	60
1	69919	93746	71205	93299	72441	92834	59
2	69941	93738	71226	93291	72461	92826	58
3	69963	93731	71247	93284	72482	92818	57
4	69984	93724	71268	93276	72502	92810	56
5	70006	93717	71289	93269	72522	92803	55
6	70028	93709	71310	93261	72542	92795	54
7	70050	93702	71331	93253	72562	92787	53
8	70072	93695	71352	93246	72582	92779	52
9	70093	93687	71373	93238	72602	92771	51
10	9.70115	9.93680	9.71393	9.93230	9.72622	9.92763	50
11	70137	93673	71414	93223	72643	92755	49
12	70159	93665	71435	93215	72663	92747	48
13	70180	93658	71456	93207	72683	92739	47
14	70202	93650	71477	93200	72703	92731	46
15	70224	93643	71498	93192	72723	92723	45
16	70245	93636	71519	93184	72743	92715	44
17	70267	93628	71539	93177	72763	92707	43
18	70288	93621	71560	93169	72783	92699	42
19	70310	93614	71581	93161	72803	92691	41
20	9.70332	9.93606	9.71602	9.93154	9.72823	9.92683	40
21	70353	93599	71622	93146	72843	92675	39
22	70375	93591	71643	93138	72863	92667	38
23	70396	93584	71664	93131	72883	92659	37
24	70418	93577	71685	93123	72902	92651	36
25	70439	93569	71705	93115	72922	92643	35
26	70461	93562	71726	93108	72942	92635	34
27	70482	93554	71747	93100	72962	92627	33
28	70504	93547	71767	93092	72982	92619	32
29	70525	93539	71788	93084	73002	92611	31
30	9.70547	9.93532	9.71809	9.93077	9.73022	9.92603	30
31	70568	93525	71829	93069	73041	92595	29
32	70590	93517	71850	93061	73061	92587	28
33	70611	93510	71870	93053	73081	92579	27
34	70633	93502	71891	93046	73101	92571	26
35	70654	93495	71911	93038	73121	92563	25
36	70675	93487	71932	93030	73140	92555	24
37	70697	93480	71952	93022	73160	92546	23
38	70718	93472	71973	93014	73180	92538	22
39	70739	93465	71994	93007	73200	92530	21
40	9.70761	9.93457	9.72014	9.92999	9.73219	9.92522	20
41	70782	93450	72034	92991	73239	92514	19
42	70803	93442	72055	92983	73259	92506	18
43	70824	93435	72075	92976	73278	92498	17
44	70846	93427	72096	92968	73298	92490	16
45	70867	93420	72116	92960	73318	92482	15
46	70888	93412	72137	92952	73337	92473	14
47	70909	93405	72157	92944	73357	92465	13
48	70931	93397	72177	92936	73377	92457	12
49	70952	93390	72198	92929	73396	92449	11
50	9.70973	9.93382	9.72218	9.92921	9.73116	9.92441	10
51	70994	93375	72238	92913	73435	92433	9
52	71015	93367	72259	92905	73455	92425	8
53	71036	93360	72279	92897	73474	92416	7
54	71058	93352	72299	92889	73494	92408	6
55	71079	93344	72320	92881	73513	92400	5
56	71100	93337	72340	92874	73533	92392	4
57	71121	93329	72360	92866	73552	92384	3
58	71142	93322	72381	92858	73572	92376	2
59	71163	93314	72401	92850	73591	92367	1
60	71184	93307	72421	92842	73611	92359	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	59°		58°		57°		

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	33°		34°		35°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	9.73611	9.92359	9.74756	9.91857	9.75859	9.91336	60
1	73630	92351	74775	91849	75877	91328	59
2	73650	92343	74794	91840	75895	91319	58
3	73669	92335	74812	91832	75913	91310	57
4	73689	92326	74831	91823	75931	91301	56
5	73708	92318	74850	91815	75949	91292	55
6	73727	92310	74868	91806	75967	91283	54
7	73747	92302	74887	91798	75985	91274	53
8	73766	92293	74906	91789	76003	91266	52
9	73785	92285	74924	91781	76021	91257	51
10	9.73805	9.92277	9.74943	9.91772	9.76039	9.91248	50
11	73824	92269	74961	91763	76057	91239	49
12	73843	92260	74980	91755	76075	91230	48
13	73863	92252	74999	91746	76093	91221	47
14	73882	92244	75017	91738	76111	91212	46
15	73901	92235	75036	91729	76129	91203	45
16	73921	92227	75054	91720	76146	91194	44
17	73940	92219	75073	91712	76164	91185	43
18	73959	92211	75091	91703	76182	91176	42
19	73978	92202	75110	91695	76200	91167	41
20	9.73997	9.92194	9.75128	9.91686	9.76218	9.91158	40
21	74017	92186	75147	91677	76236	91149	39
22	74036	92177	75165	91669	76253	91141	38
23	74055	92169	75184	91660	76271	91132	37
24	74074	92161	75202	91651	76289	91123	36
25	74093	92152	75221	91643	76307	91114	35
26	74113	92144	75239	91634	76324	91105	34
27	74132	92136	75258	91625	76342	91096	33
28	74151	92127	75276	91617	76360	91087	32
29	74170	92119	75294	91608	76378	91078	31
30	9.74189	9.92111	9.75313	9.91599	9.76395	9.91069	30
31	74208	92102	75331	91591	76413	91060	29
32	74227	92094	75350	91582	76431	91051	28
33	74246	92086	75368	91573	76448	91042	27
34	74265	92077	75386	91565	76466	91033	26
35	74284	92069	75405	91556	76484	91023	25
36	74303	92060	75423	91547	76501	91014	24
37	74322	92052	75441	91538	76519	91005	23
38	74341	92044	75459	91530	76537	90996	22
39	74360	92035	75478	91521	76554	90987	21
40	9.74379	9.92027	9.75496	9.91512	9.76572	9.90978	20
41	74398	92018	75514	91504	76590	90969	19
42	74417	92010	75533	91495	76607	90960	18
43	74436	92002	75551	91486	76625	90951	17
44	74455	91993	75569	91477	76642	90942	16
45	74474	91985	75587	91469	76660	90933	15
46	74493	91976	75605	91460	76677	90924	14
47	74512	91968	75624	91451	76695	90915	13
48	74531	91959	75642	91442	76712	90906	12
49	74549	91951	75660	91433	76730	90896	11
50	9.74568	9.91942	9.75678	9.91425	9.76747	9.90887	10
51	74587	91934	75696	91416	76765	90878	9
52	74606	91925	75714	91407	76782	90869	8
53	74625	91917	75733	91398	76800	90860	7
54	74644	91908	75751	91389	76817	90851	6
55	74662	91900	75769	91381	76835	90842	5
56	74681	91891	75787	91372	76852	90832	4
57	74700	91883	75805	91363	76870	90823	3
58	74719	91874	75823	91354	76887	90814	2
59	74737	91866	75841	91345	76904	90805	1
60	74756	91857	75859	91336	76922	90796	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	56°		55°		54°		

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	36°		37°		38°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	9.76922	9.90796	9.77946	9.90235	9.78934	9.89653	60
1	76939	90787	77963	90225	78950	89643	59
2	76957	90777	77980	90216	78967	89633	58
3	76974	90768	77997	90206	78983	89624	57
4	76991	90759	78013	90197	78999	89614	56
5	77009	90750	78030	90187	79015	89604	55
6	77026	90741	78047	90178	79031	89594	54
7	77043	90731	78063	90168	79047	89584	53
8	77061	90722	78080	90159	79063	89574	52
9	77078	90713	78097	90149	79079	89564	51
10	9.77095	9.90704	9.78113	9.90139	9.79095	9.89554	50
11	77112	90694	78130	90130	79111	89544	49
12	77130	90685	78147	90120	79128	89534	48
13	77147	90676	78163	90111	79144	89524	47
14	77164	90667	78180	90101	79160	89514	46
15	77181	90657	78197	90091	79176	89501	45
16	77199	90648	78213	90082	79192	89495	44
17	77216	90639	78230	90072	79208	89485	43
18	77233	90630	78246	90063	79224	89475	42
19	77250	90620	78263	90053	79240	89465	41
20	9.77268	9.90611	9.78280	9.90043	9.79256	9.89455	40
21	77285	90602	78296	90034	79272	89445	39
22	77302	90592	78313	90024	79288	89435	38
23	77319	90583	78329	90014	79304	89425	37
24	77336	90574	78346	90005	79319	89415	36
25	77353	90565	78362	89995	79335	89405	35
26	77370	90555	78379	89985	79351	89395	34
27	77387	90546	78395	89976	79367	89385	33
28	77405	90537	78412	89966	79383	89375	32
29	77422	90527	78428	89956	79399	89364	31
30	9.77439	9.90518	9.78445	9.89947	9.79415	9.89354	30
31	77456	90509	78461	89937	79431	89344	29
32	77473	90499	78478	89927	79447	89334	28
33	77490	90490	78494	89918	79463	89324	27
34	77507	90480	78510	89908	79478	89314	26
35	77524	90471	78527	89898	79494	89304	25
36	77541	90462	78543	89888	79510	89294	24
37	77558	90452	78560	89879	79526	89284	23
38	77575	90443	78576	89869	79542	89274	22
39	77592	90434	78592	89859	79558	89264	21
40	9.77609	9.90424	9.78609	9.89849	9.79573	9.89254	20
41	77626	90415	78625	89840	79589	89244	19
42	77643	90405	78642	89830	79605	89233	18
43	77660	90396	78658	89820	79621	89223	17
44	77677	90386	78674	89810	79636	89213	16
45	77694	90377	78691	89801	79652	89203	15
46	77711	90368	78707	89791	79668	89193	14
47	77728	90358	78723	89781	79684	89183	13
48	77744	90349	78739	89771	79699	89173	12
49	77761	90339	78756	89761	79715	89162	11
50	9.77778	9.90330	9.78772	9.89752	9.79731	9.89152	10
51	77795	90320	78788	89742	79746	89142	9
52	77812	90311	78805	89732	79762	89132	8
53	77829	90301	78821	89722	79778	89122	7
54	77846	90292	78837	89712	79793	89112	6
55	77862	90282	78853	89702	79809	89101	5
56	77879	90273	78869	89693	79825	89091	4
57	77896	90263	78886	89683	79810	89081	3
58	77913	90254	78902	89673	79856	89071	2
59	77930	90244	78918	89663	79872	89060	1
60	77946	90235	78934	89653	79887	89050	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	53°		52°		51°		

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	39° Sine	39° Cosine	40° Sine	40° Cosine	41° Sine	41° Cosine	′
0	9.79887	9.89050	9.80807	9.88425	9.81694	9.87778	60
1	79903	89040	80822	88415	81709	87767	59
2	79918	89030	80837	88404	81723	87756	58
3	79934	89020	80852	88394	81738	87745	57
4	79950	89009	80867	88383	81752	87734	56
5	79965	88999	80882	88372	81767	87723	55
6	79981	88989	80897	88362	81781	87712	54
7	79996	88978	80912	88351	81796	87701	53
8	80012	88968	80927	88340	81810	87690	52
9	80027	88958	80942	88330	81825	87679	51
10	9.80043	9.88948	9.80957	9.88319	9.81839	9.87668	50
11	80058	88937	80972	88308	81854	87657	49
12	80074	88927	80987	88298	81868	87646	48
13	80089	88917	81002	88287	81882	87635	47
14	80105	88906	81017	88276	81897	87624	46
15	80120	88896	81032	88266	81911	87613	45
16	80136	88886	81047	88255	81926	87601	44
17	80151	88875	81061	88244	81940	87590	43
18	80166	88865	81076	88234	81955	87579	42
19	80182	88855	81091	88223	81969	87568	41
20	9.80197	9.88844	9.81106	9.88212	9.81983	9.87557	40
21	80213	88834	81121	88201	81998	87546	39
22	80228	88824	81136	88191	82012	87535	38
23	80244	88813	81151	88180	82026	87524	37
24	80259	88803	81166	88169	82041	87513	36
25	80274	88793	81180	88158	82055	87501	35
26	80290	88782	81195	88148	82069	87490	34
27	80305	88772	81210	88137	82084	87479	33
28	80320	88761	81225	88126	82098	87468	32
29	80336	88751	81240	88115	82112	87457	31
30	9.80351	9.88741	9.81254	9.88105	9.82126	9.87446	30
31	80366	88730	81269	88094	82141	87434	29
32	80382	88720	81284	88083	82155	87423	28
33	80397	88709	81299	88072	82169	87412	27
34	80412	88699	81314	88061	82184	87401	26
35	80428	88688	81328	88051	82198	87390	25
36	80443	88678	81343	88040	82212	87378	24
37	80458	88668	81358	88029	82226	87367	23
38	80473	88657	81372	88018	82240	87356	22
39	80489	88647	81387	88007	82255	87345	21
40	9.80504	9.88636	9.81402	9.87996	9.82269	9.87334	20
41	80519	88626	81417	87985	82283	87322	19
42	80534	88615	81431	87975	82297	87311	18
43	80550	88605	81446	87964	82311	87300	17
44	80565	88594	81461	87953	82326	87288	16
45	80580	88584	81475	87942	82340	87277	15
46	80595	88573	81490	87931	82354	87266	14
47	80610	88563	81505	87920	82368	87255	13
48	80625	88552	81519	87909	82382	87243	12
49	80641	88542	81534	87898	82396	87232	11
50	9.80656	9.88531	9.81549	9.87887	9.82410	9.87221	10
51	80671	88521	81563	87877	82424	87209	9
52	80686	88510	81578	87866	82439	87198	8
53	80701	88499	81592	87855	82453	87187	7
54	80716	88489	81607	87844	82467	87175	6
55	80731	88478	81622	87833	82481	87164	5
56	80746	88468	81636	87822	82495	87153	4
57	80762	88457	81651	87811	82509	87141	3
58	80777	88447	81665	87800	82523	87130	2
59	80792	88436	81680	87789	82537	87119	1
60	80807	88425	81694	87778	82551	87107	0
′	50° Cosine	50° Sine	49° Cosine	49° Sine	48° Cosine	48° Sine	′

TABLE II.—LOGARITHMIC SINES AND COSINES.

′	42°		43°		44°		′
	Sine	Cosine	Sine	Cosine	Sine	Cosine	
0	9.82551	9.87107	9.83378	9.86413	9.84177	9.85693	60
1	82565	87096	83392	86401	84190	85681	59
2	82579	87085	83405	86389	84203	85669	58
3	82593	87073	83419	86377	84216	85657	57
4	82607	87062	83432	86366	84229	85645	56
5	82621	87050	83446	86354	84242	85632	55
6	82635	87039	83459	86342	84255	85620	54
7	82649	87028	83473	86330	84269	85608	53
8	82663	87016	83486	86318	84282	85596	52
9	82677	87005	83500	86306	84295	85583	51
10	9.82691	9.86993	9.83513	9.86295	9.84308	9.85571	50
11	82705	86982	83527	86283	84321	85559	49
12	82719	86970	83540	86271	84334	85547	48
13	82733	86959	83554	86259	84347	85534	47
14	82747	86947	83567	86247	84360	85522	46
15	82761	86936	83581	86235	84373	85510	45
16	82775	86924	83594	86223	84385	85497	44
17	82788	86913	83608	86211	84398	85485	43
18	82802	86902	83621	86200	84411	85473	42
19	82816	86890	83634	86188	84424	85460	41
20	9.82830	9.86879	9.83648	9.86176	9.84437	9.85448	40
21	82844	86867	83661	86164	84450	85436	39
22	82858	86855	83674	86152	84463	85423	38
23	82872	86844	83688	86140	84476	85411	37
24	82885	86832	83701	86128	84489	85399	36
25	82899	86821	83715	86116	84502	85386	35
26	82913	86809	83728	86104	84515	85374	34
27	82927	86798	83741	86092	84528	85361	33
28	82941	86786	83755	86080	84540	85349	32
29	82955	86775	83768	86068	84553	85337	31
30	9.82968	9.86763	9.83781	9.86056	9.84566	9.85324	30
31	82982	86752	83795	86044	84579	85312	29
32	82996	86740	83808	86032	84592	85299	28
33	83010	86728	83821	86020	84605	85287	27
34	83023	86717	83834	86008	84618	85274	26
35	83037	86705	83848	85996	84630	85262	25
36	83051	86694	83861	85984	84643	85250	24
37	83065	86682	83874	85972	84656	85237	23
38	83078	86670	83887	85960	84669	85225	22
39	83092	86659	83901	85948	84682	85212	21
40	9.83106	9.86647	9.83914	9.85936	9.84694	9.85200	20
41	83120	86635	83927	85924	84707	85187	19
42	83133	86624	83940	85912	84720	85175	18
43	83147	86612	83954	85900	84733	85162	17
44	83161	86600	83967	85888	84745	85150	16
45	83174	86589	83980	85876	84758	85137	15
46	83188	86577	83993	85864	84771	85125	14
47	83202	86565	84006	85851	84784	85112	13
48	83215	86554	84020	85839	84796	85100	12
49	83229	86542	84033	85827	84809	85087	11
50	9.83242	9.86530	9.84046	9.85815	9.84822	9.85074	10
51	83256	86518	84059	85803	84835	85062	9
52	83270	86507	84072	85791	84847	85049	8
53	83283	86495	84085	85779	84860	85037	7
54	83297	86483	84098	85766	84873	85024	6
55	83310	86472	84112	85754	84885	85012	5
56	83324	86460	84125	85742	84898	84999	4
57	83338	86448	84138	85730	84911	84986	3
58	83351	86436	84151	85718	84923	84974	2
59	83365	86425	84164	85706	84936	84961	1
60	83378	86413	84177	85693	84949	84949	0
′	Cosine	Sine	Cosine	Sine	Cosine	Sine	′
	47°		46°		45°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	0°		1°		2°		′
	Tan	Cotan	Tan	Cotan	Tan	Cotan	
0	− ∞	∞	8.24192	11.75808	8.54308	11.45692	60
1	6.46373	13.53627	24910	75090	54669	45331	59
2	76476	23524	25616	74384	55027	44973	58
3	94085	05915	26312	73688	55382	44618	57
4	7.06579	12.93421	26996	73004	55734	44266	56
5	16270	83730	27669	72331	56083	43917	55
6	24188	75812	28332	71668	56429	43571	54
7	30882	69118	28986	71014	56773	43227	53
8	36682	63318	29629	70371	57114	42886	52
9	41797	58203	30263	69737	57452	42548	51
10	7.46373	12.53627	8.30888	11.69112	8.57788	11.42212	50
11	50512	49488	31505	68495	58121	41879	49
12	54291	45709	32112	67888	58451	41549	48
13	57767	42233	32711	67289	58779	41221	47
14	60986	39014	33302	66698	59105	40895	46
15	63982	36018	33886	66114	59428	40572	45
16	66785	33215	34461	65539	59749	40251	44
17	69418	30582	35029	64971	60068	39932	43
18	71900	28100	35590	64410	60384	39616	42
19	74248	25752	36143	63857	60698	39302	41
20	7.76476	12.23524	8.36689	11.63311	8.61009	11.38991	40
21	78595	21405	37229	62771	61319	38681	39
22	80615	19385	37762	62238	61626	38374	38
23	82546	17454	38289	61711	61931	38069	37
24	84394	15606	38809	61191	62234	37766	36
25	86167	13833	39323	60677	62535	37465	35
26	87871	12129	39832	60168	62834	37166	34
27	89510	10490	40334	59666	63131	36869	33
28	91089	08911	40830	59170	63426	36574	32
29	92613	07387	41321	58679	63718	36282	31
30	7.94086	12.05914	8.41807	11.58193	8.64009	11.35991	30
31	95510	04490	42287	57713	64298	35702	29
32	96889	03111	42762	57238	64585	35415	28
33	98225	01775	43232	56768	64870	35130	27
34	99522	00478	43696	56304	65154	34846	26
35	8.00781	11.99219	44156	55844	65435	34565	25
36	02004	97996	44611	55389	65715	34285	24
37	03194	96806	45061	54939	65993	34007	23
38	04353	95647	45507	54493	66269	33731	22
39	05481	94519	45948	54052	66543	33457	21
40	8.06581	11.93419	8.46385	11.53615	8.66816	11.33184	20
41	07653	92347	46817	53183	67087	32913	19
42	08700	91300	47245	52755	67356	32644	18
43	09722	90278	47669	52331	67624	32376	17
44	10720	89280	48089	51911	67890	32110	16
45	11696	88304	48505	51495	68154	31846	15
46	12651	87349	48917	51083	68417	31583	14
47	13585	86415	49325	50675	68678	31322	13
48	14500	85500	49729	50271	68938	31062	12
49	15395	84605	50130	49870	69196	30804	11
50	8.16273	11.83727	8.50527	11.49473	8.69453	11.30547	10
51	17133	82867	50920	49080	69708	30292	9
52	17976	82024	51310	48690	69962	30038	8
53	18804	81196	51696	48304	70214	29786	7
54	19616	80384	52079	47921	70465	29535	6
55	20413	79587	52459	47541	70714	29286	5
56	21195	78805	52835	47165	70962	29038	4
57	21961	78036	53208	46792	71208	28792	3
58	22720	77280	53578	46422	71453	28547	2
59	23462	76538	53945	46055	71697	28303	1
60	24192	75808	54308	45692	71940	28060	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	89°		88°		87°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	3°		4°		5°		′
	Tan	Cotan	Tan	Cotan	Tan	Cotan	
0	8.71940	11.28060	8.84464	11.15536	8.94195	11.05805	60
1	72181	27819	84616	15384	94340	05660	59
2	72420	27580	84826	15174	94485	05515	58
3	72659	27341	85006	14994	94630	05370	57
4	72896	27104	85185	14815	94773	05227	56
5	73132	26868	85363	14637	94917	05083	55
6	73366	26634	85540	14460	95060	04940	54
7	73600	26400	85717	14283	95202	04798	53
8	73832	26168	85893	14107	95344	04656	52
9	74063	25937	86069	13931	95486	04514	51
10	8.74292	11.25708	8.86243	11.13757	8.95627	11.04373	50
11	74521	25479	86417	13583	95767	04233	49
12	74748	25252	86591	13109	95908	04092	48
13	74974	25026	86763	13237	96047	03953	47
14	75199	24801	86935	13065	96187	03813	46
15	75423	24577	87106	12894	96325	03675	45
16	75645	24355	87277	12723	96464	03536	44
17	75867	24133	87447	12553	96602	03398	43
18	76087	23913	87616	12384	96739	03261	42
19	76306	23694	87785	12215	96877	03123	41
20	8 76525	11.23475	8.87953	11 12047	8.97013	11.02987	40
21	76742	23258	88120	11880	97150	02850	39
22	76958	23042	88287	11713	97285	02715	38
23	77173	22827	88453	11547	97421	02579	37
24	77387	22613	88618	11382	97556	02444	36
25	77600	22400	88783	11217	97691	02309	35
26	77811	22189	88948	11052	97825	02175	34
27	78022	21978	89111	10889	97959	02041	33
28	78232	21768	89274	10726	98092	01908	32
29	78441	21559	89437	10563	98225	01775	31
30	8.78649	11.21351	8.89598	11.10402	8.98358	11.01642	30
31	78855	21145	89760	10240	98490	01510	29
32	79061	20939	89920	10080	98622	01378	28
33	79266	20734	90080	09920	98753	01247	27
34	79470	20530	90240	09760	98881	01116	26
35	79673	20327	90399	09601	99015	00985	25
36	79875	20125	90557	09443	99145	00855	24
37	80076	19924	90715	09285	99275	00725	23
38	80277	19723	90872	09128	99405	00595	22
39	80476	19524	91029	08971	99534	00466	21
40	8.80674	11.19326	8.91185	11.08815	8.99662	11.00338	20
41	80872	19128	91340	08660	99791	00209	19
42	81068	18932	91495	08505	99919	00081	18
43	81264	18736	91650	08350	9.00046	10.99954	17
44	81459	18541	91803	08197	00174	99826	16
45	81653	18347	91957	08043	00301	99699	15
46	81846	18154	92110	07890	00427	99573	14
47	82038	17962	92262	07738	00553	99447	13
48	82230	17770	92414	07586	00679	99321	12
49	82420	17580	92565	07435	00805	99195	11
50	8.82610	11.17390	8.92716	11.07284	9.00930	10.99070	10
51	82799	17201	92866	07134	01055	98945	9
52	82987	17013	93016	06984	01179	98821	8
53	83175	16825	93165	06835	01303	98697	7
54	83361	16639	93313	06687	01427	98573	6
55	83547	16453	93462	06538	01550	98450	5
56	83732	16268	93609	06391	01673	98327	4
57	83916	16084	93756	06244	01796	98204	3
58	84100	15900	93903	06097	01918	98082	2
59	84282	15718	94049	05951	02040	97960	1
60	84464	15536	94195	05805	02162	97838	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	86°		85°		84°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	6°		7°		8°		′
	Tan	Cotan	Tan	Cotan	Tan	Cotan	
0	9.02162	10 97838	9.08914	10.91086	9.14780	10.85220	60
1	02283	97717	09019	90981	14872	85128	59
2	02404	97596	09123	90877	14963	85037	58
3	02525	97475	09227	90773	15054	84946	57
4	02645	97355	09330	90670	15145	84855	56
5	02766	97234	09434	90566	15236	84764	55
6	02885	97115	09537	90463	15327	84673	54
7	03005	96995	09640	90360	15417	84583	53
8	03124	96876	09742	90258	15508	84492	52
9	03242	96758	09845	90155	15598	84402	51
10	9.03361	10.96639	9.09947	10.90053	9.15688	10.84312	50
11	03479	96521	10049	89951	15777	84223	49
12	03597	96403	10150	89850	15867	84133	48
13	03714	96286	10252	89748	15956	84044	47
14	03832	96168	10353	89647	16046	83954	46
15	03948	96052	10454	89546	16135	83865	45
16	04065	95935	10555	89445	16224	83776	44
17	04181	95819	10656	89344	16312	83688	43
18	04297	95703	10756	89244	16401	83599	42
19	04413	95587	10856	89144	16489	83511	41
20	9.04528	10.95472	9.10956	10.89044	9.16577	10.83423	40
21	04643	95357	11056	88944	16665	83335	39
22	04758	95242	11155	88845	16753	83247	38
23	04873	95127	11254	88746	16841	83159	37
24	04987	95013	11353	88647	16928	83072	36
25	05101	94899	11452	88548	17016	82984	35
26	05214	94786	11551	88449	17103	82897	34
27	05328	94672	11649	88351	17190	82810	33
28	05441	94559	11747	88253	17277	82723	32
29	05553	94447	11845	88155	17363	82637	31
30	9.05666	10.94334	9.11943	10.88057	9.17450	10.82550	30
31	05778	94222	12040	87960	17536	82464	29
32	05890	94110	12138	87862	17622	82378	28
33	06002	93998	12235	87765	17708	82292	27
34	06113	93887	12332	87668	17794	82206	26
35	06224	93776	12428	87572	17880	82120	25
36	06335	93665	12525	87475	17965	82035	24
37	06445	93555	12621	87379	18051	81949	23
38	06556	93444	12717	87283	18136	81864	22
39	06666	93334	12813	87187	18221	81779	21
40	9.06775	10.93225	9.12909	10.87091	9.18306	10.81694	20
41	06885	93115	13004	86996	18391	81609	19
42	06994	93006	13099	86901	18475	81525	18
43	07103	92897	13194	86806	18560	81440	17
44	07211	92789	13289	86711	18644	81356	16
45	07320	92680	13384	86616	18728	81272	15
46	07428	92572	13478	86522	18812	81188	14
47	07536	92464	13573	86427	18896	81104	13
48	07643	92357	13667	86333	18979	81021	12
49	07751	92249	13761	86239	19063	80937	11
50	9.07858	10.92142	9.13854	10.86146	9.19146	10.80854	10
51	07964	92036	13948	86052	19229	80771	9
52	08071	91929	14041	85959	19312	80688	8
53	08177	91823	14134	85866	19395	80605	7
54	08283	91717	14227	85773	19478	80522	6
55	08389	91611	14320	85680	19561	80439	5
56	08495	91505	14412	85588	19643	80357	4
57	08600	91400	14504	85496	19725	80275	3
58	08705	91295	14597	85403	19807	80193	2
59	08810	91190	14688	85312	19889	80111	1
60	08914	91086	14780	85220	19971	80029	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	83°		82°		81°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	9°		10°		11°		′
	Tan	Cotan	Tan	Cotan	Tan	Cotan	
0	9.19971	10.80029	9.24632	10.75368	9.28865	10.71135	60
1	20053	79947	24706	75294	28933	71067	59
2	20134	79866	24779	75221	29000	71000	58
3	20216	79784	24853	75147	29067	70933	57
4	20297	79703	24926	75074	29134	70866	56
5	20378	79622	25000	75000	29201	70799	55
6	20459	79541	25073	74927	29268	70732	54
7	20540	79460	25146	74854	29335	70665	53
8	20621	79379	25219	74781	29402	70598	52
9	20701	79299	25292	74708	29468	70532	51
10	9.20782	10.79218	9.25365	10.74635	9.29535	10.70465	50
11	20862	79138	25437	74563	29601	70399	49
12	20942	79058	25510	74490	29668	70332	48
13	21022	78978	25582	74418	29734	70266	47
14	21102	78898	25655	74345	29800	70200	46
15	21182	78818	25727	74273	29866	70134	45
16	21261	78739	25799	74201	29932	70068	44
17	21341	78659	25871	74129	29998	70002	43
18	21420	78580	25943	74057	30064	69936	42
19	21499	78501	26015	73985	30130	69870	41
20	9.21578	10.78422	9.26086	10.73914	9.30195	10.69805	40
21	21657	78343	26158	73842	30261	69739	39
22	21736	78264	26229	73771	30326	69674	38
23	21814	78186	26301	73699	30391	69609	37
24	21893	78107	26372	73628	30457	69543	36
25	21971	78029	26443	73557	30522	69478	35
26	22049	77951	26514	73486	30587	69413	34
27	22127	77873	26585	73415	30652	69348	33
28	22205	77795	26655	73345	30717	69283	32
29	22283	77717	26726	73274	30782	69218	31
30	9.22361	10.77639	9.26797	10.73203	9.30846	10.69154	30
31	22438	77562	26867	73133	30911	69089	29
32	22516	77484	26937	73063	30975	69025	28
33	22593	77407	27008	72992	31040	68960	27
34	22670	77330	27078	72922	31104	68896	26
35	22747	77253	27148	72852	31168	68832	25
36	22824	77176	27218	72782	31233	68767	24
37	22901	77099	27288	72712	31297	68703	23
38	22977	77023	27357	72643	31361	68639	22
39	23054	76946	27427	72573	31425	68575	21
40	9.23130	10.76870	9.27496	10.72504	9.31489	10.68511	20
41	23206	76794	27566	72434	31552	68448	19
42	23283	76717	27635	72365	31616	68384	18
43	23359	76641	27704	72296	31679	68321	17
44	23435	76565	27773	72227	31743	68257	16
45	23510	76490	27842	72158	31806	68194	15
46	23586	76414	27911	72089	31870	68130	14
47	23661	76339	27980	72020	31933	68067	13
48	23737	76263	28049	71951	31996	68004	12
49	23812	76188	28117	71883	32059	67941	11
50	9.23887	10.76113	9.28186	10.71814	9.32122	10.67878	10
51	23962	76038	28254	71746	32185	67815	9
52	24037	75963	28323	71677	32248	67752	8
53	24112	75888	28391	71609	32311	67689	7
54	24186	75814	28459	71541	32373	67627	6
55	24261	75739	28527	71473	32436	67564	5
56	24335	75665	28595	71405	32498	67502	4
57	24410	75590	28662	71338	32561	67439	3
58	24484	75516	28730	71270	32623	67377	2
59	24558	75442	28798	71202	32685	67315	1
60	24632	75368	28865	71135	32747	67253	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	80°		79°		78°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	12°		13°		14°		′
	Tan	Cotan	Tan	Cotan	Tan	Cotan	
0	9.32747	10.67253	9.36336	10.63664	9.39677	10.60323	60
1	32810	67190	36394	63606	39731	60269	59
2	32872	67128	36452	63548	39785	60215	58
3	32933	67067	36509	63491	39838	60162	57
4	32995	67005	36566	63434	39892	60108	56
5	33057	66943	36624	63376	39945	60055	55
6	33119	66881	36681	63319	39999	60001	54
7	33180	66820	36738	63262	40052	59948	53
8	33242	66758	36795	63205	40106	59894	52
9	33303	66697	36852	63148	40159	59841	51
10	9.33365	10.66635	9.36909	10.63091	9.40212	10.59788	50
11	33426	66574	36966	63034	40266	59734	49
12	33487	66513	37023	62977	40319	59681	48
13	33548	66452	37080	62920	40372	59628	47
14	33609	66391	37137	62863	40425	59575	46
15	33670	66330	37193	62807	40478	59522	45
16	33731	66269	37250	62750	40531	59469	44
17	33792	66208	37306	62694	40584	59416	43
18	33853	66147	37363	62637	40636	59364	42
19	33913	66087	37419	62581	40689	59311	41
20	9.33974	10.66026	9.37476	10.62524	9.40742	10.59258	40
21	34034	65966	37532	62468	40795	59205	39
22	34095	65905	37588	62412	40847	59153	38
23	34155	65845	37644	62356	40900	59100	37
24	34215	65785	37700	62300	40952	59048	36
25	34276	65724	37756	62244	41005	58995	35
26	34336	65664	37812	62188	41057	58943	34
27	34396	65604	37868	62132	41109	58891	33
28	34456	65544	37924	62076	41161	58839	32
29	34516	65484	37980	62020	41214	58786	31
30	9.34576	10.65424	9.38035	10.61965	9.41266	10.58734	30
31	34635	65365	38091	61909	41318	58682	29
32	34695	65305	38147	61853	41370	58630	28
33	34755	65245	38202	61798	41422	58578	27
34	34814	65186	38257	61743	41474	58526	26
35	34874	65126	38313	61687	41526	58474	25
36	34933	65067	38368	61632	41578	58422	24
37	34992	65008	38423	61577	41629	58371	23
38	35051	64949	38479	61521	41681	58319	22
39	35111	64889	38534	61466	41733	58267	21
40	9.35170	10.64830	9.38589	10.61411	9.41784	10.58216	20
41	35229	64771	38644	61356	41836	58164	19
42	35288	64712	38699	61301	41887	58113	18
43	35347	64653	38754	61246	41939	58061	17
44	35405	64595	38808	61192	41990	58010	16
45	35464	64536	38863	61137	42041	57959	15
46	35523	64477	38918	61082	42093	57907	14
47	35581	64419	38972	61028	42144	57856	13
48	35640	64360	39027	60973	42195	57805	12
49	35698	64302	39082	60918	42246	57754	11
50	9.35757	10.64243	9.39136	10.60864	9.42297	10.57703	10
51	35815	64185	39190	60810	42348	57652	9
52	35873	64127	39245	60755	42399	57601	8
53	35931	64069	39299	60701	42450	57550	7
54	35989	64011	39353	60647	42501	57499	6
55	36047	63953	39407	60593	42552	57448	5
56	36105	63895	39461	60539	42603	57397	4
57	36163	63837	39515	60485	42653	57347	3
58	36221	63779	39569	60431	42704	57296	2
59	36279	63721	39623	60377	42755	57245	1
60	36336	63664	39677	60323	42805	57195	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	77°		76°		75°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	15°		16°		17°		′
	Tan	Cotan	Tan	Cotan	Tan	Cotan	
0	9.42805	10.57195	9.45750	10.54250	9.48584	10.51466	60
1	42856	57144	45797	54203	48579	51421	59
2	42906	57094	45845	54155	48624	51376	58
3	42957	57043	45892	54108	48669	51331	57
4	43007	56993	45940	54060	48714	51286	56
5	43057	56943	45987	54013	48759	51241	55
6	43108	56892	46035	53965	48804	51196	54
7	43158	56842	46082	53918	48849	51151	53
8	43208	56792	46130	53870	48894	51106	52
9	43258	56742	46177	53823	48939	51061	51
10	9.43308	10.56692	9.46221	10.53776	9.48984	10.51016	50
11	43358	56642	46271	53729	49029	50971	49
12	43408	56592	46319	53681	49073	50927	48
13	43458	56542	46366	53634	49118	50882	47
14	43508	56492	46413	53587	49163	50837	46
15	43558	56442	46460	53540	49207	50793	45
16	43607	56393	46507	53493	49252	50748	44
17	43657	56343	46554	53446	49296	50701	43
18	43707	56293	46601	53399	49341	50659	42
19	43756	56244	46648	53352	49385	50615	41
20	9 43806	10.56194	9.46694	10 53306	9.49430	10.50570	40
21	43855	56145	46741	53259	49474	50526	39
22	43905	56095	46788	53212	49519	50481	38
23	43954	56046	46835	53165	49563	50437	37
24	44004	55996	46881	53119	49607	50393	36
25	44053	55947	46928	53072	49652	50348	35
26	44102	55898	46975	53025	49696	50304	34
27	44151	55849	47021	52979	49740	50260	33
28	44201	55799	47068	52932	49784	50216	32
29	44250	55750	47114	52886	49828	50172	31
30	9.44299	10.55701	9.47160	10.52840	9.49872	10.50128	30
31	44348	55652	47207	52793	49916	50084	29
32	44397	55603	47253	52747	49960	50040	28
33	44446	55554	47299	52701	50004	49996	27
34	44495	55505	47346	52654	50048	49952	26
35	44544	55456	47392	52608	50092	49908	25
36	44592	55408	47438	52562	50136	49864	24
37	44641	55359	47484	52516	50180	49820	23
38	44690	55310	47530	52470	50223	49777	22
39	44738	55262	47576	52424	50267	49733	21
40	9.44787	10.55213	9.47622	10.52378	9.50311	10.49689	20
41	44836	55164	47668	52332	50355	49645	19
42	44884	55116	47714	52286	50398	49602	18
43	44933	55067	47760	52240	50442	49558	17
44	44981	55019	47806	52194	50485	49515	16
45	45029	54971	47852	52148	50529	49471	15
46	45078	54922	47897	52103	50572	49428	14
47	45126	54874	47943	52057	50616	49384	13
48	45174	54826	47989	52011	50659	49341	12
49	45222	54778	48035	51965	50703	49297	11
50	9.45271	10.54729	9.48080	10.51920	9.50746	10.49254	10
51	45319	54681	48126	51874	50789	49211	9
52	45367	54633	48171	51829	50833	49167	8
53	45415	54585	48217	51783	50876	49124	7
54	45463	54537	48262	51738	50919	49081	6
55	45511	54489	48307	5 693	50962	49038	5
56	45559	54441	48353	51647	51005	48995	4
57	45606	54394	48398	51602	51048	48952	3
58	45654	54346	48443	51557	51092	48908	2
59	45702	54298	48489	51511	51135	48865	1
60	45750	54250	48534	51466	51178	48822	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	74°		73°		72°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	18°		19°		20°		′
	Tan	Cotan	Tan	Cotan	Tan	Cotan	
0	9.51178	10 48822	9.53697	10.46303	9.56107	10.43893	60
1	51221	48779	53738	46262	56146	43854	59
2	51264	48736	53779	46221	56185	438.5	58
3	51306	48694	53820	46180	56224	43776	57
4	51349	48651	53861	46139	56264	43736	56
5	51392	48608	53902	46098	56303	43697	55
6	51435	48565	53943	46057	56342	43658	54
7	51478	48522	53984	46016	56381	43619	53
8	51520	48480	54025	45975	56420	43580	52
9	51563	48437	54065	45935	56459	43541	51
10	9.51606	10.48394	9.54106	10.45894	9.56498	10.43502	50
11	51648	48352	54147	45853	56537	43463	49
12	51691	48309	54187	45813	56576	43424	48
13	51734	48266	54228	45772	56615	43385	47
14	51776	48224	54269	45731	56654	43346	46
15	51819	48181	54309	45691	56693	43307	45
16	51861	48139	54350	45650	56732	43268	44
17	51903	48097	54390	45610	56771	43229	43
18	51946	48054	54431	45569	56810	43190	42
19	51988	48012	54471	45529	56849	43151	41
20	9.52031	10.47969	9.54512	10.45488	9.56887	10.43113	40
21	52073	47927	54552	45448	56926	43074	39
22	52115	47885	54593	45407	56965	43035	38
23	52157	47843	54633	45367	57004	42996	37
24	52200	47800	54673	45327	57042	42958	36
25	52242	47758	54714	45286	57081	42919	35
26	52284	47716	54754	45246	57120	42880	34
27	52326	47674	54794	45206	57158	42842	33
28	52368	47632	54835	45165	57197	42803	32
29	52410	47590	54875	45125	57235	42765	31
30	9.52452	10.47548	9.54915	10.45085	9.57274	10.42726	30
31	52494	47506	54955	45045	57312	42688	29
32	52536	47464	54995	45005	57351	42649	28
33	52578	47422	55035	44965	57389	42611	27
34	52620	47380	55075	44925	57428	42572	26
35	52661	47339	55115	44885	57466	42534	25
36	52703	47297	55155	44845	57504	42496	24
37	52745	47255	55195	44805	57543	42457	23
38	52787	47213	55235	44765	57581	42419	22
39	52829	47171	55275	44725	57619	42381	21
40	9.52870	10.47130	9.55315	10.44685	9.57658	10.42342	20
41	52912	47088	55355	44645	57696	42304	19
42	52953	47047	55395	44605	57734	42266	18
43	52995	47005	55434	44566	57772	42228	17
44	53037	46963	55474	44526	57810	42190	16
45	53078	46922	55514	44486	57849	42151	15
46	53120	46880	55554	44446	57887	42113	14
47	53161	46839	55593	44407	57925	42075	13
48	53202	46798	55633	44367	57963	42037	12
49	53244	46756	55673	44327	58001	41999	11
50	9.53285	10.46715	9.55712	10.44288	9.58039	10.41961	10
51	53327	46673	55752	44248	58077	41923	9
52	53368	46632	55791	44209	58115	41885	8
53	53409	46591	55831	44169	58153	41847	7
54	53450	46550	55870	44130	58191	41809	6
55	53492	46508	55910	44090	58229	41771	5
56	53533	46467	55949	44051	58267	41733	4
57	53574	46426	55989	44011	58304	41696	3
58	53615	46385	56028	43972	58342	41658	2
59	53656	46344	56067	43933	58380	41620	1
60	53697	46303	56107	43893	58418	41582	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	71°		70°		69°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	21°		22°		23°		′
	Tan	Cotan	Tan	Cotan	Tan	Cotan	
0	9.58418	10.41582	9.60641	10.39359	9.62785	10.37215	60
1	58455	41545	60677	39323	62820	37180	59
2	58493	41507	60714	39286	62855	37145	58
3	58531	41469	60750	39250	62890	37110	57
4	58569	41431	60786	39214	62926	37074	56
5	58606	41394	60823	39177	62961	37039	55
6	58644	41356	60859	39141	62996	37004	54
7	58681	41319	60895	39105	63031	36969	53
8	58719	41281	60931	39069	63066	36934	52
9	58757	41243	60967	39033	63101	36899	51
10	9.58794	10.41206	9.61004	10.38996	9.63135	10.36865	50
11	58832	41168	61040	38960	63170	36830	49
12	58869	41131	61076	38924	63205	36795	48
13	58907	41093	61112	38888	63240	36760	47
14	58944	41056	61148	38852	63275	36725	46
15	58981	41019	61184	38816	63310	36690	45
16	59019	40981	61220	38780	63345	36655	44
17	59056	40944	61256	38744	63379	36621	43
18	59094	40906	61292	38708	63414	36586	42
19	59131	40869	61328	38672	63449	36551	41
20	9.59168	10.40832	9.61364	10.38636	9.63484	10.36516	40
21	59205	40795	61400	38600	63519	36481	39
22	59243	40757	61436	38564	63553	36447	38
23	59280	40720	61472	38528	63588	36412	37
24	59317	40683	61508	38492	63623	36377	36
25	59354	40646	61544	38456	63657	36343	35
26	59391	40609	61579	38421	63692	36308	34
27	59429	40571	61615	38385	63726	36274	33
28	59466	40534	61651	38349	63761	36239	32
29	59503	40497	61687	38313	63796	36204	31
30	9.59540	10.40460	9.61722	10.38278	9.63830	10.36170	30
31	59577	40423	61758	38242	63865	36135	29
32	59614	40386	61794	38206	63899	36101	28
33	59651	40349	61830	38170	63934	36066	27
34	59688	40312	61865	38135	63968	36032	26
35	59725	40275	61901	38099	64003	35997	25
36	59762	40238	61936	38064	64037	35963	24
37	59799	40201	61972	38028	64072	35928	23
38	59835	40165	62008	37992	64106	35894	22
39	59872	40128	62043	37957	64140	35860	21
40	9.59909	10.40091	9.62079	10.37921	9.64175	10.35825	20
41	59946	40054	62114	37886	64209	35791	19
42	59983	40017	62150	37850	64243	35757	18
43	60019	39981	62185	37815	64278	35722	17
44	60056	39944	62221	37779	64312	35688	16
45	60093	39907	62256	37744	64316	35654	15
46	60130	39870	62292	37708	64381	35619	14
47	60166	39834	62327	37673	64415	35585	13
48	60203	39797	62362	37638	64449	35551	12
49	60240	39760	62398	37602	64483	35517	11
50	9.60276	10.39724	9.62433	10.37567	9.64517	10.35483	10
51	60313	39687	62468	37532	64552	35448	9
52	60349	39651	62504	37496	64586	35414	8
53	60386	39614	62539	37461	64620	35380	7
54	60422	39578	62574	37426	64654	35346	6
55	60459	39541	62609	37391	64688	35312	5
56	60495	39505	62645	37355	64722	35278	4
57	60532	39468	62680	37320	64756	35244	3
58	60568	39432	62715	37285	64790	35210	2
59	60605	39395	62750	37250	64824	35176	1
60	60641	39359	62785	37215	64858	35142	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	68°		67°		66°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	24° Tan	24° Cotan	25° Tan	25° Cotan	26° Tan	26° Cotan	′
0	9.64858	10.35142	9.66867	10.33133	9.68818	10.31182	60
1	64892	35108	66900	33100	68850	31150	59
2	64926	35074	66933	33067	68882	31118	58
3	64960	35040	66966	33034	68914	31086	57
4	64994	35006	66999	33001	68946	31054	56
5	65028	34972	67032	32968	68978	31022	55
6	65062	34938	67065	32935	69010	30990	54
7	65096	34904	67098	32902	69042	30958	53
8	65130	34870	67131	32869	69074	30926	52
9	65164	34836	67163	32837	69106	30894	51
10	9.65197	10.34803	9.67196	10.32804	9.69138	10.30862	50
11	65231	34769	67229	32771	69170	30830	49
12	65265	34735	67262	32738	69202	30798	48
13	65299	34701	67295	32705	69234	30766	47
14	65333	34667	67327	32673	69266	30734	46
15	65366	34634	67360	32640	69298	30702	45
16	65400	34600	67393	32607	69329	30671	44
17	65434	34566	67426	32574	69361	30639	43
18	65467	34533	67458	32542	69393	30607	42
19	65501	34499	67491	32509	69425	30575	41
20	9.65535	10.34465	9.67524	10.32476	9.69457	10.30543	40
21	65568	34432	67556	32444	69488	30512	39
22	65602	34398	67589	32411	69520	30480	38
23	65636	34364	67622	32378	69552	30448	37
24	65669	34331	67654	32346	69584	30416	36
25	65703	34297	67687	32313	69615	30385	35
26	65736	34264	67719	32281	69647	30353	34
27	65770	34230	67752	32248	69679	30321	33
28	65803	34197	67785	32215	69710	30290	32
29	65837	34163	67817	32183	69742	30258	31
30	9.65870	10.34130	9.67850	10.32150	9.69774	10.30226	30
31	65904	34096	67882	32118	69805	30195	29
32	65937	34063	67915	32085	69837	30163	28
33	65971	34029	67947	32053	69868	30132	27
34	66004	33996	67980	32020	69900	30100	26
35	66038	33962	68012	31988	69932	30068	25
36	66071	33929	68044	31956	69963	30037	24
37	66104	33896	68077	31923	69995	30005	23
38	66138	33862	68109	31891	70026	29974	22
39	66171	33829	68142	31858	70058	29942	21
40	9.66204	10.33796	9.68174	10.31826	9.70089	10.29911	20
41	66238	33762	68206	31794	70121	29879	19
42	66271	33729	68239	31761	70152	29848	18
43	66304	33696	68271	31729	70184	29816	17
44	66337	33663	68303	31697	70215	29785	16
45	66371	33629	68336	31664	70247	29753	15
46	66404	33596	68368	31632	70278	29722	14
47	66437	33563	68400	31600	70309	29691	13
48	66470	33530	68432	31568	70341	29659	12
49	66503	33497	68465	31535	70372	29628	11
50	9.66537	10.33463	9.68497	10.31503	9.70404	10.29596	10
51	66570	33430	68529	31471	70435	29565	9
52	66603	33397	68561	31439	70466	29534	8
53	66636	33364	68593	31407	70498	29502	7
54	66669	33331	68626	31374	70529	29471	6
55	66702	33298	68658	31342	70560	29440	5
56	66735	33265	68690	31310	70592	29408	4
57	66768	33232	68722	31278	70623	29377	3
58	66801	33199	68754	31246	70654	29346	2
59	66834	33166	68786	31214	70685	29315	1
60	66867	33133	68818	31182	70717	29283	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	65°		64°		63°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	27°		28°		29°		′
	Tan	Cotan	Tan	Cotan	Tan	Cotan	
0	9.70717	10.29283	9.72567	10.27433	9.74375	10.25625	60
1	70748	29252	72598	27402	74405	25595	59
2	70779	29221	72628	27372	74435	25565	58
3	70810	29190	72659	27341	74465	25535	57
4	70841	29159	72689	27311	74494	25506	56
5	70873	29127	72720	27280	74524	25476	55
6	70904	29096	72750	27250	74554	25446	54
7	70935	29065	72780	27220	74583	25417	53
8	70966	29034	72811	27189	74613	25387	52
9	70997	29003	72841	27159	74643	25357	51
10	9.71028	10.28972	9.72872	10.27128	9.74673	10.25327	50
11	71059	28941	72902	27098	74702	25298	49
12	71090	28910	72932	27068	74732	25268	48
13	71121	28879	72963	27037	74762	25238	47
14	71153	28847	72993	27007	74791	25209	46
15	71184	28816	73023	26977	74821	25179	45
16	71215	28785	73054	26946	74851	25149	44
17	71246	28754	73084	26916	74880	25120	43
18	71277	28723	73114	26886	74910	25090	42
19	71308	28692	73144	26856	74939	25061	41
20	9.71339	10.28661	9.73175	10.26825	9.74969	10.25031	40
21	71370	28630	73205	26795	74998	25002	39
22	71401	28599	73235	26765	75028	24972	38
23	71431	28569	73265	26735	75058	24942	37
24	71462	28538	73295	26705	75087	24913	36
25	71493	28507	73326	26674	75117	24883	35
26	71524	28476	73356	26644	75146	24854	34
27	71555	28445	73386	26614	75176	24824	33
28	71586	28414	73416	26584	75205	24795	32
29	71617	28383	73446	26554	75235	24765	31
30	9.71648	10.28352	9.73476	10.26524	9.75264	10.24736	30
31	71679	28321	73507	26493	75291	24706	29
32	71709	28291	73537	26463	75323	24677	28
33	71740	28260	73567	26433	75353	24647	27
34	71771	28229	73597	26403	75382	24618	26
35	71802	28198	73627	26373	75411	24589	25
36	71833	28167	73657	26343	75441	24559	24
37	71863	28137	73687	26313	75470	24530	23
38	71894	28106	73717	26283	75500	24500	22
39	71925	28075	73747	26253	75529	24471	21
40	9.71955	10.28045	9.73777	10 26223	9.75558	10.24442	20
41	71986	28014	73807	26193	75588	24412	19
42	72017	27983	73837	26163	75617	24383	18
43	72048	27952	73867	26133	75647	24353	17
44	72078	27922	73897	26103	75676	24324	16
45	72109	27891	73927	26073	75705	24295	15
46	72140	27860	73957	26043	75735	24265	14
47	72170	27830	73987	26013	75764	24236	13
48	72201	27799	74017	25983	75793	24207	12
49	72231	27769	74047	25953	75822	24178	11
50	9.72262	10.27738	9.74077	10.25923	9.75852	10.24148	10
51	72293	27707	74107	25893	75881	24119	9
52	72323	27677	74137	25863	75910	24090	8
53	72354	27646	74166	25834	75939	24061	7
54	72384	27616	74196	25804	75969	24031	6
55	72415	27585	74226	25774	75998	24002	5
56	72445	27555	74256	25744	76027	23973	4
57	72476	27524	74286	25714	76056	23944	3
58	72506	27494	74316	25684	76086	23914	2
59	72537	27463	74345	25655	76115	23885	1
60	72567	27433	74375	25625	76144	23856	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	62°		61°		60°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	30° Tan	30° Cotan	31° Tan	31° Cotan	32° Tan	32° Cotan	′
0	9.76144	10.23856	9.77877	10.22123	9.79579	10.20421	60
1	76173	23827	77906	22094	79607	20393	59
2	76202	23798	77935	22065	79635	20365	58
3	76231	23769	77963	22037	79663	20337	57
4	76261	23739	77992	22008	79691	20309	56
5	76290	23710	78020	21980	79719	20281	55
6	76319	23681	78049	21951	79747	20253	54
7	76348	23652	78077	21923	79776	20224	53
8	76377	23623	78106	21894	79804	20196	52
9	76406	23594	78135	21865	79832	20168	51
10	9.76435	10.23565	9.78163	10.21837	9.79860	10.20140	50
11	76464	23536	78192	21808	79888	20112	49
12	76493	23507	78220	21780	79916	20084	48
13	76522	23478	78249	21751	79944	20056	47
14	76551	23449	78277	21723	79972	20028	46
15	76580	23420	78306	21694	80000	20000	45
16	76609	23391	78334	21666	80028	19972	44
17	76639	23361	78363	21637	80056	19944	43
18	76668	23332	78391	21609	80084	19916	42
19	76697	23303	78419	21581	80112	19888	41
20	9.76725	10.23275	9.78448	10.21552	9.80140	10.19860	40
21	76754	23246	78476	21524	80168	19832	39
22	76783	23217	78505	21495	80195	19805	38
23	76812	23188	78533	21467	80223	19777	37
24	76841	23159	78562	21438	80251	19749	36
25	76870	23130	78590	21410	80279	19721	35
26	76899	23101	78618	21382	80307	19693	34
27	76928	23072	78647	21353	80335	19665	33
28	76957	23043	78675	21325	80363	19637	32
29	76986	23014	78704	21296	80391	19609	31
30	9.77015	10.22985	9.78732	10.21268	9.80419	10.19581	30
31	77044	22956	78760	21240	80447	19553	29
32	77073	22927	78789	21211	80474	19526	28
33	77101	22899	78817	21183	80502	19498	27
34	77130	22870	78845	21155	80530	19470	26
35	77159	22841	78874	21126	80558	19442	25
36	77188	22812	78902	21098	80586	19414	24
37	77217	22783	78930	21070	80614	19386	23
38	77246	22754	78959	21041	80642	19358	22
39	77274	22726	78987	21013	80669	19331	21
40	9.77303	10.22697	9.79015	10.20985	9.80697	10.19303	20
41	77332	22668	79043	20957	80725	19275	19
42	77361	22639	79072	20928	80753	19247	18
43	77390	22610	79100	20900	80781	19219	17
44	77418	22582	79128	20872	80808	19192	16
45	77447	22553	79156	20844	80836	19164	15
46	77476	22524	79185	20815	80864	19136	14
47	77505	22495	79213	20787	80892	19108	13
48	77533	22467	79241	20759	80919	19081	12
49	77562	22438	79269	20731	80947	19053	11
50	9.77591	10.22409	9.79297	10.20703	9.80975	10.19025	10
51	77619	22381	79326	20674	81003	18997	9
52	77648	22352	79354	20646	81030	18970	8
53	77677	22323	79382	20618	81058	18942	7
54	77706	22294	79410	20590	81086	18914	6
55	77734	22266	79438	20562	81113	18887	5
56	77763	22237	79466	20534	81141	18859	4
57	77791	22209	79495	20505	81169	18831	3
58	77820	22180	79523	20477	81196	18804	2
59	77849	22151	79551	20449	81224	18776	1
60	77877	22123	79579	20421	81252	18748	0
′	59° Cotan	59° Tan	58° Cotan	58° Tan	57° Cotan	57° Tan	′

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	33°		34°		35°		′
	Tan	Cotan	Tan	Cotan	Tan	Cotan	
0	9.81252	10.18748	9.82899	10.17101	9.84523	10.15477	60
1	81279	18721	82926	17074	84550	15450	59
2	81307	18693	82953	17047	84576	15424	58
3	81335	18665	82980	17020	84603	15397	57
4	81362	18638	83008	16992	84630	15370	56
5	81390	18610	83035	16965	84657	15343	55
6	81418	18582	83062	16938	84684	15316	54
7	81445	18555	83089	16911	84711	15289	53
8	81473	18527	83117	16883	84738	15262	52
9	81500	18500	83144	16856	84764	15236	51
10	9.81528	10.18472	9.83171	10.16829	9.84791	10.15209	50
11	81556	18444	83198	16802	84818	15182	49
12	81583	18417	83225	16775	84845	15155	48
13	81611	18389	83252	16748	84872	15128	47
14	81638	18362	83280	16720	84899	15101	46
15	81666	18331	83307	16693	84925	15075	45
16	81693	18307	83334	16666	84952	15048	44
17	81721	18279	83361	16639	84979	15021	43
18	81748	18252	83388	16612	85006	14994	42
19	81776	18224	83415	16585	85033	14967	41
20	9.81803	10.18197	9.83442	10.16558	9.85059	10.14941	40
21	81831	18169	83470	16530	85086	14914	39
22	81858	18142	83497	16503	85113	14887	38
23	81886	18114	83524	16476	85140	14860	37
24	81913	18087	83551	16449	85166	14834	36
25	81941	18059	83578	16422	85193	14807	35
26	81968	18032	83605	16395	85220	14780	34
27	81996	18004	83632	16368	85247	14753	33
28	82023	17977	83659	16341	85273	14727	32
29	82051	17949	83686	16314	85300	14700	31
30	9.82078	10.17922	9.83713	10.16287	9.85327	10.14673	30
31	82106	17894	83740	16260	85354	14646	29
32	82133	17867	83768	16232	85380	14620	28
33	82161	17839	83795	16205	85407	14593	27
34	82188	17812	83822	16178	85434	14566	26
35	82215	17785	83849	16151	85460	14540	25
36	82243	17757	83876	16124	85487	14513	24
37	82270	17730	83903	16097	85514	14486	23
38	82298	17702	83930	16070	85540	14460	22
39	82325	17675	83957	16043	85567	14433	21
40	9.82352	10.17648	9.83984	10.16016	9.85594	10.14406	20
41	82380	17620	84011	15989	85620	14380	19
42	82407	17593	84038	15962	85647	14353	18
43	82435	17565	84065	15935	85674	14326	17
44	82462	17538	84092	15908	85700	14300	16
45	82489	17511	84119	15881	85727	14273	15
46	82517	17483	84146	15854	85754	14246	14
47	82544	17456	84173	15827	85780	14220	13
48	82571	17429	84200	15800	85807	14193	12
49	82599	17401	84227	15773	85834	14166	11
50	9.82626	10.17374	9.84254	10.15746	9.85860	10.14140	10
51	82653	17347	84280	15720	85887	14113	9
52	82681	17319	84307	15693	85913	14087	8
53	82708	17292	84334	15666	85940	14060	7
54	82735	17265	84361	15639	85967	14033	6
55	82762	17238	84388	15612	85993	14007	5
56	82790	17210	84415	15585	86020	13980	4
57	82817	17183	84442	15558	86046	13954	3
58	82844	17156	84469	15531	86073	13927	2
59	82871	17129	84496	15504	86100	13900	1
60	82899	17101	84523	15477	86126	13874	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	56°		55°		54°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	36° Tan	36° Cotan	37° Tan	37° Cotan	38° Tan	38° Cotan	′
0	9.86126	10.13874	9.87711	10.12289	9.89281	10.10719	60
1	86153	13847	87738	12262	89307	10693	59
2	86179	13821	87764	12236	89333	10667	58
3	86206	13794	87790	12210	89359	10641	57
4	86232	13768	87817	12183	89385	10615	56
5	86259	13741	87843	12157	89411	10589	55
6	86285	13715	87869	12131	89437	10563	54
7	86312	13688	87895	12105	89463	10537	53
8	86338	13662	87922	12078	89489	10511	52
9	86365	13635	87948	12052	89515	10485	51
10	9.86392	10.13608	9.87974	10.12026	9.89541	10.10459	50
11	86418	13582	88000	12000	89567	10433	49
12	86445	13555	88027	11973	89593	10407	48
13	86471	13529	88053	11947	89619	10381	47
14	86498	13502	88079	11921	89645	10355	46
15	86524	13476	88105	11895	89671	10329	45
16	86551	13449	88131	11869	89697	10303	44
17	86577	13423	88158	11842	89723	10277	43
18	86603	13397	88184	11816	89749	10251	42
19	86630	13370	88210	11790	89775	10225	41
20	9.86656	10.13344	9.88236	10.11764	9.89801	10.10199	40
21	86683	13317	88262	11738	89827	10173	39
22	86709	13291	88289	11711	89853	10147	38
23	86736	13264	88315	11685	89879	10121	37
24	86762	13238	88341	11659	89905	10095	36
25	86789	13211	88367	11633	89931	10069	35
26	86815	13185	88393	11607	89957	10043	34
27	86842	13158	88420	11580	89983	10017	33
28	86868	13132	88446	11554	90009	09991	32
29	86894	13106	88472	11528	90035	09965	31
30	9.86921	10.13079	9.88498	10.11502	9.90061	10.09939	30
31	86947	13053	88524	11476	90086	09914	29
32	86974	13026	88550	11450	90112	09888	28
33	87000	13000	88577	11423	90138	09862	27
34	87027	12973	88603	11397	90164	09836	26
35	87053	12947	88629	11371	90190	09810	25
36	87079	12921	88655	11345	90216	09784	24
37	87106	12894	88681	11319	90242	09758	23
38	87132	12868	88707	11293	90268	09732	22
39	87158	12842	88733	11267	90294	09706	21
40	9.87185	10.12815	9.88759	10.11241	9.90320	10.09680	20
41	87211	12789	88786	11214	90346	09654	19
42	87238	12762	88812	11188	90371	09629	18
43	87264	12736	88838	11162	90397	09603	17
44	87290	12710	88864	11136	90423	09577	16
45	87317	12683	88890	11110	90449	09551	15
46	87343	12657	88916	11084	90475	09525	14
47	87369	12631	88942	11058	90501	09499	13
48	87396	12604	88968	11032	90527	09473	12
49	87422	12578	88994	11006	90553	09447	11
50	9.87448	10.12552	9.89020	10.10980	9.90578	10.09422	10
51	87475	12525	89046	10954	90604	09396	9
52	87501	12499	89073	10927	90630	09370	8
53	87527	12473	89099	10901	90656	09344	7
54	87554	12446	89125	10875	90682	09318	6
55	87580	12420	89151	10849	90708	09292	5
56	87606	12394	89177	10823	90734	09266	4
57	87633	12367	89203	10797	90759	09241	3
58	87659	12341	89229	10771	90785	09215	2
59	87685	12315	89255	10745	90811	09189	1
60	87711	12289	89281	10719	90837	09163	0
′	53° Cotan	53° Tan	52° Cotan	52° Tan	51° Cotan	51° Tan	′

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	39°		40°		41°		′
	Tan	Cotan	Tan	Cotan	Tan	Cotan	
0	9.90837	10.09163	9.92381	10.07619	9.93916	10.06084	60
1	90863	09137	92407	07593	93942	06058	59
2	90889	09111	92433	07567	93967	06033	58
3	90914	09086	92458	07542	93993	06007	57
4	90940	09060	92484	07516	94018	05982	56
5	90966	09034	92510	07490	94044	05956	55
6	90992	09008	92535	07465	94069	05931	54
7	91018	08982	92561	07439	94095	05905	53
8	91043	08957	92587	07413	94120	05880	52
9	91069	08931	92612	07388	94146	05854	51
10	9.91095	10.08905	9.92638	10.07362	9.94171	10.05829	50
11	91121	08879	92663	07337	94197	05803	49
12	91147	08853	92689	07311	94222	05778	48
13	91172	08828	92715	07285	94248	05752	47
14	91198	08802	92740	07260	94273	05727	46
15	91224	08776	92766	07234	94299	05701	45
16	91250	08750	92792	07208	94324	05676	44
17	91276	08724	92817	07183	94350	05650	43
18	91301	08699	92843	07157	94375	05625	42
19	91327	08673	92868	07132	94401	05599	41
20	9.91353	10.08647	9.92894	10.07106	9.94426	10.05574	40
21	91379	08621	92920	07080	94452	05548	39
22	91404	08596	92945	07055	94477	05523	38
23	91430	08570	92971	07029	94503	05497	37
24	91456	08544	92996	07004	94528	05472	36
25	91482	08518	93022	06978	94554	05446	35
26	91507	08493	93048	06952	94579	05421	34
27	91533	08467	93073	06927	94604	05396	33
28	91559	08441	93099	06901	94630	05370	32
29	91585	08415	93124	06876	94655	05345	31
30	9.91610	10.08390	9.93150	10.06850	9.94681	10.05319	30
31	91636	08364	93175	06825	94706	05294	29
32	91662	08338	93201	06799	94732	05268	28
33	91688	08312	93227	06773	94757	05243	27
34	91713	08287	93252	06748	94783	05217	26
35	91739	08261	93278	06722	94808	05192	25
36	91765	08235	93303	06697	94834	05166	24
37	91791	08209	93329	06671	94859	05141	23
38	91816	08184	93354	06646	94884	05116	22
39	91842	08158	93380	06620	94910	05090	21
40	9.91868	10.08132	9.93406	10.06594	9.94935	10.05065	20
41	91893	08107	93431	06569	94961	05039	19
42	91919	08081	93457	06543	94986	05014	18
43	91945	08055	93482	06518	95012	04988	17
44	91971	08029	93508	06492	95037	04963	16
45	91996	08004	93533	06467	95062	04938	15
46	92022	07978	93559	06441	95088	04912	14
47	92048	07952	93584	06416	95113	04887	13
48	92073	07927	93610	06390	95139	04861	12
49	92099	07901	93636	06364	95164	04836	11
50	9.92125	10.07875	9.93661	10.06339	9.95190	10.04810	10
51	92150	07850	93687	06313	95215	04785	9
52	92176	07824	93712	06288	95240	04760	8
53	92202	07798	93738	06262	95266	04734	7
54	92227	07773	93763	06237	95291	04709	6
55	92253	07747	93789	06211	95317	04683	5
56	92279	07721	93814	06186	95342	04658	4
57	92304	07696	93840	06160	95368	04632	3
58	92330	07670	93865	06135	95393	04607	2
59	92356	07644	93891	06109	95418	04582	1
60	92381	07619	93916	06084	95444	04556	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	50°		49°		48°		

TABLE III.—LOG. TANGENTS AND COTANGENTS.

′	42° Tan	42° Cotan	43° Tan	43° Cotan	44° Tan	44° Cotan	′
0	9.95444	10.04556	9.96966	10.03034	9.98484	10.01516	60
1	95469	04531	96991	03009	98509	01491	59
2	95495	04505	97016	02984	98534	01466	58
3	95520	04480	97042	02958	98560	01440	57
4	95545	04455	97067	02933	98585	01415	56
5	95571	04429	97092	02908	98610	01390	55
6	95596	04404	97118	02882	98635	01365	54
7	95622	04378	97143	02857	98661	01339	53
8	95647	04353	97168	02832	98686	01314	52
9	95672	04328	97193	02807	98711	01289	51
10	9.95698	10.04302	9.97219	10.02781	9.98737	10.01263	50
11	95723	04277	97244	02756	98762	01238	49
12	95748	04252	97269	02731	98787	01213	48
13	95774	04226	97295	02705	98812	01188	47
14	95799	04201	97320	02680	98838	01162	46
15	95825	04175	97345	02655	98863	01137	45
16	95850	04150	97371	02629	98888	01112	44
17	95875	04125	97396	02604	98913	01087	43
18	95901	04099	97421	02579	98939	01061	42
19	95926	04074	97447	02553	98964	01036	41
20	9.95952	10.04048	9.97472	10.02528	9.98989	10.01011	40
21	95977	04023	97497	02503	99015	00985	39
22	96002	03998	97523	02477	99040	00960	38
23	96028	03972	97548	02452	99065	00935	37
24	96053	03947	97573	02427	99090	00910	36
25	96078	03922	97598	02402	99116	00884	35
26	96104	03896	97624	02376	99141	00859	34
27	96129	03871	97649	02351	99166	00834	33
28	96155	03845	97674	02326	99191	00809	32
29	96180	03820	97700	02300	99217	00783	31
30	9.96205	10.03795	9.97725	10.02275	9.99242	10.00758	30
31	96231	03769	97750	02250	99267	00733	29
32	96256	03744	97776	02224	99293	00707	28
33	96281	03719	97801	02199	99318	00682	27
34	96307	03693	97826	02174	99343	00657	26
35	96332	03668	97851	02149	99368	00632	25
36	96357	03643	97877	02123	99394	00606	24
37	96383	03617	97902	02098	99419	00581	23
38	96408	03592	97927	02073	99444	00556	22
39	96433	03567	97953	02047	99469	00531	21
40	9.96459	10.03541	9.97978	10.02022	9.99495	10.00505	20
41	96484	03516	98003	01997	99520	00480	19
42	96510	03490	98029	01971	99545	00455	18
43	96535	03465	98054	01946	99570	00430	17
44	96560	03440	98079	01921	99596	00404	16
45	96586	03414	98104	01896	99621	00379	15
46	96611	03389	98130	01870	99646	00354	14
47	96636	03364	98155	01845	99672	00328	13
48	96662	03338	98180	01820	99697	00303	12
49	96687	03313	98206	01794	99722	00278	11
50	9.96712	10.03288	9.98231	10.01769	9.99747	10.00253	10
51	96738	03262	98256	01744	99773	00227	9
52	96763	03237	98281	01719	99798	00202	8
53	96788	03212	98307	01693	99823	00177	7
54	96814	03186	98332	01668	99848	00152	6
55	96839	03161	98357	01643	99874	00126	5
56	96864	03136	98383	01617	99899	00101	4
57	96890	03110	98408	01592	99924	00076	3
58	96915	03085	98433	01567	99949	00051	2
59	96940	03060	98458	01542	99975	00025	1
60	96966	03034	98484	01516	10.00000	00000	0
′	Cotan	Tan	Cotan	Tan	Cotan	Tan	′
	47°		46°		45°		

TABLE IV.—NATURAL SINES AND COSINES.

′	0°		1°		2°		3°		4°		′
	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	
0	.00000	One.	.01745	.99985	.03490	.99939	.05234	.99863	.06976	.99756	60
1	.00029	One.	.01774	.99984	.03519	.99938	.05263	.99861	.07005	.99754	59
2	.00058	One.	.01803	.99984	.03548	.99937	.05292	.99860	.07034	.99752	58
3	.00087	One.	.01832	.99983	.03577	.99936	.05321	.99858	.07063	.99750	57
4	.00116	One.	.01862	.99983	.03606	.99935	.05350	.99857	.07092	.99748	56
5	.00145	One.	.01891	.99982	.03635	.99934	.05379	.99855	.07121	.99746	55
6	.00175	One.	.01920	.99982	.03664	.99933	.05408	.99854	.07150	.99744	54
7	.00204	One.	.01949	.99981	.03693	.99932	.05437	.99852	.07179	.99742	53
8	.00233	One.	.01978	.99980	.03723	.99931	.05466	.99851	.07208	.99740	52
9	.00262	One.	.02007	.99980	.03752	.99930	.05495	.99849	.07237	.99738	51
10	.00291	One.	.02036	.99979	.03781	.99929	.05524	.99847	.07266	.99736	50
11	.00320	.99999	.02065	.99979	.03810	.99927	.05553	.99846	.07295	.99734	49
12	.00349	.99999	.02094	.99978	.03839	.99926	.05582	.99844	.07324	.99731	48
13	.00378	.99999	.02123	.99977	.03868	.99925	.05611	.99842	.07353	.99729	47
14	.00407	.99999	.02152	.99977	.03897	.99924	.05640	.99841	.07382	.99727	46
15	.00436	.99999	.02181	.99976	.03926	.99923	.05669	.99839	.07411	.99725	45
16	.00465	.99999	.02211	.99976	.03955	.99922	.05698	.99838	.07440	.99723	44
17	.00495	.99999	.02240	.99975	.03984	.99921	.05727	.99836	.07469	.99721	43
18	.00524	.99999	.02269	.99974	.04013	.99919	.05756	.99834	.07498	.99719	42
19	.00553	.99998	.02298	.99974	.04042	.99918	.05785	.99833	.07527	.99716	41
20	.00582	.99998	.02327	.99973	.04071	.99917	.05814	.99831	.07556	.99714	40
21	.00611	.99998	.02356	.99972	.04100	.99916	.05844	.99829	.07585	.99712	39
22	.00640	.99998	.02385	.99972	.04129	.99915	.05873	.99827	.07614	.99710	38
23	.00669	.99998	.02414	.99971	.04159	.99913	.05902	.99826	.07643	.99708	37
24	.00698	.99998	.02443	.99970	.04188	.99912	.05931	.99824	.07672	.99705	36
25	.00727	.99997	.02472	.99969	.04217	.99911	.05960	.99822	.07701	.99703	35
26	.00756	.99997	.02501	.99969	.04246	.99910	.05989	.99821	.07730	.99701	34
27	.00785	.99997	.02530	.99968	.04275	.99909	.06018	.99819	.07759	.99699	33
28	.00814	.99997	.02560	.99967	.04304	.99907	.06047	.99817	.07788	.99696	32
29	.00844	.99996	.02589	.99966	.04333	.99906	.06076	.99815	.07817	.99694	31
30	.00873	.99996	.02618	.99966	.04362	.99905	.06105	.99813	.07846	.99692	30
31	.00902	.99996	.02647	.99965	.04391	.99904	.06134	.99812	.07875	.99689	29
32	.00931	.99996	.02676	.99964	.04420	.99902	.06163	.99810	.07901	.99687	28
33	.00960	.99995	.02705	.99963	.04449	.99901	.06192	.99808	.07933	.99685	27
34	.00989	.99995	.02734	.99963	.04478	.99900	.06221	.99806	.07962	.99683	26
35	.01018	.99995	.02763	.99962	.04507	.99898	.06250	.99804	.07991	.99680	25
36	.01047	.99995	.02792	.99961	.04536	.99897	.06279	.99803	.08020	.99678	24
37	.01076	.99994	.02821	.99960	.04565	.99896	.06308	.99801	.08049	.99676	23
38	.01105	.99994	.02850	.99959	.04594	.99894	.06337	.99799	.08078	.99673	22
39	.01134	.99994	.02879	.99959	.04623	.99893	.06366	.99797	.08107	.99671	21
40	.01164	.99993	.02908	.99958	.04653	.99892	.06395	.99795	.08136	.99668	20
41	.01193	.99993	.02938	.99957	.04682	.99890	.06424	.99793	.08165	.99666	19
42	.01222	.99993	.02967	.99956	.04711	.99889	.06453	.99792	.08194	.99664	18
43	.01251	.99992	.02996	.99955	.04740	.99888	.06482	.99790	.08223	.99661	17
44	.01280	.99992	.03025	.99954	.04769	.99886	.06511	.99788	.08252	.99659	16
45	.01309	.99991	.03054	.99953	.04798	.99885	.06540	.99786	.08281	.99657	15
46	.01338	.99991	.03083	.99952	.04827	.99883	.06569	.99784	.08310	.99654	14
47	.01367	.99991	.03112	.99952	.04856	.99882	.06598	.99782	.08339	.99652	13
48	.01396	.99990	.03141	.99951	.04885	.99881	.06627	.99780	.08368	.99649	12
49	.01425	.99990	.03170	.99950	.04914	.99879	.06656	.99778	.08397	.99647	11
50	.01454	.99989	.03199	.99949	.04943	.99878	.06685	.99776	.08426	.99644	10
51	.01483	.99989	.03228	.99948	.04972	.99876	.06714	.99774	.08455	.99642	9
52	.01513	.99989	.03257	.99947	.05001	.99875	.06743	.99772	.08484	.99639	8
53	.01542	.99988	.03286	.99946	.05030	.99873	.06773	.99770	.08513	.99637	7
54	.01571	.99988	.03316	.99945	.05059	.99872	.06802	.99768	.08542	.99635	6
55	.01600	.99987	.03345	.99944	.05088	.99870	.06831	.99766	.08571	.99632	5
56	.01629	.99987	.03374	.99943	.05117	.99869	.06860	.99764	.08600	.99630	4
57	.01658	.99986	.03403	.99942	.05146	.99867	.06889	.99762	.08629	.99627	3
58	.01687	.99986	.03432	.99941	.05175	.99866	.06918	.99760	.08658	.99625	2
59	.01716	.99985	.03461	.99940	.05205	.99864	.06947	.99758	.08687	.99622	1
60	.01745	.99985	.03490	.99939	.05234	.99863	.06976	.99756	.08716	.99619	0
′	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	′
	89°		88°		87°		86°		85°		

TABLE IV.—NATURAL SINES AND COSINES.

′	5°		6°		7°		8°		9°		′
	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	
0	.08716	.99619	.10453	.99452	.12187	.99255	.13917	.99027	.15643	.98769	60
1	.08745	.99617	.10482	.99449	.12216	.99251	.13946	.99023	.15672	.98764	59
2	.08774	.99614	.10511	.99446	.12245	.99248	.13975	.99019	.15701	.98760	58
3	.08803	.99612	.10540	.99443	.12274	.99241	.14004	.99015	.15730	.98755	57
4	.08831	.99609	.10569	.99440	.12302	.99240	.14033	.99011	.15758	.98751	56
5	.08860	.99607	.10597	.99437	.12331	.99237	.14061	.99006	.15787	.98746	55
6	.08889	.99604	.10626	.99434	.12360	.99233	.14090	.99002	.15816	.98741	54
7	.08918	.99602	.10655	.99431	.12389	.99230	.14119	.98998	.15845	.98737	53
8	.08947	.99599	.10684	.99428	.12418	.99226	.14148	.98994	.15873	.98732	52
9	.08976	.99596	.10713	.99424	.12447	.99222	.14177	.98990	.15902	.98728	51
10	.09005	.99594	.10742	.99421	.12476	.99219	.14205	.98986	.15931	.98723	50
11	.09034	.99591	.10771	.99418	.12504	.99215	.14234	.98982	.15959	.98718	49
12	.09063	.99588	.10800	.99415	.12533	.99211	.14263	.98978	.15988	.98714	48
13	.09092	.99586	.10829	.99412	.12562	.99208	.14292	.98973	.16017	.98709	47
14	.09121	.99583	.10858	.99409	.12591	.99204	.14320	.98969	.16046	.98704	46
15	.09150	.99580	.10887	.99406	.12620	.99200	.14349	.98965	.16074	.98700	45
16	.09179	.99578	.10916	.99402	.12649	.99197	.14378	.98961	.16103	.98695	44
17	.09208	.99575	.10945	.99399	.12678	.99193	.14407	.98957	.16132	.98690	43
18	.09237	.99572	.10973	.99396	.12706	.99189	.14436	.98953	.16160	.98686	42
19	.09266	.99570	.11002	.99393	.12735	.99186	.14464	.98948	.16189	.98681	41
20	.09295	.99567	.11031	.99390	.12764	.99182	.14493	.98944	.16218	.98676	40
21	.09324	.99564	.11060	.99386	.12793	.99178	.14522	.98940	.16246	.98671	39
22	.09353	.99562	.11089	.99383	.12822	.99175	.14551	.98936	.16275	.98667	38
23	.09382	.99559	.11118	.99380	.12851	.99171	.14580	.98931	.16304	.98662	37
24	.09411	.99556	.11147	.99377	.12880	.99167	.14608	.98927	.16333	.98657	36
25	.09440	.99553	.11176	.99374	.12908	.99163	.14637	.98923	.16361	.98652	35
26	.09469	.99551	.11205	.99370	.12937	.99160	.14666	.98919	.16390	.98648	34
27	.09498	.99548	.11234	.99367	.12966	.99156	.14695	.98914	.16419	.98643	33
28	.09527	.99545	.11263	.99364	.12995	.99152	.14723	.98910	.16447	.98638	32
29	.09556	.99542	.11291	.99360	.13024	.99148	.14752	.98906	.16476	.98633	31
30	.09585	.99540	.11320	.99357	.13053	.99144	.14781	.98902	.16505	.98629	30
31	.09614	.99537	.11349	.99351	.13081	.99141	.14810	.98897	.16533	.98624	29
32	.09642	.99534	.11378	.99351	.13110	.99137	.14838	.98893	.16562	.98619	28
33	.09671	.99531	.11407	.99347	.13139	.99133	.14867	.98889	.16591	.98614	27
34	.09700	.99528	.11436	.99344	.13168	.99129	.14896	.98884	.16620	.98609	26
35	.09729	.99526	.11465	.99341	.13197	.99125	.14925	.98880	.16648	.98604	25
36	.09758	.99523	.11494	.99337	.13226	.99122	.14954	.98876	.16677	.98600	24
37	.09787	.99520	.11523	.99334	.13254	.99118	.14982	.98871	.16706	.98595	23
38	.09816	.99517	.11552	.99331	.13283	.99114	.15011	.98867	.16734	.98590	22
39	.09845	.99514	.11580	.99327	.13312	.99110	.15040	.98863	.16763	.98585	21
40	.09874	.99511	.11609	.99324	.13341	.99106	.15069	.98858	.16792	.98580	20
41	.09903	.99508	.11638	.99320	.13370	.99102	.15097	.98854	.16820	.98575	19
42	.09932	.99506	.11667	.99317	.13399	.99098	.15126	.98849	.16849	.98570	18
43	.09961	.99503	.11696	.99314	.13427	.99094	.15155	.98845	.16878	.98565	17
44	.09990	.99500	.11725	.99310	.13456	.99091	.15184	.98841	.16906	.98561	16
45	.10019	.99497	.11754	.99307	.13485	.99087	.15212	.98836	.16935	.98556	15
46	.10048	.99494	.11783	.99303	.13514	.99083	.15241	.98832	.16964	.98551	14
47	.10077	.99491	.11812	.99300	.13543	.99079	.15270	.98827	.16992	.98546	13
48	.10106	.99488	.11840	.99297	.13572	.99075	.15299	.98823	.17021	.98541	12
49	.10135	.99485	.11869	.99293	.13600	.99071	.15327	.98818	.17050	.98536	11
50	.10164	.99482	.11898	.99290	.13629	.99067	.15356	.98814	.17078	.98531	10
51	.10192	.99479	.11927	.99286	.13658	.99063	.15385	.98809	.17107	.98526	9
52	.10221	.99476	.11956	.99283	.13687	.99059	.15414	.98805	.17136	.98521	8
53	.10250	.99473	.11985	.99279	.13716	.99055	.15442	.98800	.17164	.98516	7
54	.10279	.99470	.12014	.99276	.13744	.99051	.15471	.98796	.17193	.98511	6
55	.10308	.99467	.12043	.99272	.13773	.99047	.15500	.98791	.17222	.98506	5
56	.10337	.99464	.12071	.99269	.13802	.99043	.15529	.98787	.17250	.98501	4
57	.10366	.99461	.12100	.99265	.13831	.99039	.15557	.98782	.17279	.98496	3
58	.10395	.99458	.12129	.99262	.13860	.99035	.15586	.98778	.17308	.98491	2
59	.10424	.99455	.12158	.99258	.13889	.99031	.15615	.98773	.17336	.98486	1
60	.10453	.99452	.12187	.99255	.13917	.99027	.15643	.98769	.17365	.98481	0
′	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	′
	84°		83°		82°		81°		80°		

TABLE IV.—NATURAL SINES AND COSINES.

′	10°		11°		12°		13°		14°		′
	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	
0	.17365	.98481	.19081	.98163	.20791	.97815	.22495	.97437	.24192	.97030	60
1	.17393	.98476	.19109	.98157	.20820	.97809	.22523	.97430	.24220	.97023	59
2	.17422	.98471	.19138	.98152	.20848	.97803	.22552	.97424	.24245	.97015	58
3	.17451	.98466	.19167	.98146	.20877	.97797	.22580	.97417	.24277	.97008	57
4	.17479	.98461	.19195	.98140	.20905	.97791	.22608	.97411	.24305	.97001	56
5	.17508	.98455	.19224	.98135	.20933	.97784	.22637	.97404	.24333	.96994	55
6	.17537	.98450	.19252	.98129	.20962	.97778	.22665	.97398	.24362	.96987	54
7	.17565	.98445	.19281	.98124	.20990	.97772	.22693	.97391	.24390	.96980	53
8	.17594	.98440	.19309	.98118	.21019	.97766	.22722	.97384	.24418	.96973	52
9	.17623	.98435	.19338	.98112	.21047	.97760	.22750	.97378	.24446	.96966	51
10	.17651	.98430	.19366	.98107	.21076	.97754	.22778	.97371	.24474	.96959	50
11	.17680	.98425	.19395	.98101	.21104	.97748	.22807	.97365	.24503	.96952	49
12	.17708	.98420	.19423	.98096	.21132	.97742	.22835	.97358	.24531	.96945	48
13	.17737	.98414	.19452	.98090	.21161	.97735	.22863	.97351	.24559	.96937	47
14	.17766	.98409	.19481	.98081	.21189	.97729	.22892	.97345	.24587	.96930	46
15	.17794	.98404	.19509	.98079	.21218	.97723	.22920	.97338	.24615	.96923	45
16	.17823	.98399	.19538	.98073	.21246	.97717	.22948	.97331	.24644	.96916	44
17	.17852	.98394	.19566	.98067	.21275	.97711	.22977	.97325	.24672	.96909	43
18	.17880	.98389	.19595	.98061	.21303	.97705	.23005	.97318	.24700	.96902	42
19	.17909	.98383	.19623	.98056	.21331	.97698	.23033	.97311	.24728	.96894	41
20	.17937	.98378	.19652	.98050	.21360	.97692	.23062	.97304	.24756	.96887	40
21	.17966	.98373	.19680	.98044	.21388	.97686	.23090	.97298	.24784	.96880	39
22	.17995	.98368	.19709	.98039	.21417	.97680	.23118	.97291	.24813	.96873	38
23	.18023	.98362	.19737	.98033	.21445	.97673	.23146	.97284	.24841	.96866	37
24	.18052	.98357	.19766	.98027	.21474	.97667	.23175	.97278	.24869	.96858	36
25	.18081	.98352	.19794	.98021	.21502	.97661	.23203	.97271	.24897	.96851	35
26	.18109	.98347	.19823	.98016	.21530	.97655	.23231	.97264	.24925	.96844	34
27	.18138	.98341	.19851	.98010	.21559	.97648	.23260	.97257	.24954	.96837	33
28	.18166	.98336	.19880	.98004	.21587	.97642	.23288	.97251	.24982	.96829	32
29	.18195	.98331	.19908	.97998	.21616	.97636	.23316	.97244	.25010	.96822	31
30	.18224	.98325	.19937	.97992	.21644	.97630	.23345	.97237	.25038	.96815	30
31	.18252	.98320	.19965	.97987	.21672	.97624	.23373	.97230	.25066	.96807	29
32	.18281	.98315	.19994	.97981	.21701	.97617	.23401	.97223	.25094	.96800	28
33	.18309	.98310	.20022	.97975	.21729	.97611	.23429	.97217	.25122	.96793	27
34	.18338	.98304	.20051	.97969	.21758	.97604	.23458	.97210	.25151	.96786	26
35	.18367	.98299	.20079	.97963	.21786	.97598	.23486	.97203	.25179	.96778	25
36	.18395	.98294	.20108	.97958	.21814	.97592	.23514	.97196	.25207	.96771	24
37	.18424	.98288	.20136	.97952	.21843	.97585	.23542	.97189	.25235	.96764	23
38	.18452	.98283	.20165	.97946	.21871	.97579	.23571	.97182	.25263	.96756	22
39	.18481	.98277	.20193	.97940	.21899	.97573	.23599	.97176	.25291	.96749	21
40	.18509	.98272	.20222	.97934	.21928	.97566	.23627	.97169	.25320	.96742	20
41	.18538	.98267	.20250	.97928	.21956	.97560	.23656	.97162	.25348	.96734	19
42	.18567	.98261	.20279	.97922	.21985	.97553	.23684	.97155	.25376	.96727	18
43	.18595	.98256	.20307	.97916	.22013	.97547	.23712	.97148	.25404	.96719	17
44	.18624	.98250	.20336	.97910	.22041	.97541	.23740	.97141	.25432	.96712	16
45	.18652	.98245	.20364	.97905	.22070	.97534	.23769	.97134	.25460	.96705	15
46	.18681	.98240	.20393	.97899	.22098	.97528	.23797	.97127	.25488	.96697	14
47	.18710	.98234	.20421	.97893	.22126	.97521	.23825	.97120	.25516	.96690	13
48	.18738	.98229	.20450	.97887	.22155	.97515	.23853	.97113	.25545	.96682	12
49	.18767	.98223	.20478	.97881	.22183	.97508	.23882	.97106	.25573	.96675	11
50	.18795	.98218	.20507	.97875	.22212	.97502	.23910	.97100	.25601	.96667	10
51	.18824	.98212	.20535	.97869	.22240	.97496	.23938	.97093	.25629	.96660	9
52	.18852	.98207	.20563	.97863	.22268	.97489	.23966	.97086	.25657	.96653	8
53	.18881	.98201	.20592	.97857	.22297	.97483	.23995	.97079	.25685	.96645	7
54	.18910	.98196	.20620	.97851	.22325	.97476	.24023	.97072	.25713	.96638	6
55	.18938	.98190	.20649	.97845	.22353	.97470	.24051	.97065	.25741	.96630	5
56	.18967	.98185	.20677	.97839	.22382	.97463	.24079	.97058	.25769	.96623	4
57	.18995	.98179	.20706	.97833	.22410	.97457	.24108	.97051	.25798	.96615	3
58	.19024	.98174	.20734	.97827	.22438	.97450	.24136	.97044	.25826	.96608	2
59	.19052	.98168	.20763	.97821	.22467	.97444	.24164	.97037	.25854	.96600	1
60	.19081	.98163	.20791	.97815	.22495	.97437	.24192	.97030	.25882	.96593	0
′	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	′
	79°		78°		77°		76°		75°		

TABLE IV.—NATURAL SINES AND COSINES.

′	15°		16°		17°		18°		19°		′
	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	
0	.25882	.96593	.27564	.96126	.29237	.95630	.30902	.95106	.32557	.94552	60
1	.25910	.96585	.27592	.96118	.29265	.95622	.30929	.95097	.32584	.94542	59
2	.25938	.96578	.27620	.96110	.29293	.95613	.30957	.95088	.32612	.94533	58
3	.25966	.96570	.27648	.96102	.29321	.95605	.30985	.95079	.32639	.94523	57
4	.25994	.96562	.27676	.96094	.29348	.95596	.31012	.95070	.32667	.94514	56
5	.26022	.96555	.27704	.96086	.29376	.95588	.31040	.95061	.32694	.94504	55
6	.26050	.96547	.27731	.96078	.29404	.95579	.31068	.95052	.32722	.94495	54
7	.26079	.96540	.27759	.96070	.29432	.95571	.31095	.95043	.32749	.94485	53
8	.26107	.96532	.27787	.96062	.29460	.95562	.31123	.95033	.32777	.94476	52
9	.26135	.96524	.27815	.96054	.29487	.95554	.31151	.95024	.32804	.94466	51
10	.26163	.96517	.27843	.96046	.29515	.95545	.31178	.95015	.32832	.94457	50
11	.26191	.96509	.27871	.96037	.29543	.95536	.31206	.95006	.32859	.94447	49
12	.26219	.96502	.27899	.96029	.29571	.95528	.31233	.94997	.32887	.94438	48
13	.26247	.96494	.27927	.96021	.29599	.95519	.31261	.94988	.32914	.94428	47
14	.26275	.96486	.27955	.96013	.29626	.95511	.31289	.94979	.32942	.94418	46
15	.26303	.96479	.27983	.96005	.29654	.95502	.31316	.94970	.32969	.94409	45
16	.26331	.96471	.28011	.95997	.29682	.95493	.31344	.94961	.32997	.94399	44
17	.26359	.96463	.28039	.95989	.29710	.95485	.31372	.94952	.33024	.94390	43
18	.26387	.96456	.28067	.95981	.29737	.95476	.31399	.94943	.33051	.94380	42
19	.26415	.96448	.28095	.95972	.29765	.95467	.31427	.94933	.33079	.94370	41
20	.26443	.96440	.28123	.95964	.29793	.95459	.31454	.94924	.33106	.94361	40
21	.26471	.96433	.28150	.95956	.29821	.95450	.31482	.94915	.33134	.94351	39
22	.26500	.96425	.28178	.95948	.29849	.95441	.31510	.94906	.33161	.94342	38
23	.26528	.96417	.28206	.95940	.29876	.95433	.31537	.94897	.33189	.94332	37
24	.26556	.96410	.28234	.95931	.29904	.95424	.31565	.94888	.33216	.94322	36
25	.26584	.96402	.28262	.95923	.29932	.95415	.31593	.94878	.33244	.94313	35
26	.26612	.96394	.28290	.95915	.29960	.95407	.31620	.94869	.33271	.94303	34
27	.26640	.96386	.28318	.95907	.29987	.95398	.31648	.94860	.33298	.94293	33
28	.26668	.96379	.28346	.95898	.30015	.95389	.31675	.94851	.33326	.94284	32
29	.26696	.96371	.28374	.95890	.30043	.95380	.31703	.94842	.33353	.94274	31
30	.26724	.96363	.28402	.95882	.30071	.95372	.31730	.94832	.33381	.94264	30
31	.26752	.96355	.28429	.95874	.30098	.95363	.31758	.94823	.33408	.94254	29
32	.26780	.96347	.28457	.95865	.30126	.95354	.31786	.94814	.33436	.94245	28
33	.26808	.96340	.28485	.95857	.30154	.95345	.31813	.94805	.33463	.94235	27
34	.26836	.96332	.28513	.95849	.30182	.95337	.31841	.94795	.33490	.94225	26
35	.26864	.96324	.28541	.95841	.30209	.95328	.31868	.94786	.33518	.94215	25
36	.26892	.96316	.28569	.95832	.30237	.95319	.31896	.94777	.33545	.94206	24
37	.26920	.96308	.28597	.95824	.30265	.95310	.31923	.94768	.33573	.94196	23
38	.26948	.96301	.28625	.95816	.30292	.95301	.31951	.94758	.33600	.94186	22
39	.26976	.96293	.28652	.95807	.30320	.95293	.31979	.94749	.33627	.94176	21
40	.27004	.96285	.28680	.95799	.30348	.95284	.32006	.94740	.33655	.94167	20
41	.27032	.96277	.28708	.95791	.30376	.95275	.32034	.94730	.33682	.94157	19
42	.27060	.96269	.28736	.95782	.30403	.95266	.32061	.94721	.33710	.94147	18
43	.27088	.96261	.28764	.95774	.30431	.95257	.32089	.94712	.33737	.94137	17
44	.27116	.96253	.28792	.95766	.30459	.95248	.32116	.94702	.33764	.94127	16
45	.27144	.96246	.28820	.95757	.30486	.95240	.32144	.94693	.33792	.94118	15
46	.27172	.96238	.28847	.95749	.30514	.95231	.32171	.94684	.33819	.94108	14
47	.27200	.96230	.28875	.95740	.30542	.95222	.32199	.94674	.33846	.94098	13
48	.27228	.96222	.28903	.95732	.30570	.95213	.32227	.94665	.33874	.94088	12
49	.27256	.96214	.28931	.95724	.30597	.95204	.32254	.94656	.33901	.94078	11
50	.27284	.96206	.28959	.95715	.30625	.95195	.32282	.94646	.33929	.94068	10
51	.27312	.96198	.28987	.95707	.30653	.95186	.32309	.94637	.33956	.94058	9
52	.27340	.96190	.29015	.95698	.30680	.95177	.32337	.94627	.33983	.94049	8
53	.27368	.96182	.29042	.95690	.30708	.95168	.32364	.94618	.34011	.94039	7
54	.27396	.96174	.29070	.95681	.30736	.95159	.32392	.94609	.34038	.94029	6
55	.27424	.96166	.29098	.95673	.30763	.95150	.32419	.94599	.34065	.94019	5
56	.27452	.96158	.29126	.95664	.30791	.95142	.32447	.94590	.34093	.94009	4
57	.27480	.96150	.29154	.95656	.30819	.95133	.32474	.94580	.34120	.93999	3
58	.27508	.96142	.29182	.95647	.30846	.95124	.32502	.94571	.34147	.93989	2
59	.27536	.96134	.29209	.95639	.30874	.95115	.32529	.94561	.34175	.93979	1
60	.27564	.96126	.29237	.95630	.30902	.95106	.32557	.94552	.34202	.93969	0
′	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	′
	74°		73°		72°		71°		70°		

TABLE IV.—NATURAL SINES AND COSINES.

′	20°		21°		22°		23°		24°		′
	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	
0	.34202	.93969	.35837	.93358	.37461	.92718	.39073	.92050	.40674	.91355	60
1	.34229	.93959	.35864	.93348	.37488	.92707	.39100	.92039	.40700	.91343	59
2	.34257	.93949	.35891	.93337	.37515	.92697	.39127	.92028	.40727	.91331	58
3	.34284	.93939	.35918	.93327	.37542	.92686	.39153	.92016	.40753	.91319	57
4	.34311	.93929	.35945	.93316	.37569	.92675	.39180	.92005	.40780	.91307	56
5	.34339	.93919	.35973	.93306	.37595	.92664	.39207	.91994	.40806	.91295	55
6	.34366	.93909	.36000	.93295	.37622	.92653	.39234	.91982	.40833	.91283	54
7	.34393	.93899	.36027	.93285	.37649	.92642	.39260	.91971	.40860	.91272	53
8	.34421	.93889	.36054	.93274	.37676	.92631	.39287	.91959	.40886	.91260	52
9	.34448	.93879	.36081	.93264	.37703	.92620	.39314	.91948	.40913	.91248	51
10	.34475	.93869	.36108	.93253	.37730	.92609	.39341	.91936	.40939	.91236	50
11	.34503	.93859	.36135	.93243	.37757	.92598	.39367	.91925	.40966	.91224	49
12	.34530	.93849	.36162	.93232	.37784	.92587	.39394	.91914	.40992	.91212	48
13	.34557	.93839	.36190	.93222	.37811	.92576	.39421	.91902	.41019	.91200	47
14	.34584	.93829	.36217	.93211	.37838	.92565	.39448	.91891	.41045	.91188	46
15	.34612	.93819	.36244	.93201	.37865	.92554	.39474	.91879	.41072	.91176	45
16	.34639	.93809	.36271	.93190	.37892	.92543	.39501	.91868	.41098	.91164	44
17	.34666	.93799	.36298	.93180	.37919	.92532	.39528	.91856	.41125	.91152	43
18	.34694	.93789	.36325	.93169	.37946	.92521	.39555	.91845	.41151	.91140	42
19	.34721	.93779	.36352	.93159	.37973	.92510	.39581	.91833	.41178	.91128	41
20	.34748	.93769	.36379	.93148	.37999	.92499	.39608	.91822	.41204	.91116	40
21	.34775	.93759	.36406	.93137	.38026	.92488	.39635	.91810	.41231	.91104	39
22	.34803	.93748	.36434	.93127	.38053	.92477	.39661	.91799	.41257	.91092	38
23	.34830	.93738	.36461	.93116	.38080	.92466	.39688	.91787	.41284	.91080	37
24	.34857	.93728	.36488	.93106	.38107	.92455	.39715	.91775	.41310	.91068	36
25	.34884	.93718	.36515	.93095	.38134	.92444	.39741	.91764	.41337	.91056	35
26	.34912	.93708	.36542	.93084	.38161	.92432	.39768	.91752	.41363	.91044	34
27	.34939	.93698	.36569	.93074	.38188	.92421	.39795	.91741	.41390	.91032	33
28	.34966	.93688	.36596	.93063	.38215	.92410	.39822	.91729	.41416	.91020	32
29	.34993	.93677	.36623	.93052	.38241	.92399	.39848	.91718	.41443	.91008	31
30	.35021	.93667	.36650	.93042	.38268	.92388	.39875	.91706	.41469	.90996	30
31	.35048	.93657	.36677	.93031	.38295	.92377	.39902	.91694	.41496	.90984	29
32	.35075	.93647	.36704	.93020	.38322	.92366	.39928	.91683	.41522	.90972	28
33	.35102	.93637	.36731	.93010	.38349	.92355	.39955	.91671	.41549	.90960	27
34	.35130	.93626	.36758	.92999	.38376	.92343	.39982	.91660	.41575	.90948	26
35	.35157	.93616	.36785	.92988	.38403	.92332	.40008	.91648	.41602	.90936	25
36	.35184	.93606	.36812	.92978	.38430	.92321	.40035	.91636	.41628	.90924	24
37	.35211	.93596	.36839	.92967	.38456	.92310	.40062	.91625	.41655	.90911	23
38	.35239	.93585	.36867	.92956	.38483	.92299	.40088	.91613	.41681	.90899	22
39	.35266	.93575	.36894	.92945	.38510	.92287	.40115	.91601	.41707	.90887	21
40	.35293	.93565	.36921	.92935	.38537	.92276	.40141	.91590	.41734	.90875	20
41	.35320	.93555	.36948	.92924	.38564	.92265	.40168	.91578	.41760	.90863	19
42	.35347	.93544	.36975	.92913	.38591	.92254	.40195	.91566	.41787	.90851	18
43	.35375	.93534	.37002	.92902	.38617	.92243	.40221	.91555	.41813	.90839	17
44	.35402	.93524	.37029	.92892	.38644	.92231	.40248	.91543	.41840	.90826	16
45	.35429	.93514	.37056	.92881	.38671	.92220	.40275	.91531	.41866	.90814	15
46	.35456	.93503	.37083	.92870	.38698	.92209	.40301	.91519	.41892	.90802	14
47	.35484	.93493	.37110	.92859	.38725	.92198	.40328	.91508	.41919	.90790	13
48	.35511	.93483	.37137	.92849	.38752	.92186	.40355	.91496	.41945	.90778	12
49	.35538	.93472	.37164	.92838	.38778	.92175	.40381	.91484	.41972	.90766	11
50	.35565	.93462	.37191	.92827	.38805	.92164	.40408	.91472	.41998	.90753	10
51	.35592	.93452	.37218	.92816	.38832	.92152	.40434	.91461	.42024	.90741	9
52	.35619	.93441	.37245	.92805	.38859	.92141	.40461	.91449	.42051	.90729	8
53	.35647	.93431	.37272	.92794	.38886	.92130	.40488	.91437	.42077	.90717	7
54	.35674	.93420	.37299	.92784	.38912	.92119	.40514	.91425	.42104	.90704	6
55	.35701	.93410	.37326	.92773	.38939	.92107	.40541	.91414	.42130	.90692	5
56	.35728	.93400	.37353	.92762	.38966	.92096	.40567	.91402	.42156	.90680	4
57	.35755	.93389	.37380	.92751	.38993	.92085	.40594	.91390	.42183	.90668	3
58	.35782	.93379	.37407	.92740	.39020	.92073	.40621	.91378	.42209	.90655	2
59	.35810	.93368	.37434	.92729	.39046	.92062	.40647	.91366	.42235	.90643	1
60	.35837	.93358	.37461	.92718	.39073	.92050	.40674	.91355	.42262	.90631	0
′	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	′
	69°		68°		67°		66°		65°		

TABLE IV.—NATURAL SINES AND COSINES.

′	25°		26°		27°		28°		29°		′
	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	
0	.42262	.90631	.43837	.89879	.45399	.89101	.46947	.88295	.48481	.87462	60
1	.42288	.90618	.43863	.89867	.45425	.89087	.46973	.88281	.48506	.87448	59
2	.42315	.90606	.43889	.89854	.45451	.89074	.46999	.88267	.48532	.87434	58
3	.42341	.90594	.43916	.89841	.45477	.89061	.47024	.88254	.48557	.87420	57
4	.42367	.90582	.43942	.89828	.45503	.89048	.47050	.88240	.48583	.87406	56
5	.42394	.90569	.43968	.89816	.45529	.89035	.47076	.88226	.48608	.87391	55
6	.42420	.90557	.43994	.89803	.45554	.89021	.47101	.88213	.48634	.87377	54
7	.42446	.90545	.44020	.89790	.45580	.89008	.47127	.88199	.48659	.87363	53
8	.42473	.90532	.44046	.89777	.45606	.88995	.47153	.88185	.48684	.87349	52
9	.42499	.90520	.44072	.89764	.45632	.88981	.47178	.88172	.48710	.87335	51
10	.42525	.90507	.44098	.89752	.45658	.88968	.47204	.88158	.48735	.87321	50
11	.42552	.90495	.44124	.89739	.45684	.88955	.47229	.88144	.48761	.87306	49
12	.42578	.90483	.44151	.89726	.45710	.88942	.47255	.88130	.48786	.87292	48
13	.42604	.90470	.44177	.89713	.45736	.88928	.47281	.88117	.48811	.87278	47
14	.42631	.90458	.44203	.89700	.45762	.88915	.47306	.88103	.48837	.87264	46
15	.42657	.90446	.44229	.89687	.45787	.88902	.47332	.88089	.48862	.87250	45
16	.42683	.90433	.44255	.89674	.45813	.88888	.47358	.88075	.48888	.87235	44
17	.42709	.90421	.44281	.89662	.45839	.88875	.47383	.88062	.48913	.87221	43
18	.42736	.90408	.44307	.89649	.45865	.88862	.47409	.88048	.48938	.87207	42
19	.42762	.90396	.44333	.89636	.45891	.88848	.47434	.88034	.48964	.87193	41
20	.42788	.90383	.44359	.89623	.45917	.88835	.47460	.88020	.48989	.87178	40
21	.42815	.90371	.44385	.89610	.45942	.88822	.47486	.88006	.49014	.87164	39
22	.42841	.90358	.44411	.89597	.45968	.88808	.47511	.87993	.49040	.87150	38
23	.42867	.90346	.44437	.89584	.45994	.88795	.47537	.87979	.49065	.87136	37
24	.42894	.90334	.44464	.89571	.46020	.88782	.47562	.87965	.49090	.87121	36
25	.42920	.90321	.44490	.89558	.46046	.88768	.47588	.87951	.49116	.87107	35
26	.42946	.90309	.44516	.89545	.46072	.88755	.47614	.87937	.49141	.87093	34
27	.42972	.90296	.44542	.89532	.46097	.88741	.47639	.87923	.49166	.87079	33
28	.42999	.90284	.44568	.89519	.46123	.88728	.47665	.87909	.49192	.87064	32
29	.43025	.90271	.44594	.89506	.46149	.88715	.47690	.87896	.49217	.87050	31
30	.43051	.90259	.44620	.89493	.46175	.88701	.47716	.87882	.49242	.87036	30
31	.43077	.90246	.44646	.89480	.46201	.88688	.47741	.87868	.49268	.87021	29
32	.43104	.90233	.44672	.89467	.46226	.88674	.47767	.87854	.49293	.87007	28
33	.43130	.90221	.44698	.89454	.46252	.88661	.47793	.87840	.49318	.86993	27
34	.43156	.90208	.44724	.89441	.46278	.88647	.47818	.87826	.49344	.86978	26
35	.43182	.90196	.44750	.89428	.46304	.88634	.47844	.87812	.49369	.86964	25
36	.43209	.90183	.44776	.89415	.46330	.88620	.47869	.87798	.49394	.86949	24
37	.43235	.90171	.44802	.89402	.46355	.88607	.47895	.87784	.49419	.86935	23
38	.43261	.90158	.44828	.89389	.46381	.88593	.47920	.87770	.49445	.86921	22
39	.43287	.90146	.44854	.89376	.46407	.88580	.47946	.87756	.49470	.86906	21
40	.43313	.90133	.44880	.89363	.46433	.88566	.47971	.87743	.49495	.86892	20
41	.43340	.90120	.44906	.89350	.46458	.88553	.47997	.87729	.49521	.86878	19
42	.43366	.90108	.44932	.89337	.46484	.88539	.48022	.87715	.49546	.86863	18
43	.43392	.90095	.44958	.89324	.46510	.88526	.48048	.87701	.49571	.86849	17
44	.43418	.90082	.44984	.89311	.46536	.88512	.48073	.87687	.49596	.86834	16
45	.43445	.90070	.45010	.89298	.46561	.88499	.48099	.87673	.49622	.86820	15
46	.43471	.90057	.45036	.89285	.46587	.88485	.48124	.87659	.49647	.86805	14
47	.43497	.90045	.45062	.89272	.46613	.88472	.48150	.87645	.49672	.86791	13
48	.43523	.90032	.45088	.89259	.46639	.88458	.48175	.87631	.49697	.86777	12
49	.43549	.90019	.45114	.89245	.46664	.88445	.48201	.87617	.49723	.86762	11
50	.43575	.90007	.45140	.89232	.46690	.88431	.48226	.87603	.49748	.86748	10
51	.43602	.89994	.45166	.89219	.46716	.88417	.48252	.87589	.49773	.86733	9
52	.43628	.89981	.45192	.89206	.46742	.88404	.48277	.87575	.49798	.86719	8
53	.43654	.89968	.45218	.89193	.46767	.88390	.48303	.87561	.49824	.86704	7
54	.43680	.89956	.45243	.89180	.46793	.88377	.48328	.87546	.49849	.86690	6
55	.43706	.89943	.45269	.89167	.46819	.88363	.48354	.87532	.49874	.86675	5
56	.43733	.89930	.45295	.89153	.46844	.88349	.48379	.87518	.49899	.86661	4
57	.43759	.89918	.45321	.89140	.46870	.88336	.48405	.87504	.49924	.86646	3
58	.43785	.89905	.45347	.89127	.46896	.88322	.48430	.87490	.49950	.86632	2
59	.43811	.89892	.45373	.89114	.46921	.88308	.48456	.87476	.49975	.86617	1
60	.43837	.89879	.45399	.89101	.46947	.88295	.48481	.87462	.50000	.86603	0
′	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	′
	64°		63°		62°		61°		60°		

TABLE IV.—NATURAL SINES AND COSINES.

′	30°		31°		32°		33°		34°		′
	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	
0	.50000	.86603	.51504	.85717	.52992	.84805	.54464	.83867	.55919	.82904	60
1	.50025	.86588	.51529	.85702	.53017	.84789	.54488	.83851	.55943	.82887	59
2	.50050	.86573	.51554	.85687	.53041	.84774	.54513	.83835	.55968	.82871	58
3	.50076	.86559	.51579	.85672	.53066	.84759	.54537	.83819	.55992	.82855	57
4	.50101	.86544	.51604	.85657	.53091	.84743	.54561	.83804	.56016	.82839	56
5	.50126	.86530	.51628	.85642	.53115	.84728	.54586	.83788	.56040	.82822	55
6	.50151	.86515	.51653	.85627	.53140	.84712	.54610	.83772	.56064	.82806	54
7	.50176	.86501	.51678	.85612	.53164	.84697	.54635	.83756	.56088	.82790	53
8	.50201	.86486	.51703	.85597	.53189	.84681	.54659	.83740	.56112	.82773	52
9	.50227	.86471	.51728	.85582	.53214	.84666	.54683	.83724	.56136	.82757	51
10	.50252	.86457	.51753	.85567	.53238	.84650	.54708	.83708	.56160	.82741	50
11	.50277	.86442	.51778	.85551	.53263	.84635	.54732	.83692	.56184	.82724	49
12	.50302	.86427	.51803	.85536	.53288	.84619	.54756	.83676	.56208	.82708	48
13	.50327	.86413	.51828	.85521	.53312	.84604	.54781	.83660	.56232	.82692	47
14	.50352	.86398	.51852	.85506	.53337	.84588	.54805	.83645	.56256	.82675	46
15	.50377	.86384	.51877	.85491	.53361	.84573	.54829	.83629	.56280	.82659	45
16	.50403	.86369	.51902	.85476	.53386	.84557	.54851	.83613	.56305	.82643	44
17	.50428	.86354	.51927	.85461	.53411	.84542	.54878	.83597	.56329	.82626	43
18	.50453	.86340	.51952	.85446	.53435	.84526	.54902	.83581	.56353	.82610	42
19	.50478	.86325	.51977	.85431	.53460	.84511	.54927	.83565	.56377	.82593	41
20	.50503	.86310	.52002	.85416	.53484	.84495	.54951	.83549	.56401	.82577	40
21	.50528	.86295	.52026	.85401	.53509	.84480	.54975	.83533	.56425	.82561	39
22	.50553	.86281	.52051	.85385	.53534	.84464	.54999	.83517	.56449	.82544	38
23	.50578	.86266	.52076	.85370	.53558	.84448	.55024	.83501	.56473	.82528	37
24	.50603	.86251	.52101	.85355	.53583	.84433	.55048	.83485	.56497	.82511	36
25	.50628	.86237	.52126	.85340	.53607	.84417	.55072	.83469	.56521	.82495	35
26	.50654	.86222	.52151	.85325	.53632	.84402	.55097	.83453	.56545	.82478	34
27	.50679	.86207	.52175	.85310	.53656	.84386	.55121	.83437	.56569	.82462	33
28	.50704	.86192	.52200	.85294	.53681	.84370	.55145	.83421	.56593	.82446	32
29	.50729	.86178	.52225	.85279	.53705	.84355	.55169	.83405	.56617	.82429	31
30	.50754	.86163	.52250	.85264	.53730	.84339	.55194	.83389	.56641	.82413	30
31	.50779	.86148	.52275	.85249	.53754	.84324	.55218	.83373	.56665	.82396	29
32	.50804	.86133	.52299	.85234	.53779	.84308	.55242	.83356	.56689	.82380	28
33	.50829	.86119	.52324	.85218	.53804	.84292	.55266	.83340	.56713	.82363	27
34	.50854	.86104	.52349	.85203	.53828	.84277	.55291	.83324	.56736	.82347	26
35	.50879	.86089	.52374	.85188	.53853	.84261	.55315	.83308	.56760	.82330	25
36	.50904	.86074	.52399	.85173	.53877	.84245	.55339	.83292	.56784	.82314	24
37	.50929	.86059	.52423	.85157	.53902	.84230	.55363	.83276	.56808	.82297	23
38	.50954	.86045	.52448	.85142	.53926	.84214	.55388	.83260	.56832	.82281	22
39	.50979	.86030	.52473	.85127	.53951	.84198	.55412	.83244	.56856	.82264	21
40	.51004	.86015	.52498	.85112	.53975	.84182	.55436	.83228	.56880	.82248	20
41	.51029	.86000	.52522	.85096	.54000	.84167	.55460	.83212	.56904	.82231	19
42	.51054	.85985	.52547	.85081	.54024	.84151	.55484	.83195	.56928	.82214	18
43	.51079	.85970	.52572	.85066	.54049	.84135	.55509	.83179	.56952	.82198	17
44	.51104	.85956	.52597	.85051	.54073	.84120	.55533	.83163	.56976	.82181	16
45	.51129	.85941	.52621	.85035	.54097	.84104	.55557	.83147	.57000	.82165	15
46	.51154	.85926	.52646	.85020	.54122	.84088	.55581	.83131	.57024	.82148	14
47	.51179	.85911	.52671	.85005	.54146	.84072	.55605	.83115	.57047	.82132	13
48	.51204	.85896	.52696	.84989	.54171	.84057	.55630	.83098	.57071	.82115	12
49	.51229	.85881	.52720	.84974	.54195	.84041	.55654	.83082	.57095	.82098	11
50	.51254	.85866	.52745	.84959	.54220	.84025	.55678	.83066	.57119	.82082	10
51	.51279	.85851	.52770	.84943	.54244	.84009	.55702	.83050	.57143	.82065	9
52	.51304	.85836	.52794	.84928	.54269	.83994	.55726	.83034	.57167	.82048	8
53	.51329	.85821	.52819	.84913	.54293	.83978	.55750	.83017	.57191	.82032	7
54	.51354	.85806	.52844	.84897	.54317	.83962	.55775	.83001	.57215	.82015	6
55	.51379	.85792	.52869	.84882	.54342	.83946	.55799	.82985	.57238	.81999	5
56	.51404	.85777	.52893	.84866	.54366	.83930	.55823	.82969	.57262	.81982	4
57	.51429	.85762	.52918	.84851	.54391	.83915	.55847	.82953	.57286	.81965	3
58	.51454	.85747	.52943	.84836	.54415	.83899	.55871	.82936	.57310	.81949	2
59	.51479	.85732	.52967	.84820	.54440	.83883	.55895	.82920	.57334	.81932	1
60	.51504	.85717	.52992	.84805	.54464	.83867	.55919	.82904	.57358	.81915	0
′	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	′
	59°		58°		57°		56°		55°		

TABLE IV.—NATURAL SINES AND COSINES.

′	35°		36°		37°		38°		39°		′
	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	
0	.57358	.81915	.58779	.80902	.60182	.79864	.61566	.78801	.62932	.77715	60
1	.57381	.81899	.58802	.80885	.60205	.79846	.61589	.78783	.62955	.77696	59
2	.57405	.81882	.58826	.80867	.60228	.79829	.61612	.78765	.62977	.77678	58
3	.57429	.81865	.58849	.80850	.60251	.79811	.61635	.78747	.63000	.77660	57
4	.57453	.81848	.58873	.80833	.60274	.79793	.61658	.78729	.63022	.77641	56
5	.57477	.81832	.58896	.80816	.60298	.79776	.61681	.78711	.63045	.77623	55
6	.57501	.81815	.58920	.80799	.60321	.79758	.61704	.78694	.63068	.77605	54
7	.57524	.81798	.58943	.80782	.60344	.79741	.61726	.78676	.63090	.77586	53
8	.57548	.81782	.58967	.80765	.60367	.79723	.61749	.78658	.63113	.77568	52
9	.57572	.81765	.58990	.80748	.60390	.79706	.61772	.78640	.63135	.77550	51
10	.57596	.81748	.59014	.80730	.60414	.79688	.61795	.78622	.63158	.77531	50
11	.57619	.81731	.59037	.80713	.60437	.79671	.61818	.78604	.63180	.77513	49
12	.57643	.81714	.59061	.80696	.60460	.79653	.61841	.78586	.63203	.77494	48
13	.57667	.81698	.59084	.80679	.60483	.79635	.61864	.78568	.63225	.77476	47
14	.57691	.81681	.59108	.80662	.60506	.79618	.61887	.78550	.63248	.77458	46
15	.57715	.81664	.59131	.80644	.60529	.79600	.61909	.78532	.63271	.77439	45
16	.57738	.81647	.59154	.80627	.60553	.79583	.61932	.78514	.63293	.77421	44
17	.57762	.81631	.59178	.80610	.60576	.79565	.61955	.78496	.63316	.77402	43
18	.57786	.81614	.59201	.80593	.60599	.79547	.61978	.78478	.63338	.77384	42
19	.57810	.81597	.59225	.80576	.60622	.79530	.62001	.78460	.63361	.77366	41
20	.57833	.81580	.59248	.80558	.60645	.79512	.62024	.78442	.63383	.77347	40
21	.57857	.81563	.59272	.80541	.60668	.79494	.62046	.78424	.63406	.77329	39
22	.57881	.81546	.59295	.80524	.60691	.79477	.62069	.78405	.63428	.77310	38
23	.57904	.81530	.59318	.80507	.60714	.79459	.62092	.78387	.63451	.77292	37
24	.57928	.81513	.59342	.80489	.60738	.79441	.62115	.78369	.63473	.77273	36
25	.57952	.81496	.59365	.80472	.60761	.79424	.62138	.78351	.63496	.77255	35
26	.57976	.81479	.59389	.80455	.60784	.79406	.62160	.78333	.63518	.77236	34
27	.57999	.81462	.59412	.80438	.60807	.79388	.62183	.78315	.63540	.77218	33
28	.58023	.81445	.59436	.80420	.60830	.79371	.62206	.78297	.63563	.77199	32
29	.58047	.81428	.59459	.80403	.60853	.79353	.62229	.78279	.63585	.77181	31
30	.58070	.81412	.59482	.80386	.60876	.79335	.62251	.78261	.63608	.77162	30
31	.58094	.81395	.59506	.80368	.60899	.79318	.62274	.78243	.63630	.77144	29
32	.58118	.81378	.59529	.80351	.60922	.79300	.62297	.78225	.63653	.77125	28
33	.58141	.81361	.59552	.80334	.60945	.79282	.62320	.78206	.63675	.77107	27
34	.58165	.81344	.59576	.80316	.60968	.79264	.62342	.78188	.63698	.77088	26
35	.58189	.81327	.59599	.80299	.60991	.79247	.62365	.78170	.63720	.77070	25
36	.58212	.81310	.59622	.80282	.61015	.79229	.62388	.78152	.63742	.77051	24
37	.58236	.81293	.59646	.80264	.61038	.79211	.62411	.78134	.63765	.77033	23
38	.58260	.81276	.59669	.80247	.61061	.79193	.62433	.78116	.63787	.77014	22
39	.58283	.81259	.59693	.80230	.61084	.79176	.62456	.78098	.63810	.76996	21
40	.58307	.81242	.59716	.80212	.61107	.79158	.62479	.78079	.63832	.76977	20
41	.58330	.81225	.59739	.80195	.61130	.79140	.62502	.78061	.63854	.76959	19
42	.58354	.81208	.59763	.80178	.61153	.79122	.62524	.78043	.63877	.76940	18
43	.58378	.81191	.59786	.80160	.61176	.79105	.62547	.78025	.63899	.76921	17
44	.58401	.81174	.59809	.80143	.61199	.79087	.62570	.78007	.63922	.76903	16
45	.58425	.81157	.59832	.80125	.61222	.79069	.62592	.77988	.63944	.76884	15
46	.58449	.81140	.59856	.80108	.61245	.79051	.62615	.77970	.63966	.76866	14
47	.58472	.81123	.59879	.80091	.61268	.79033	.62638	.77952	.63989	.76847	13
48	.58496	.81106	.59902	.80073	.61291	.79016	.62660	.77934	.64011	.76828	12
49	.58519	.81089	.59926	.80056	.61314	.78998	.62683	.77916	.64033	.76810	11
50	.58543	.81072	.59949	.80038	.61337	.78980	.62706	.77897	.64056	.76791	10
51	.58567	.81055	.59972	.80021	.61360	.78962	.62728	.77879	.64078	.76772	9
52	.58590	.81038	.59995	.80003	.61383	.78944	.62751	.77861	.64100	.76754	8
53	.58614	.81021	.60019	.79986	.61406	.78926	.62774	.77843	.64123	.76735	7
54	.58637	.81004	.60042	.79968	.61429	.78908	.62796	.77824	.64145	.76717	6
55	.58661	.80987	.60065	.79951	.61451	.78891	.62819	.77806	.64167	.76698	5
56	.58684	.80970	.60089	.79934	.61474	.78873	.62842	.77788	.64190	.76679	4
57	.58708	.80953	.60112	.79916	.61497	.78855	.62864	.77769	.64212	.76661	3
58	.58731	.80936	.60135	.79899	.61520	.78837	.62887	.77751	.64234	.76642	2
59	.58755	.80919	.60158	.79881	.61543	.78819	.62909	.77733	.64256	.76623	1
60	.58779	.80902	.60182	.79864	.61566	.78801	.62932	.77715	.64279	.76604	0
′	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	
	54°		53°		52°		51°		50°		

TABLE IV.—NATURAL SINES AND COSINES.

′	40°		41°		42°		43°		44°		′
	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	
0	.64279	.76604	.65606	.75471	.66913	.74314	.68200	.73135	.69466	.71934	60
1	.64301	.76586	.65628	.75452	.66935	.74295	.68221	.73116	.69487	.71914	59
2	.64323	.76567	.65650	.75433	.66956	.74276	.68242	.73096	.69508	.71894	58
3	.64346	.76548	.65672	.75414	.66978	.74256	.68264	.73076	.69529	.71873	57
4	.64368	.76530	.65694	.75395	.66999	.74237	.68285	.73056	.69549	.71853	56
5	.64390	.76511	.65716	.75375	.67021	.74217	.68306	.73036	.69570	.71833	55
6	.64412	.76492	.65738	.75356	.67043	.74198	.68327	.73016	.69591	.71813	54
7	.64435	.76473	.65759	.75337	.67064	.74178	.68349	.72996	.69612	.71792	53
8	.64457	.76455	.65781	.75318	.67086	.74159	.68370	.72976	.69633	.71772	52
9	.64479	.76436	.65803	.75299	.67107	.74139	.68391	.72957	.69654	.71752	51
10	.64501	.76417	.65825	.75280	.67129	.74120	.68412	.72937	.69675	.71732	50
11	.64524	.76398	.65847	.75261	.67151	.74100	.68434	.72917	.69696	.71711	49
12	.64546	.76380	.65869	.75241	.67172	.74080	.68455	.72897	.69717	.71691	48
13	.64568	.76361	.65891	.75222	.67194	.74061	.68476	.72877	.69737	.71671	47
14	.64590	.76342	.65913	.75203	.67215	.74041	.68497	.72857	.69758	.71650	46
15	.64612	.76323	.65935	.75184	.67237	.74022	.68518	.72837	.69779	.71630	45
16	.64635	.76304	.65956	.75165	.67258	.74002	.68539	.72817	.69800	.71610	44
17	.64657	.76286	.65978	.75146	.67280	.73983	.68561	.72797	.69821	.71590	43
18	.64679	.76267	.66000	.75126	.67301	.73963	.68582	.72777	.69842	.71569	42
19	.64701	.76248	.66022	.75107	.67323	.73944	.68603	.72757	.69862	.71549	41
20	.64723	.76229	.66044	.75088	.67344	.73924	.68624	.72737	.69883	.71529	40
21	.64746	.76210	.66066	.75069	.67366	.73904	.68645	.72717	.69904	.71508	39
22	.64768	.76192	.66088	.75050	.67387	.73885	.68666	.72697	.69925	.71488	38
23	.64790	.76173	.66109	.75030	.67409	.73865	.68688	.72677	.69946	.71468	37
24	.64812	.76154	.66131	.75011	.67430	.73846	.68709	.72657	.69966	.71447	36
25	.64834	.76135	.66153	.74992	.67452	.73826	.68730	.72637	.69987	.71427	35
26	.64856	.76116	.66175	.74973	.67473	.73806	.68751	.72617	.70008	.71407	34
27	.64878	.76097	.66197	.74953	.67495	.73787	.68772	.72597	.70029	.71386	33
28	.64901	.76078	.66218	.74934	.67516	.73767	.68793	.72577	.70049	.71366	32
29	.64923	.76059	.66240	.74915	.67538	.73747	.68814	.72557	.70070	.71345	31
30	.64945	.76041	.66262	.74896	.67559	.73728	.68835	.72537	.70091	.71325	30
31	.64967	.76022	.66284	.74876	.67580	.73708	.68857	.72517	.70112	.71305	29
32	.64989	.76003	.66306	.74857	.67602	.73688	.68878	.72497	.70132	.71284	28
33	.65011	.75984	.66327	.74838	.67623	.73669	.68899	.72477	.70153	.71264	27
34	.65033	.75965	.66349	.74818	.67645	.73649	.68920	.72457	.70174	.71243	26
35	.65055	.75946	.66371	.74799	.67666	.73629	.68941	.72437	.70195	.71223	25
36	.65077	.75927	.66393	.74780	.67688	.73610	.68962	.72417	.70215	.71203	24
37	.65100	.75908	.66414	.74760	.67709	.73590	.68983	.72397	.70236	.71182	23
38	.65122	.75889	.66436	.74741	.67730	.73570	.69004	.72377	.70257	.71162	22
39	.65144	.75870	.66458	.74722	.67752	.73551	.69025	.72357	.70277	.71141	21
40	.65166	.75851	.66480	.74703	.67773	.73531	.69046	.72337	.70298	.71121	20
41	.65188	.75832	.66501	.74683	.67795	.73511	.69067	.72317	.70319	.71100	19
42	.65210	.75813	.66523	.74664	.67816	.73491	.69088	.72297	.70339	.71080	18
43	.65232	.75794	.66545	.74644	.67837	.73472	.69109	.72277	.70360	.71059	17
44	.65254	.75775	.66566	.74625	.67859	.73452	.69130	.72257	.70381	.71039	16
45	.65276	.75756	.66588	.74606	.67880	.73432	.69151	.72236	.70401	.71019	15
46	.65298	.75738	.66610	.74586	.67901	.73413	.69172	.72216	.70422	.70998	14
47	.65320	.75719	.66632	.74567	.67923	.73393	.69193	.72196	.70443	.70978	13
48	.65342	.75700	.66653	.74548	.67944	.73373	.69214	.72176	.70463	.70957	12
49	.65364	.75680	.66675	.74528	.67965	.73353	.69235	.72156	.70484	.70937	11
50	.65386	.75661	.66697	.74509	.67987	.73333	.69256	.72136	.70505	.70916	10
51	.65408	.75642	.66718	.74489	.68008	.73314	.69277	.72116	.70525	.70896	9
52	.65430	.75623	.66740	.74470	.68029	.73294	.69298	.72095	.70546	.70875	8
53	.65452	.75604	.66762	.74451	.68051	.73274	.69319	.72075	.70567	.70855	7
54	.65474	.75585	.66783	.74431	.68072	.73254	.69340	.72055	.70587	.70834	6
55	.65496	.75566	.66805	.74412	.68093	.73234	.69361	.72035	.70608	.70813	5
56	.65518	.75547	.66827	.74392	.68115	.73215	.69382	.72015	.70628	.70793	4
57	.65540	.75528	.66848	.74373	.68136	.73195	.69403	.71995	.70649	.70772	3
58	.65562	.75509	.66870	.74352	.68157	.73175	.69424	.71974	.70670	.70752	2
59	.65584	.75490	.66891	.74334	.68179	.73155	.69445	.71954	.70690	.70731	1
60	.65606	.75471	.66913	.74314	.68200	.73135	.69466	.71934	.70711	.70711	0
′	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	′
	49°		48°		47°		46°		45°		

TABLE V.—NATURAL TANGENTS AND COTANGENTS.

′	0°		1°		2°		3°		′
	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	
0	.00000	Infinite.	.01746	57.2900	.03492	28.6363	.05241	19.0811	60
1	.00029	3437.75	.01775	56.3506	.03521	28.3994	.05270	18.9755	59
2	.00058	1718.87	.01804	55.4415	.03550	28.1664	.05299	18.8711	58
3	.00087	1145.92	.01833	54.5613	.03579	27.9372	.05328	18.7678	57
4	.00116	859.436	.01862	53.7086	.03609	27.7117	.05357	18.6656	56
5	.00145	687.549	.01891	52.8821	.03638	27.4899	.05387	18.5645	55
6	.00175	572.957	.01920	52.0807	.03667	27.2715	.05416	18.4645	54
7	.00204	491.106	.01949	51.3032	.03696	27.0566	.05445	18.3655	53
8	.00233	429.718	.01978	50.5485	.03725	26.8450	.05474	18.2677	52
9	.00262	381.971	.02007	49.8157	.03754	26.6367	.05503	18.1708	51
10	.00291	343.774	.02036	49.1039	.03783	26.4316	.05533	18.0750	50
11	.00320	312.521	.02066	48.4121	.03812	26.2296	.05562	17.9802	49
12	.00349	286.478	.02095	47.7395	.03842	26.0307	.05591	17.8863	48
13	.00378	264.441	.02124	47.0853	.03871	25.8348	.05620	17.7934	47
14	.00407	245.552	.02153	46.4489	.03900	25.6418	.05649	17.7015	46
15	.00436	229.182	.02182	45.8294	.03929	25.4517	.05678	17.6106	45
16	.00465	214.858	.02211	45.2261	.03958	25.2644	.05708	17.5205	44
17	.00495	202.219	.02240	44.6386	.03987	25.0798	.05737	17.4314	43
18	.00524	190.984	.02269	44.0661	.04016	24.8978	.05766	17.3432	42
19	.00553	180.932	.02298	43.5081	.04046	24.7185	.05795	17.2558	41
20	.00582	171.885	.02328	42.9641	.04075	24.5418	.05824	17.1693	40
21	.00611	163.700	.02357	42.4335	.04104	24.3675	.05854	17.0837	39
22	.00640	156.259	.02386	41.9158	.04133	24.1957	.05883	16.9990	38
23	.00669	149.465	.02415	41.4106	.04162	24.0263	.05912	16.9150	37
24	.00698	143.237	.02444	40.9174	.04191	23.8593	.05941	16.8319	36
25	.00727	137.507	.02473	40.4358	.04220	23.6945	.05970	16.7496	35
26	.00756	132.219	.02502	39.9655	.04250	23.5321	.05999	16.6681	34
27	.00785	127.321	.02531	39.5059	.04279	23.3718	.06029	16.5874	33
28	.00815	122.774	.02560	39.0568	.04308	23.2137	.06058	16.5075	32
29	.00844	118.540	.02589	38.6177	.04337	23.0577	.06087	16.4283	31
30	.00873	114.589	.02619	38.1885	.04366	22.9038	.06116	16.3499	30
31	.00902	110.892	.02648	37.7686	.04395	22.7519	.06145	16.2722	29
32	.00931	107.426	.02677	37.3579	.04424	22.6020	.06175	16.1952	28
33	.00960	104.171	.02706	36.9560	.04454	22.4541	.06204	16.1190	27
34	.00989	101.107	.02735	36.5627	.04483	22.3081	.06233	16.0435	26
35	.01018	98.2179	.02764	36.1776	.04512	22.1640	.06262	15.9687	25
36	.01047	95.4895	.02793	35.8006	.04541	22.0217	.06291	15.8945	24
37	.01076	92.9085	.02822	35.4313	.04570	21.8813	.06321	15.8211	23
38	.01105	90.4633	.02851	35.0695	.04599	21.7426	.06350	15.7483	22
39	.01135	88.1436	.02881	34.7151	.04628	21.6056	.06379	15.6762	21
40	.01164	85.9398	.02910	34.3678	.04658	21.4704	.06408	15.6048	20
41	.01193	83.8435	.02939	34.0273	.04687	21.3369	.06437	15.5340	19
42	.01222	81.8470	.02968	33.6935	.04716	21.2049	.06467	15.4638	18
43	.01251	79.9434	.02997	33.3662	.04745	21.0747	.06496	15.3943	17
44	.01280	78.1263	.03026	33.0452	.04774	20.9460	.06525	15.3254	16
45	.01309	76.3900	.03055	32.7303	.04803	20.8188	.06554	15.2571	15
46	.01338	74.7292	.03084	32.4213	.04833	20.6932	.06584	15.1893	14
47	.01367	73.1390	.03114	32.1181	.04862	20.5691	.06613	15.1222	13
48	.01396	71.6151	.03143	31.8205	.04891	20.4465	.06642	15.0557	12
49	.01425	70.1533	.03172	31.5284	.04920	20.3253	.06671	14.9898	11
50	.01455	68.7501	.03201	31.2416	.04949	20.2056	.06700	14.9244	10
51	.01484	67.4019	.03230	30.9599	.04978	20.0872	.06730	14.8596	9
52	.01513	66.1055	.03259	30.6833	.05007	19.9702	.06759	14.7954	8
53	.01542	64.8580	.03288	30.4116	.05037	19.8546	.06788	14.7317	7
54	.01571	63.6567	.03317	30.1446	.05066	19.7403	.06817	14.6685	6
55	.01600	62.4992	.03346	29.8823	.05095	19.6273	.06847	14.6059	5
56	.01629	61.3829	.03376	29.6245	.05124	19.5156	.06876	14.5438	4
57	.01658	60.3058	.03405	29.3711	.05153	19.4051	.06905	14.4823	3
58	.01687	59.2659	.03434	29.1220	.05182	19.2959	.06934	14.4212	2
59	.01716	58.2612	.03463	28.8771	.05212	19.1879	.06963	14.3607	1
60	.01746	57.2900	.03492	28.6363	.05241	19.0811	.06993	14.3007	0
′	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	′
	89°		88°		87°		86°		

TABLE V.—NATURAL TANGENTS AND COTANGENTS.

′	4°		5°		6°		7°		′
	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	
0	.06993	14.3007	.08749	11.4301	.10510	9.51436	.12278	8.14435	60
1	.07022	14.2411	.08778	11.3919	.10540	9.48781	.12308	8.12481	59
2	.07051	14.1821	.08807	11.3540	.10569	9.46141	.12338	8.10536	58
3	.07080	14.1235	.08837	11.3163	.10599	9.43515	.12367	8.08600	57
4	.07110	14.0655	.08866	11.2789	.10628	9.40904	.12397	8.06674	56
5	.07139	14.0079	.08895	11.2417	.10657	9.38307	.12426	8.04756	55
6	.07168	13.9507	.08925	11.2048	.10687	9.35724	.12456	8.02848	54
7	.07197	13.8940	.08954	11.1681	.10716	9.33155	.12185	8.00948	53
8	.07227	13.8378	.08983	11.1316	.10746	9.30599	.12515	7.99058	52
9	.07256	13.7821	.09013	11.0954	.10775	9.28058	.12544	7.97176	51
10	.07285	13.7267	.09042	11.0594	.10805	9.25530	.12574	7.95302	50
11	.07314	13.6719	.09071	11.0237	.10834	9.23016	.12603	7.93438	49
12	.07344	13.6174	.09101	10.9882	.10863	9.20516	.12633	7.91582	48
13	.07373	13.5634	.09130	10.9529	.10893	9.18028	.12662	7.89734	47
14	.07402	13.5098	.09159	10.9178	.10922	9.15554	.12692	7.87895	46
15	.07431	13.4566	.09189	10.8829	.10952	9.13093	.12722	7.86064	45
16	.07461	13.4039	.09218	10.8483	.10981	9.10646	.12751	7.84242	44
17	.07490	13.3515	.09247	10.8139	.11011	9.08211	.12781	7.82428	43
18	.07519	13.2996	.09277	10.7797	.11040	9.05789	.12810	7.80622	42
19	.07548	13.2480	.09306	10.7457	.11070	9.03379	.12840	7.78825	41
20	.07578	13.1969	.09335	10.7119	.11099	9.00983	.12869	7.77035	40
21	.07607	13.1461	.09365	10.6783	.11128	8.98598	.12899	7.75254	39
22	.07636	13.0958	.09394	10.6450	.11158	8.96227	.12929	7.73480	38
23	.07665	13.0458	.09423	10.6118	.11187	8.93867	.12958	7.71715	37
24	.07695	12.9962	.09453	10.5789	.11217	8.91520	.12988	7.69957	36
25	.07724	12.9469	.09482	10.5462	.11246	8.89185	.13017	7.68208	35
26	.07753	12.8981	.09511	10.5136	.11276	8.86862	.13047	7.66466	34
27	.07782	12.8496	.09541	10.4813	.11305	8.84551	.13076	7.64732	33
28	.07812	12.8014	.09570	10.4491	.11335	8.82252	.13106	7.63005	32
29	.07841	12.7536	.09600	10.4172	.11364	8.79964	.13136	7.61287	31
30	.07870	12.7062	.09629	10.3854	.11394	8.77689	.13165	7.59575	30
31	.07899	12.6591	.09658	10.3538	.11423	8.75425	.13195	7.57872	29
32	.07929	12.6124	.09688	10.3224	.11452	8.73172	.13224	7.56176	28
33	.07958	12.5660	.09717	10.2913	.11482	8.70931	.13254	7.54487	27
34	.07987	12.5199	.09746	10.2602	.11511	8.68701	.13284	7.52806	26
35	.08017	12.4742	.09776	10.2294	.11541	8.66482	.13313	7.51132	25
36	.08046	12.4288	.09805	10.1988	.11570	8.64275	.13343	7.49465	24
37	.08075	12.3838	.09834	10.1683	.11600	8.62078	.13372	7.47806	23
38	.08104	12.3390	.09864	10.1381	.11629	8.59893	.13102	7.46151	22
39	.08134	12.2946	.09893	10.1080	.11659	8.57718	.13432	7.44509	21
40	.08163	12.2505	.09923	10.0780	.11688	8.55555	.13461	7.42871	20
41	.08192	12.2067	.09952	10.0483	.11718	8.53402	.13491	7.41240	19
42	.08221	12.1632	.09981	10.0187	.11747	8.51259	.13521	7.39616	18
43	.08251	12.1201	.10011	9.98931	.11777	8.49128	.13550	7.37999	17
44	.08280	12.0772	.10040	9.96007	.11806	8.47007	.13580	7.36389	16
45	.08309	12.0346	.10069	9.93101	.11836	8.44896	.13609	7.34786	15
46	.08339	11.9923	.10099	9.90211	.11865	8.42795	.13639	7.33190	14
47	.08368	11.9504	.10128	9.87338	.11895	8.40705	.13669	7.31600	13
48	.08397	11.9087	.10158	9.84482	.11924	8.38625	.13698	7.30018	12
49	.08427	11.8673	.10187	9.81641	.11954	8.36555	.13728	7.28442	11
50	.08456	11.8262	.10216	9.78817	.11983	8.34496	.13758	7.26873	10
51	.08485	11.7853	.10246	9.76009	.12013	8.32446	.13787	7.25310	9
52	.08514	11.7448	.10275	9.73217	.12042	8.30406	.13817	7.23754	8
53	.08544	11.7045	.10305	9.70441	.12072	8.28376	.13846	7.22204	7
54	.08573	11.6645	.10334	9.67680	.12101	8.26355	.13876	7.20661	6
55	.08602	11.6248	.10363	9.64935	.12131	8.24345	.13906	7.19125	5
56	.08632	11.5853	.10393	9.62205	.12160	8.22344	.13935	7.17594	4
57	.08661	11.5461	.10422	9.59490	.12190	8.20352	.13965	7.16071	3
58	.08690	11.5072	.10452	9.56791	.12219	8.18370	.13995	7.14553	2
59	.08720	11.4685	.10481	9.54106	.12249	8.16398	.14024	7.13042	1
60	.08749	11.4301	.10510	9.51436	.12278	8.14435	.14054	7.11537	0
′	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	′
	85°		84°		83°		82°		

TABLE V.—NATURAL TANGENTS AND COTANGENTS.

′	8°		9°		10°		11°		′
	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	
0	.14054	7.11537	.15838	6.31375	.17632	5.67128	.19438	5.14455	60
1	.14084	7.10038	.15868	6.30189	.17663	5.66165	.19468	5.13658	59
2	.14113	7.08546	.15898	6.29007	.17693	5.65205	.19498	5.12862	58
3	.14143	7.07059	.15928	6.27829	.17723	5.64248	.19529	5.12069	57
4	.14173	7.05579	.15958	6.26655	.17753	5.63295	.19559	5.11279	56
5	.14202	7.04105	.15988	6.25486	.17783	5.62344	.19589	5.10490	55
6	.14232	7.02637	.16017	6.24321	.17813	5.61397	.19619	5.09704	54
7	.14262	7.01174	.16047	6.23160	.17843	5.60452	.19649	5.08921	53
8	.14291	6.99718	.16077	6.22003	.17873	5.59511	.19680	5.08139	52
9	.14321	6.98268	.16107	6.20851	.17903	5.58573	.19710	5.07360	51
10	.14351	6.96823	.16137	6.19703	.17933	5.57638	.19740	5.06584	50
11	.14381	6.95385	.16167	6.18559	.17963	5.56706	.19770	5.05809	49
12	.14410	6.93952	.16196	6.17419	.17993	5.55777	.19801	5.05037	48
13	.14440	6.92525	.16226	6.16283	.18023	5.54851	.19831	5.04267	47
14	.14470	6.91104	.16256	6.15151	.18053	5.53927	.19861	5.03499	46
15	.14499	6.89688	.16286	6.14023	.18083	5.53007	.19891	5.02734	45
16	.14529	6.88278	.16316	6.12899	.18113	5.52090	.19921	5.01971	44
17	.14559	6.86874	.16346	6.11779	.18143	5.51176	.19952	5.01210	43
18	.14588	6.85475	.16376	6.10664	.18173	5.50264	.19982	5.00451	42
19	.14618	6.84082	.16405	6.09552	.18203	5.49356	.20012	4.99695	41
20	.14648	6.82694	.16435	6.08444	.18233	5.48451	.20042	4.98940	40
21	.14678	6.81312	.16465	6.07340	.18263	5.47548	.20073	4.98188	39
22	.14707	6.79936	.16495	6.06240	.18293	5.46648	.20103	4.97438	38
23	.14737	6.78564	.16525	6.05143	.18323	5.45751	.20133	4.96690	37
24	.14767	6.77199	.16555	6.04051	.18353	5.44857	.20164	4.95945	36
25	.14796	6.75838	.16585	6.02962	.18384	5.43966	.20194	4.95201	35
26	.14826	6.74483	.16615	6.01878	.18414	5.43077	.20224	4.94460	34
27	.14856	6.73133	.16645	6.00797	.18444	5.42192	.20254	4.93721	33
28	.14886	6.71789	.16674	5.99720	.18474	5.41309	.20285	4.92984	32
29	.14915	6.70450	.16704	5.98646	.18504	5.40429	.20315	4.92249	31
30	.14945	6.69116	.16734	5.97576	.18534	5.39552	.20345	4.91516	30
31	.14975	6.67787	.16764	5.96510	.18564	5.38677	.20376	4.90785	29
32	.15005	6.66463	.16794	5.95448	.18594	5.37805	.20406	4.90056	28
33	.15034	6.65144	.16824	5.94390	.18624	5.36936	.20436	4.89330	27
34	.15064	6.63831	.16854	5.93335	.18654	5.36070	.20466	4.88605	26
35	.15094	6.62523	.16884	5.92283	.18684	5.35206	.20497	4.87882	25
36	.15124	6.61219	.16914	5.91236	.18714	5.34345	.20527	4.87162	24
37	.15153	6.59921	.16944	5.90191	.18745	5.33487	.20557	4.86444	23
38	.15183	6.58627	.16974	5.89151	.18775	5.32631	.20588	4.85727	22
39	.15213	6.57339	.17004	5.88114	.18805	5.31778	.20618	4.85013	21
40	.15243	6.56055	.17033	5.87080	.18835	5.30928	.20648	4.84300	20
41	.15272	6.54777	.17063	5.86051	.18865	5.30080	.20679	4.83590	19
42	.15302	6.53503	.17093	5.85024	.18895	5.29235	.20709	4.82882	18
43	.15332	6.52234	.17123	5.84001	.18925	5.28393	.20739	4.82175	17
44	.15362	6.50970	.17153	5.82982	.18955	5.27553	.20770	4.81471	16
45	.15391	6.49710	.17183	5.81966	.18986	5.26715	.20800	4.80769	15
46	.15421	6.48456	.17213	5.80953	.19016	5.25880	.20830	4.80068	14
47	.15451	6.47206	.17243	5.79944	.19046	5.25048	.20861	4.79370	13
48	.15481	6.45961	.17273	5.78938	.19076	5.24218	.20891	4.78673	12
49	.15511	6.44720	.17303	5.77936	.19106	5.23391	.20921	4.77978	11
50	.15540	6.43484	.17333	5.76937	.19136	5.22566	.20952	4.77286	10
51	.15570	6.42253	.17363	5.75941	.19166	5.21744	.20982	4.76595	9
52	.15600	6.41026	.17393	5.74949	.19197	5.20925	.21013	4.75906	8
53	.15630	6.39804	.17423	5.73960	.19227	5.20107	.21043	4.75219	7
54	.15660	6.38587	.17453	5.72974	.19257	5.19293	.21073	4.74534	6
55	.15689	6.37374	.17483	5.71992	.19287	5.18480	.21104	4.73851	5
56	.15719	6.36165	.17513	5.71013	.19317	5.17671	.21134	4.73170	4
57	.15749	6.34961	.17543	5.70037	.19347	5.16863	.21164	4.72490	3
58	.15779	6.33761	.17573	5.69064	.19378	5.16058	.21195	4.71813	2
59	.15809	6.32566	.17603	5.68094	.19408	5.15256	.21225	4.71137	1
60	.15838	6.31375	.17633	5.67128	.19438	5.14455	.21256	4.70463	0
′	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	′
	81°		80°		79°		78°		

TABLE V.—NATURAL TANGENTS AND COTANGENTS.

′	12°		13°		14°		15°		′
	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	
0	.21256	4.70463	.23087	4.33148	.24933	4.01078	.26795	3.73205	60
1	.21286	4.69791	.23117	4.32573	.24964	4.00582	.26826	3.72771	59
2	.21316	4.69121	.23148	4.32001	.24995	4.00086	.26857	3.72338	58
3	.21347	4.68452	.23179	4.31430	.25026	3.99592	.26888	3.71907	57
4	.21377	4.67786	.23209	4.30860	.25056	3.99099	.26920	3.71476	56
5	.21408	4.67121	.23210	4.30291	.25087	3.98607	.26951	3.71046	55
6	.21438	4.66458	.23271	4.29724	.25118	3.98117	.26982	3.70616	54
7	.21469	4.65797	.23301	4.29159	.25149	3.97627	.27013	3.70188	53
8	.21499	4.65138	.23332	4.28595	.25180	3.97139	.27044	3.69761	52
9	.21529	4.64480	.23363	4.28032	.25211	3.96651	.27076	3.69335	51
10	.21560	4.63825	.23393	4.27471	.25242	3.96165	.27107	3.68909	50
11	.21590	4.63171	.23424	4.26911	.25273	3.95680	.27138	3.68485	49
12	.21621	4.62518	.23455	4.26352	.25304	3.95196	.27169	3.68061	48
13	.21651	4.61868	.23485	4.25795	.25335	3.94713	.27201	3.67638	47
14	.21682	4.61219	.23516	4.25239	.25366	3.94232	.27232	3.67217	46
15	.21712	4.60572	.23547	4.24685	.25397	3.93751	.27263	3.66796	45
16	.21743	4.59927	.23578	4.24132	.25428	3.93271	.27294	3.66376	44
17	.21773	4.59283	.23608	4.23580	.25459	3.92793	.27326	3.65957	43
18	.21804	4.58641	.23639	4.23030	.25490	3.92316	.27357	3.65538	42
19	.21834	4.58001	.23670	4.22481	.25521	3.91839	.27388	3.65121	41
20	.21864	4.57363	.23700	4.21933	.25552	3.91364	.27419	3.64705	40
21	.21895	4.56726	.23731	4.21387	.25583	3.90890	.27451	3.64289	39
22	.21925	4.56091	.23762	4.20842	.25614	3.90417	.27482	3.63874	38
23	.21956	4.55458	.23793	4.20298	.25645	3.89945	.27513	3.63461	37
24	.21986	4.54826	.23823	4.19756	.25676	3.89474	.27545	3.63048	36
25	.22017	4.54196	.23854	4.19215	.25707	3.89004	.27576	3.62636	35
26	.22047	4.53568	.23885	4.18675	.25738	3.88536	.27607	3.62224	34
27	.22078	4.52941	.23916	4.18137	.25769	3.88068	.27638	3.61814	33
28	.22108	4.52316	.23946	4.17600	.25800	3.87601	.27670	3.61405	32
29	.22139	4.51693	.23977	4.17064	.25831	3.87136	.27701	3.60996	31
30	.22169	4.51071	.24008	4.16530	.25862	3.86671	.27732	3 60588	30
31	.22200	4.50451	.24039	4.15997	.25893	3.86208	.27764	3.60181	29
32	.22231	4.49832	.24069	4.15465	.25924	3.85745	.27795	3.59775	28
33	.22261	4.49215	.24100	4.14934	.25955	3.85284	.27826	3.59370	27
34	.22292	4.48600	.24131	4.14405	.25986	3.84824	.27858	3.58966	26
35	.22322	4.47986	.24162	4.13877	.26017	3.84364	.27889	3.58562	25
36	.22353	4.47374	.24193	4.13350	.26048	3.83906	.27921	3.58160	24
37	.22383	4.46764	.24223	4.12825	.26079	3.83449	.27952	3.57758	23
38	.22414	4.46155	.24254	4.12301	.26110	3.82992	.27983	3.57357	22
39	.22444	4.45548	.24285	4.11778	.26141	3.82537	.28015	3.56957	21
40	.22475	4.44942	.24316	4.11256	.26172	3.82083	.28046	3.56557	20
41	.22505	4.44338	.24347	4.10736	.26203	3.81630	.28077	3.56159	19
42	.22536	4.43735	.24377	4.10216	.26235	3.81177	.28109	3.55761	18
43	.22567	4.43134	.24408	4.09699	.26266	3.80726	.28140	3.55364	17
44	.22597	4.42534	.24439	4.09182	.26297	3.80276	.28172	3.54968	16
45	.22628	4.41936	.24470	4.08666	.26328	3.79827	.28203	3.54573	15
46	.22658	4.41340	.24501	4.08152	.26359	3.79378	.28234	3.54179	14
47	.22689	4.40745	.24532	4.07639	.26390	3.78931	.28266	3.53785	13
48	.22719	4.40152	.24562	4.07127	.26421	3.78485	.28297	3.53393	12
49	.22750	4.39560	.24593	4.06616	.26452	3.78040	.28329	3.53001	11
50	.22781	4.38969	.24624	4.06107	.26483	3.77595	.28360	3.52609	10
51	.22811	4.38381	.24655	4.05599	.26515	3.77152	.28391	3.52219	9
52	.22842	4.37793	.24686	4.05092	.26546	3.76709	.28423	3.51829	8
53	.22872	4.37207	.24717	4.04586	.26577	3.76268	.28454	3.51441	7
54	.22903	4.36623	.24747	4.04081	.26608	3.75828	.28486	3.51053	6
55	.22934	4.36040	.24778	4.03578	.26639	3.75388	.28517	3.50666	5
56	.22964	4.35459	.24809	4.03076	.26670	3.74950	.28549	3.50279	4
57	.22995	4.34879	.24840	4.02574	.26701	3.74512	.28580	3.49894	3
58	.23026	4.34300	.24871	4.02074	.26733	3.74075	.28612	3.49509	2
59	.23056	4.33723	.24902	4.01576	.26764	3.73640	.28643	3.49125	1
60	.23087	4.33148	.24933	4.01078	.26795	3.73205	.28675	3.48741	0
′	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	′
	77°		76°		75°		74°		

TABLE V.—NATURAL TANGENTS AND COTANGENTS.

′	16°		17°		18°		19°		′
	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	
0	.28675	3.48741	.30573	3.27085	.32492	3.07768	.34433	2.90421	60
1	.28706	3.48359	.30605	3.26745	.32524	3.07464	.34465	2.90147	59
2	.28738	3.47977	.30637	3.26406	.32556	3.07160	.34498	2.89873	58
3	.28769	3.47596	.30669	3.26067	.32588	3.06857	.34530	2.89600	57
4	.28800	3.47216	.30700	3.25729	.32621	3.06554	.34563	2.89327	56
5	.28832	3.46837	.30732	3.25392	.32653	3.06252	.34596	2.89055	55
6	.28864	3.46458	.30764	3.25055	.32685	3.05950	.34628	2.88783	54
7	.28895	3.46080	.30796	3.24719	.32717	3.05649	.34661	2.88511	53
8	.28927	3.45703	.30828	3.24383	.32749	3.05349	.34693	2.88240	52
9	.28958	3.45327	.30860	3.24049	.32782	3.05049	.34726	2.87970	51
10	.28990	3.44951	.30891	3.23714	.32814	3.04749	.34758	2.87700	50
11	.29021	3.44576	.30923	3.23381	.32846	3.04450	.34791	2.87430	49
12	.29053	3.44202	.30955	3.23048	.32878	3.04152	.34824	2.87161	48
13	.29084	3.43829	.30987	3.22715	.32911	3.03854	.34856	2.86892	47
14	.29116	3.43456	.31019	3.22384	.32943	3.03556	.34889	2.86624	46
15	.29147	3.43084	.31051	3.22053	.32975	3.03260	.34922	2.86356	45
16	.29179	3.42713	.31083	3.21722	.33007	3.02963	.34954	2.86089	44
17	.29210	3.42343	.31115	3.21392	.33040	3.02667	.34987	2.85822	43
18	.29242	3.41973	.31147	3.21063	.33072	3.02372	.35020	2.85555	42
19	.29274	3.41604	.31178	3.20734	.33104	3.02077	.35052	2.85289	41
20	.29305	3.41236	.31210	3.20406	.33136	3.01783	.35085	2.85023	40
21	.29337	3.40869	.31242	3.20079	.33169	3.01489	.35118	2.84758	39
22	.29368	3.40502	.31274	3.19752	.33201	3.01196	.35150	2.84494	38
23	.29400	3.40136	.31306	3.19426	.33233	3.00903	.35183	2.84229	37
24	.29432	3.39771	.31338	3.19100	.33266	3.00611	.35216	2.83965	36
25	.29463	3.39406	.31370	3.18775	.33298	3.00319	.35248	2.83702	35
26	.29495	3.39042	.31402	3.18451	.33330	3.00028	.35281	2.83439	34
27	.29526	3.38679	.31434	3.18127	.33363	2.99738	.35314	2.83176	33
28	.29558	3.38317	.31466	3.17804	.33395	2.99447	.35346	2.82914	32
29	.29590	3.37955	.31498	3.17481	.33427	2.99158	.35379	2.82653	31
30	.29621	3.37594	.31530	3.17159	.33460	2.98868	.35412	2.82391	30
31	.29653	3.37234	.31562	3.16838	.33492	2.98580	.35445	2.82130	29
32	.29685	3.36875	.31594	3.16517	.33524	2.98292	.35477	2.81870	28
33	.29716	3.36516	.31626	3.16197	.33557	2.98004	.35510	2.81610	27
34	.29748	3.36158	.31658	3.15877	.33589	2.97717	.35543	2.81350	26
35	.29780	3.35800	.31690	3.15558	.33621	2.97430	.35576	2.81091	25
36	.29811	3.35443	.31722	3.15240	.33654	2.97144	.35608	2.80833	24
37	.29843	3.35087	.31754	3.14922	.33686	2.96858	.35641	2.80574	23
38	.29875	3.34732	.31786	3.14605	.33718	2.96573	.35674	2.80316	22
39	.29906	3.34377	.31818	3.14288	.33751	2.96288	.35707	2.80059	21
40	.29938	3.34023	.31850	3.13972	.33783	2.96004	.35740	2.79802	20
41	.29970	3.33670	.31882	3.13656	.33816	2.95721	.35772	2.79545	19
42	.30001	3.33317	.31914	3.13341	.33848	2.95437	.35805	2.79289	18
43	.30033	3.32965	.31946	3.13027	.33881	2.95155	.35838	2.79033	17
44	.30065	3.32614	.31978	3.12713	.33913	2.94872	.35871	2.78778	16
45	.30097	3.32264	.32010	3.12400	.33945	2.94591	.35904	2.78523	15
46	.30128	3.31914	.32042	3.12087	.33978	2.94309	.35937	2.78269	14
47	.30160	3.31565	.32074	3.11775	.34010	2.94028	.35969	2.78014	13
48	.30192	3.31216	.32106	3.11464	.34043	2.93748	.36002	2.77761	12
49	.30224	3.30868	.32139	3.11153	.34075	2.93468	.36035	2.77507	11
50	.30255	3.30521	.32171	3.10842	.34108	2.93189	.36068	2.77254	10
51	.30287	3.30174	.32203	3.10532	.34140	2.92910	.36101	2.77002	9
52	.30319	3.29829	.32235	3.10223	.34173	2.92632	.36134	2.76750	8
53	.30351	3.29483	.32267	3.09914	.34205	2.92354	.36167	2.76498	7
54	.30382	3.29139	.32299	3.09606	.34238	2.92076	.36199	2.76247	6
55	.30414	3.28795	.32331	3.09298	.34270	2.91799	.36232	2.75996	5
56	.30446	3.28452	.32363	3.08991	.34303	2.91523	.36265	2.75746	4
57	.30478	3.28109	.32396	3.08685	.34335	2.91246	.36298	2.75496	3
58	.30509	3.27767	.32428	3.08379	.34368	2.90971	.36331	2.75246	2
59	.30541	3.27426	.32460	3.08073	.34400	2.90696	.36364	2.74997	1
60	.30573	3.27085	.32492	3.07768	.34433	2.90421	.36397	2.74748	0
′	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	′
	73°		72°		71°		70°		

TABLE V.—NATURAL TANGENTS AND COTANGENTS.

′	20°		21°		22°		23°		′
	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	
0	.36397	2.74748	.38386	2.60509	.40403	2.47509	.42447	2.35585	60
1	.36430	2.74499	.38420	2.60283	.40436	2.47302	.42482	2.35395	59
2	.36463	2.74251	.38453	2.60057	.40470	2.47095	.42516	2.35205	58
3	.36496	2.74004	.38487	2.59831	.40504	2.46888	.42551	2.35015	57
4	.36529	2.73756	.38520	2.59606	.40538	2.46682	.42585	2.34825	56
5	.36562	2.73509	.38553	2.59381	.40572	2.46476	.42619	2.34636	55
6	.36595	2.73263	.38587	2.59156	.40606	2.46270	.42654	2.34447	54
7	.36628	2.73017	.38620	2.58932	.40640	2.46065	.42688	2.34258	53
8	.36661	2.72771	.38654	2.58708	.40674	2.45860	.42722	2.34069	52
9	.36694	2.72526	.38687	2.58484	.40707	2.45655	.42757	2.33881	51
10	.36727	2.72281	.38721	2.58261	.40741	2.45451	.42791	2.33693	50
11	.36760	2.72036	.38754	2.58038	.40775	2.45246	.42826	2.33505	49
12	.36793	2.71792	.38787	2.57815	.40809	2.45043	.42860	2.33317	48
13	.36826	2.71548	.38821	2.57593	.40843	2.44839	.42894	2.33130	47
14	.36859	2.71305	.38854	2.57371	.40877	2.44636	.42929	2.32943	46
15	.36892	2.71062	.38888	2.57150	.40911	2.44433	.42963	2.32756	45
16	.36925	2.70819	.38921	2.56928	.40945	2.44230	.42998	2.32570	44
17	.36958	2.70577	.38955	2.56707	.40979	2.44027	.43032	2.32383	43
18	.36991	2.70335	.38988	2.56487	.41013	2.43825	.43067	2.32197	42
19	.37024	2.70094	.39022	2.56266	.41047	2.43623	.43101	2.32012	41
20	.37057	2.69853	.39055	2.56046	.41081	2.43422	.43136	2.31826	40
21	.37090	2.69612	.39089	2.55827	.41115	2.43220	.43170	2.31641	39
22	.37123	2.69371	.39122	2.55608	.41149	2.43019	.43205	2.31456	38
23	.37157	2.69131	.39156	2.55389	.41183	2.42819	.43239	2.31271	37
24	.37190	2.68892	.39190	2.55170	.41217	2.42618	.43274	2.31086	36
25	.37223	2.68653	.39223	2.54952	.41251	2.42418	.43308	2.30902	35
26	.37256	2.68414	.39257	2.54734	.41285	2.42218	.43343	2.30718	34
27	.37289	2.68175	.39290	2.54516	.41319	2.42019	.43378	2.30534	33
28	.37322	2.67937	.39324	2.54299	.41353	2.41819	.43412	2.30351	32
29	.37355	2.67700	.39357	2.54082	.41387	2.41620	.43447	2.30167	31
30	.37388	2.67462	.39391	2.53865	.41421	2.41421	.43481	2.29984	30
31	.37422	2.67225	.39425	2.53648	.41455	2.41223	.43516	2.29801	29
32	.37455	2.66989	.39458	2.53432	.41490	2.41025	.43550	2.29619	28
33	.37488	2.66752	.39492	2.53217	.41524	2.40827	.43585	2.29437	27
34	.37521	2.66516	.39526	2.53001	.41558	2.40629	.43620	2.29254	26
35	.37554	2.66281	.39559	2.52786	.41592	2.40432	.43654	2.29073	25
36	.37588	2.66046	.39593	2.52571	.41626	2.40235	.43689	2.28891	24
37	.37621	2.65811	.39626	2.52357	.41660	2.40038	.43724	2.28710	23
38	.37654	2.65576	.39660	2.52142	.41694	2.39841	.43758	2.28528	22
39	.37687	2.65342	.39694	2.51929	.41728	2.39645	.43793	2.28348	21
40	.37720	2.65109	.39727	2.51715	.41763	2.39449	.43828	2.28167	20
41	.37754	2.64875	.39761	2.51502	.41797	2.39253	.43862	2.27987	19
42	.37787	2.64642	.39795	2.51289	.41831	2.39058	.43897	2.27806	18
43	.37820	2.64410	.39829	2.51076	.41865	2.38863	.43932	2.27626	17
44	.37853	2.64177	.39862	2.50864	.41899	2.38668	.43966	2.27447	16
45	.37887	2.63945	.39896	2.50652	.41933	2.38473	.44001	2.27267	15
46	.37920	2.63714	.39930	2.50440	.41968	2.38279	.44036	2.27088	14
47	.37953	2.63483	.39963	2.50229	.42002	2.38084	.44071	2.26909	13
48	.37986	2.63252	.39997	2.50018	.42036	2.37891	.44105	2.26730	12
49	.38020	2.63021	.40031	2.49807	.42070	2.37697	.44140	2.26552	11
50	.38053	2.62791	.40065	2.49597	.42105	2.37504	.44175	2.26374	10
51	.38086	2.62561	.40098	2.49386	.42139	2.37311	.44210	2.26196	9
52	.38120	2.62332	.40132	2.49177	.42173	2.37118	.44244	2.26018	8
53	.38153	2.62103	.40166	2.48967	.42207	2.36925	.44279	2.25840	7
54	.38186	2.61874	.40200	2.48758	.42242	2.36733	.44314	2.25663	6
55	.38220	2.61646	.40234	2.48549	.42276	2.36541	.44349	2.25486	5
56	.38253	2.61418	.40267	2.48340	.42310	2.36349	.44384	2.25309	4
57	.38286	2.61190	.40301	2.48132	.42345	2.36158	.44418	2.25132	3
58	.38320	2.60963	.40335	2.47924	.42379	2.35967	.44453	2.24956	2
59	.38353	2.60736	.40369	2.47716	.42413	2.35776	.44488	2.24780	1
60	.38386	2.60509	.40403	2.47509	.42447	2.35585	.44523	2.24604	0
′	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	′
	69°		68°		67°		66°		

TABLE V.—NATURAL TANGENTS AND COTANGENTS.

′	24°		25°		26°		27°		′
	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	
0	.44523	2.24604	.46631	2.14451	.48773	2.05030	.50953	1.96261	60
1	.44558	2.24428	.46666	2.14288	.48809	2.04879	.50989	1.96120	59
2	.44593	2.24252	.46702	2.14125	.48845	2.04728	.51026	1.95979	58
3	.44627	2.24077	.46737	2.13963	.48881	2.04577	.51063	1.95838	57
4	.44662	2.23902	.46772	2.13801	.48917	2.04426	.51099	1.95698	56
5	.44697	2.23727	.46808	2.13639	.48953	2.04276	.51136	1.95557	55
6	.44732	2.23553	.46843	2.13477	.48989	2.04125	.51173	1.95417	54
7	.44767	2.23378	.46879	2.13316	.49026	2.03975	.51209	1.95277	53
8	.44802	2.23204	.46914	2.13154	.49062	2.03825	.51246	1.95137	52
9	.44837	2.23030	.46950	2.12993	.49098	2.03675	.51283	1.94997	51
10	.44873	2.22857	.46985	2.12832	.49134	2.03526	.51319	1.94858	50
11	.44907	2.22683	.47021	2.12671	.49170	2.03376	.51356	1.94718	49
12	.44942	2.22510	.47056	2.12511	.49206	2.03227	.51393	1.94579	48
13	.44977	2.22337	.47092	2.12350	.49242	2.03078	.51430	1.94440	47
14	.45012	2.22164	.47128	2.12190	.49278	2.02929	.51467	1.94301	46
15	.45047	2.21992	.47163	2.12030	.49315	2.02780	.51503	1.94162	45
16	.45082	2.21819	.47199	2.11871	.49351	2.02631	.51540	1.94023	44
17	.45117	2.21647	.47234	2.11711	.49387	2.02483	.51577	1.93885	43
18	.45152	2.21475	.47270	2.11552	.49423	2.02335	.51614	1.93746	42
19	.45187	2.21304	.47305	2.11392	.49459	2.02187	.51651	1.93608	41
20	.45222	2.21132	.47341	2.11233	.49495	2.02039	.51688	1.93470	40
21	.45257	2.20961	.47377	2.11075	.49532	2.01891	.51724	1.93332	39
22	.45292	2.20790	.47412	2.10916	.49568	2.01743	.51761	1.93195	38
23	.45327	2.20619	.47448	2.10758	.49604	2.01596	.51798	1.93057	37
24	.45362	2.20449	.47483	2.10600	.49640	2.01449	.51835	1.92920	36
25	.45397	2.20278	.47519	2.10442	.49677	2.01302	.51872	1.92782	35
26	.45432	2.20108	.47555	2.10284	.49713	2.01155	.51909	1.92645	34
27	.45467	2.19938	.47590	2.10126	.49749	2.01008	.51946	1.92508	33
28	.45502	2.19769	.47626	2.09969	.49786	2.00862	.51983	1.92371	32
29	.45538	2.19599	.47662	2.09811	.49822	2.00715	.52020	1.92235	31
30	.45573	2.19430	.47698	2.09654	.49858	2.00569	.52057	1.92098	30
31	.45608	2.19261	.47733	2.09498	.49894	2.00423	.52094	1.91962	29
32	.45643	2.19092	.47769	2.09341	.49931	2.00277	.52131	1.91826	28
33	.45678	2.18923	.47805	2.09184	.49967	2.00131	.52168	1.91690	27
34	.45713	2.18755	.47840	2.09028	.50004	1.99986	.52205	1.91554	26
35	.45748	2.18587	.47876	2.08872	.50040	1.99841	.52242	1.91418	25
36	.45784	2.18419	.47912	2.08716	.50076	1.99695	.52279	1.91282	24
37	.45819	2.18251	.47948	2.08560	.50113	1.99550	.52316	1.91147	23
38	.45854	2.18084	.47984	2.08405	.50149	1.99406	.52353	1.91012	22
39	.45889	2.17916	.48019	2.08250	.50185	1.99261	.52390	1.90876	21
40	.45924	2.17749	.48055	2.08094	.50222	1.99116	.52427	1.90741	20
41	.45960	2.17582	.48091	2.07939	.50258	1.98972	.52464	1.90607	19
42	.45995	2.17416	.48127	2.07785	.50295	1.98828	.52501	1.90472	18
43	.46030	2.17249	.48163	2.07630	.50331	1.98684	.52538	1.90337	17
44	.46065	2.17083	.48198	2.07476	.50368	1.98540	.52575	1.90203	16
45	.46101	2.16917	.48234	2.07321	.50404	1.98396	.52613	1.90069	15
46	.46136	2.16751	.48270	2.07167	.50441	1.98253	.52650	1.89935	14
47	.46171	2.16585	.48306	2.07014	.50477	1.98110	.52687	1.89801	13
48	.46206	2.16420	.48342	2.06860	.50514	1.97966	.52724	1.89667	12
49	.46242	2.16255	.48378	2.06706	.50550	1.97823	.52761	1.89533	11
50	.46277	2.16090	.48414	2.06553	.50587	1.97681	.52798	1.89400	10
51	.46312	2.15925	.48450	2.06400	.50623	1.97538	.52836	1.89266	9
52	.46348	2.15760	.48486	2.06247	.50660	1.97395	.52873	1.89133	8
53	.46383	2.15596	.48521	2.06094	.50696	1.97253	.52910	1.89000	7
54	.46418	2.15432	.48557	2.05942	.50733	1.97111	.52947	1.88867	6
55	.46454	2.15268	.48593	2.05790	.50769	1.96969	.52985	1.88734	5
56	.46489	2.15104	.48629	2.05637	.50806	1.96827	.53022	1.88602	4
57	.46525	2.14940	.48665	2.05485	.50843	1.96685	.53059	1.88469	3
58	.46560	2.14777	.48701	2.05333	.50879	1.96544	.53096	1.88337	2
59	.46595	2.14614	.48737	2.05182	.50916	1.96402	.53134	1.88205	1
60	.46631	2.14451	.48773	2.05030	.50953	1.96261	.53171	1.88073	0
′	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	′
	65°		64°		63°		62°		

TABLE V.—NATURAL TANGENTS AND COTANGENTS.

′	28°		29°		30°		31°		′
	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	
0	.53171	1.88073	.55431	1.80405	.57735	1.73205	.60086	1.66428	60
1	.53208	1.87941	.55469	1.80281	.57774	1.73089	.60126	1.66318	59
2	.53246	1.87809	.55507	1.80158	.57813	1.72973	.60165	1.66209	58
3	.53283	1.87677	.55545	1.80034	.57851	1.72857	.60205	1.66099	57
4	.53320	1.87546	.55583	1.79911	.57890	1.72741	.60245	1.65990	56
5	.53358	1.87415	.55621	1.79788	.57929	1.72625	.60284	1.65881	55
6	.53395	1.87283	.55659	1.79665	.57968	1.72509	.60324	1.65772	54
7	.53432	1.87152	.55697	1.79542	.58007	1.72393	.60364	1.65663	53
8	.53470	1.87021	.55736	1.79419	.58046	1.72278	.60403	1.65554	52
9	.53507	1.86891	.55774	1.79296	.58085	1.72163	.60443	1.65445	51
10	.53545	1.86760	.55812	1.79174	.58124	1.72047	.60483	1.65337	50
11	.53582	1.86630	.55850	1.79051	.58162	1.71932	.60522	1.65228	49
12	.53620	1.86499	.55888	1.78929	.58201	1.71817	.60562	1.65120	48
13	.53657	1.86369	.55926	1.78807	.58240	1.71702	.60602	1.65011	47
14	.53694	1.86239	.55964	1.78685	.58279	1.71588	.60642	1.64903	46
15	.53732	1.86109	.56003	1.78563	.58318	1.71473	.60681	1.64795	45
16	.53769	1.85979	.56041	1.78441	.58357	1.71358	.60721	1.64687	44
17	.53807	1.85850	.56079	1.78319	.58396	1.71244	.60761	1.64579	43
18	.53844	1.85720	.56117	1.78198	.58435	1.71129	.60801	1.64471	42
19	.53882	1.85591	.56156	1.78077	.58474	1.71015	.60841	1.64363	41
20	.53920	1.85462	.56194	1.77955	.58513	1.70901	.60881	1.64256	40
21	.53957	1.85333	.56232	1.77834	.58552	1.70787	.60921	1.64148	39
22	.53995	1.85204	.56270	1.77713	.58591	1.70673	.60960	1.64041	38
23	.54032	1.85075	.56309	1.77592	.58631	1.70560	.61000	1.63934	37
24	.54070	1.84946	.56347	1.77471	.58670	1.70446	.61040	1.63826	36
25	.54107	1.84818	.56385	1.77351	.58709	1.70332	.61080	1.63719	35
26	.54145	1.84689	.56424	1.77230	.58748	1.70219	.61120	1.63612	34
27	.54183	1.84561	.56462	1.77110	.58787	1.70106	.61160	1.63505	33
28	.54220	1.84433	.56501	1.76990	.58826	1.69992	.61200	1.63398	32
29	.54258	1.84305	.56539	1.76869	.58865	1.69879	.61240	1.63292	31
30	.54296	1.84177	.56577	1.76749	.58905	1.69766	.61280	1.63185	30
31	.54333	1.84049	.56616	1.76629	.58944	1.69653	.61320	1.63079	29
32	.54371	1.83922	.56655	1.76510	.58983	1.69541	.61360	1.62972	28
33	.54409	1.83794	.56693	1.76390	.59022	1.69428	.61400	1.62866	27
34	.54446	1.83667	.56731	1.76271	.59061	1.69316	.61440	1.62760	26
35	.54484	1.83540	.56769	1.76151	.59101	1.69203	.61480	1.62654	25
36	.54522	1.83413	.56808	1.76032	.59140	1.69091	.61520	1.62548	24
37	.54560	1.83286	.56846	1.75913	.59179	1.68979	.61561	1.62442	23
38	.54597	1.83159	.56885	1.75794	.59218	1.68866	.61601	1.62336	22
39	.54635	1.83033	.56923	1.75675	.59258	1.68754	.61641	1.62230	21
40	.54673	1.82906	.56962	1.75556	.59297	1.68643	.61681	1.62125	20
41	.54711	1.82780	.57000	1.75437	.59336	1.68531	.61721	1.62019	19
42	.54748	1.82654	.57039	1.75319	.59376	1.68419	.61761	1.61914	18
43	.54786	1.82528	.57078	1.75200	.59415	1.68308	.61801	1.61808	17
44	.54824	1.82402	.57116	1.75082	.59454	1.68196	.61842	1.61703	16
45	.54862	1.82276	.57155	1.74964	.59494	1.68085	.61882	1.61598	15
46	.54900	1.82150	.57193	1.74846	.59533	1.67974	.61922	1.61493	14
47	.54938	1.82025	.57232	1.74728	.59573	1.67863	.61962	1.61388	13
48	.54975	1.81899	.57271	1.74610	.59612	1.67752	.62003	1.61283	12
49	.55013	1.81774	.57309	1.74492	.59651	1.67641	.62043	1.61179	11
50	.55051	1.81649	.57348	1.74375	.59691	1.67530	.62083	1.61074	10
51	.55089	1.81524	.57386	1.74257	.59730	1.67419	.62124	1.60970	9
52	.55127	1.81399	.57425	1.74140	.59770	1.67309	.62164	1.60865	8
53	.55165	1.81274	.57464	1.74022	.59809	1.67198	.62204	1.60761	7
54	.55203	1.81150	.57503	1.73905	.59849	1.67088	.62245	1.60657	6
55	.55241	1.81025	.57541	1.73788	.59888	1.66978	.62285	1.60553	5
56	.55279	1.80901	.57580	1.73671	.59928	1.66867	.62325	1.60449	4
57	.55317	1.80777	.57619	1.73555	.59967	1.66757	.62366	1.60345	3
58	.55355	1.80653	.57657	1.73438	.60007	1.66647	.62406	1.60241	2
59	.55393	1.80529	.57696	1.73321	.60046	1.66538	.62446	1.60137	1
60	.55431	1.80405	.57735	1.73205	.60086	1.66428	.62487	1.60033	0
′	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	′
	61°		60°		59°		58°		

TABLE V.—NATURAL TANGENTS AND COTANGENTS.

′	32° Tang	32° Cotang	33° Tang	33° Cotang	34° Tang	34° Cotang	35° Tang	35° Cotang	′
0	.62487	1.60033	.64941	1.53986	.67451	1.48256	.70021	1.42815	60
1	.62527	1.59930	.64982	1.53888	.67493	1.48163	.70064	1.42726	59
2	.62568	1.59826	.65024	1.53791	.67536	1.48070	.70107	1.42638	58
3	.62608	1.59723	.65065	1.53693	.67578	1.47977	.70151	1.42550	57
4	.62649	1.59620	.65106	1.53595	.67620	1.47885	.70194	1.42462	56
5	.62689	1.59517	.65148	1.53497	.67663	1.47792	.70238	1.42374	55
6	.62730	1.59414	.65189	1.53400	.67705	1.47699	.70281	1.42286	54
7	.62770	1.59311	.65231	1.53302	.67748	1.47607	.70325	1.42198	53
8	.62811	1.59208	.65272	1.53205	.67790	1.47514	.70368	1.42110	52
9	.62852	1.59105	.65314	1.53107	.67832	1.47422	.70412	1.42022	51
10	.62892	1.59002	.65355	1.53010	.67875	1.47330	.70455	1.41934	50
11	.62933	1.58900	.65397	1.52913	.67917	1.47238	.70499	1.41847	49
12	.62973	1.58797	.65438	1.52816	.67960	1.47146	.70542	1.41759	48
13	.63014	1.58695	.65480	1.52719	.68002	1.47053	.70586	1.41672	47
14	.63055	1.58593	.65521	1.52622	.68045	1.46962	.70629	1.41584	46
15	.63095	1.58490	.65563	1.52525	.68088	1.46870	.70673	1.41497	45
16	.63136	1.58388	.65604	1.52429	.68130	1.46778	.70717	1.41409	44
17	.63177	1.58286	.65646	1.52332	.68173	1.46686	.70760	1.41322	43
18	.63217	1.58184	.65688	1.52235	.68215	1.46595	.70804	1.41235	42
19	.63258	1.58083	.65729	1.52139	.68258	1.46503	.70848	1.41148	41
20	.63299	1.57981	.65771	1.52043	.68301	1.46411	.70891	1.41061	40
21	.63340	1.57879	.65813	1.51946	.68343	1.46320	.70935	1.40974	39
22	.63380	1.57778	.65854	1.51850	.68386	1.46229	.70979	1.40887	38
23	.63421	1.57676	.65896	1.51754	.68429	1.46137	.71023	1.40800	37
24	.63462	1.57575	.65938	1.51658	.68471	1.46046	.71066	1.40714	36
25	.63503	1.57474	.65980	1.51562	.68514	1.45955	.71110	1.40627	35
26	.63544	1.57372	.66021	1.51466	.68557	1.45864	.71154	1.40540	34
27	.63584	1.57271	.66063	1.51370	.68600	1.45773	.71198	1.40454	33
28	.63625	1.57170	.66105	1.51275	.68642	1.45682	.71242	1.40367	32
29	.63666	1.57069	.66147	1.51179	.68685	1.45592	.71285	1.40281	31
30	.63707	1.56969	.66189	1.51084	.68728	1.45501	.71329	1.40195	30
31	.63748	1.56868	.66230	1.50988	.68771	1.45410	.71373	1.40109	29
32	.63789	1.56767	.66272	1.50893	.68814	1.45320	.71417	1.40022	28
33	.63830	1.56667	.66314	1.50797	.68857	1.45229	.71461	1.39936	27
34	.63871	1.56566	.66356	1.50702	.68900	1.45139	.71505	1.39850	26
35	.63912	1.56466	.66398	1.50607	.68942	1.45049	.71549	1.39764	25
36	.63953	1.56366	.66440	1.50512	.68985	1.44958	.71593	1.39679	24
37	.63994	1.56265	.66482	1.50417	.69028	1.44868	.71637	1.39593	23
38	.64035	1.56165	.66524	1.50322	.69071	1.44778	.71681	1.39507	22
39	.64076	1.56065	.66566	1.50228	.69114	1.44688	.71725	1.39421	21
40	.64117	1.55966	.66608	1.50133	.69157	1.44598	.71769	1.39336	20
41	.64158	1.55866	.66650	1.50038	.69200	1.44508	.71813	1.39250	19
42	.64199	1.55766	.66692	1.49944	.69243	1.44418	.71857	1.39165	18
43	.64240	1.55666	.66734	1.49849	.69286	1.44329	.71901	1.39079	17
44	.64281	1.55567	.66776	1.49755	.69329	1.44239	.71946	1.38994	16
45	.64322	1.55467	.66818	1.49661	.69372	1.44149	.71990	1.38909	15
46	.64363	1.55368	.66860	1.49566	.69416	1.44060	.72034	1.38824	14
47	.64404	1.55269	.66902	1.49472	.69459	1.43970	.72078	1.38738	13
48	.64446	1.55170	.66944	1.49378	.69502	1.43881	.72122	1.38653	12
49	.64487	1.55071	.66986	1.49284	.69545	1.43792	.72167	1.38568	11
50	.64528	1.54972	.67028	1.49190	.69588	1.43703	.72211	1.38484	10
51	.64569	1.54873	.67071	1.49097	.69631	1.43614	.72255	1.38399	9
52	.64610	1.54774	.67113	1.49003	.69675	1.43525	.72299	1.38314	8
53	.64652	1.54675	.67155	1.48909	.69718	1.43436	.72344	1.38229	7
54	.64693	1.54576	.67197	1.48816	.69761	1.43347	.72388	1.38145	6
55	.64734	1.54478	.67239	1.48722	.69804	1.43258	.72432	1.38060	5
56	.64775	1.54379	.67282	1.48629	.69847	1.43169	.72521	1.37976	4
57	.64817	1.54281	.67324	1.48536	.69891	1.43080	.72565	1.37891	3
58	.64858	1.54183	.67366	1.48442	.69934	1.42992	.72610	1.37807	2
59	.64899	1.54085	.67409	1.48349	.69977	1.42903	.72654	1.37722	1
60	.64941	1.53986	.67451	1.48256	.70021	1.42815	.72654	1.37638	0
′	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	′
	57°		56°		55°		54°		

TABLE V.—NATURAL TANGENTS AND COTANGENTS.

′	36°		37°		38°		39°		′
	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	
0	.72654	1.37638	.75355	1.32704	.78129	1.27994	.80978	1.23490	60
1	.72699	1.37554	.75401	1.32624	.78175	1.27917	.81027	1.23416	59
2	.72743	1.37470	.75447	1.32544	.78222	1.27841	.81075	1.23343	58
3	.72788	1.37386	.75492	1.32464	.78269	1.27764	.81123	1.23270	57
4	.72832	1.37302	.75538	1.32384	.78316	1.27688	.81171	1.23196	56
5	.72877	1.37218	.75584	1.32304	.78363	1.27611	.81220	1.23123	55
6	.72921	1.37134	.75629	1.32224	.78410	1.27535	.81268	1.23050	54
7	.72966	1.37050	.75675	1.32144	.78457	1.27458	.81316	1.22977	53
8	.73010	1.36967	.75721	1.32064	.78504	1.27382	.81364	1.22904	52
9	.73055	1.36883	.75767	1.31984	.78551	1.27306	.81413	1.22831	51
10	.73100	1.36800	.75812	1.31904	.78598	1.27230	.81461	1.22758	50
11	.73144	1.36716	.75858	1.31825	.78645	1.27153	.81510	1.22685	49
12	.73189	1.36633	.75904	1.31745	.78692	1.27077	.81558	1.22612	48
13	.73234	1.36549	.75950	1.31666	.78739	1.27001	.81606	1.22539	47
14	.73278	1.36466	.75996	1.31586	.78786	1.26925	.81655	1.22467	46
15	.73323	1.36383	.76042	1.31507	.78834	1.26849	.81703	1.22394	45
16	.73368	1.36300	.76088	1.31427	.78881	1.26774	.81752	1.22321	44
17	.73413	1.36217	.76134	1.31348	.78928	1.26698	.81800	1.22249	43
18	.73457	1.36134	.76180	1.31269	.78975	1.26622	.81849	1.22176	42
19	.73502	1.36051	.76226	1.31190	.79022	1.26546	.81898	1.22104	41
20	.73547	1.35968	.76272	1.31110	.79070	1.26471	.81946	1.22031	40
21	.73592	1.35885	.76318	1.31031	.79117	1.26395	.81995	1.21959	39
22	.73637	1.35802	.76364	1.30952	.79164	1.26319	.82044	1.21886	38
23	.73681	1.35719	.76410	1.30873	.79212	1.26244	.82092	1.21814	37
24	.73726	1.35637	.76456	1.30795	.79259	1.26169	.82141	1.21742	36
25	.73771	1.35554	.76502	1.30716	.79306	1.26093	.82190	1.21670	35
26	.73816	1.35472	.76548	1.30637	.79354	1.26018	.82238	1.21598	34
27	.73861	1.35389	.76594	1.30558	.79401	1.25943	.82287	1.21526	33
28	.73906	1.35307	.76640	1.30480	.79449	1.25867	.82336	1.21454	32
29	.73951	1.35224	.76686	1.30401	.79496	1.25792	.82385	1.21382	31
30	.73996	1.35142	.76733	1.30323	.79544	1.25717	.82434	1.21310	30
31	.74041	1.35060	.76779	1.30244	.79591	1.25642	.82483	1.21238	29
32	.74086	1.34978	.76825	1.30166	.79639	1.25567	.82531	1.21166	28
33	.74131	1.34896	.76871	1.30087	.79686	1.25492	.82580	1.21094	27
34	.74176	1.34814	.76918	1.30009	.79734	1.25417	.82629	1.21023	26
35	.74221	1.34732	.76964	1.29931	.79781	1.25343	.82678	1.20951	25
36	.74267	1.34650	.77010	1.29853	.79829	1.25268	.82727	1.20879	24
37	.74312	1.34568	.77057	1.29775	.79877	1.25193	.82776	1.20808	23
38	.74357	1.34487	.77103	1.29696	.79924	1.25118	.82825	1.20736	22
39	.74402	1.34405	.77149	1.29618	.79972	1.25044	.82874	1.20665	21
40	.74447	1.34323	.77196	1.29541	.80020	1.24969	.82923	1.20593	20
41	.74492	1.34242	.77242	1.29463	.80067	1.24895	.82972	1.20522	19
42	.74538	1.34160	.77289	1.29385	.80115	1.24820	.83022	1.20451	18
43	.74583	1.34079	.77335	1.29307	.80163	1.24746	.83071	1.20379	17
44	.74628	1.33998	.77382	1.29229	.80211	1.24672	.83120	1.20308	16
45	.74674	1.33916	.77428	1.29152	.80258	1.24597	.83169	1.20237	15
46	.74719	1.33835	.77475	1.29074	.80306	1.24523	.83218	1.20166	14
47	.74764	1.33754	.77521	1.28997	.80354	1.24449	.83268	1.20095	13
48	.74810	1.33673	.77568	1.28919	.80402	1.24375	.83317	1.20024	12
49	.74855	1.33592	.77615	1.28842	.80450	1.24301	.83366	1.19953	11
50	.74900	1.33511	.77661	1.28764	.80498	1.24227	.83415	1.19882	10
51	.74946	1.33430	.77708	1.28687	.80546	1.24153	.83465	1.19811	9
52	.74991	1.33349	.77754	1.28610	.80594	1.24079	.83514	1.19740	8
53	.75037	1.33268	.77801	1.28533	.80642	1.24005	.83564	1.19669	7
54	.75082	1.33187	.77848	1.28456	.80690	1.23931	.83613	1.19599	6
55	.75128	1.33107	.77895	1.28379	.80738	1.23858	.83662	1.19528	5
56	.75173	1.33026	.77941	1.28302	.80786	1.23784	.83712	1.19457	4
57	.75219	1.32946	.77988	1.28225	.80834	1.23710	.83761	1.19387	3
58	.75264	1.32865	.78035	1.28148	.80882	1.23637	.83811	1.19316	2
59	.75310	1.32785	.78082	1.28071	.80930	1.23563	.83860	1.19246	1
60	.75355	1.32704	.78129	1.27994	.80978	1.23490	.83910	1.19175	0
′	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	′
	53°		52°		51°		50°		

TABLE V.—NATURAL TANGENTS AND COTANGENTS.

′	40°		41°		42°		43°		′
	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	
0	.83910	1.19175	.86929	1.15037	.90040	1.11061	.93252	1.07237	60
1	.83960	1.19105	.86980	1.14969	.90093	1.10996	.93306	1.07174	59
2	.84009	1.19035	.87031	1.14902	.90146	1.10931	.93360	1.07112	58
3	.84059	1.18964	.87082	1.14834	.90199	1.10867	.93415	1.07049	57
4	.84108	1.18894	.87133	1.14767	.90251	1.10802	.93469	1.06987	56
5	.84158	1.18824	.87184	1.14699	.90304	1.10737	.93524	1.06925	55
6	.84208	1.18754	.87236	1.14632	.90357	1.10672	.93578	1.06862	54
7	.84258	1.18684	.87287	1.14565	.90410	1.10607	.93633	1.06800	53
8	.84307	1.18614	.87338	1.14498	.90463	1.10543	.93688	1.06738	52
9	.84357	1.18544	.87389	1.14430	.90516	1.10478	.93742	1.06676	51
10	.84407	1.18474	.87441	1.14363	.90569	1.10414	.93797	1.06613	50
11	.84457	1.18404	.87492	1.14296	.90621	1.10349	.93852	1.06551	49
12	.84507	1.18334	.87543	1.14229	.90674	1.10285	.93906	1.06489	48
13	.84556	1.18264	.87595	1.14162	.90727	1.10220	.93961	1.06427	47
14	.84606	1.18194	.87646	1.14095	.90781	1.10156	.94016	1.06365	46
15	.84656	1.18125	.87698	1.14028	.90834	1.10091	.94071	1.06303	45
16	.84706	1.18055	.87749	1.13961	.90887	1.10027	.94125	1.06241	44
17	.84756	1.17986	.87801	1.13894	.90940	1.09963	.94180	1.06179	43
18	.84806	1.17916	.87852	1.13828	.90993	1.09899	.94235	1.06117	42
19	.84856	1.17846	.87904	1.13761	.91046	1.09834	.94290	1.06056	41
20	.84906	1.17777	.87955	1.13694	.91099	1.09770	.94345	1.05994	40
21	.84956	1.17708	.88007	1.13627	.91153	1.09706	.94400	1.05932	39
22	.85006	1.17638	.88059	1.13561	.91206	1.09642	.94455	1.05870	38
23	.85057	1.17569	.88110	1.13494	.91259	1.09578	.94510	1.05809	37
24	.85107	1.17500	.88162	1.13428	.91313	1.09514	.94565	1.05747	36
25	.85157	1.17430	.88214	1.13361	.91366	1.09450	.94620	1.05685	35
26	.85207	1.17361	.88265	1.13295	.91419	1.09386	.94676	1.05624	34
27	.85257	1.17292	.88317	1.13228	.91473	1.09322	.94731	1.05562	33
28	.85308	1.17223	.88369	1.13162	.91526	1.09258	.94786	1.05501	32
29	.85358	1.17154	.88421	1.13096	.91580	1.09195	.94841	1.05439	31
30	.85408	1.17085	.88473	1.13029	.91633	1.09131	.94896	1.05378	30
31	.85458	1.17016	.88524	1.12963	.91687	1.09067	.94952	1.05317	29
32	.85509	1.16947	.88576	1.12897	.91740	1.09003	.95007	1.05255	28
33	.85559	1.16878	.88628	1.12831	.91794	1.08940	.95062	1.05194	27
34	.85609	1.16809	.88680	1.12765	.91847	1.08876	.95118	1.05133	26
35	.85660	1.16741	.88732	1.12699	.91901	1.08813	.95173	1.05072	25
36	.85710	1.16672	.88784	1.12633	.91955	1.08749	.95229	1.05010	24
37	.85761	1.16603	.88836	1.12567	.92008	1.08686	.95284	1.04949	23
38	.85811	1.16535	.88888	1.12501	.92062	1.08622	.95340	1.04888	22
39	.85862	1.16466	.88940	1.12435	.92116	1.08559	.95395	1.04827	21
40	.85912	1.16398	.88992	1.12369	.92170	1.08496	.95451	1.04766	20
41	.85963	1.16329	.89045	1.12303	.92224	1.08432	.95506	1.04705	19
42	.86014	1.16261	.89097	1.12238	.92277	1.08369	.95562	1.04644	18
43	.86064	1.16192	.89149	1.12172	.92331	1.08306	.95618	1.04583	17
44	.86115	1.16124	.89201	1.12106	.92385	1.08243	.95673	1.04522	16
45	.86166	1.16056	.89253	1.12041	.92439	1.08179	.95729	1.04461	15
46	.86216	1.15987	.89306	1.11975	.92493	1.08116	.95785	1.04401	14
47	.86267	1.15919	.89358	1.11909	.92547	1.08053	.95841	1.04340	13
48	.86318	1.15851	.89410	1.11844	.92601	1.07990	.95897	1.04279	12
49	.86368	1.15783	.89463	1.11778	.92655	1.07927	.95952	1.04218	11
50	.86419	1.15715	.89515	1.11713	.92709	1.07864	.96008	1.04158	10
51	.86470	1.15647	.89567	1.11648	.92763	1.07801	.96064	1.04097	9
52	.86521	1.15579	.89620	1.11582	.92817	1.07738	.96120	1.04036	8
53	.86572	1.15511	.89672	1.11517	.92872	1.07676	.96176	1.03976	7
54	.86623	1.15443	.89725	1.11452	.92926	1.07613	.96232	1.03915	6
55	.86674	1.15375	.89777	1.11387	.92980	1.07550	.96288	1.03855	5
56	.86725	1.15308	.89830	1.11321	.93034	1.07487	.96344	1.03794	4
57	.86776	1.15240	.89883	1.11256	.93088	1.07425	.96400	1.03734	3
58	.86827	1.15172	.89935	1.11191	.93143	1.07362	.96457	1.03674	2
59	.86878	1.15104	.89988	1.11126	.93197	1.07299	.96513	1.03613	1
60	.86929	1.15037	.90040	1.11061	.93252	1.07237	.96569	1.03553	0
′	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	′
	49°		48°		47°		46°		

TABLE V.—NATURAL TANGENTS AND COTANGENTS.

′	44° Tang	44° Cotang	′	′	44° Tang	44° Cotang	′	′	44° Tang	44° Cotang	′
0	.96569	1.03553	60	20	.97700	1.02355	40	40	.98843	1.01170	20
1	.96625	1.03493	59	21	.97756	1.02295	39	41	.98901	1.01112	19
2	.96681	1.03433	58	22	.97813	1.02236	38	42	.98958	1.01053	18
3	.96738	1.03372	57	23	.97870	1.02176	37	43	.99016	1.00994	17
4	.96791	1.03312	56	24	.97927	1.02117	36	44	.99073	1.00935	16
5	.96850	1.03252	55	25	.97984	1.02057	35	45	.99131	1.00876	15
6	.96907	1.03192	54	26	.98041	1.01998	34	46	.99189	1.00818	14
7	.96963	1.03132	53	27	.98098	1.01939	33	47	.99247	1.00759	13
8	.97020	1.03072	52	28	.98155	1.01879	32	48	.99304	1.00701	12
9	.97076	1.03012	51	29	.98213	1.01820	31	49	.99362	1.00642	11
10	.97133	1.02952	50	30	.98270	1.01761	30	50	.99420	1.00583	10
11	.97189	1.02892	49	31	.98327	1.01702	29	51	.99478	1.00525	9
12	.97246	1.02832	48	32	.98384	1.01642	28	52	.99536	1.00467	8
13	.97302	1.02772	47	33	.98441	1.01583	27	53	.99594	1.00408	7
14	.97359	1.02713	46	34	.98499	1.01524	26	54	.99652	1.00350	6
15	.97416	1.02653	45	35	.98556	1.01465	25	55	.99710	1.00291	5
16	.97472	1.02593	44	36	.98613	1.01406	24	56	.99768	1.00233	4
17	.97529	1.02533	43	37	.98671	1.01347	23	57	.99826	1.00175	3
18	.97586	1.02474	42	38	.98728	1.01288	22	58	.99884	1.00116	2
19	.97643	1.02414	41	39	.98786	1.01229	21	59	.99942	1.00058	1
20	.97700	1.02355	40	40	.98843	1.01170	20	60	1.00000	1.00000	0
′	45° Cotang	45° Tang	′	′	45° Cotang	45° Tang	′	′	45° Cotang	45° Tang	′

Table VI. — Natural Versed Sines.

			3°	4°	5°	6°	7°	8°	9°
0° 00′	.00000	00′	.00137	.00244	.00381	.00548	.00745	.00973	.01231
05	000	01	139	246	383	551	749	977	236
10	000	02	140	248	386	554	752	981	240
15	001	03	142	250	388	557	756	985	245
20	002	04	143	252	391	560	760	989	249
25	003	05	.00145	.00254	.00393	.00563	.00763	.00994	.01254
30	.00004	06	146	256	396	566	767	998	259
35	005	07	148	258	398	569	770	.01002	263
40	007	08	149	260	401	572	774	006	268
45	009	09	151	262	404	576	778	010	272
50	011	10	.00153	.00264	.00406	.00579	.00781	.01014	.01277
55	013	11	154	266	409	582	785	018	282
1° 00′	.00015	12	156	269	412	585	789	022	286
05	018	13	158	271	414	588	792	027	291
10	021	14	159	273	417	591	796	031	296
15	024	15	.00161	.00275	.00420	.00594	.00800	.01035	.01300
20	027	16	162	277	422	598	803	039	305
25	031	17	164	279	425	601	807	043	310
30	.00034	18	166	281	428	604	811	047	314
35	038	19	167	284	430	607	814	052	319
40	042	20	.00169	.00286	.00433	.00610	.00818	.01056	.01324
45	047	21	171	288	436	614	822	060	329
50	051	22	173	290	438	617	825	064	333
55	056	23	174	292	441	620	829	069	338
2° 00′	.00061	24	176	295	444	623	833	073	343
		25	.00178	.00297	.00447	.00626	.00837	.01077	.01348
		26	179	299	449	630	840	081	352
		27	181	301	452	633	844	086	357
		28	183	304	455	636	848	090	362
		29	185	306	458	640	852	094	367
2° 00′	.00061	30	.00187	.00308	.00460	.00643	.00856	.01098	.01371
02	063	31	188	311	463	646	859	103	376
04	065	32	190	313	466	649	863	107	381
06	067	33	192	315	469	653	867	111	386
08	069	34	194	317	472	656	871	116	391
10	.00071	35	00196	.00320	.00474	.00659	.00875	.01120	.01396
12	074	36	197	322	477	663	878	124	400
14	076	37	199	324	480	666	882	129	405
16	078	38	201	327	483	669	886	133	410
18	081	39	203	329	486	673	890	137	415
20	.00083	40	.00205	.00332	.00489	.00676	.00894	.01142	.01420
22	085	41	207	334	492	680	898	146	425
24	088	42	208	336	494	683	902	151	430
26	090	43	210	339	497	686	906	155	435
28	093	44	212	341	500	690	909	159	439
30	.00095	45	.00214	.00343	.00503	.00693	.00913	.01164	.01444
32	098	46	216	346	506	697	917	168	449
34	100	47	218	348	509	700	921	173	454
36	103	48	220	351	512	703	925	177	459
38	106	49	222	353	515	707	929	182	464
40	.00108	50	.00224	.00356	.00518	.00710	.00933	.01186	.01469
42	111	51	226	358	521	714	937	191	474
44	114	52	228	361	524	717	941	195	479
46	117	53	230	363	527	721	945	200	484
48	120	54	232	365	530	724	949	204	489
50	.00122	55	.00234	.00368	.00533	.00728	.00953	.01209	.01494
52	125	56	236	370	536	731	957	213	499
54	128	57	238	373	539	735	961	218	504
56	131	58	240	375	542	738	965	222	509
58	134	59	0242	378	545	742	969	227	514
3° 00′	.00137	60	.0244	.00381	.00548	.00745	.00973	.01231	.01519

TABLE VI. — NATURAL VERSED SINES.

	10°	11°	12°	13°	14°	15°	16°	17°
00′	.01519	.01837	.02185	.02563	.02970	.03407	.03874	.04370
01	524	843	191	570	977	415	882	378
02	529	848	197	576	985	422	890	387
03	534	854	203	583	992	430	898	395
04	539	860	209	589	999	438	906	404
05	.01545	.01865	.02216	.02596	.03006	.03445	.03914	.04412
06	550	871	222	602	013	453	922	421
07	555	876	228	609	020	460	930	429
08	560	882	234	616	027	468	938	438
09	565	888	240	622	034	476	946	446
10	.01570	.01803	.02246	.02629	.03041	.03483	.03954	.04455
11	575	899	252	635	048	491	963	464
12	580	904	258	642	055	498	971	472
13	586	910	265	649	063	506	979	481
14	591	916	271	655	070	514	987	489
15	.01596	.01921	.02277	.02662	.03077	.03521	.03995	.04498
16	601	927	283	669	084	529	.04003	507
17	606	933	289	675	091	537	011	515
18	611	939	295	682	098	544	019	524
19	617	944	302	689	106	552	028	533
20	.01622	.01950	.02308	.02696	.03113	.03560	.04036	.04541
21	627	956	314	702	120	567	044	550
22	632	961	320	709	127	575	052	559
23	638	967	327	716	134	583	060	567
24	643	973	333	722	142	590	069	576
25	.01648	.01979	.02339	.02729	.03149	.03598	.04077	.04585
26	653	984	345	736	156	606	085	593
27	659	990	352	743	163	614	093	602
28	664	996	358	749	171	621	102	611
29	669	.02002	364	756	178	629	110	620
30	.01675	.02008	.02370	.02763	.03185	.03637	.04118	.04628
31	680	013	377	770	193	645	126	637
32	685	019	383	777	200	653	135	646
33	690	025	389	783	207	660	143	655
34	696	031	396	790	214	668	151	663
35	.01701	.02037	.02402	.02797	.03222	.03676	.04159	.04672
36	706	042	408	804	229	684	168	681
37	712	048	415	811	236	692	176	690
38	717	054	421	818	244	699	184	699
39	723	060	427	824	251	707	193	707
40	.01728	.02066	.02434	.02831	.03258	.03715	.04201	.04716
41	733	072	440	838	266	723	209	725
42	739	078	447	845	273	731	218	734
43	744	084	453	852	281	739	226	743
44	750	090	459	859	288	747	234	752
45	.01755	.02095	.02466	.02866	.03295	.03754	.04243	.04760
46	760	101	472	873	303	762	251	769
47	766	107	479	880	310	770	260	778
48	771	113	485	887	318	778	268	787
49	777	119	492	894	325	786	276	796
50	.01782	.02125	.02498	.02900	.03333	.03794	.04285	.04805
51	788	131	504	907	340	802	293	814
52	793	137	511	914	347	810	302	823
53	799	143	517	921	355	818	310	832
54	804	149	524	928	362	826	319	841
55	.01810	.02155	.02530	.02935	.03370	.03834	.04327	.04850
56	815	161	537	942	377	842	336	858
57	821	167	543	949	385	850	344	867
58	826	173	550	956	392	858	353	876
59	832	179	556	963	400	866	361	885
60	.01837	.02185	.02563	.02970	.03407	.03874	.04370	.04894

TABLE VII.—LENGTHS OF CIRCULAR ARCS: RADIUS = 1.

Sec.	Length.	Min.	Length.	Deg.	Length.	Deg.	Length.
1	.0000048	1	.0002909	1	.0174533	61	1.0646508
2	.0000097	2	.0005818	2	.0349066	62	1.0821041
3	.0000145	3	.0008727	3	.0523599	63	1.0995574
4	.0000194	4	.0011636	4	.0698132	64	1.1170107
5	.0000242	5	.0014544	5	.0872665	65	1.1344640
6	.0000291	6	.0017453	6	.1047198	66	1.1519173
7	.0000339	7	.0020362	7	.1221730	67	1.1693706
8	.0000388	8	.0023271	8	.1396263	68	1.1868239
9	.0000436	9	.0026180	9	.1570796	69	1.2042772
10	.0000485	10	.0029089	10	.1745329	70	1.2217305
11	.0000533	11	.0031998	11	.1919862	71	1.2391838
12	.0000582	12	.0034907	12	.2094395	72	1.2566371
13	.0000630	13	.0037815	13	.2268928	73	1.2740904
14	.0000679	14	.0040724	14	.2443461	74	1.2915436
15	.0000727	15	.0043633	15	.2617994	75	1.3089969
16	.0000776	16	.0046542	16	.2792527	76	1.3264502
17	.0000824	17	.0049451	17	.2967060	77	1.3439035
18	.0000873	18	.0052360	18	.3141593	78	1.3613568
19	.0000921	19	.0055269	19	.3316126	79	1.3788101
20	.0000970	20	.0058178	20	.3490659	80	1.3962634
21	.0001018	21	.0061087	21	.3665191	81	1.4137167
22	.0001067	22	.0063995	22	.3839724	82	1.4311700
23	.0001115	23	.0066904	23	.4014257	83	1.4486233
24	.0001164	24	.0069813	24	.4188790	84	1.4660766
25	.0001212	25	.0072722	25	.4363323	85	1.4835299
26	.0001261	26	.0075631	26	.4537856	86	1.5009832
27	.0001309	27	.0078540	27	.4712389	87	1.5184364
28	.0001357	28	.0081449	28	.4886922	88	1.5358897
29	.0001406	29	.0084358	29	.5061455	89	1.5533430
30	.0001454	30	.0087266	30	.5235988	90	1.5707963
31	.0001503	31	.0090175	31	.5410521	91	1.5882496
32	.0001551	32	.0093084	32	.5585054	92	1.6057029
33	.0001600	33	.0095993	33	.5759587	93	1.6231562
34	.0001648	34	.0098902	34	.5934119	94	1.6406095
35	.0001697	35	.0101811	35	.6108652	95	1.6580628
36	.0001745	36	.0104720	36	.6283185	96	1.6755161
37	.0001794	37	.0107629	37	.6457718	97	1.6929694
38	.0001842	38	.0110538	38	.6632251	98	1.7104227
39	.0001891	39	.0113446	39	.6806784	99	1.7278760
40	.0001939	40	.0116355	40	.6981317	100	1.7453293
41	.0001988	41	.0119264	41	.7155850	101	1.7627825
42	.0002036	42	.0122173	42	.7330383	102	1.7802358
43	.0002085	43	.0125082	43	.7504916	103	1.7976891
44	.0002133	44	.0127991	44	.7679449	104	1.8151424
45	.0002182	45	.0130900	45	.7853982	105	1.8325957
46	.0002230	46	.0133809	46	.8028515	106	1.8500490
47	.0002279	47	.0136717	47	.8203047	107	1.8675023
48	.0002327	48	.0139626	48	.8377580	108	1.8849556
49	.0002376	49	.0142535	49	.8552113	109	1.9024089
50	.0002424	50	.0145444	50	.8726646	110	1.9198622
51	.0002473	51	.0148353	51	.8901179	111	1.9373155
52	.0002521	52	.0151262	52	.9075712	112	1.9547688
53	.0002570	53	.0154171	53	.9250245	113	1.9722221
54	.0002618	54	.0157080	54	.9424778	114	1.9896753
55	.0002666	55	.0159989	55	.9599311	115	2.0071286
56	.0002715	56	.0162897	56	.9773844	116	2.0245819
57	.0002763	57	.0165806	57	.9948377	117	2.0420352
58	.0002812	58	.0168715	58	1.0122910	118	2.0594885
59	.0002860	59	.0171624	59	1.0297443	119	2.0769418
60	.0002909	60	.0174533	60	1.0471976	120	2.0943951

Vertical Heights

Minutes	0°	1°	2°	3°	4°	5°	6°	7°	8°	9°
0...	0.00	1.74	3.49	5.23	6.96	8.68	10.40	12.10	13.78	15.45
2...	0.06	1.80	3.55	5.28	7.02	8.74	10.45	12.15	13.84	15.51
4...	0.12	1.86	3.60	5.34	7.07	8.80	10.51	12.21	13.89	15.56
6...	0.17	1.92	3.66	5.40	7.13	8.85	10.57	12.26	13.95	15.62
8...	0.23	1.98	3.72	5.46	7.19	8.91	10.62	12.32	14.01	15.67
10...	0.29	2.04	3.78	5.52	7.25	8.97	10.68	12.38	14.06	15.73
12...	0.35	2.09	3.84	5.57	7.30	9.03	10.74	12.43	14.12	15.78
14...	0.41	2.15	3.90	5.63	7.36	9.08	10.79	12.49	14.17	15.84
16...	0.47	2.21	3.95	5.69	7.42	9.14	10.85	12.55	14.23	15.89
18...	0.52	2.27	4.01	5.75	7.48	9.20	10.91	12.60	14.28	15.95
20...	0.58	2.33	4.07	5.80	7.53	9.25	10.96	12.66	14.34	16.00
22...	0.64	2.38	4.13	5.86	7.59	9.31	11.02	12.72	14.40	16.06
24...	0.70	2.44	4.18	5.92	7.65	9.37	11.08	12.77	14.45	16.11
26...	0.76	2.50	4.24	5.98	7.71	9.43	11.13	12.83	14.51	16.17
28...	0.81	2.56	4.30	6.04	7.76	9.48	11.19	12.88	14.56	16.22
30...	0.87	2.62	4.36	6.09	7.82	9.54	11.25	12.94	14.62	16.28
32...	0.93	2.67	4.42	6.15	7.88	9.60	11.30	13.00	14.67	16.33
34...	0.99	2.73	4.48	6.21	7.94	9.65	11.36	13.05	14.73	16.39
36...	1.05	2.79	4.53	6.27	7.99	9.71	11.42	13.11	14.79	16.44
38...	1.11	2.85	4.59	6.33	8.05	9.77	11.47	13.17	14.84	16.50
40...	1.16	2.91	4.65	6.38	8.11	9.83	11.53	13.22	14.90	16.55
42...	1.22	2.97	4.71	6.44	8.17	9.88	11.59	13.28	14.95	16.61
44...	1.28	3.02	4.76	6.50	8.22	9.94	11.64	13.33	15.01	16.66
46...	1.34	3.08	4.82	6.56	8.28	10.00	11.70	13.39	15.06	16.72
48...	1.40	3.14	4.88	6.61	8.34	10.05	11.76	13.45	15.12	16.77
50...	1.45	3.20	4.94	6.67	8.40	10.11	11.81	13.50	15.17	16.83
52...	1.51	3.26	4.99	6.73	8.45	10.17	11.87	13.56	15.23	16.88
54...	1.57	3.31	5.05	6.79	8.51	10.22	11.93	13.61	15.28	16.94
56...	1.63	3.37	5.11	6.84	8.57	10.28	11.98	13.67	15.34	16.99
58...	1.69	3.43	5.17	6.90	8.63	10.34	12.04	13.73	15.40	17.05
60...	1.74	3.49	5.23	6.96	8.68	10.40	12.10	13.78	15.45	17.10

Horizontal Corrections

Dist.	0°	1°	2°	3°	4°	5°	6°	7°	8°	9°
100..	0.0	0.0	0.1	0.3	0.5	0.8	1.1	1.5	1.9	2.5
200..	0.0	0.1	0.2	0.5	1.0	1.5	2.2	3.0	3.9	4.9
300..	0.0	0.1	0.4	0.8	1.5	2.3	3.3	4.5	5.8	7.4
400..	0.0	0.1	0.5	1.1	2.0	3.0	4.4	6.0	7.8	9.8
500..	0.0	0.2	0.6	1.4	2.5	3.8	5.5	7.5	9.7	12.3
600..	0.0	0.2	0.7	1.6	2.9	4.6	6.5	8.9	11.6	14.7
700..	0.0	0.2	0.8	1.9	3.4	5.3	7.6	10.4	13.6	17.2
800..	0.0	0.2	1.0	2.2	3.9	6.1	8.7	11.9	15.5	19.6
900..	0.0	0.3	1.1	2.4	4.4	6.8	9.8	13.4	17.5	22.1
1000..	0.0	0.3	1.2	2.7	4.9	7.6	10.9	14.9	19.4	24.5

VERTICAL HEIGHTS

Minutes	10°	11°	12°	13°	14°	15°	16°	17°	18°	19°
0...	17.10	18.73	20.34	21.92	23.47	25.00	26.50	27.96	29.39	30.78
2...	17.16	18.78	20.39	21.97	23.52	25.05	26.55	28.01	29.44	30.83
4...	17.21	18.84	20.44	22.02	23.58	25.10	26.59	28.06	29.48	30.87
6...	17.26	18.89	20.50	22.08	23.63	25.15	26.64	28.10	29.53	30.92
8...	17.32	18.95	20.55	22.13	23.68	25.20	26.69	28.15	29.58	30.97
10...	17.37	19.00	20.60	22.18	23.73	25.25	26.74	28.20	29.62	31.01
12...	17.43	19.05	20.66	22.23	23.78	25.30	26.79	28.25	29.67	31.06
14...	17.48	19.11	20.71	22.28	23.83	25.35	26.84	28.30	29.72	31.10
16...	17.54	19.16	20.76	22.34	23.88	25.40	26.89	28.34	29.76	31.15
18...	17.59	19.21	20.81	22.39	23.93	25.45	26.94	28.39	29.81	31.19
20...	17.65	19.27	20.87	22.44	23.99	25.50	26.99	28.44	29.86	31.24
22...	17.70	19.32	20.92	22.49	24.04	25.55	27.04	28.49	29.90	31.28
24...	17.76	19.38	20.97	22.54	24.09	25.60	27.09	28.54	29.95	31.33
26..	17.81	19.43	21.03	22.60	24.14	25.65	27.13	28.58	30.00	31.38
28...	17.86	19.48	21.08	22.65	24.19	25.70	27.18	28.63	30.04	31.42
30...	17.92	19.54	21.13	22.70	24.24	25.75	27.23	28.68	30.09	31.47
32...	17.97	19.59	21.18	22.75	24.29	25.80	27.28	28.73	30.14	31.51
34...	18.03	19.64	21.24	22.80	24.34	25.85	27.33	28.77	30.19	31.56
36...	18.08	19.70	21.29	22.85	24.39	25.90	27.38	28.82	30.23	31.60
38...	18.14	19.75	21.34	22.91	24.44	25.95	27.43	28.87	30.28	31.65
40...	18.19	19.80	21.39	22.96	24.49	26.00	27.48	28.92	30.32	31.69
42...	18.24	19.86	21.45	23.01	24.55	26.05	27.52	28.96	30.37	31.74
44...	18.30	19.91	21.50	23.06	24.60	26.10	27.57	29.01	30.41	31.78
46...	18.35	19.96	21.55	23.11	24.65	26.15	27.62	29.06	30.46	31.83
48...	18.41	20.02	21.60	23.16	24.70	26.20	27.67	29.11	30.51	31.87
50...	18.46	20.07	21.66	23.22	24.75	26.25	27.72	29.15	30.55	31.92
52...	18.51	20.12	21.71	23.27	24.80	26.30	27.77	29.20	30.60	31.96
54. .	18.57	20.18	21.76	23.32	24.85	26.35	27.81	29.25	30.65	32.01
56...	18.62	20.23	21.81	23.37	24.90	26.40	27.86	29.30	30.69	32.05
58...	18.68	20.28	21.87	23.42	24.95	26.45	27.91	29.34	30.74	32.09
60...	18.73	20.34	21.92	23.47	25.00	26.50	27.96	29.39	30.78	32.14

HORIZONTAL CORRECTIONS

Dist.	10°	11°	12°	13°	14°	15°	16°	17°	18°	19°
100..	3.0	3.6	4.3	5.1	5.9	6.7	7.6	8.5	9.5	10.6
200..	6.0	7.3	8.6	10.1	11.7	13.4	15.2	17.1	19.1	21.2
300..	9.1	10.9	13.0	15.2	17.6	20.1	22.8	25.6	28.6	31.8
400..	12.1	14.6	17.3	20.2	23.4	26.8	30.4	34.2	38.2	42.4
500..	15.1	18.2	21.6	25.3	29.3	33.5	38.0	42.7	47.7	53.0
600..	18.1	21.8	25.9	30.4	35.1	40.2	45.6	51.3	57.3	63.6
700..	21.1	25.5	30.2	35.4	41.0	46.9	53.2	59.8	66.8	74.2
800..	24.2	29.1	34.6	40.5	46.8	53.6	60.8	68.4	76.4	84.8
900..	27.2	32.8	38.9	45.5	52.7	60.3	68.4	76.9	85.9	95.4
1000..	30.2	36.4	43.2	50.6	58.5	67.0	76.0	85.5	95.5	106.0

Vertical Heights

Minutes	20°	21°	22°	23°	24°	25°	26°	27°	28°	29°
0...	32.14	33.46	34.73	35.97	37.16	38.30	39.40	40.45	41.45	42.40
2...	32.18	33.50	34.77	36.01	37.20	38.34	39.44	40.49	41.48	42.43
4...	32.23	33.54	34.82	36.05	37.23	38.38	39.47	40.52	41.52	42.46
6...	32.27	33.59	34.86	36.09	37.27	38.41	39.51	40.55	41.55	42.49
8...	32.32	33.63	34.90	36.13	37.31	38.45	39.54	40.59	41.58	42.53
10...	32.36	33.67	34.94	36.17	37.35	38.49	39.58	40.62	41.61	42.56
12...	32.41	33.72	34.98	36.21	37.39	38.53	39.61	40.66	41.65	42.59
14...	32.45	33.76	35.02	36.25	37.43	38.56	39.65	40.69	41.68	42.62
16...	32.49	33.80	35.07	36.29	37.47	38.60	39.69	40.72	41.71	42.65
18...	32.54	33.84	35.11	36.33	37.51	38.64	39.72	40.76	41.74	42.68
20...	32.58	33.89	35.15	36.37	37.54	38.67	39.76	40.79	41.77	42.71
22...	32.63	33.93	35.19	36.41	37.58	38.71	39.79	40.82	41.81	42.74
24...	32.67	33.97	35.23	36.45	37.62	38.75	39.83	40.86	41.84	42.77
26...	32.72	34.01	35.27	36.49	37.66	38.78	39.86	40.89	41.87	42.80
28...	32.76	34.06	35.31	36.53	37.70	38.82	39.90	40.92	41.90	42.83
30...	32.80	34.10	35.36	36.57	37.74	38.86	39.93	40.96	41.93	42.86
32...	32.85	34.14	35.40	36.61	37.77	38.89	39.97	40.99	41.97	42.89
34...	32.89	34.18	35.44	36.65	37.81	38.93	40.00	41.02	42.00	42.92
36...	32.93	34.23	35.48	36.69	37.85	38.97	40.04	41.06	42.03	42.95
38...	32.98	34.27	35.52	36.73	37.89	39.00	40.07	41.09	42.06	42.98
40...	33.02	34.31	35.56	36.77	37.93	39.04	40.11	41.12	42.09	43.01
42...	33.07	34.35	35.60	36.80	37.96	39.08	40.14	41.16	42.12	43.04
44...	33.11	34.40	35.64	36.84	38.00	39.11	40.18	41.19	42.15	43.07
46...	33.15	34.44	35.68	36.88	38.04	39.15	40.21	41.22	42.19	43.10
48...	33.20	34.48	35.72	36.92	38.08	39.18	40.24	41.26	42.22	43.13
50...	33.24	34.52	35.76	36.96	38.11	39.22	40.28	41.29	42.25	43.16
52...	33.28	34.57	35.80	37.00	38.15	39.26	40.31	41.32	42.28	43.18
54...	33.33	34.61	35.85	37.04	38.19	39.29	40.35	41.35	42.31	43.21
56...	33.37	34.65	35.89	37.08	38.23	39.33	40.38	41.39	42.34	43.24
58...	33.41	34.69	35.93	37.12	38.26	39.36	40.42	41.42	42.37	43.27
60...	33.46	34.73	35.97	37.16	38.30	39.40	40.45	41.45	42.40	43.30

Horizontal Corrections

Dist.	20°	21°	22°	23°	24°	25°	26°	27°	28°	29°
100..	11.7	12.8	14.0	15.3	16.5	17.9	19.2	20.6	22.0	23.5
200..	23.4	25.7	28.1	30.5	33.1	35.7	38.4	41.2	44.1	47.0
300..	35.1	38.5	42.1	45.8	49.6	53.6	57.7	61.8	66.1	70.5
400..	46.8	51.4	56.1	61.1	66.2	71.4	76.9	82.4	88.2	94.0
500..	58.5	64.2	70.2	76.4	82.7	89.3	96.1	103.1	110.2	117.5
600..	70.2	77.0	84.2	91.6	99.2	107.2	115.3	123.7	132.2	141.0
700..	81.9	89.9	98.2	106.9	115.8	125.0	134.5	144.3	154.3	164.5
800..	93.6	102.7	112.2	122.2	132.3	142.9	153.8	164.9	176.3	188.0
900..	105.3	115.6	126.3	137.4	148.9	160.7	173.0	185.5	198.4	211.5
1000..	117.0	128.4	140.3	152.7	165.4	178.6	192.2	206.1	220.4	235.0

Vertical Heights.

Minutes	30°	31°	32°	33°	34°	35°	36°	37°	38°	39°
0....	43.30	44.15	44.94	45.68	46.36	46.98	47.55	48.06	48.52	48.91
2....	43.33	44.17	44.97	45.70	46.38	47.00	47.57	48.08	48.53	48.92
4....	43.36	44.20	44.99	45.72	46.40	47.02	47.59	48.10	48.54	48.93
6....	43.39	44.23	45.02	45.75	46.42	47.04	47.61	48.11	48.56	48.94
8....	43.42	44.26	45.04	45.77	46.45	47.06	47.62	48.13	48.57	48.96
10....	43.45	44.28	45.07	45.80	46.47	47.08	47.64	48.14	48.58	48.97
12....	43.47	44.31	45.09	45.82	46.49	47.10	47.66	48.16	48.60	48.98
14....	43.50	44.34	45.12	45.84	46.51	47.12	47.68	48.17	48.61	48.99
16....	43.52	44.36	45.14	45.86	46.53	47.14	47.69	48.19	48.63	49.00
18....	43.56	44.39	45.17	45.89	46.55	47.16	47.71	48.21	48.64	49.01
20....	43.59	44.42	45.19	45.91	46.57	47.18	47.73	48.22	48.65	49.03
22....	43.62	44.44	45.22	45.93	46.60	47.20	47.75	48.24	48.67	49.04
24....	43.65	44.47	45.24	45.96	46.62	47.22	47.76	48.25	48.68	49.05
26....	43.67	44.50	45.27	45.98	46.64	47.24	47.78	48.27	48.69	49.06
28....	43.70	44.52	45.29	46.00	46.66	47.26	47.80	48.28	48.71	49.07
30....	43.73	44.55	45.32	46.03	46.68	47.28	47.82	48.30	48.72	49.08
32....	43.76	44.58	45.34	46.05	46.70	47.30	47.83	48.31	48.73	49.09
34....	43.79	44.60	45.36	46.07	46.72	47.31	47.85	48.33	48.74	49.10
36....	43.82	44.63	45.39	46.09	46.74	47.33	47.87	48.34	48.76	49.11
38....	43.84	44.66	45.41	46.12	46.76	47.35	47.88	48.36	48.77	49.13
40....	43.87	44.68	45.44	46.14	46.78	47.37	47.90	48.37	48.78	49.14
42....	43.90	44.71	45.46	46.16	46.80	47.39	47.92	48.39	48.80	49.15
44....	43.93	44.74	45.49	46.18	46.82	47.41	47.93	48.40	48.81	49.16
46....	43.95	44.76	45.51	46.21	46.84	47.43	47.95	48.41	48.82	49.17
48....	43.98	44.79	45.53	46.23	46.86	47.44	47.97	48.43	48.83	49.18
50....	44.01	44.81	45.56	46.25	46.88	47.46	47.98	48.44	48.85	49.19
52....	44.04	44.84	45.58	46.27	46.90	47.48	48.00	48.46	48.86	49.20
54....	44.07	44.86	45.61	46.29	46.92	47.50	48.01	48.47	48.87	49.21
56....	44.09	44.89	45.63	46.32	46.94	47.52	48.03	48.49	48.88	49.22
58....	44.12	44.91	45.65	46.34	46.96	47.54	48.05	48.50	48.90	49.23
60....	44.15	44.94	45.68	46.36	46.98	47.55	48.06	48.52	48.91	49.24

Horizontal Corrections.

Dist.	30° 00′	30° 30′	31° 00′	31° 30′	32° 00′	32° 30′	33° 00′	33° 30′	34° 00′	34° 30
100....	25.0	25.8	26.5	27.3	28.1	28.9	29.7	30.5	31.3	32.1
200....	50.0	51.5	53.1	54.6	56.2	57.7	59.3	60.9	62.5	64.2
300....	75.0	77.3	79.6	81.9	84.2	86.6	89.0	91.4	93.8	96.2
400....	100.0	103.0	106.1	109.2	112.3	115.5	118.6	121.8	125.1	128.3
500....	125.0	128.8	132.6	136.5	140.4	144.3	148.3	152.3	156.3	160.4

Dist.	35° 00′	35° 30′	36° 00′	36° 30′	37° 00′	37° 30′	38° 00′	38° 30′	39° 00′	39° 30
100....	32.9	33.7	34.6	35.4	36.2	37.1	37.9	38.7	39.6	40.5
200....	65.8	67.4	69.1	70.8	72.4	74.1	75.8	77.5	79.2	80.9
300....	98.7	101.2	103.7	106.1	108.7	111.2	113.7	116.2	118.8	121.3
400....	131.6	134.9	138.2	141.5	144.9	148.2	151.6	155.0	158.4	161.7
500....	164.5	168.6	172.8	176.9	181.1	185.3	189.5	193.7	198.0	202.2

TABLE IX.

Mean Refractions in Declination.*

TO BE USED WITH THE SOLAR ATTACHMENT.

Computed by Edward W. Arms, C. E., for W. & L. E. Gurley, Troy, N. Y.)

Hour Angle.†	DECLINATIONS.								
	For Latitude 2° 30′.								
	+20°	+15°	+10°	+5°	0°	−5°	−10°	−15°	−20°
0 h.	−18″	−12″	−07″	−02″	+02″	07″	12″	18″	23″
2	−18	−12	−07	−02	+02	07	12	18	23
3	−17	−11	−06	−01	+03	08	13	19	25
4	−15	−10	−05	0	+05	10	15	21	27
5	−10	−05	0	+05	10	15	20	26	32
	For Latitude 5°.								
0 h.	−15″	−10″	−05″	0″	+05″	10″	15″	20″	27″
2	−15	−10	−05	0	+05	10	15	20	27
3	−13	−08	−03	+02	07	12	17	23	29
4	−10	−05	0	+05	10	15	20	27	32
5	−05	0	+05	10	15	20	27	32	40
	For Latitude 7° 30′.								
0 h.	−13″	−08″	−02″	+02″	08″	13″	18″	24″	29″
2	−12	−07	−01	+03	09	14	19	25	31
3	−10	−05	0	+05	10	15	20	26	32
4	−05	0	+05	10	15	20	26	32	39
5	+07	12	17	23	29	36	43	51	1′01
	For Latitude 10°.								
0 h.	−10″	−05″	0″	+05″	10″	15″	20″	26″	32″
2	−07	−03	+02	07	12	17	22	28	34
3	−05	0	+03	08	13	19	25	31	38
4	0	05	10	15	20	26	32	39	46
5	+15	20	26	32	39	46	55	1′06	1′19
	For Latitude 12° 30′.								
0 h.	−08″	−02″	+02″	8″	13″	18″	24″	30″	36″
2	−06	00	+05	10	15	20	26	32	39
3	+02	07	12	17	23	29	36	43	51
4	04	09	14	20	25	31	40	48	55
5	21	27	33	40	48	57	1′08	1′23	1′41
	For Latitude 15°.								
0 h.	−05″	0″	+05″	10″	15″	21″	27″	33″	40″
2	−03	+02	07	12	18	23	29	36	43
3	+01	05	11	16	22	28	34	41	49
4	08	12	19	24	30	37	44	53	1′04
5	29	34	41	49	59	1′10	1′24	1′43	2 08

* Printed by permission of W. & L. E. Gurley.

† Hour angles are reckoned either way from local noon.

For Latitude 17° 30′.

Hour Angle	DECLINATIONS. +20°	+15°	+10°	+5°	0°	−5°	−10°	−15°	−20°
0 h.	−02″	+02″	08″	13″	18″	24″	30″	36″	44″
2	0	05	10	15	21	27	33	40	48
3	+02	10	15	21	27	33	40	48	57
4	13	18	23	29	35	43	51	1′01	1′13
5	34	41	49	58	1′10	1′23	1′41	2 06	2 42

For Latitude 20°.

0 h.	0″	05″	10″	15″	21″	27″	33″	40″	48″
2	03	07	13	18	24	30	36	44	52
3	06	13	18	24	30	36	44	52	1′02
4	17	22	28	35	42	50	1′00	1′11	1 26
5	39	47	57	1′07	1′20	1′37	2 00	2 32	3 25

For Latitude 22° 30′.

0 h.	02″	08″	13″	18″	24″	30″	36″	44″	52″
2	06	11	15	21	27	33	40	48	57
3	11	15	21	27	33	40	48	57	1′08
4	20	26	32	39	46	56	1′07	1′19	1 37
5	45	53	1′03	1′16	1′31	1′52	2 21	3 07	4 28

For Latitude 25°.

0 h.	05″	10″	15″	21″	27″	33″	40″	48″	57″
2	08	14	19	25	31	38	46	54	1′05
3	12	18	24	30	37	44	53	1′04	1 18
4	23	29	35	45	53	1′03	1′16	1 31	1 52
5	49	59	1′10	1′24	1′52	2 07	2 44	3 46	5 43

For Latitude 27° 30′.

0 h.	08″	13″	18″	24″	30″	36″	44″	52″	1′02″
2	11	16	22	28	34	41	49	1′00	1 10
3	17	22	28	35	42	50	1′00	1 11	1 26
4	28	35	42	50	1′00	1′11	1 26	1 43	2 09
5	54	1′05	1′18	1′34	1 54	2 24	3 11	4 38	8 15

For Latitude 30°.

0 h.	10″	15″	21″	27″	33″	40″	48″	57″	1′08″
2	14	19	25	31	38	46	54	1′05	1 18
3	20	26	32	39	47	55	1′06	1 19	1 36
4	32	39	46	52	1′06	1′19	1 35	1 57	2 29
5	1 00	1′10	1′24	1′52	2 07	2 44	3 46	5 43	13 06

For Latitude 32° 30′.

0 h.	13″	18″	24″	30″	36″	44″	52″	1′02″	1′14″
2	17	22	28	35	42	50	1′00	1 11	1 26
3	23	29	35	43	51	1′01	1 13	1 28	1 47
4	35	43	51	1′01	1′13	1 27	1 46	2 13	2 54
5	1′03	1′15	1′31	1 53	2 20	3 05	4 25	7 36	

Hour Angle	DECLINATIONS.								
	For Latitude 35°.								
	+20°	+15°	+10°	+5°	0°	−5°	−10°	−15°	−20°
0 h.	15″	21″	27″	33″	40″	48″	57″	1′08″	1′21″
2	20	25	32	38	46	55	1′05	1 18	1 35
3	26	33	39	47	56	1′07	1 21	1 38	2 00
4	39	47	56	1′07	1′20	1 36	1 59	2 32	3 25
5	1′07	1′20	1′38	2 00	2 34	3 29	5 14	10 16	
	For Latitude 37° 30′.								
0 h.	18″	24″	30″	36″	44″	52″	1′02″	1′14″	1′29
2	22	28	35	42	50	1′00	1 12	1 26	1 45
3	29	36	43	52	1′02	1 14	1 29	1 49	2 16
4	43	51	1′01	1′13	1 27	1 49	2 14	2 54	4 05
5	1′11	1′26	1 54	2 10	2 49	3 55	6 15	14 58	
	For Latitude 40°.								
0 h.	21″	27″	33″	40″	48″	57″	1′08″	1′21″	1′39″
2	25	32	39	46	52	1′06	1 19	1 35	1 57
3	33	40	48	57	1′08	1 21	1 38	2 02	2 36
4	47	55	1′06	1′19	1 36	1 58	2 30	3 21	4 59
5	1′15	1′31	1 51	2 20	3 05	4 25	7 34	25 18	
	For Latitude 42° 30′.								
0 h.	24″	30″	36″	44″	52″	1′02″	1′14″	1′29″	1′49″
2	28	35	39	50	1′00	1 12	1 26	1 45	2 11
3	36	43	52	1′02	1 13	1 29	1 49	2 17	2 59
4	50	1′00	1′11	1 26	1 44	2 10	2 49	3 55	6 16
5	1′19	1 36	1 58	2 30	3 22	5 00	9 24		
	For Latitude 45°.								
0 h.	27″	33″	40″	48″	57″	1′08″	1′21″	1′39″	2′02″
2	32	39	46	52	1′06	1 19	1 35	1 57	2 29
3	40	47	56	1′07	1 21	1 38	2 00	2 34	3 29
4	54	1′04	1′16	1 33	1 54	2 24	3 11	4 38	8 15
5	1′23	1 41	2 05	2 41	3 40	5 40	12 02		
	For Latitude 47° 30′.								
0 h.	30″	36″	44″	52″	1′02″	1′14″	1′29″	1′49″	2′18″
2	35	42	50	1′00	1 12	1 26	1 45	2 01	2 51
3	43	51	1′01	1 13	1 28	1 47	2 15	2 56	4 08
4	56	1′09	1 23	1 40	2 05	2 40	3 39	5 37	11 18
5	1′27	1 46	2 12	2 52	4 01	6 30	16 19		
	For Latitude 50°.								
0 h.	33″	40″	48″	57″	1′08″	1′21″	1′39″	2′02″	2′36″
2	38	46	55	1′06	1 18	1 35	1 57	2 28	3 19
3	47	56	1′06	1 19	1 36	2 29	2 31	3 23	5 62
4	1′02	1′14	1 29	1 48	2 16	2 58	4 18	6 59	19 47
5	1 30	1 51	2 19	3 04	4 22	7 28	24 10		

HOUR ANGLE.	DECLINATIONS.								
	For Latitude 52° 30′.								
	+20°	+15°	+10°	+5°	0°	−5°	−10°	−15°	−20°
0 h.	36″	44″	52″	1′02″	1′14″	1′29″	1′49″	2′18″	3′05″
2	43	50	59	1 11	1 26	1 42	2 23	2 49	3 55
3	50	1′00	1′11	1 26	1 45	2 11	2 51	2 58	6 22
4	1′05	1 18	1 35	2 10	2 28	3 19	4 53	8 42	
5	1 34	1 56	2 27	3 16	4 47	8 52			
	For Latitude 55°.								
0 h.	40″	48″	57″	1′08″	1′21″	1′39″	2′02″	2′36″	3′33″
2	46	55	1′05	1 18	1 34	1 56	2 30	3 15	4 47
3	55	1′06	1 19	1 35	1 58	2 30	3 21	4 58	9 19
4	1′10	1 23	1 42	2 06	2 43	3 44	5 49	12 41	
5	1 37	2 01	2 34	3 28	5 15	10 18			
	For Latitude 57° 30′.								
0 h.	44″	52″	1′02″	1′14″	1′29″	1′49″	2′18″	3′05″	4′37″
2	50	59	1 11	1 25	1 43	2 09	2 47	3 51	6 04
3	58	1′10	1 24	1 42	2 07	2 43	3 45	5 50	12 47
4	1′11	1 25	1 43	2 10	2 50	3 55	6 14	14 49	
5	1 41	2 06	2 42	3 42	5 46	12 26			
	For Latitude 60°.								
0 h.	48″	57″	1′08″	1′21″	1′39″	2′02″	2′36″	3′33″	5′23″
2	54	1′04	1 17	1 33	1 54	2 24	3 12	4 38	8 15
3	1′03	1 15	1 30	1 51	2 20	3 04	4 24	7 31	24 44
4	1 18	1 34	1 56	2 28	3 18	4 50	8 53		
5	1 45	2 11	2 50	3 57	6 21	15 32			
	For Latitude 62° 30′.								
0 h.	52″	1′02″	1′14″	1′29″	1′50″	2′18″	3′00″	4′17″	7′13″
2	58	1′09	1 23	1 41	2 06	2 43	3 44	5 50	12 44
3	1′07″	1 23	1 38	2 01	2 35	3 30	5 16	10 24	
4	1 23	1 40	2 05	2 40	3 40	5 37	11 50		
5	1 48	2 17	2 59	4 14	7 03				
	For Latitude 65°.								
0 h.	57″	1′08″	1′21″	1′39″	2′02″	2′36″	3′33″	5′23″	10′51″
2	1′03″	1 16	1 31	1 52	2 21	3 07	4 28	7 44	
3	1 12	1 27	1 46	2 12	2 52	4 02	6 33		
4	1 27	1 47	2 13	2 54	4 05	6 40			
5	1 52	2 22	3 08	4 30	7 52				
	For Latitude 67° 30′.								
0 h.	1′02″	1′14″	1′29″	1′50″	2′18″	3′00″	4′17″	7′13″	
2	1 08	1 22	1 40	2 03	2 39	3 37	5 32	11 28	
3	1 17	1 34	1 55	2 26	3 14	4 44	8 34		
4	1 32	1 53	2 23	3 14	4 35	8 05			
5	1 56	2 28	3 17	4 40	8 51				
	For Latitude 70°.								
0 h.	1′08″	1′21″	1′39″	2′02″	2′36″	3′33″	5′23″	10′51″	
2	1 14	1 29	1 50	2 18	3 00	4 17	7 13		
3	1 23	1 43	2 05	2 41	3 41	5 59	12 15		
4	1 37	2 00	2 34	3 28	5 20	10 12			
5	2 02	2 33	3 27	5 11	10 05				

TABLE X. TRIGONOMETRIC AND MISCELLANEOUS FORMULAS.



RIGHT TRIANGLE



OBLIQUE TRIANGLE

SOLUTION OF RIGHT TRIANGLES.

$\sin A = \frac{a}{c} = \cos B$ $\qquad$ $\cos A = \frac{b}{c} = \sin B$

$\tan A = \frac{a}{b} = \cot B$ $\qquad$ $\cot A = \frac{b}{a} = \tan B$

$\sec A = \frac{c}{b} = \operatorname{cosec} B$ $\qquad$ $\operatorname{cosec} A = \frac{c}{a} = \sec B$

$\operatorname{vers} A = \frac{c-b}{c} = \frac{d}{c}$ $\qquad$ $\operatorname{exsec} A = \frac{e}{c}$

$a = c \sin A = b \tan A = c \cos B = b \cot B = \sqrt{(c+b)(c-b)}$

$b = c \cos A = a \cot A = c \sin B = a \tan B = \sqrt{(c+a)(c-a)} = c - c \operatorname{vers} A$

$d = c \operatorname{vers} A$ $\qquad$ $e = c \operatorname{exsec} A$

$$c = \frac{a}{\cos B} = \frac{b}{\sin B} = \frac{a}{\sin A} = \frac{b}{\cos A} = \frac{d}{\operatorname{vers} A} = \frac{e}{\operatorname{exsec} A} = b + b \operatorname{exsec} A$$

SOLUTION OF OBLIQUE TRIANGLES.

Given.	Sought.	Formulas.
A, B, a	b, c	$b = \frac{a}{\sin A} \cdot \sin B, \qquad c = \frac{a}{\sin A} \sin (A+B)$
A, a, b	B, c	$\sin B = \frac{\sin A}{a} \cdot b, \qquad c = \frac{a}{\sin A} \cdot \sin C.$
C, a, b	$A - B$	$\tan \frac{1}{2}(A-B) = \frac{a-b}{a+b} \tan \frac{1}{2}(A+B)$
a, b, c	A	If $s = \frac{1}{2}(a+b+c)$, $\sin \frac{1}{2} A = \sqrt{\frac{(s-b)(s-c)}{bc}}$
		$\cos \frac{1}{2} A = \sqrt{\frac{s(s-a)}{bc}}$; $\tan \frac{1}{2} A = \sqrt{\frac{(s-b)(s-c)}{s(s-a)}}$.
		$\sin A = \frac{2\sqrt{s(s-a)(s-b)(s-c)}}{bc}$;
		$\operatorname{vers} A = \frac{2(s-b)(s-c)}{bc}$
	area	$\text{area} = \sqrt{s(s-a)(s-b)(s-c)}$
A, B, C, a	area	$\text{area} = \frac{a^2 \sin B \cdot \sin C}{2 \sin A}$
C, a, b	area	$\text{area} = \frac{1}{2} a b \sin C.$

TABLE X. TRIGONOMETRIC AND MISCELLANEOUS FORMULAS.

GENERAL TRIGONOMETRIC FORMULAS.

$$\sin A = 2 \sin \tfrac{1}{2} A \cos \tfrac{1}{2} A = \sqrt{1-\cos^2 A} = \tan A \cos A = \sqrt{\tfrac{1}{2}(1-\cos 2A)}$$

$$\cos A = 2\cos^2 \tfrac{1}{2}A - 1 = 1 - 2\sin^2 \tfrac{1}{2} A = \cos^2 \tfrac{1}{2}A - \sin^2 \tfrac{1}{2} A = 1 - \text{vers } A$$

$$\tan A = \frac{\sin A}{\cos A} = \frac{\sqrt{1-\cos^2 A}}{\cos A} = \frac{\sin 2A}{1+\cos 2A}$$

$$\cot A = \frac{\cos A}{\sin A} = \frac{\sin 2A}{1-\cos 2A} = \frac{\sin 2A}{\text{vers } 2A}$$

$$\text{vers } A = 1 - \cos A = \sin A \tan \tfrac{1}{2} A = 2\sin^2 \tfrac{1}{2} A$$

$$\text{exsec } A = \sec A - 1 = \tan A \tan \tfrac{1}{2} A = \frac{\text{vers } A}{\cos A}$$

$$\sin 2A = 2 \sin A \cos A$$

$$\cos 2A = 2\cos^2 A - 1 = \cos^2 A - \sin^2 A = 1 - 2\sin^2 A$$

$$\tan 2A = \frac{2\tan A}{1-\tan^2 A}$$

$$\cot 2A = \frac{\cot^2 A - 1}{2\cot A}$$

$$\text{vers } 2A = 2\sin^2 A = 2 \sin A \cos A \tan A$$

$$\text{exsec } 2A = \frac{2\tan^2 A}{1-\tan^2 A}$$

$$\sin^2 A + \cos^2 A = 1$$

$$\sin (A \pm B) = \sin A \cos B \pm \sin B \cos A$$

$$\cos (A \pm B) = \cos A \cos B \mp \sin A \sin B$$

$$\sin A + \sin B = 2 \sin \tfrac{1}{2} (A+B) \cos \tfrac{1}{2} (A-B)$$

$$\sin A - \sin B = 2 \cos \tfrac{1}{2} (A+B) \sin \tfrac{1}{2} (A-B)$$

$$\cos A + \cos B = 2 \cos \tfrac{1}{2} (A+B) \cos \tfrac{1}{2} (A-B)$$

$$\cos B - \cos A = 2 \sin \tfrac{1}{2} (A+B) \sin \tfrac{1}{2} (A-B)$$

$$\sin^2 A - \sin^2 B = \cos^2 B - \cos^2 A = \sin (A+B) \sin (A-B)$$

$$\cos^2 A - \sin^2 B = \cos (A+B) \cos (A-B)$$

$$\tan A + \tan B = \frac{\sin (A+B)}{\cos A \cos B}$$

$$\tan A - \tan B = \frac{\sin (A-B)}{\cos A \cos B}$$

TABLE XI. CIRCULAR CURVE FORMULAS.

R = Radius
I = Central Angle
T = Tangent Distance
E = External Distance
M = Middle Ordinate
L_c = Length of Arc
C = Chord
t = Tangent Offset

$T = R \tan \frac{1}{2} I$

$E = R \operatorname{exsec} \frac{1}{2} I$

$M = R \operatorname{vers} \frac{1}{2} I$

$C = 2 R \sin \frac{1}{2} I$

$L_c = R \times$ Circular Measure I

$L_c - C = \frac{C^3}{24 R^2}$ (Approximate)

$M = R - \sqrt{R^2 - \left(\frac{C}{2}\right)^2}$

$M = \frac{C^2}{8R}$ (Approximate)

$t = \frac{C^2}{2R}$

TABLE XII. GEOMETRIC FORMULAS.

Required.	Given.	Formulas.
Area of		
Circle	Radius $= r$	πr^2
Sector of Circle	Radius $= r$, Arc $= L_c$	$\frac{rL_c}{2}$
Segment of Circle	Chord $= C$, Middle Ordinate $= M$	$\frac{2}{3} CM$ (Approximate)
Ellipse	Semi-axes $= a$ and b	πab
Surface of		
Cone	Radius of Base $= r$; Slant Height $= s$	πrs
Cylinder	Radius $= r$, Height $= h$	$2 \pi rh$
Sphere	Radius $= r$	$4 \pi r^2$
Zone	Radius of Sphere $= r$, Height of Zone $= h$	$2 \pi rh$
Volume of		
Prism or Cylinder	Area of Base $= b$; Height $= h$	bh
Pyramid or Cone	Area of Base $= b$; Height $= h$	$\frac{bh}{3}$
Frustum of Pyramid or Cone	Area of bases $= b$ and b'; Height $= h$	$\frac{h}{3}(b + b' + \sqrt{bb'})$
Sphere	Radius $= r$	$\frac{4}{3} \pi r^3$

TABLE XIII. LINEAR MEASURE.

1 foot = 12 inches
1 yard = 3 feet
1 rod = $5\frac{1}{2}$ yards = $16\frac{1}{2}$ feet
1 mile = 320 rods = 1760 yards = 5280 feet

TABLE XIV. SQUARE MEASURE.

1 sq. foot = 144 sq. inches
1 sq. yard = 9 sq. feet = 1296 sq. inches
1 sq. rod = $30\frac{1}{4}$ sq. yards = $272\frac{1}{4}$ sq. feet
1 acre = 160 sq. rods = 4840 sq. yards = 43,560 sq. feet
1 sq. mile = 640 acres = 102,400 sq. rods = 27,878,400 sq. feet

---

TABLE XV. LINEAR MEASURE—METRIC SYSTEM.

1 myriameter = 10 kilometers
1 kilometer = 10 hectometers
1 hectometer = 10 decameters
1 decameter = 10 meters
1 meter = 10 decimeters
1 decimeter = 10 centimeters
1 centimeter = 10 millimeters

TABLE XVI. SQUARE MEASURE—METRIC SYSTEM.

1 centare = 1 sq. meter
1 are = 100 sq. meters
1 hectare = 100 ares = 10,000 sq. meters

TABLE XVII. CONSTANTS.

	Number.	Logarithm.
Ratio of circumference to diameter	3.14159	0.49715
Base of hyperbolic logarithms	2.71828	0.43429
Modulus of common system of logs	0.43429	9.63778–10
Length of seconds pendulum at N. Y. (inches)	39.1017	1.59220
Acceleration due to gravity at N. Y.	32.15949	1.50731
Cubic inches in 1 U. S. gallon	231	2.36361
Cubic feet in 1 U. S. gallon	0.1337	9.12613–10
U. S. gallons in 1 cubic foot	7.4805	0.87393
Pounds of water in 1 cubic foot	62.5	1.79588
Pounds of water in 1 U. S. gallon	8.355	0.92195
Pounds per square inch due to 1 atmosphere	14.7	1.16732
Pounds per square inch due to 1 foot head of water	0.434	9.63749–10
Feet of head for pressure of 1 pound per square inch	2.304	0.36248
Inches in 1 centimeter	0.3937	9.59517–10
Centimeters in 1 inch	2.5400	0.40483
Feet in 1 meter	3.2808	0.51598
Meters in 1 foot	0.3048	9.48402–10
Miles in 1 kilometer	0.62137	9.79335–10
Kilometers in 1 mile	1.60935	0.20665
Square inches in 1 square centimeter	0.1550	9.19033–10
Square centimeters in 1 square inch	6.4520	0.80969
Square feet in 1 square meter	10.764	1.03107
Square meters in 1 square foot	0.09290	8.96802–10
Cubic feet in 1 cubic meter	35.3156	1.54797
Pounds (av.) in 1 kilogram	2.2046	0.34333
Kilograms in 1 pound (av.)	0.4536	9.65667–10
Ft.-lbs. in 1 kilogram-meter	7.23308	0.85932

APPROXIMATE VALUES OF SINES.

$$\text{Natural sine of } 1^\circ = \frac{1.75 \text{ ft.}}{100 \text{ ft.}} = \frac{1}{60} \text{ (roughly)}$$

$$\text{Natural sine of } 0^\circ\,1' = \frac{0.03 \text{ ft.}}{100 \text{ ft.}}$$

$$\text{Natural sine of } 0^\circ\,00'\,01'' = \frac{0.3 \text{ inch}}{1 \text{ mile}}$$

Greek Alphabet.

LETTERS	NAME
A, α,	Alpha
B, β,	Beta
Γ, γ,	Gamma
Δ, δ,	Delta
E, ϵ,	Epsilon
Z, ζ,	Zeta
H, η,	Eta
Θ, θ,	Theta
I, ι,	Iota
K, κ,	Kappa
Λ, λ,	Lambda
M, μ,	Mu
N, ν,	Nu
Ξ, ξ,	Xi
O, o,	Omicron
Π, π,	Pi
P, ρ,	Rho
Σ, σ, s,	Sigma
T, τ,	Tau
Υ, υ,	Upsilon
Φ, ϕ,	Phi
X, χ,	Chi
Ψ, ψ,	Psi
Ω, ω,	Omega

APPENDICES

APPENDIX A.

THE PLANIMETER.

The planimeter is an instrument used to determine the area of a figure by moving the tracing point of the instrument around the perimeter of the plotted area. When the figure has a regular shape its area can be easily computed from its dimensions, but when the boundaries are crooked, such as river boundaries, the planimeter is most useful, and with careful manipulation results can be obtained which are accurate enough for many engineering purposes.

The Amsler Polar Planimeter. — The most common planimeter is the *Amsler Polar Planimeter* (Fig. 213). This instrument



FIG. 213.

has two arms, *BO* and *HP*. The arm *BO* is of fixed length; it is anchored at *O* by a needle point which sticks into the paper and is held in position by a small weight which is detachable. At *B* it is connected by a pivot to a collar, *C*, through which the tracing arm *HP* can slide. At *P* is a tracing point which is moved along the outline of the area to be measured; the distance *CP* being adjusted to conform to the scale of the map. The graduated wheel *S*, whose axis is parallel to *HP*, records the area in units dependent upon the length of the arm *CP*.

The planimeter rests then on three points, the anchor, the tracing point, and the periphery of the wheel. As the tracing point is moved around the given area, the wheel drags along, sometimes slipping and sometimes rolling, and the difference between the reading of the scale on the wheel at the beginning and end of the circuit represents the area of the figure. Besides the scale on the wheel there is a small disk D which records the number of full revolutions of the wheel. The result of reading the disk, the wheel, and its vernier will usually give four figures.

Since the length of the anchor arm is fixed and the point O stationary, the pivot B moves on the circular arc whose center is O and whose radius (R) is the distance OB. The wheel, however, does not follow the arc of a circle, but the instrument must be so constructed that the wheel will always lie somewhere on the line dC or on dC produced (Fig. 214).

If in moving the tracing point its arm be maintained in such a position with reference to the anchor arm that the plane of the wheel will always pass through the anchor point, it is evident that the wheel will not revolve at all on its axis but will slip on the paper without changing its reading. The tracing point can therefore be started at a given point and moved about in the path of a circumference, returning to the same point again without recording any reading of the wheel. This circumference is called the *zero circumference*, or the *correction circle*.

Theory of the Amsler Polar Planimeter. — The following proof has been taken from Cours de Mécanique, by Édouard Collignon.

Let A (Fig. 214) be the area to be measured. Conceive cd (corresponding to the tracing arm) to be a straight line of constant length moving so that one end d is always upon the outline of A and the other end c is always upon a given curve cc' (in general a circle described from O).

Let cd and $c'd'$ be consecutive positions of the moving line, and let an expression be obtained for the elementary area $cdd'c'$ generated by the line in moving from the first position to the second. This movement may be considered as composed of two

parts; a translation from cd to a parallel position $c'e$, and a rotation from $c'e$ to $c'd'$, the first generating a parallelogram $cdec'$, and the second a sector $c'ed'$.

Let dA' = the elementary area $cdd'c'$
L = the length of cd
dh = the width of the parallelogram
$d\alpha$ = the elementary angle of rotation

Then
$$dA' = L \cdot dh + \tfrac{1}{2}L^2 \cdot d\alpha \qquad [1]$$



FIG. 214.

Now suppose a wheel F fixed upon cd, its plane perpendicular to that line, so that in the displacement of cd the wheel rolls when the point F moves perpendicularly to cd, and glides without turning when F is displaced in the direction of cd. Let $d\theta$ be the angle through which the wheel turns upon its axis in passing from F to F'. If r is the radius of the wheel, $rd\theta$ is the length of arc applied to the paper. This length is equal to dh (the rotation

of the wheel in the translation from cd to $c'e$ corresponding to the normal displacement only) + the arc $L'd\alpha$ (letting $cF = L' = c'F'$).

$$\therefore r \cdot d\theta = dh + L'd\alpha \qquad [2]$$

With the wheel beyond c on dc produced, $r \cdot d\theta = dh - L'd\alpha$

Eliminating dh from equations [1] and [2]

$$dA' = r \cdot L \cdot d\theta + \left(\frac{L^2}{2} - LL'\right)d\alpha \qquad [3]$$

$$\int dA' = \int r \cdot L \cdot d\theta + \int\left(\frac{L^2}{2} - LL'\right)d\alpha \qquad [4]$$

Conceive now the point d to traverse the entire outline of A, the elements dA' being reckoned positively or negatively according to the direction in which they are generated. Two cases are to be noticed:

(a) When the directing curve cc' is exterior to (but not including) the area A (Fig. 197). The algebraic sum, $\int dA'$, will be the difference between the sum of the positive and the sum of the negative elementary areas, and will equal the area A.

$$\int r \cdot L \cdot d\theta = rL\theta$$

$= Lu$ (where $u = r\theta$ = algebraic sum of arcs applied to paper by wheel).

$\int d\alpha = 0$, since cd returns to its original position without having made a circuit about O.

$\therefore$ Integrating expression [4], $A' = A = Lu$.

(b) When the directing curve cc' is within the area A (Fig. 215). The line cd now makes an entire revolution in order to return to its primitive position, and $\int d\alpha = 2\pi$. Also the area

$$A = \int dA' + \text{area of circle described by } Oc.$$

By integrating expression [4]

$$A' = Lu + 2\pi\left(\frac{L^2}{2} - LL'\right)$$

$$A = A' + \pi R^2$$
$$= Lu + \pi\,(L^2 - 2\,LL' + R^2)$$
$$= Lu + \text{the area of a circle of radius } \sqrt{L^2 - 2\,LL' + R^2}.$$

The sign of $2\,LL'$ is $-$ if the wheel be between tracing point and pivot point; otherwise it is $+$.



FIG. 215.

This circle is called the "circle of correction" and its value may be found by measuring with the planimeter a circle or other figure of known area inclosing the directing curve cc'.

It will be seen that the radius $\sqrt{L^2 \pm 2\,LL' + R^2}$ is the distance from anchor point to tracing point, when the plane of the wheel passes through the anchor point; in other words, is the radius of the zero circle.

If C = circumference of wheel
and n = number of revolutions made in a given measurement
$Lu = LnC$

If L and C be given in inches A will be found in square inches. By varying L the area A corresponding to one revolution of the wheel ($n = 1$) may be varied at pleasure. Commonly, if the area is sought in square inches the length L is made such, by adjustment on the tracing arm, that one complete revolution of the wheel corresponds to 10 square inches of area.

Since, for the anchor point **outside** the area to be measured, $A = LnC$, it appears that for any setting of L, A is directly proportional to n. So that L may be set at random and n' determined for a known area A' (say a circle or rectangle) in whatever unit the area is desired, then $\frac{A}{A'} = \frac{n}{n'}$. But this process evidently does not apply to the case of anchor point **inside** the area to be measured.

In finding the area of the circle of correction, the instrument gives directly only the **difference** between circle and known area.

If the known area lies entirely outside of circle (Fig. 216), then the record of instrument gives the shaded area only, and this **subtracted** from known area will equal the circle of correction.

If the known area (Fig. 216) does not lie entirely without the



FIG. 216.

circle then record of instrument must be **added** to the known area if the circle of correction is the larger, otherwise **subtracted.**

Use of Polar Planimeter. — In measuring a closed area the anchor point is pressed into the paper at a position **outside** of the area of the figure, if it is not too large, and the tracing point is started from a definite point on the periphery of the area, preferably such as will bring the two arms approximately at right

angles to each other. The wheel is then read. The tracing point is then moved around the outline of the area, being careful to follow the line accurately, until the starting point is reached again. The wheel is again read and the difference between the two wheel readings gives the area in the unit depending upon the setting of the arm. The disk should also be read when the wheel is read if the area is large enough to require a full revolution of the wheel. Care must be taken to bring the tracing point **exactly** back to the point from which it was started.

While some instruments have a tracing arm of fixed length, so that all areas recorded by the wheel are in the same unit, square inches for example, many planimeters have adjustable tracing arms which can be set by means of a clamp and slow-motion screw at whatever reading of the scale on the tracing arm is desired. Usually it will be necessary to use a reading glass to make this setting accurately. The arm is sometimes marked by vertical lines and beside these lines are letters and figures indicating the unit of area to which the setting corresponds. In some instances, however, the scale is marked as a continuous scale and the proper settings for given area units are supplied by the instrument maker.

A way of avoiding the use of the correction circle in measuring large areas is to divide the area into smaller ones by light pencil lines and to determine each fractional area separately. If, however, the anchor point is placed inside the area the value of the correction circle must be applied to the reading of the wheel as explained in the previous article.

A planimeter can be readily used even though the setting of the arm is not known. A square, say four inches on a side, can be accurately drawn on the map and its area determined with the planimeter in the usual manner, making several independent determinations with the anchor point in different positions so that if there are any irregularities in the paper over which the wheel passes which are affecting one result, this error will not enter into the other determinations. The mean of these results divided by the number of square inches in the given area will be the wheel reading for one square inch. This being determined the area in square inches of any given figure can be obtained

by the planimeter and this can be easily converted into the desired units by using the scale of the map.

It is well before beginning to trace out the figure to run the tracing point around the figure, keeping approximately on the line so as to be sure that the anchor point has been placed in a satisfactory position. To insure accuracy the area should always be measured by at least two independent determinations with a different position of the anchor for each measurement for the reason explained above. Furthermore, it is of extreme importance to check the area roughly by observation or by scaling and rough calculations. If the paper has shrunk since the drawing was made the amount of this change should be determined and allowed for in arriving at a correct value for the area. By the use of a polar planimeter a result which is not in error more than one per cent is easily obtained, except in the case of very small areas.

The Rolling Planimeter. — The rolling planimeter, unlike the polar planimeter, is not anchored to the drawing. It has a tracing point at the end of an adjustable pivoted arm which is fastened to a frame which is supported on two rollers. In using this planimeter the whole instrument moves forward or backward in a straight line while the tracing point traverses the outline of the area to be measured.

With the rolling planimeter it is possible to obtain a remarkable degree of accuracy, results correct to a tenth of a per cent being easily reached.

APPENDIX B.

MOUNTING PAPER FOR DRAWINGS.

In making a large map in which a high degree of accuracy is essential, especially if the plotting is to extend over a long period of time, it will be found advantageous to mount the paper on cloth stretched upon a drawing board. When so mounted the paper presents a better surface to work upon and is less liable to change its dimensions with changes in atmospheric conditions than mounted paper that is simply fastened by thumb tacks to the board.

The cloth, which may be ordinary bleached cotton, should be tacked to the edges (not to the top) of the board in such a way as to draw the cloth tightly and yet evenly. In order to prevent the paper, while drying, from tearing the cloth away from the tacks it will be necessary to space the tacks not more than an inch or so apart along the edges of the board. It is evident that a T-square cannot be used when the drawing is mounted in this manner; but since the T-square is not as reliable as a steel straight-edge the latter will be preferable in any case if great accuracy is desired.

After the cloth is stretched the back of the drawing paper should be moistened slightly with a sponge. This is done to prevent the paste from drying too rapidly. The paste used should be common flour paste such as is used for wall paper, properly thinned out, thoroughly mixed, and carefully strained to remove all dirt and lumps. It should be laid on evenly with a wide brush and so as to cover all parts of the paper. If any part is left dry it may spring up from the cloth and cannot afterward be made to lie flat. All pieces of dirt, lumps of paste, hairs from the brush, etc. should be picked off before the paper is laid on the cloth, as they will make rough spots on the surface of the paper which may afterward wear through or cause dirty spots. The pasting should be done quickly enough so that no part of the surface dries before the paper is mounted. It is well to run the brush around the edges the last thing before the paper is laid on the cloth.

After the paper has been thoroughly pasted it should be laid carefully on the cloth in the correct position. The center of the

paper should strike the cloth first, and should be placed at once in its final position as it is impossible to move the paper around on the cloth. It may require two persons to do this if the drawing paper is large, say "double-elephant" size or larger. As soon as the paper is in position it should be rubbed down to prevent any part from drying before it sticks to the cloth. In order to keep the surface clean a piece of manila paper may be laid over the drawing paper. It should be rubbed down in the center first, then radially outward and in such a way as not to crease or tear the paper. Care should be taken that the edges are kept well pressed down while the paste is drying; the edges of the paper expand so greatly while the paste is wet that they will rise up from the cloth and it will require constant attention for several minutes to keep the edges in contact with the cloth. The paper should **not** be rubbed parallel to the edges of the board as this is almost certain to crease the paper wherever it is not flat, and it is impossible, after the creases are once formed, to entirely remove them or to give the drawing a clean, smooth surface. If the paper is rubbed gently from the center outward the creasing may always be avoided. It should be remembered that while the paper is wet it will not stand hard rubbing. If it is found that the paper has dried in some places along the edges, a little paste may be introduced under the edge with a knife-blade and the paper held down until it has dried.

After the paste has dried enough to hold the paper securely it should be left for about 24 hours to dry thoroughly before plotting is begun, but it should not be left near a heating apparatus to dry. When the drawing paper is quite dry it may be found that small particles in the paste cause the paper in some places to project above the general surface. This defect may sometimes be remedied by taking a flat, hard surface (such as a glass paper weight) and pressing down heavily on the spot; this will press the object into the cloth or board without injuring the paper.

It is needless to say that the drawing board used must have a true plane surface if a good drawing surface is desired. The board should also be free from ink or paint stains; any stains on the board will be soaked up by the paste and are likely to show on the drawing paper.

INDEX.

Abbreviations in notes, 113
Abscissa, 292.
Accident plans, 287.
Accidental errors, 15.
Accumulative errors, 15.
Accuracy,
  in measuring lines, 11.
  of measurements, 14.
  of traverses, 111.
Acre, 1.
Additions, to blue prints, 444.
Adit, 321.
Adjusting screws, 25.
Adjustment,
  of chain, 2.
  of compass, 25.
  of dumpy level, 92.
  of level, 89.
    bubble, 90.
    cross-hairs, 89.
    direct method, 92.
    indirect method, 90.
    peg method, 92.
    wyes, 90.
  of Locke level, 94.
  of solar attachment, 70.
  of transit, 56.
    bubble, 56.
    collimation, 58.
    cross-hairs, 57.
    long bubble on telescope, 59.
    mining, 328.
    objective slide, 60.
    standards, 59.
  of traverses, 406, 412.
    angles, 381.
Agonic line, 25.
Alignment, 6, 10, 13.
Allen, C. F., 269, 390.
Almanac, Nautical, 68, 216, 220.
Altitude, of sun, 69, 222, 225.
American Ephemeris (see almanac).
Angles,
  brass, 83.
  calculated from bearings, 30.
  deflection, 108.
  doubling, 108.
  horizontal, 47.
  interior, 108.
  laying off, 50.
  measured by repetition, 48.
  parallel lines, 102.
  vertical, 54.
Angular,
  convergence of meridians, 141, 161.
  value of one division of level, 73.
Annual variation, 20.
Apparent,
  motion of heavenly bodies, 212.
  declination of sun, 229.
Apex,
  of vein, 321.
Approximate times of culmination and elongation of Polaris, 218.
Areas,
  averaging end, 392.
  computation of,
    by double meridian distances, 400.
    by double parallel distances, 407.
    by offsets, 381.
    by Simpson's one-third rule, 382.
    by trapezoidal rule, 382.
    by triangles, 384.
  coördinates, 422.
  curved corner lot, 386.
  quadrilateral, 385.
Arrangement of computations, 378.
Astronomy,
  observation for
    azimuth, 212.
    latitude, 230.
Atmosphere, refraction, "boiling of," 87.
Attachment,
  for plumbing rods, 82.
  solar, 65.
Attraction, local magnetic, 29.
Aurora Borealis, 25.
Automatic tide gauge, 247.
Auxiliary level, 59.
Averaging end areas, 392.
Axe, 19.
Axis,
  polar, 65.
    adjustment of, 70.
Azimuth,
  angles, 17, 108, 199.
  assumed, 109.
  at any hour, 220.
  in city triangulation, 298.
  needle checks on, 110.
  of line, 17.
  of Polaris, 215.
  to distant object, 420.

Back,
  bearing, 19.
  ground, 52.
  sight, 51, 86.
Balancing surveys, 406, 412.
Ball and socket joint, 16, 32.
Baltimore triangulation, 294.
Base, 243.
  board, 106.
  line, 124, 134, 297.
Batterboards, 289.
Bauer, L. A., 20.
Beam compass, 434.
Bearings, 16.
  method of taking, 18.
  reverse, 19.
Bed of stream, ownership, 118.
Bench, 236.
  marks, 236.
  establishing, 232.
  in cities, 261.
Bent,
  needle, 26.
  pivot, 27.

Bisection,
method, 180.
target, 80.
Black prints, 441.
Blazing trees, 107, 130.
Blue prints, 439.
Blocks,
irregular, 281.
size of, 257.
"Boiling" of atmosphere, 87.
Border lines, 475.
Boreholes, 359.
Borrow-pits, 244, 391.
Boston rod, 78.
Boundaries,
of land,
conventional sign for, 467.
disputed, 117.
identification, 106, 116.
irregular, 105.
relocating, 118.
Bounds,
control, 116.
stone, 264.
Breast, 348.
Brunton Pocket Transit, 331.
Bubbles,
levels, construction of vial, 72.
angular value, one division, 73.
Buildings, location of, 166, 175.
Bulletin of University of Wisconsin, 69.
Bureau of Equipment, Navy, 216.
Bureau of Standards, 252.
Burnt sienna, 444.

Calculated bearings, 110.
Calculating angles from bearings, 29.
Calculation (see computation).
Camel's-hair brush, 61, 439.
Capstan-head screw, 36.
Card, for sighting, 52.
Care of instruments, 61.
Carrying the transit, 62.
Cassiopeia, 214.
Catenary, 13.
Celestial sphere, 65, 212.
Cellar, excavation, 391.
Cemeteries, 287.
Centering pivot point, 27.
Chaining,
method of, 8.
on slopes, 9.
Chains,
Gunter's, 1, 99.
engineer's, 1.
testing, 2.
Chain surveying, 106.
Change, magnetic, 20, 119.
Chart, isogonic, 22.
Checking,
angles, 110.
azimuths, 109.
bench marks, 233.
buildings, 167.
computations, 339, 378, 385, 387.
distances, 6, 11.
field work, 109.
lots, city, 282.
target reading, 84.
traverses, 100, 102, 105, 111, 163, 202.
traverses not closed, 163.
Chinese white, 444.
Chords, plotting by, 456.
Circular curve, 267.
City surveys, 251.
blocks, 257, 281.

City surveys (Continued)
contour map, 254.
datum, 261.
laying out town site, 254, 262, 266.
location of streets, 255.
marking corners, 264.
monuments, 262.
permanent beach works, 261.
plans, 291.
provision for growth, 254.
staking out, 285.
standard, 253.
steel tapes, 251.
streets, 252, 254, 285, 286.
cross-section, 278.
curb lines, 282.
grades, 259, 275, 286.
gutters, 279.
location, 255.
width, 257.
Claims, mining, 362.
Clamps, 32.
Cleaning drawings, 478.
Clinometer, 331.
Clips, 89.
Closure, error of, 99.
limits, public lands, 135.
Cloth tape, 3.
Coast and Geodetic Survey, 20, 22, 25, 77, 82, 110, 216, 236.
Coefficient of expansion, steel, 12.
Co-latitude, 67.
Collimators, 58.
Compass, beam, 434.
box, 16.
Compass,
surveyor's, 16.
adjustments, 25.
reading bearings, 18.
remagnetizing, 28.
running traverse with, 99.
pocket (compass), 18.
prismatic (compass), 18.
used in mines, 294.
Compartment, 286.
Compensating errors, 14.
Comstock's refraction formula, 69.
Computations,
area, 382.
arrangement of, 378.
book, 378.
borrow-pits, 390.
checks, 378.
coördinates, 421.
deflection angles, 389.
estimates, 393, 397.
logarithmic, 375.
preparing notes for, 381.
prismoids, 392.
short cuts, 376.
significant figures, 371.
slide rule, 378.
triangulation, 420.
volumes, 390.
Concrete, 265.
Connecting surface with underground, 334.
Constellations, 213.
Contour, 301, 458.
found by cross-sections, 312.
incorrectly sketched, 312.
interpolated, 312.
locating, 314.
locating by hand level, 315.
maps, 306.
pen, 434.
problem, 317.

Contour (Continued)
properties of, 304.
Contracts, 121, 128.
Control by triangulation, 292, 300.
Conventional signs, 465, 467.
Convergence of meridians, 121, 141, 161.
Cooley, Chief Justice, 118.
Coördinates,
area by, 422.
calculation, 421.
plotting by, 449.
system for cities, 291.
Copying notes, 480.
Copying plans, 433, 439.
Corners,
closing, 141.
locating and marking, 106, 146.
lost, 155.
meander, 149.
monuments, 148, 262.
obliterated, 155.
section, 150.
selecting, 106.
standard, 141.
witness, 149.
witnessing, 148.
Correction,
line, 136.
triangle, 418.
Corrections,
for refraction,
in altitude, 227.
in declination, 69.
on slopes, 10, 13, 252, 378.
Counting, tape lengths, 8.
Counterweight, on needle, 19.
Courts, 117.
Cross-cuts, 322.
Cross-hairs, 34, 36.
illuminating, 214.
Cross-section,
areas of, 392.
contours determined by, 312.
for earthwork, 241.
paper, 438.
road, 241.
Crow foot, 108, 113.
Crown, glass, 36.
of pavements, 279.
Culmination of Polaris, 212.
Cultivated lands, conventional sign, 465.
Cumulative errors, 14.
Curb lines, 282.
Currents, electric, 19.
Curvature and refraction, 3, 87.
Curves,
laying out, 268.
principles, 267.
street corners, 273.
vertical, 277.
Cut, 242.
Cut-off line, 111, 164, 419.

Daily, variation of needle, 20.
Dam, 309.
Dark glass, 222.
Data,
to be noted (public lands), 145.
missing, 414.
Datum plane, 232, 261.
establishing, 245.
Day, civil and astronomical, 219.
Decimals of foot in inches, 4.
Decimal division of vernier, 44.
Declination,
of needle, 19, 119.
Declination (Continued)
variation, 20, 119.
daily, 20.
secular, 20.
irregular, 20.
determination by observation, 25.
of sun, 68, 227.
correction for refraction, 227.
Deed,
description, 115.
interpretation, 117.
looking up, 120.
recording, 120.
survey for, 114.
Deflection angles, 110, 268, 455.
Degree of longitude, length of, 162.
Departure,
computation of, 401.
total, 449.
Depth, cut or fill, 242.
Detecting local attraction, 29.
Dial, miner's, 330.
Difference in elevation, 85.
Differential leveling, 85.
Dip of needle, 19.
of vein, 322.
Direct, adjustment, 91.
position of instrument, 34.
Direction,
measurement of, 16.
Disappearing stadia hairs, 189.
Distances,
with chain, 8.
with stadia, 5, 200.
with tape, 5, 8.
between end points, 419.
on slope, 13, 252, 381.
Distant object, checking angles, 165.
Disturbed corners, 266.
Dividers,
proportional, 435.
Division of land, 416.
Division of level tube, 73.
Double area, 403.
meridian distance, 403.
rodded lines, 235.
verniers, 39.
Doubling angles, 50, 163.
Drafts in shaft, 336.
Drafting instruments, 429.
Drainage,
area, 309.
provision for, 255.
Drawing paper, 436.
Drift, 322.
Drill-hole, 263, 340.
Drying prints, 440, 441.
Dumpy level, 74.
adjustment of, 91.
Duty of surveyor, 116.

Earth,
curvature, 1, 87.
magnetism, 19.
Earthwork,
computation, 390.
end area method, 392.
estimate of, from contour map, 393, 397.
prismoidal formula, 392.
Easting, 400.
Eccentricity,
correction for mining transits, 326, 327.
of circles, 44.
Effect of sag, 13.
Elaborate, titles, etc., 475.
Electric current, 19.

Electric printing frame, 443.
Electrification, compass cover, 18.
Elevation,
difference of, 85.
Elimination of errors, 61, 87, 215, 234.
Elongation,
azimuth at, 213.
of Polaris, times of, 218.
meridian observation at, 214.
Embankment, 242.
End area method, 392.
Engineer's,
chain, 1, 2.
scale, 430.
transit, 34.
Enlarging plans, 433.
Ephemeris, 68, 216, 220.
Equal backsights and foresights, 87.
Equation of time, 230.
Equator, 66.
Erecting eyepiece, 37.
Errors,
accidental, 14.
amount of, 12.
cumulative, 14.
compensating, 14.
in compass work, 28.
in measuring lines, 11.
in tape, 11.
in use of level, 94.
in use of transit, 62.
of adjustment, 61.
elimination of, 61, 87.
of closure, 99.
of graduation, 49, 61.
Establishing corners, 139.
Estimates, earthwork, 393.
Etched, marks on tape, 3.
European surveys, 82.
Excavation, 242.
Expansion,
coefficient of, steel, 13.
of paper, 476.
Exterior, township, 138.
External secant, 377.
Eyepiece, erecting and inverting, 37.
diagonal, 329.

Farm surveys, 99.
Farnham, I. T., 273.
Federal laws, mining, 363.
Fences,
measurement of, 110.
conventional signs, 467.
Field,
book (see notes)
checks, 109.
methods, 101.
notes, Pub. Lands, 146.
Land Surveying, 100, 103.
Leveling, 234, 238.
Topographical, 302.
work, 99, 198.
Figures, significant, 371.
Filing,
drawings, 463.
note-books, 479.
Fill, 242.
Finding, lost corners, 116.
Floats, 52.
Focus, principal, 35.
Focusing, 35.
"Folding" vernier (Fig. 26), 43.
Foresights, 51, 52, 53, 86, 87.
Formulas,
area by coördinates, 422.

Formulas (Continued)
area of triangle, 384, 385.
area curved corner lot, 386.
azimuth by Polaris, 215, 219.
azimuth by sun, 222, 228.
convergence of meridians, 161.
cross-section of street, 279.
curves, 267.
prismoid, 392.
sag and alignment, 13.
Simpson's rule, 392.
side and top telescope, 324.
tangent offset and middle ordinate, 387.
trapezoid, 382.
Fractional areas, 383.
French curves, 435.
Frost, 50, 263.
Functions, judicial, of the surveyor, 116.

Gauge,
self registering, 247.
tide staff, 246.
Geodetic surveying, 1.
Geographical meridian, 16.
Geological data, 356.
Geological Survey, U. S.
bench marks, 236.
Geology, relation to topography, 309.
Geometric principles, 166.
Giving line, 111.
Glass, magnifying, 47.
Grade of street, 259.
line, 241, 254, 285.
leveling for, 244.
Graduation,
errors of, 49, 61.
compass-box, 16.
numbering, 32.
tapes, 3.
Grantee, 117.
Grantor, 117.
Gravity, 72.
Great Dipper, 214.
Greenwich time, 68, 219.
Group of claims, 364, 366.
Growth of cities, 254.
Guide meridians, 126.
Gunter's chain, 1.

Hachure, 303.
Handkerchief, signals, 54.
Hand level, 77.
adjustments, 93.
topography with, 314.
Hayford, J. F., 220.
Head,
tape-man, 5.
shifting, 31.
Heading, 322.
Height of instrument, 232.
High water mark, 151.
Holman, S. W., 371.
Horizon, 66.
Horizontal,
angles, 47.
measurements, 1.
line, defined, 72.
Hourly change in declination of sun, 68, 223.
Houses,
conventional signs, 467.
locating, 166.
Hypotenuse, 13.

Identification of bounds, 106.
Illumination,
cross-hairs, 214.

lumination (Continued)
plumb line, 219.
nage, 34, 37.
naccessible distances, 182–6.
ach, not used in surveying, 1.
nclination,
correction for, 1, 13, 252, 381.
nclined sights, 195.
ndex correction, 54.
ndexing, 480.
ndia ink, 444.
ndirect, adjustment, 89.
nformation in notes, 114.
nitial point, 134.
nk, 443.
nstructions, Manual of, 122.
nstrument,
care of, 61.
height of, 232.
nstrumental errors,
elimination of, 61, 87, 215, 234.
nstruments, drafting, 429.
nstruments, surveying and plotting,
chain, 1.
compass, 16.
pocket, 18.
prismatic, 18.
level, 72, 73.
Locke, 77.
rod, 78.
lining pole, 5.
measuring rod, 6.
pins, 5.
planimeter, 387.
protractor, 430, 432, 446.
slide rule, 378.
stadia, 5, 189, 190.
targets, level rod, 80.
telescope, 34.
Thacher rule, 381.
transit, 31.
solar attachment, 65.
Interchangeable side and top telescope, 325.
Interior angles, 108.
Interpolating contours, 312.
Interval, contour, 303.
Inverting eyepiece, 37.
Iron, effect on needle, 19.
Irregular,
areas, 392.
variation, 25.
Isogonic,
chart, 22,25.
lines, 25.

Judicial functions of the surveyor, 116.

Keys, 19.

Lamp targets, 344.
Land Office, 123, 134.
Land surveying,
by compass and chain, 99.
by transit and tape, 101.
error of closure, 99.
computing area,
by D. M. D.'s, 404.
by coördinates, 422.
additional areas, 382.
dividing land, 416.
obstacles, 178.
resurveys, 118.
supplying omissions, 117, 414.
survey for deed, 114.
U. S. Public Lands, 121.
Lateral,
adjustment, 89.
Lateral (Continued)
movement of transit head, 32.
Latitude,
difference, 400.
error in, 406, 412.
observation, 230.
of a line, 400.
parallel, 128.
total, 449.
Laws, mining, 363.
Laying out curves, 271.
Laying out land, 257.
Laying out town site, 254.
Least squares, method of, 14, 298
Legal lines, 106.
Length,
absolute of, tape, 252.
standard of, 253.
Lenses, 36, 78.
Lettering on maps, 468, 469, 470.
Level,
bubble, 73.
dumpy, 74.
hand, 78.
Locke, 78.
precise, 73.
rod, 78.
section, 244.
surface, 72.
(term in mining), 322.
use of, 83.
vial, 72.
wye, 73.
Leveling, 232.
across a river, 247.
for bench marks, 232.
for grade line, 244.
for profile, 237.
instruments used in, 72.
roads, 78.
screws, 32.
signals used in, 85.
Levels,
divergence in duplicate lines, 235.
double rodded lines, 235.
Limb,
of sun, 69, 224.
of transit (graduated), 31.
Lines,
clearing out, 131.
horizontal, 1.
legal, 106.
of collimation, 34.
stretching, 264.
Lining in, 6, 13.
Lining-poles, 18.
Link, 1.
Local,
attraction, 29.
mean time, 219, 231.
Locating,
buildings, 166.
points from transit line, 301.
property lines, 299.
Locke hand level, 77.
Lode, 323.
claim, 364.
coloring on maps, 354.
Logarithms,
computing by, 375.
Long rod, 80.
Longitude,
difference, 400.
table of lengths, 162.
Lost monuments, 106, 116.
Lots, city, 257.

Magnet, earth a, 19.
bar, used, 28.
Magnetic,
attraction, 29.
bearing, 16.
declination, 19.
variation of, 20.
observations for, 214.
meridian, 16.
needle, 16, 32.
storms, 25.
Magnetism, weakened, 27.
of earth, 19.
Magnifying glass, 47.
Magnifying power, 37.
Man-hole (mining), 322.
"Manual of Instructions," 122, 220.
Map,
Baltimore, 294.
Washington, 258.
Maps,
city, 291.
large, 477.
lettering on, 468.
mine, 354.
topographical, 306.
requirements, 114.
Marking points in tape measurement, 10.
Marsh, conventional sign, 465.
Massachusetts,
observed declinations, 20.
Mean,
tide, 232, 246.
time, 219, 230.
Meandering, 151.
Meander lines, 152.
Meandering a stream, 151.
Measurements,
accuracy of, 14.
chain, 8.
mistakes in recording, 11.
odometer, 5.
on slope-reducing, 376.
pacing, 7.
stadia, 5.
tape, 5.
Measuring,
angles by repetition, 48.
base line, 297.
differences in elevation, 72.
distances, 5.
Mental estimates, 12, 378.
Meridians,
angular convergence of, 121, 141, 161.
determination of, 212.
by solar attachment, 66.
guide, 136.
magnetic and true, 16, 17.
on maps, 475.
principal, 124, 136.
Metallic tape, 3.
Method of least squares, 14, 298.
Method of surveying field, 101.
Metric chain, 3.
Metropolitan Water and Sewerage Board, 81.
Microscope, 35.
Mill-hole, 322.
Mine,
boreholes, 350.
boundaries, 358.
carrying meridian into, 332, 334.
claims, 358.
connecting surface and underground, 338.
connection, 358.
heave, 322.
laying out work, 357.
Mine (Continued)
lead, 323.
ledge, 323.
mapping, 354.
patent surveying, 365.
placer claims, 365.
plotting traverses, 354.
seam, 322.
shoot, 321.
surface surveys, 362.
surveys, 321.
throw, 322.
underground leveling, 331.
Miner's dial, 330.
Mining claims, 358.
terms, 321.
Missing data, 414.
Missouri River Commission, 236.
Mistakes,
avoiding, 10.
in compass work, 28.
in level work, 94.
in measuring lines, 10.
in transit work, 62.
in using solar attachment, 70.
Moisture, effect on level rod, 83.
Monuments,
at section corner, 150.
in city work, 262.
lost, 116.
significance and authority of, 116.
Motion of fingers in leveling, 46.
Multiplication by slide rule, 380.

Nails, in marking points, 10, 340.
Natural, functions, 375.
scale of maps, 430.
Nautical Almanac, 68, 216, 220.
Navigators, 20.
Needle, compass,
bent, 26.
remagnetizing, 28.
New York rod, 80.
Night, observations at, 214.
Noon observation, 230.
Normal position of telescope, 34.
North star, 212.
Northing, 400.
Note-book, 84, 100, 112.
Notekeeper, 11.
Notekeeping, 112.
bench levels, 234.
cross-section, 240.
double rodded lines, 235.
mine, 345, 351.
profile, 238.
road, cross-section, 243.
topographical survey, 302.
Notes, 112.
compass and chain, 100.
stadia, 202.
transit and tape, 103.
traverse, 164.
Numbering,
graduations, 32.
townships, 126.
sections, 127.

Objective, 35.
slide, adjustment, 60.
Obstacles, 178, 181.
Observations,
for declination of needle, 25.
for meridian by solar, 66.
on Polaris, 214.
on Polaris, with compass, 219.

dometer, 5.
ffice,
plans, 479.
work, 107.
ffsetting transit line, 178, 181.
ffsets, 105, 166.
missions, supplied, 414.
ptical, axis, 35.
center, 36.
rdinates, 292.
re shoot, 357.
rganization of transit party, 111.
rigin of coördinates, 292.
riginal notes, 100, 112.
utcrop, 322.
wners of property, 117.
wnership of surveys, 114.

acing, 7.
antograph, 433.
aper, 436.
expansion of, 476.
mounted, 436.
mounting, 581.
protractor, 432.
arabolic curve, 277.
araffin, 83.
arallax, 19, 34, 48.
arallel,
of latitude, 128.
ruler, 434.
standard, 128, 136.
arty, transit, 111.
atent, mining claims, 365.
eg adjustment, 91.
adjustment for hand level, 93.
en, contour, 434.
encil, 52, 91, 112.
ermanence, bench marks, 237.
hiladelphia rod, 81.
hotograph of landscape, 307
ins, 5.
ivot, 16, 77.
bent, 27.
cap, 59.
lacer, 365.
lain transit, 34.
lan, 114, 291.
lane intersecting surface, 316.
lane surveying, 5.
lanimeter, 388, 573.
lates, of transit, 31.
lotting, 445.
by coördinates, 449.
by chords, 457.
by protractor, 446.
by tangents, 453.
cross-sections, 459.
details, 458.
land surveys, 445.
stadia surveys, 210.
lumb-bob, 32, 335.
lumb line, 52, 334.
in chaining, 8.
lumbing,
attachment, 82.
down a shaft, 334.
rod, 82.
lummet lamp, 331.
lus, station, 163.
ocket compass, 18.
olar axis, 65.
ole, 52, 212.
olaris,
elongation of, 218.
observation on, 25, 212.
Polaris (Continued)
polar distance, 212, 216.
Pole star, 18, 212.
Position, zero point, 10.
Precautions,
in using level, 88.
in using transit, 55.
Precise level, 73.
rod, 82.
Precision, 372.
Preliminary railroad surveys, 6.
Primary triangulation, 292, 300.
Principal focus, 35, 103.
Principal meridian, 124, 136.
Printing frames, 443.
Prints, blue, 439.
Vandyke, 441.
Prismatic, compass, 18.
eyepiece, 329.
Prismoidal formula, 392.
Prismoids, 392.
Process papers, 439.
Profile,
leveling, 237.
paper, 438.
Profiles, 478.
Projection, 307.
Proportion (see balancing surveys)
Proportional dividers, 435.
Protractors, 398, 430, 446.
Prussian blue, 444.
Public Lands Surveys, 121.
rates of payment for, 123.
records and maps, 153.
Pull,
tape, 12.
Purposes, of surveys, 3.

Quadrant, 17.
Quadrilateral, 186, 385.
Quarter-section, 135, 157.
Questioned measurement, 413.

Rack and pinion, 34.
Radius, of curve, level vial, 72.
Railroads,
curves, 435.
surveys, 4.
tracks, 285.
Raise, 322.
Random line, 51, 138, 177.
Range,
line, 125, 166, 167.
pole, 5, 52, 53.
townships, 125.
Raymond, W. G., 114.
Reading glass, 47.
Rear tape-man, 5.
Records, 291.
Rectangular coördinates, 291.
Reducing slope measurements, 376, 381.
Reference measurements, 107.
Refraction,
curvature and, 89.
in altitude, 225.
in declination, 561.
Registry of deeds, 120.
Remagnetizing needle, 28.
Repeating angles, 48.
tape measurements, 7.
Report (see U. S. Coast and Geodetic Survey).
Results, 371.
Resurveys, 118.
Reverse bearings, 29.
Reverse position of telescope, 34.
Reversing E. and W. points, 18.

Reversion, 56.
Revising street lines, 315.
  street grades, 315.
Revolution of wheel, 5.
Right ascension, 220.
Ring, cross-hair, 58.
Rivers, 118.
Roads,
  measuring on, 7.
Rod, 1.
Rod levels, 82.
Rodman, 78.
Rod readings, 84.
  for grade, 241.
Rods,
  leveling, 78.
    Boston, 78.
    measuring, 6.
    New York, 80.
    Philadelphia, 81.
    precise level, 82.
    special, 81.
    tape, 81.
Roof, transit on, 180.
Rule,
  parallel, 434.
  slide, 378.
  two foot, 5.
Runner, on slide rule, 379.
Running street lines, 314.
  street grades, 315.

Sag, 13.
Sand, 465.
Scales,
  engineer's, 430.
  logarithmic, 379.
  of maps, 445, 477.
Screen, for sun's image, 65.
Screw, leveling, 32.
Sea-level (see datum).
Secant method, 129.
Secondary triangulation, 299.
Section, of level, 74.
  of transit, 31.
Section, public lands, 126.
  fractional, 142.
  subdivision of, 157.
Secular, variation, 20.
Self-reading rods, 81.
Setting up transit, 45.
Sewer, 255, 285.
Shading (see hachures).
Shafts, 332, 334, 337.
Sherman, C. W., 253.
Shifting head of transit, 31, 46.
Shirley, Maj. J. W., 294.
"Shooting in" grades, 245.
Shop adjustments, 61.
Shore lines, 316.
Short rod, 80.
Shrinkage of paper, 476.
Side telescope, 324.
Sidereal time, 220.
Sights, compass, 16, 18.
  length of, 87.
  showing, 52.
Sighting rod, 5.
Signals,
  level work, 85.
  transit work, 53.
  triangulation, 292.
Signs, conventional, 465, 467.
Simpson's one-third rule, 382.
Sines, 533.
Sketch, 233.
Sketching contours, 312.
Slide rule, 379.
  Thacher rule, 381.
Slopes,
  reducing slope measurements, 10, 376, 381.
  side, 242.
  slope stakes, 242.
Slow motion, 32.
Solar,
  attachment, 65, 135, 329.
  observations, 222, 225.
Sources of error,
  compass work, 28.
  level work, 94.
  measuring lines, 10.
  transit work, 62.
Southing, 400.
Speaking rods (see self-reading).
Spherical triangle, 67.
Specimen notes, 146.
Spider lines, 36.
Spindle, 31.
Spirit level, 16, 32, 72.
Spline, 435.
Spring balance, 251.
Stadia, 5, 188.
Staff gauge, 246.
Staking out lots, 262.
Standard,
  length, 2, 12, 253.
  of transit, 32.
  parallel, 128, 136.
  time, 68.
State surveys, 165.
Stations, 10, 163.
  marking, 339.
Steel tape, 3, 10, 12.
  measurements, 10.
Stopes, 322.
Stop screw, 88.
Straight-edge, 429.
Straight lines, 51, 52.
Straightening crooked boundary, 384.
Streams, 316.
  meandering, 151.
Street lines, 255.
Street grades, 259.
Streets, 254, 285.
Striding level, 323.
Strike, 322.
Stull, 322.
Sub-grade, 241.
Subdivision of land, 416.
Subway, 360.
Supplying missing data, 414.
Surveying.
  plane and geodetic, 1.
  for area, 99.
  for deed, 114.
  Public Lands, 121.
Surveyor general, 121.
Surveyor's,
  chain, 1.
  compass, 16.
  transit, 32.
Surveys, accuracy of, 14.
Swamp, conventional sign, 465.
Swing offset, 166.
System, Public Lands, 121.

T-square, 429, 448.
Tack, 108.
Tables,
  convergence of meridians, 141.
  decimals of foot in inches, 4.
  hourly change in sun's declination, 223.

ables (Continued)
length of degree of longitude, 162.
mean polar distances of Polaris, 216.
observed declinations in Massachusetts, 20.
refraction in altitude, 227.
tangent method, parallel, 132.
times of elongation and culmination, 218.
secant method, parallel, 129.
ag, on chain, 2.
'angent, method, 131.
plotting by, 453.
screws, 32.
'ape-rod, 81, 240.
'apes, city work, 251.
cloth, 3.
metallic, 3.
steel, 3.
'arget,
bisection, 80.
rod, 80.
'elescope, 34, 324.
eccentric, 324.
'emperature, 12.
'ension handle, 251.
'ests, on transit, 55.
'hacher slide rule, 381.
'hermometer, on leveling rod, 82.
'hree-armed protractor, 432.
'ide,
gauge, 246.
observation of, 245.
'ies, 101, 107, 166.
'iers, township, 127.
'ime (see mean time).
'itles, 471.
'op telescope, 324.
'opographical surveying, 300.
'opographical symbols, 465, 467.
'opography,
contour map, 306.
field methods, 188, 300.
methods of representing, 465, 467.
'otal latitude and departure, 449.
'ownship, 121.
corners, 172.
exteriors, 138.
numbering, 126.
subdivision, 139.
'racing,
cloth, 222, 437.
paper, 437.
'ransit, 31.
adjustment of, 56.
carrying, 62.
engineer's, 34.
measuring angles with, 47, 48, 54.
mining, 324.
plain, 34.
running straight line, 51.
setting up, 45.
solar attachment, 65.
traversing, 101.
used in land surveys, 135.
used in mining, 324.
'raverse, definition, 100.
adjusting, 412.
'raversing,
with compass, 99.
with transit, 101.
'raverses,
in city work, 299.
inking in, 463.
locating from, 166.
stadia, 202.
underground, 338, 342.
Trench excavation, 244.
Triangles, inaccurate, 450.
Triangulation,
calculation, 420.
scheme, 294.
stations, 292.
system, 292.
Tripod, 32, 45, 61.
Tube reflector, 329.
Tunnel, 323, 360.
Turning points, 86, 232, 236.
double (see double rodded lines)
True,
bearing, 17.
meridian (see observations).
Two-foot rule, 5, 52.

Underground surveys, 332.
United States,
Coast and Geodetic Survey, 20, 25, 77, 119, 216, 236.
Deputy surveyors (see deputy).
Geological Survey, 236.
Isogonic Chart, 22–23.
Public Lands, Surveys, 121.
angular convergence of meridians, 141.
base-line, 134.
corners, 172.
guide meridians, 125.
legal requirements, 122.
meandering, 151.
notes, 146.
principal meridian, 136.
scheme of subdivision, 121.
standard parallels, 136.
subdivision of township, 139.
township, 138.
standard of length, 11.
surveyor general, 121.
Units, 1, 2.
Ursa Major, 214.

Value of one division, level, 73.
Valley, 255, 306.
Vandyke paper, 441.
Variation of compass (see declination).
of declination, 20.
Veins, 323.
Vermilion, 444.
Vernier, 38.
Vertical,
angle, 54, 200, 326.
circle, 34.
Volumes, 390.

Wall, 323.
conventional sign, 467.
Washington, 258.
Water, boundaries, 118.
color, 443.
lining, 465.
Waterproof ink, 443.
Watershed, 305, 309.
Waving the rod, 84.
Westing, 400.
Wheel, revolution of, 5.
Wind, effect of, 10.
Winze, 323.
Wires, illuminating, 214.
Wooden rods, 5.
"Working into line," 51.

Zenith, 66.
Zero point, 10.

LIBRARY
DEC
19
69
UNIVERSITY OF MISSOURI

TA
545
B8
1916
c.1
ENGI

LIBRARY
USE UNTIL
AUG 2 - 1991
ENGINEERING